

## PRE-RENOVATION INVESTIGATIVE SURVEY FOR ASBESTOS-CONTAINING MATERIALS 18-20 TRINITY STREET HARTFORD, CONNECTICUT

Project No. 2B-05-31 DPW No. 19360

Prepared for
State of Connecticut
Department of Public Works
Hartford, Connecticut

Prepared by
TRC Environmental Corporation
Windsor, Connecticut

Donald LePage Project Manager

TRC Project No. 43500-2840-00001 November 16, 2005

TRC Environmental Corporation
5 Waterside Crossing
Windsor, Connecticut 06095

Telephone (860) 298-9692 Facsimile (860) 298-6399

## TABLE OF CONTENTS

## **EXECUTIVE SUMMARY**

## PROJECT OUTLINE

## **TABLES**

1	BULK SAMPLE SUMMARY OF SUSPECT ASBESTOS CONTAINING
	MATERIALS
2	IDENTIFIED ASBESTOS CONTAINING MATERIALS
3	CONFIRMED NON-ASBESTOS CONTAINING MATERIALS

## **APPENDICES**

A	SITE SKETCH
В	LABORATORY AND INSPECTOR ACCREDITATIONS
C	ASBESTOS BULK SAMPLE CHAIN OF CUSTODY FORMS
D	PLM LABORATORY ANALYSIS DATA

## **EXECUTIVE SUMMARY**

On November 2, 2005 TRC Environmental Corporation (TRC) of Windsor, Connecticut conducted an inspection for suspect asbestos-containing materials (ACM) at 18-20 Trinity Street in Hartford, Connecticut. The inspection was initiated prior to planned renovation activities in accordance with USEPA Asbestos National Emissions Standard for Hazardous Air Pollutants (NESHAPS) requirements.

The scope of the inspection was limited to the first and fourth floor north and south wing mechanical rooms, and the third floor roof penthouse mechanical room at the facility. A Connecticut licensed asbestos inspector from TRC conducted the inspection in accordance with USEPA AHERA protocols and ASTM Standard E2356-04. Bulk samples of suspect materials were collected and analyzed via polarized light microscopy (PLM) methods at CTDPH/NVLAP accredited laboratories. ACM was identified as woven brown pipe wrap on the exterior of HVAC Unit FA8 in the 4<sup>th</sup> floor south mechanical room and as woven brown pipe wrap on the interior of HVAC Unit FA10 in the 3<sup>rd</sup> floor roof penthouse. ACM as woven brown pipe wrap is also assumed to be on the interior of HVAC Units FA6 and FA7 in the 4<sup>th</sup> floor north mechanical room. ACM to be impacted by renovation activities must be removed prior to disturbance in accordance with OSHA, USEPA, CTDPH, and CTDEP standards for asbestos abatement/disposal. Detailed results of the asbestos survey can be found in Tables 1-3 and Appendices A through D.

## PROJECT OUTLINE

Project Address:

18-20 Trinity Street

Hartford, CT

DAS Contract No.

03PSX0346E

DPW Project Manager

Michael Sanders

DPW Project No.:

2B-05

DPW Building No:

19360

TRC Project No.:

43500-2840-00001

Asbestos Inspector:

Jacob Smith (LIC #000621)

Date of Inspection:

November 2, 2005

Asbestos Identified:

Yes

## Additional Notes:

The site investigation was limited to the collection and analysis of suspect asbestos-containing pipe wrapping materials from within the 1<sup>st</sup> and 4<sup>th</sup> floor north and south wing mechanical rooms and from the 3<sup>rd</sup> floor roof penthouse mechanical room of the building.

**TABLES** 

## TABLE 1 BULK SAMPLE SUMMARY OF SUSPECT ASBESTOS CONTAINING MATERIALS 18-20 TRINITY STREET HARTFORD, CONNECTICUT

Sample No.	Sample Location	Homogeneous Material	% and Type Asbestos
. 01	4 <sup>th</sup> floor-south wing mechanical room HVAC Unit FA8	Brown woven pipe wrap located on the 2 exterior horizontal pipes on the side of the unit	40% Chrysotile
02	4 <sup>th</sup> floor-south wing mechanical room HVAC Unit FA8	Brown woven pipe wrap located on the 2 exterior horizontal pipes on the side of the unit	NA/PS
03	4 <sup>th</sup> floor-south wing mechanical room HVAC Unit FA8	Brown woven pipe wrap located on the 2 exterior horizontal pipes on the side of the unit	, NA/PS
04	4 <sup>th</sup> floor-north wing mechanical room HVAC Unit FA7	Brown corrugated pipe wrap located on the 2 short sections of pipe extruding from the front of the unit	ND<1%
05	4 <sup>th</sup> floor-north wing mechanical room HVAC Unit FA7	Brown corrugated pipe wrap located on the 2 short sections of pipe extruding from the front of the unit	ND<1%
06	4 <sup>th</sup> floor-north wing mechanical room HVAC Unit FA6	Brown corrugated pipe wrap located on the 2 short sections of pipe extruding from the front of the unit	ND<1%
07	3 <sup>rd</sup> floor-roof penthouse HVAC Unit FA10	Brown woven pipe wrap located on the 2 interior sections of pipe that are inside the unit	80% Chrysotile
08	3 <sup>rd</sup> floor-roof penthouse HVAC Unit FA10	Brown woven pipe wrap located on the 2 interior sections of pipe that are inside the unit	NA/PS
09	3 <sup>rd</sup> floor-roof penthouse HVAC Unit FA10	Brown woven pipe wrap located on the 2 interior sections of pipe that are inside the unit	NA/PS

NA/PVA Not analyzed/positive via inseparable association with a confirmed positive ACM NA/PS Not analyzed/positive stop, homogeneous to sample proven to contain asbestos

ND<1% Non-detected, less than 1% NAD No asbestos detected

+ Although found to be negative by analysis, material is homogeneous to a determined ACM and therefore must be considered positive

NOB material; result confirmed by TEM analyses
 Quantified by PLM Point Counting techniques

## TABLE 2 IDENTIFIED ASBESTOS CONTAINING MATERIALS (>1%) 18-20 TRINITY STREET HARTFORD, CONNECTIGUT

Material	Sampled- Assumed (mo/yr)	General Location	NESHAP Category	AHERA Category	Estimated Quantity
Brown woven pipe wrap	Sampled 11/05	4 <sup>th</sup> floor south wing mechanical room (HVAC Unit FA8)	Category I Non-friable	Thermal System Insulation	12 LF
Brown woven pipe wrap	Sampled 11/05	3 <sup>rd</sup> floor roof penthouse (HVAC Unit FA10)	Category I Non-friable	Thermal System Insulation	12 LF
Brown woven pipe wrap	Assumed 11/05	4 <sup>th</sup> floor north wing mechanical room (HVAC Units FA6 and FA7)	Category I Non-friable	Thermal System Insulation	12 LF

AHERA Categories = thermal system insulation (TSI), surfacing material or miscellaneous NESHAP Categories = friable, category I non-friable or category II non-friable Friable = crumbled, pulverized or reduced to powder by hand pressure when dry Category I Non-friable = packings, gaskets, resilient floor covering and asphalt roofing Category II Non-friable = all non-friable that is not Category I

<sup>\*</sup> Roof tars have been completely exempted from OSHA Asbestos regulations and, as a Category I Non-friable material, do not need to be removed from a structure prior to renovation/demolition under EPA Asbestos NESHAP regulations and, so long as the materials are exterior to a structure and will remain Category I Non-friable materials during renovation/demolition, are not covered under the CTDPH Asbestos Abatement standards. In addition, as Category I Non-friable materials, the roof tars do not need to be disposed of as asbestos waste under the EPA Asbestos NESHAP regulations; however, the CTDEP special waste regulations would not allow the material to be disposed of as general construction waste within the State of Connecticut. Disposal of the roof tars as general construction waste (so long as the materials are not rendered into a state which would define them as regulated asbestos-containing materials (RACM), i.e., friable) is, however, allowed in other states such as Massachusetts.

## TABLE 3 CONFIRMED NON-ASBESTOS CONTAINING MATERIALS 18-20 TRINITY STREET HARTFORD, CONNECTICUT

Material	General Location
Brown corrugated pipe wrap	4 <sup>th</sup> floor north mechanical room HVAC Units FA6 and FA7

<sup>\*</sup> There was no visible suspect ACM material in the 1st floor north and south mechanical rooms

APPENDIX A
SITE SKETCH

PROJECT NO. 43500 - 2840 - 00001 DATE 11/2/05 BY J. Smith Customer-Focused Solutions SUBJECT 18-20 Trivity St. CHK'D 1st Stop- 4th Floor South Mech Run (Samples 1-3) to zortal 2" dianeter pipes with weren insulation 2nd stop - 4th Florr North Mech Run (Samples 4-6)

3" long sections of 1" diameter pipe coming out of the Front of the units, with

a paper like wrop. Front of HVAZ unit FAG Front of HVAC unit FAZ Assumed that interior has weren pipe may similar to FA10 3rd stor - 1st Floor south much Room \* no visible suspect material on units FAY/FA5 4th step 1st Floor North mech Room \* no visible suspect makeral on wits 2/3 5th Stop- 3rd Flour Roof Peuthouse (Samples 7-9) 2" d'ameter infernet gipe with worker in solation. There is no insulation on 3" exterior section a (7,8) 0 Front of HUAC Unit FAIO

SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_\_

## APPENDIX B


LABORATORY AND INSPECTOR ACCREDITATIONS

## State of Connecticut, Department of Fullic Health Approved Environmental Laboratory

THIS IS TO CERTIFY THAT THE LABORATORY DESCRIBED BELOW HAS BEEN APPROVED BY THE STATE DEPARTMENT OF PUBLIC HEALTH PURSUANT TO APPLICABLE PROVISIONS OF THE PUBLIC HEALTH CODE AND GENERAL STATUTES OF CONNECTICUT, FOR MAKING THE EXAMINATIONS, DETERMINATIONS OR TESTS SPECIFIED BELOW WHICH HAVE BEEN AUTHORIZED IN WRITING BY THAT DEPARTMENT.

## TRC ENVIRONMENTAL CORPORATION

LOCATED AT 5	5 Waterside Crossing	NI NI	Windsor, CT 06095
AND REGISTERED IN THE NAME OF	JO AP	Henry Laliberte	
THIS CERTIFICATE IS ISSUED IN THE NAME OF BY THE REGISTERED OWNER/AUTHORIZED AGAPPROVAL AS FOLLOWS:	in the name of authorized agent to be	Henry Laliberte IN CHARGE OF THE LABORA	THIS CERTIFICATE IS ISSUED IN THE NAME OF BE IN CHARGE OF THE LABORATORY WORK COVERED BY THIS CERTIFICATE OF APPROVAL AS FOLLOWS:
	<b>V</b> m	AIR-FIBER COUNTING BULK IDENTIFICATION	
	SEE COMPUTER PRI	SEE COMPUTER PRINT-OUT FOR SPECIFIC TESTS APPROVED	TESTS APPROVED
THIS CERTIFICATE EXPIRES	December 31, 2005	AND IS REVOCABLE FOR	and is revocable for cause by the state department of public he
DATED AT HABTEORD CONNECTICITY THIS	CTICITY THIS	30th DAY	DAY OF DECEMBER, 2003




PH- 0426

Ellen J. Glaschinsti

IC HEALTH

DIRECTOR, DIVISION OF ENVIRONMENTAL HEALTH



# Certificate of Accreditation to ISO/IEC 17025:1999

NVLAP LAB CODE: 101424-0

## TRC Environmental Corporation

Windsor, CT

is recognized by the National Voluntary Laboratory Accreditation Program for conformance with criteria set forth in Accreditation is granted for specific services, listed on the Scope of Accreditation, for: NIST Handbook 150:2001 and all requirements of ISO/IEC Guide 17025:1999.

## BULK ASBESTOS FIBER ANALYSIS

2005-07-01 through 2006-06-30

Effective dates



1 pa. P. Wal

For the National Institute of Standards and Technology



HELP | Conne

HOME

WELCOME

**BUSINESS CENTER** 

VERIFY LICENSE

▶ QUICK CONTACTS

PHYSICIAN PROFILE

## Health Care or Environmental Health **Professional's License Status**

This site is part of CT-clic.com, the Connecticut Licensing Info Center, that links to all YOUR State licensing and registration needs.

Note: Requests for copies of documents related to past disciplinary action for professions other than physicians may be emailed as such documents are not currently available via this web site. Please include your name and telephone number on any request.

**License Type:** 

Asbestos Consultant - Inspector

License Number: 000621

Name:

SMITH, JACOB C

**Expiration Date: 1/31/2006** 

**Granted Date:** 

License Name:

6/1/2005

**License Status:** 

Jacob C. Smith

Current

Disciplinary

None

Action:

Questions

E-mail webmaster.dph@po.state.ct.us or call (860) 509-7603 Return to DPH Licensure/Renewal Page

For Business Registry Questions? Contact Smart or call 1-800-392-2122.

State of Connecticut Disclaimer and Privacy Policy. Copyright @ 2000 State of Connecticut. Universal Website Accessibility Policy applies. For comments about this site contact the webmaster

## CERTIFICATE OF ACHIEVEMENT

This certifies that

## Jacob Smith

has successfully completed the

Asbestos Accreditation Under TSCA Title II 24 Hour Asbestos Site Inspector Training 40 CFR Part 763

conducted by

West Springfield, MA 01089 73 William Franks Drive ATC Associates Inc. (413) 781-0070

Charal Mulies

Principal Instructor

February 9-11, 2005 Date of Course

February 11, 2006 Expiration Date

February 11, 2005

Dregoy A- Morac

Examination Date

## **APPENDIX C**

ASBESTOS BULK SAMPLE CHAIN OF CUSTODY FORMS

5 WATERSIDE CROSSING WINDSOR, CONNECTICUT 06095 TELEPHONE (860) 298-9692 FAX (860) 298-6399 Customer-Focused Solutions

## ASBESTOS BULK SAMPLING CHAIN OF CUSTODY

FAX (860) 298-6399					LAB ID #.	X453		
PROJECT NUMBER			PROJECT NAME		TUR	TURNAROUND :	TIME	
45500-2840-0001			18-20 Town to st - DOW	PARAMETERS	PLM: X 24hr	48hr	3day	Sday
		1			TEM: X 24hr	48hr	3day	Sday
INSPECTOR: (SIGNATURE)	(E)		rOP) 198.1 duction)	198'4 nl vakek				
FIELD SAMPLE NUMBER	TIME	COMP THE	SAMPLE LOCATION PLM EPA 600/R PLM EPA 600/R PLM STAVING TO	(IR PLM SERIES TEM UY NOB THAT YOUR TOUT COUR ANALYZE BY L		MATERIAL		
01 11/2/05	PM		x 44 Flor- Soth Mah RM x		Workn Pire insulation	· ·	- Unit PAB	
20	-		<i>x</i>	-		•		_
03			×					
40			X 44 Floor - North Mech Rm X		Commated Pipe word	1 .	- Unit FA	4
50	-		x   x		1) /	1	i	
70			<u> </u>		Converted Pipe Wron-		UNY FAG	ی
01	-		X 3rd Flor - Roof Porthouse X		Woven pipe	4	+	FA10
08			× ×		4			
- 40	7		X			_		
							٠	•
Relinquished by: (Signature)		Date: 11/2/05	Received by: (Signature) 0900	Relinquished by: (Signature)	Date:	Received by: (Signature)	ignature)	
Orinted) Jorcolo: Sin. H		Time: (600	Mauren Cr		Time:	(Printed)		
Remarks:								

## APPENDIX D PLM LABORATORY ANALYSIS DATA

## TRC ENVIRONMENTAL CORPORATION

**Environmental Chemistry Laboratory** 21 Griffin Road North Windsor, CT 06095 (860) 298-6308

## **BULK ASBESTOS ANALYSIS REPORT**

CLIENT:

CT Department of Public Works

Site:

18-20 Trinity Street

Lab Log #:

31453

Project #:

43500-2840-00001

Date Received:

11/03/05

Date Analyzed:

11/03/05

## RESULTS

Sample No.	Color	Homogeneous	Multi- Layered	Layer No.	Other Matrix Mat'ls	Asbestos %	Asbestos Type
01	Brown	Yes	No	·	40% cellulose	40%	Chrysotile
02						NA/PS	Sin-Mai
03			<del></del>			NA/PS	
04	Brown	Yes	No		90% cellulose	ND<1%	None
05	Black/Brown	Yes	No	**	90% cellulose	ND<1%	None
06	Brown	Yes	No		90% cellulose	ND<1%	None
07	Black/White	Yes	No			80%	Chrysotile
08		100				NA/PS	·
09					** '	NA/PS	

NA/PS- Not Analyzed/Positive Stop

Reporting limit- asbestos present at 1%

ND<1% - asbestos was not detected

Trace- asbestos was observed at level of less than 1%

Note: Polarized-light microscopy is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. In those cases, negative results must be confirmed by quantitative transmission electron microscopy.

The Laboratory at TRC follows the EPA's Interim Method for the Determination of Asbestos in Bulk Insulation (1982), and the EPA recommended Method for the Determination of Asbestos in Bulk Building Materials (EPA/600/R-93/116), July 1993, R.L. Perkins and B.W. Harvey which utilizes polarized light microscopy (PLM). Our analysts have completed an accredited course in asbestos identification. TRC's Laboratory is accredited under the National Voluntary Laboratory Accreditation Program (NVLAP), for Bulk Asbestos Fiber Analysis, NVLAP Code 18/A01, effective through June 30, 2006. TRC is an American Industrial Hygiene Association (AIHA) accredited lab for PLM effective through December 1, 2005. Asbestos content is determined by visual estimate unless otherwise indicated. Quality Control is performed in-house on at least 10% of samples and the QC data related to the samples is available upon written request from the client.

This report shall not be reproduced, except in full, without the written approval of TRC. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. This report relates only to the items tested.

Analyst:

Kathleen Williamson

QC Analyst:

Kathleen Williamson

Reviewed by:

Laboratory Analyst

Approved

Hong J. Saliberte

Henry J. Laliberte

Signatory:

Laboratory Manager

Date Issued: