

Civil

Structural

Study for Outside Air Quantity 25 Sigourney Street Hartford, Connecticut

Mechanical

Final Report

August 21, 2006

Electrical

Technology

State of Connecticut
Department of Public Works
Project Number BI-2B-033 J

BVH Project Number 21-06-056

Lighting Design

Commissioning

Special Services

50 Griffin Road South Bloomfield, CT 06002 T: 860-286-9171 F: 860-242-0236 start@bvhis.com www.bvhis.com



Table of Contents

| 1. | Intro | oduction | |
|----|-------|---|----|
| 2. | Revi | ew of Outside Air Quantity | , |
| 3. | Outs | ide Air Moisture | |
| 4. | Air I | Handling Unit Condensate Drainage | , |
| 5. | Air S | Systems Replacement Scope of Work | • |
| | 5.1. | Air Handling Unit Replacement | 5 |
| | 5.2. | Replacement of VAV Boxes | (|
| | 5.3. | New Secondary Ductwork | |
| 6. | Cost | Estimates | |
| | 6.1. | Rebalancing of Outside Air Quantity | 10 |
| | 6.2. | Dehumidification Unit | 10 |
| | 6.3. | Air Handling Unit Replacement (per unit) | 11 |
| | 6.4. | VAV Box Replacement (per typical 30,000 square foot floor – floors 7-19) | |
| | 6.5. | Secondary Ductwork Replacement (per typical 30,000 square foot floor – floors 7-19) | |
| 7. | Conc | lusion and Recommendations | 14 |
| | | | |

Appendix A – Wing's Testing and Balancing Report dated June 21, 2006

Appendix B - Fan Data Related to Appendix A

Appendix C – Excerpts from Wing's Testing and Balancing Report dated January 17, 2005



1. INTRODUCTION

BVH Integrated Services, Inc. was commissioned to investigate various aspects of the HVAC systems at 25 Sigourney Street in Hartford, Connecticut. The building is a 20 year old, 420,000 square foot high-rise office building that has been the subject of various indoor air quality investigations in the past. A report by Turner Building Science, LLC from December 2005 noted that the building HVAC systems were bringing in more outside air than necessary thus causing high humidity in the occupied space and ductwork during high humidity days. The purpose of this report is to determine if it is possible to reduce the amount of outside air delivered to the building while maintaining positive pressurization. A previous project corrected outside air infiltration and stack effect.

This study encompasses many aspects of the building's HVAC systems. The scope of the project is:

- Review existing outside air quantities delivered to building spaces and compare to outside air required based on current occupancy and assumed maximum capacity.
- Determine if it is possible to reduce outside air quantities in order to reduce moisture within ductwork and spaces while maintaining building pressurization.
- Provide scope and cost estimate for a dehumidification system for outside air if available outside air reduction is insufficient to reduce humidity levels.
- Assess condition of drain pans in existing air handling units throughout the building.
- Provide schematic cost estimate for replacement of existing air handling units, fiberglass ductwork, and VAV boxes including all costs such as ceiling removal and replacement.
- Provide a budget estimate for all recommended work.

The building is a 20 story mixed use office building. The building's mechanical systems are typical of speculative office buildings built in the same era. Each typical office floor is approximately 30,000 square feet with a north and south mechanical room on each typical floor. Each mechanical room has a variable volume air handling unit with hot and chilled water coils. Air is distributed to the floors to terminal VAV boxes with pneumatic controls. The air handling units and all head-end systems are controlled by direct digital controls (DDC).

Outside air is delivered to two shafts by two separate outside air fans at the penthouse level and distributed to each mechanical room. Outside air is mixed with return air within the mechanical room, which acts as a mixed air plenum. Each floor is equipped with an airflow station on the outside air duct which modulates a damper to maintain the specified outside air quantity on each floor. The airflow stations and dampers on the outside air deliver even ventilation throughout the building and equally pressurize each floor. A relief air shaft allows excess air on each floor (when more outside air is introduced on a floor than exhausted) to relieve, through gravity, to the roof level.



2. REVIEW OF OUTSIDE AIR QUANTITY

The December 2005 report by Turner Building Science, LLC noted that existing outside air quantities exceed ASHRAE recommendations for minimum outside air by "2-3 times". Current building code and the building code at the time of the controls upgrade project dictates the amount of outside air required per occupant and dictates the number of occupants that must be used for the design.

Per code, design occupancy for each 30,000 (approximate) square foot floor plate of office is seven occupants per 1,000 square feet, which equates to 210 occupants per typical floor. The code outside air requirement is 20 cfm per person. This equates to 4,200 cfm per floor, or 2,100 cfm per air handling unit. The current outside air setting on each typical air handling unit is 2,200 cfm. To calculate outside air for the entire building, 420,000 square feet equates to an occupancy of 2,940 people. At 20 cfm/person, 58,800 cfm is required for minimum ventilation in the building.

The two existing outside air fans were designed to deliver 49,000 cfm each for a total of 98,000 cfm. The original design included provisions for air-side economizer operation; the minimum outside air delivery was 61,300 cfm total for both fans and controls allowed the fans to increase in speed to deliver 98,000 cfm in economizer. According to recent testing by Wing's Testing and Balancing (July 15 2004), the outside air fans deliver 60,713 cfm at minimum outside air and 81,480 cfm at economizer operation (maximum air delivery).

The existing ventilation meets current code requirements. Each floor receives about 20 percent outside air at peak design conditions which is typical of office buildings and exceeds minimum requirements by 3.3 percent, which is within standard balancing tolerances.

According to operations staff, the actual peak occupancy is not expected to exceed 1,500 people. Using this occupancy as a basis for design, outside air could, theoretically, be reduced to 30,000 cfm for the entire building. Any reduction in outside air quantities should be reviewed with the authority having jurisdiction; adequate proof of occupancy rates well below code requirements will be required in order to reduce outside air quantities to this level.

In addition to providing ventilation for building occupants, the outside air also pressurizes each floor to prevent potential moisture infiltration through the building envelope. Pressurization controls on each floor modulate the relief air damper on the floor in order to maintain the pressurization setpoint. Any reduction in outside air will require a reduction in the pressurization setpoint.

The current exhaust air from the building is approximately 26,300 cfm, compared to an outside air delivery of approximately 60,713 cfm. The excess air for pressurization is 34,413 cfm. Theoretically, the outside air quantity could be reduced to 30,000 cfm without producing a negative pressure and still provide enough ventilation for the assumed peak occupancy of 1,500 people. Due to the height of the building, however, equalizing the outside air and the exhaust air would likely produce a positive pressure on upper floors and a negative pressure on lower floors. Each typical floor has about 4,400 cfm of outside air at minimum conditions and 1,200 cfm exhaust. The



positive pressurization for each floor is about 3,200 cfm (note, this is a general statement and varies from floor to floor), which is removed through the relief air shaft.

The existing pressurization controls are set to maintain 0.20 inches of water differential pressure between the interior space and atmospheric pressure. The controls modulate the relief dampers on each floor to maintain the setpoint on each floor. Observations of the existing controls showed that the measured floor pressurization varied from floor to floor but, on average, was sufficiently positive. The floor static setpoint is high and can be reduced to 0.10 inches, a number that is used for healthcare and clean room pressurization applications. Reducing this number may help to reduce the pressure on the floors that are pressurized above setpoint and increase the pressure on floors where pressure is below the setpoint.

A motorized damper at the top of the relief shaft controls the total building pressurization. The control system is set up to utilize an average of all of the floor pressures. The total building static pressure setpoint at the controls was set at 0.05 inches and was observed to be measuring between 0.03 and 0.10 inches. The setpoint for this control should match the setpoint for the individual floor controls. It was observed that the relief damper modulated rapidly and appeared to need some fine tuning.

Utilizing the current relationship of pressure and flow rate differential, it may be possible to reduce outside air flow and maintain 0.10 inches positive pressure on each floor. Based on current relationships, the total outside air quantity could be reduced by about 30 percent. This would reduce the differential cfm between outside air and exhaust air from 34,413 cfm to 24,100 cfm, reducing total outside air at minimum conditions to 50,400 cfm. We would not recommend reducing airflow any lower than this number. This reduction in airflow should be done proportionally at each floor and should be performed by a commissioning agent, a certified testing and balancing agency, and a control technician. The reduction should be done by trial and error to assure that positive pressurization is maintained. If pressurization cannot be maintained at the minimum airflow prescribed in this report, then the airflow should be increased until the pressurization is maintained. The building Owner should approach the authority having jurisdiction with population data to assure that a reduction in outside air below code requirements is acceptable.

3. OUTSIDE AIR MOISTURE

The Turner Building Science Report noted that the existing HVAC system brings in "large quantities of raw, unconditioned outside air," which may be responsible for mold growth in the air handling units and in the distribution ductwork. As discussed in the previous section, the amount of outside air is typical of an office building and meets current code requirements. The physical amount of outside air delivered to the building does not create any abnormal moisture issues above and beyond typical HVAC systems for this building type. The delivery method could create moisture infiltration through the outside air shaft walls and, potentially, higher than normal moisture levels in the mechanical room. If the systems are operating as designed, the mechanical room will be under a negative pressure which will prevent any moisture infiltration to the occupied space and if the outside air shafts are properly sealed, there is no route for moisture to pass between the shaft and the occupied space. The outside air shafts are reported to be in good condition.



The outside air is mixed with return air in the mechanical room (which acts as a mixing plenum) and drawn into the air handling unit. Each air handling unit is equipped with a chilled water cooling coil which provides moisture removal from the mixed air stream.

As described in the previous section, the air systems have a limited economizer which allows additional outside air into the mechanical room plenum. The economizer controls are based on enthalpy, which takes into account both moisture and temperature. The controls will not allow the system, for example, to go into economizer operation on a very humid day with a moderate outside air temperature in the economizer temperature range.

The 0.4 percent design dehumidification day in Hartford, per ASHRAE climatic data, is 81 deg. F dry bulb/75 deg. F wet bulb (approximately 76% RH). This condition would be the basis of design for a dehumidification system; it's considered worst case for moisture (on average, only 0.4% of the year would have more moisture in the outside air than this). During these conditions, the outside air fans would be delivering minimum outside air.

To take, for example, the mechanical room with the highest amount of minimum outside air after balancing was performed on July 15, 2004 by Wing's Testing and Balancing, was in mechanical room 14N. The minimum outside air to this unit was balanced at 2,333 cfm. The design airflow for this unit is 14,500 cfm. It is reasonable to assume that the zone load would not be at full load under these conditions – taking an 80 percent diversity factor, the total supply air would be 11,600 cfm. The outside air percentage is around 20 percent at this condition. Assuming a return

air condition of 78 deg. F, 50% RH, the mixed air condition would be 79 deg. F dry bulb/67.5 deg. F wet bulb, which has slightly more moisture than the original coil design entering air condition of 79/66. The cooling coil would still remove moisture from the air in this condition, but the relative humidity may creep up slowly in the space if the coil was unable to remove all the moisture in the air. Relative humidity sensors could be installed on different floors to monitor humidity with the existing system operation to see if this is the case.

The TBS report also noted that moisture levels in the building would promote mold growth if the outside air had a high relative humidity and the cooling coils were not in operation. Due to the low amounts of outside air, there are no conditions where the humidity ratio of the outside air is greater than the humidity ratio of the inside air where the cooling coil wouldn't be active. It is also unlikely that the surface temperature inside the air handling unit would fall below the dewpoint of the discharge air and cause condensation on the inside surfaces of the unit, as long as the outside air is off during



Figure 1 - Air handling unit with failing insulation

unoccupied periods (which is the current control scheme). This may have been a problem in the past before the recent controls upgrade. Condensation could occur regularly during the summer on the outside of the casing due to warm mixed air in the mechanical room in areas where the casing



insulation within the air handling unit had worn away or fallen off. The existing internal insulation on all units is being replaced and should be complete at the time of the issue of this report.

A likely cause of moisture penetration on the former internal casing of the air handling unit and on fiberglass liner in the ductwork just downstream of the fan is moisture carryover due to a high velocity at the cooling coil. As the moisture condenses on the cooling coil, it drips down the coil and collects in the drain pan. As the velocity increases at the coil, the likelihood that the drops of condensation will be pulled into the airstream increases. Standard design typically limits the face velocity at the coil to 500-550 feet per minute. According to the most recent test report (July 14. 2005 – Wing's Testing and Balancing), the velocity at design conditions was 760 feet per minute on the typical floors. This velocity is not unusual with limited mechanical space, which is the case with this building.

Moisture carryover can be reduced with larger air handling units (or larger cooling coil face area), by installing moisture eliminators downstream of the cooling coil, or dehumidifying the outside air. The first two options require new air handling equipment in limited mechanical space. The dehumidification unit would have to be sized for economizer operation at 100,000 cfm (to match the original design and maximize the energy-saving capabilities of the system, which is limited by the existing outside air shaft sizes). A dehumidification unit would also reduce the possibility of moisture migration through the walls of the outside air shafts.

The existing mechanical rooms that house the outside air fans do not have enough space to accommodate a dehumidification unit, so a single unit would have to be placed on the roof of the penthouse and ducted over to the two existing shafts. A new pair of chilled and hot water risers originating from the service entrance of the thermal utilities in the basement would be required to serve the dehumidification unit. Significant structural modifications would likely be required in order support the unit on the roof; the scope of this work is unknown at this time.

Placement of the dehumidification unit would be crucial due to the proximity of the cooling tower discharge, which would be at the same elevation as the new intake location on the roof of the penthouse. If this option were to be pursued, a wind study using tracer gases should be commissioned to assure that the cooling tower plume will not be entrained into the outside air intake. It should be noted that the current outside air intake locations are sufficiently separated from the cooling tower plume and are located below the cooling tower discharge.

As an option, a heat recovery wheel could be added to the system to recapture heat from the toilet exhaust, as suggested in the TBS report. This would require a new toilet exhaust fan and additional ductwork from the fan to the dehumidification unit. Pricing for dehumidification options can be found in Section 6.

Another way to minimize moisture in the space is to have an unoccupied set-up temperature setpoint that will allow the individual air handling units to cycle on without any outside air to cool the space so that space temperatures and humidity levels don't become excessive over long periods of unoccupied periods. A standard set-up setpoint is 85 degrees. Control can also be set on relative humidity levels; the existing control system is not equipped with relative humidity sensors on each floor.



4. AIR HANDLING UNIT CONDENSATE DRAINAGE

The existing air handling units utilize the floor of the fan section to drain condensate. With the exception of the 19th floor unit (in the penthouse mechanical room), each unit was only drained from one side. The opposite sides of the units were inaccessible and the drain connection was capped. It was not possible to see if all of the bases were sloped to one side, but the floors of the units were not uniformly flat due to their age; the surfaces lent themselves to condensate ponding.

During the time of our survey, the units were in the process of being cleaned and re-insulated and the drain section was being coated with an anti-microbial coating. This process will be complete for all air handling units by the time the final report is submitted. Finished units were clean and in better condition than units that had not been serviced. Internal fiberglass insulation was loose on the unfinished units and the floors of the units in the fan section were corroded and in poor condition in most cases.

According to the manufacturer of the existing units (Trane), the casing is structural and there is no way to cut a new drain pan in under the existing cooling coil. It may be possible to fabricate a stainless steel drain pan and slide it under the existing coil (there is about 2 inches of clearance between the bottom of the coil and the floor of the unit), but access is limited and proper attachment would be difficult. In addition, there is not enough vertical clearance to properly pitch the drain pan to one side of the unit.

The condensate traps appeared to be properly

sized throughout. Condensate discharge piping on many units needed to be adequately secured to the floor to maintain pitch.




Figure 2 - Existing drain pan before refurbishment



Figure 3 - Condensate drain piping pitched away from drain




Figure 4 - Refurbished air handling unit floor



The new coating appears to have improved the condition of the floor, but proper pitch inside the unit cannot be verified or corrected because of the drainage arrangement. Since the unit is equipped with two drain connections and only one is connected on most units, it is possible that the floor is not draining properly in all cases. As part of preventative maintenance, pitch of discharge piping should be examined periodically and corrected, if necessary. Additionally, the fan section bases should be examined periodically during high humidity days to assure proper drainage. The units are nearing the end of their expected useful life and should be considered for replacement with units equipped with stainless steel IAQ drain pans.

5. AIR SYSTEMS REPLACEMENT SCOPE OF WORK

The scope of work described by operations staff for replacement of existing HVAC systems includes the replacement of existing air handling units, replacement of existing VAV boxes, and replacement of existing secondary ductwork (fiberglass duct downstream of VAV boxes). The scope for these improvements will be broken into three components so that work can be prioritized.

5.1. Air Handling Unit Replacement

Scope of work (typical for each mechanical room):

- Remove existing air handling unit, supply ductwork within the mechanical room, existing cooling and heating coil connections, supports, electrical connections, controls, and all associated accessories.
- Provide a new air handling unit sized for approximately 500 feet per minute at design airflow with chilled water cooling coil and hot water heating coil.
- Unit shall be equipped with a stainless steel IAQ drain pan with single or double-sided connections depending on accessibility.
- Supply fan motor shall be premium efficient and meet or exceed the more stringent of code requirements or Northeast Utilities' Energy Conscious Construction program.
- Unit shall be equipped with 85% efficient filters with 30% pre-filters.
- Reuse existing control valves and sensing devices.
- Provide new supply ductwork within mechanical room with acoustic lining that meets UL and ASTM standards for erosion, moisture, fungi and bacteria resistance.
- Reuse existing variable frequency drives.
- Provide new condensate drain piping and properly-sized trap to existing floor drain.



5.2. Replacement of VAV Boxes

Typical scope of work:

- Remove existing VAV boxes and associated hangers and supports.
- Remove existing hot water piping to boxes with hot water reheat coils cap piping and save for reuse.
- Remove existing pneumatic controls back to source.
- Provide new supply ductwork within mechanical room with acoustic lining that meets UL and ASTM standards for erosion, moisture, fungi and bacteria resistance.
- Reconnect hot water to boxes with hot water coils; provide new DDC control valve and all new trim.
- Replace existing zone thermostat with new DDC temperature sensor.
- Provide box with DDC controls tied into existing building management system.
- Provide new power to fan-powered VAV boxes.

5.3. New Secondary Ductwork

Typical scope of work:

- Remove all existing secondary ductwork between VAV boxes and diffusers.
- Provide all new galvanized steel ductwork between VAV boxes and diffusers.
- Provide all new flexible ductwork for runouts to diffusers in accessible ceiling areas (maximum flexible duct run of 6 feet).
- Provide new volume dampers at all duct takeoffs.
- Line first 10 feet of ductwork downstream of VAV boxes with acoustic lining that meets UL and ASTM standards for erosion, moisture, fungi and bacteria resistance.
- Insulate all supply ductwork with 1.5 inches fiberglass insulation with vapor barrier.
- Remove existing ceilings and install new ceilings.
- Remove existing light fixtures and ceiling devices and save for reuse.



6. COST ESTIMATES

The following is an assessment of the estimated costs associated with the recommendations made in the previous sections. Note that costs do not include any provisions for escalation and are conceptual level cost estimates for budgetary purposes only. All construction work is assumed to be on premium time. Estimates include (where noted) 35 percent for soft costs and do not include costs associated with the impact on operations or costs for cleaning upon completion.

6.1. Rebalancing of Outside Air Quantity, Commissioning, and ATC Programming Adjustments

| Item | Estimated Cost |
|---------------------------------------|----------------|
| Commissioning, Testing, and Balancing | \$24,000 |
| Control Technician | \$ 4,000 |
| Total | \$28,000 |

6.2. Dehumidification Unit

Base Unit (No Heat Recovery):

| Item | Estimated Cost |
|---|----------------|
| Dehumidification Unit | \$250,000 |
| Rigging and Installation | \$180,000 |
| New Chilled and Hot Water Risers (assuming straight path up through building) | \$125,000 |
| Roof-Mounted Ductwork (insulated) | \$ 50,000 |
| Demolition | \$ 25,000 |
| Controls | \$ 20,000 |
| Testing and Balancing | \$ 4,000 |
| Electrical | \$ 20,000 |
| Structural Modifications | \$125,000 |
| General Conditions, Contractor OH&P | \$160,000 |
| Soft Costs | \$336,000 |
| Total | \$1,295,000 |



Alternate Unit (With Heat Recovery):

| Item | Estimated Cost | | | | |
|--|----------------|--|--|--|--|
| Base Cost | \$1,295,000 | | | | |
| Heat Recovery Section | \$ 250,000 | | | | |
| Additional Ductwork, Exhaust Fan | \$ 35,000 | | | | |
| Additional Balancing | \$ 1,500 | | | | |
| Additional Controls | \$ 15,000 | | | | |
| Additional Electrical | \$ 8,000 | | | | |
| Additional General Conditions, Contractor OH&P | \$ 62,000 | | | | |
| Additional Soft Costs | \$ 130,000 | | | | |
| Total | \$1,796,500 | | | | |

6.3. Air Handling Unit Replacement

| Item | Estimated Cost (Each Unit, Floors 6S, 7-19) | Estimated Cost (Each Unit, Lobby and 6N) | Estimated Cost (Floor 20) |
|-------------------------------------|--|---|---------------------------------|
| Air Handling Unit | \$ 25,000 | \$ 19,000 | \$ 12,000 |
| Installation and Rigging | \$ 15,000 | \$ 15,000 | \$ 20,000 |
| Piping and Insulation | \$ 7,000 | \$ 7,000 | \$ 7,000 |
| Ductwork and Insulation | \$ 10,000 | \$ 9,000 | \$ 7,500 |
| Controls | \$ 8,000 | \$ 8,000 | \$ 8,000 |
| Demolition | \$ 9,000 | \$ 9,000 | \$ 9,000 |
| Testing and Balancing | \$ 2,000 | \$ 2,000 | \$ 2,000 |
| Electrical Power | \$ 6,000 | \$ 6,000 | \$ 6,000 |
| Fire Alarm Modifications | \$ 6,000 | \$ 6,000 | \$ 6,000 |
| General Conditions, Contractor OH&P | \$ 18,000 | \$ 16,000 | \$ 15,500 |
| Soft Costs | \$ 37,000 | \$ 34,000 | \$ 32,500 |
| Total (each unit) | \$143,000 | \$131,000 | \$125,500 |
| Total (all 29 units) | \$3,831,500 | | |



6.4. VAV Box Replacement

| Item | Estimated Cost (Each Floor, Floors 7-19) | Estimated Cost (Lobby and 6 th Floor) | Estimated Cost (Floor 20) |
|--|---|--|---------------------------------|
| VAV Boxes (assuming 800 SF/zone) | \$110,000 | \$115,000 | \$ 20,000 |
| Piping Reconnections and Insulation | \$ 25,000 | \$ 27,000 | \$ 5,000 |
| Ductwork Reconnections and Transitions | \$ 25,000 | \$ 27,000 | \$ 5,000 |
| Controls | \$115,000 | \$120,000 | \$ 22,000 |
| Testing and Balancing | \$ 8,000 | \$ 9,000 | \$ 1,500 |
| Demolition | \$ 15,000 | \$ 16,000 | \$ 2,000 |
| Electrical | \$ 20,000 | \$ 25,000 | \$ 5,000 |
| Ceiling Removal and Installation of New | \$ 30,000 | \$ 40,000 | \$ 5,000 |
| General Conditions, Contractor OH&P | \$ 70,000 | \$ 76,000 | \$ 13,100 |
| Soft Costs | \$146,000 | \$159,000 | \$ 27,500 |
| Total (per floor) | \$564,000 | \$614,000 | \$106,100 |
| Total (entire building) | \$7,488,000 | | |



6.5. Secondary Ductwork Replacement

| Item | Estimated Cost (Each Floor, Floors 7-19) | Estimated Cost (Lobby and 6 th Floor) | Estimated Cost (Floor 20) |
|---|---|--|---------------------------------|
| Demolition | \$ 35,000 | \$ 40,000 | \$ 8,000 |
| New Sheet Metal Ductwork | \$125,000 | \$135,000 | \$ 40,000 |
| Duct Accessories | \$ 45,000 | \$ 50,000 | \$ 8,000 |
| Duct Insulation and Lining | \$ 68,000 | \$ 74,000 | \$ 15,000 |
| Testing and Balancing | \$ 15,000 | \$ 18,000 | \$ 3,000 |
| Electrical Associated with Ceiling Work | \$ 75,000 | \$ 80,000 | \$ 15,000 |
| Ceiling Removal and Installation of New | \$180,000 | \$210,000 | \$ 30,000 |
| Allowance for Conflicts with Existing Utilities and Systems | \$ 15,000 | \$ 20,000 | \$ 5,000 |
| General Conditions, Contractor OH&P | \$112,000 | \$125,000 | \$ 25,000 |
| Soft Costs | \$235,000 | \$263,000 | \$ 52,000 |
| Total (per floor) | \$905,000 | \$1,015,000 | \$201,000 |
| Total (entire building) | \$12,076,000 | | <u> </u> |



7. CONCLUSION AND RECOMMENDATIONS

Based on the findings of this report, we recommend the following:

- Balance existing outside air quantity down to no lower than 50,400 cfm total for both outside air fans. This reduction in airflow should be done proportionally at each floor and should be performed by a commissioning agent, a certified testing and balancing agency, and a control technician. The building Owner should approach the authority having jurisdiction with population data to assure that a reduction in outside air below code requirements is acceptable. Once airflow is reduced, pressure readings should be taken to assure that all floors are positively pressurized. Where floors are not positively pressurized, minimum outside air should be increased until the floor is positive. Pressurization setpoints should be changed to 0.10 inches. Existing CO2 ventilation controls and economizer controls shall continue to operate under the current control scheme. As part of the scope of this work, the following additional items should be investigated and, if necessary, corrected:
 - ⇒ Confirm control sequences for pressurization and outside air match specified control sequences
 - ⇒ Pressurization control should be able to operate on high pressure, low pressure, or average pressure at the user interface
 - ⇒ Review existing control programming loop for building relief damper and tune to smooth operation and alleviate swings in building pressure
 - ⇒ Pneumatic relief dampers on each floor should be investigated to assure that they close tightly when controls command dampers closed
- Consider installation of new dehumidification unit for outside air delivery. Perform life cycle cost analysis to determine if heat recovery is a viable option. Perform modeling to assure that cooling tower plume is not drawn into new outside air intake location.
- Existing air handling units are approaching the end of their expected useful lives and should be replaced within 5 to 10 years. When units are replaced, they should be replaced with units that have a greater face area that will minimize the carryover of condensation from the cooling coil and are equipped with IAQ drain pans. If properly designed and installed, the new units will eliminate condensation issues that would otherwise be mitigated by the installation of a In lieu of installing the dehumidification unit on the roof, we dehumidification unit. recommend accelerating the replacement of the existing air handling units as this is a more cost effective way to deal with any moisture issues in the occupied space. The only part of the system that would be exposed to direct outside air would be the outside air intake shafts. The shafts are reported to be in good condition by building management. Ideally, units should be replaced on unoccupied floors to minimize cost and disruption. The existing duct system is a loop system that allows for one unit to feed a whole floor when the other is shut down. This arrangement provides about 50-60% of the total available capacity to the floor. This amount of capacity should be sufficient to provide adequate (though not perfect) conditioning during the winter and some of the shoulder seasons. Units should not be replaced on occupied floors



during the summer; one unit will not have enough capacity to keep the occupants comfortable on most summer days. Installation on an occupied floor would take about 2-3 weeks. If the floor was unoccupied, the work could be done in about 7-10 days since both units could be replaced at the same time.

- Initiate a preventative maintenance program to assure that all existing condensate drain piping is properly pitched and draining on existing units until new units are installed.
- Begin phased replacement of existing VAV boxes and secondary fiberglass ductwork. If feasible, VAV boxes and secondary ductwork should be replaced at the same time to minimize disruption and reduce overall cost. If not done at the same time, the VAV boxes should be replaced first, then secondary ductwork should be replaced. Ideally, the secondary ductwork should be replaced when floors are unoccupied to reduce cost and disruption. If work is done while floors are occupied, ceilings will have to be removed and reinstalled each night or weekend and much of the contractor's productive time will be spent on preparation before and reinstallation and cleaning after. Replacement of VAV boxes and secondary ductwork should be phased after the installation of new air handling units.

W:/2006/2106056/docs/21-06-056-R-JSC-2006-06-26-Final 25 Sigourney St Air Quantity Study.doc



Appendix A



94 No. Branford Rd., Branford, CT 06405 203-481-4988 Fax 203-488-5634

25 Sigourney Street Hartford, CT

B.V.H. Integrated Services Attn: Jeff Cichonski 50 Griffin Road South Bloomfield, CT 06002

June 21, 2006



94 No. Branford Rd., Branford, CT 06405 203-481-4988 Fax 203-488-5634

June 21, 2006

B.V.H. Integrated Services Attn: Jeff Cichonski 50 Griffin Road South Bloomfield, CT 06002

Re: 25 Sigourney Street, Hartford, CT

Dear Jeff:

Testing for the above referenced location has been completed. Fan totals for CEF-1 and 2, as well as Ref-1, could not be obtained by Velocity Pressure Traverse, and outlet summation would require further time and investigation. Total flows for the remainder of the fans requested are as listed on the following pages.

If you have any questions regarding the information provided, or if we can be of further assistance, please do not hesitate to call.

Very truly yours, Wing's Testing & Balancing Co., Inc.

John Flanagan

Certified TABB Technician #BB040033

CT SM-2 License 771

Name: John Flanagan
Stanp #: RB040033

issue Date: 09/20/2002

| | | EXHAU | ST FAN R | EPORT | | |
|----------------|-------------|---------------|--------------|-----------------|-------|-------------|
| PROJECT: | 25 SIGOURNE | Y STREET | | | DATE: | 6/7/06 |
| AREA SERVEL | | HARTFORD, CT | | | TECH: | J. FLANAGAN |
| | | | FAN DATA | | | |
| FAN NUM | BER | CEF-1 | CEF-2 | REF-1 | | |
| LOCATION | V | ROOF | ROOF | ROOF | | |
| AREA SEF | RVED | CAFETERIA | CAFETERIA | TOILETS | ļ | |
| MANUFAC | TURER | CENTRIMASTER | CENTRIMASTER | CENTRIMASTER | ļ | |
| MODEL O | | PUB256IU | PUB300IU | M#PN365N | | |
| TOTAL | DESIGN | N.L. | N.L. | 15600 | | |
| CFM | ACTUAL | (1) | (1) | (1) | | |
| FAN | DESIGN | N.L. | N.L. | N.L. | | <u> </u> |
| RPM | ACTUAL | 814 | 739 | 761 | | ļ |
| PULLEY | O.D. | 5 1/2" X 1" | 9" X 1" | 13 1/8"X1 3/16" | | |
| SUCTION | SP. | -1.15" (3) | -1.34" (3) | 627 (3) | | |
| | | | | | | |
| | | | | | | |
| | | | MOTOR DATA | T | | |
| MANUFAC | | MAGNETEC | MAGNETEC | CENTURY | | |
| MODEL N | UMBER | FRS182T | FRS184T | FR:S184T | | |
| MOTOR | DESIGN | N.L. | N.L. | N.L. | | |
| HP | ACTUAL | 3 | 5 | 5 | | |
| MOTOR F | RPM | 1740 | 1786 (2) | 1745 | | |
| VOLTAGE | PHASE | 460/3 | 460/3 | 460/3 | | |
| | DESIGN | 4.3 | 7.2 | 7.2 | | |
| MOTOR | ACT. LEG 1 | 2.3 | 4.5 | 7.4 | | |
| AMPS | ACT. LEG 2 | 2.5 | 4.7 | 7.6 | | |
| | ACT. LEG 3 | 2.1 | 4.1 | 7.5 | | |
| SHEAVE | | 3 1/4"X1 1/8" | 4" X 1 1/8" | 6 1/2"X1 1/8 | 11 | |
| BELTS-Q | TY/SIZE | 2/AP26 | 2/AP41 | 1/AX62 | | , |
| | POSITION | 1 | | | | |
| | | | REMARKS | | | |

⁽¹⁾ NO SUITABLE LOCATION FOR READING.

⁽²⁾ NAMEPLATE LISTING HAS BEEN SCRATCHED OFF.

⁽³⁾ SUCTION S.P. IS MEASURED BEFORE THE MOTORIZED BACKDRAFT DAMPER.

| PROJECT: | | JRNEY STR | | | E READI | 6/7/06 | | |
|--------------|------|-----------|-----|---------------|-------------|-----------|--------|---------------|
| AREA SERVED | | | | | TECH: | J. FLANAC | 2.4.61 | |
| TRAVERSE | DUCT | AREA | DES | IGN | CENTERLINE | | | NOTES |
| LOCATIONS | SIZE | SQ.FT | FPM | СFМ | STATIC PRES | | CFM | |
| DF-2 | | , | | | | | | |
| TLT'S P-6 | 10X8 | .56 | 714 | 400 | 30 | 824 | 461 | |
| DF-1 | | | | | | | | |
| TLT'S P-6 | 10X8 | .56 | 714 | 400 | 264 | 839 | 470 | (4) |
| DF-3 | | | | | 7-7-11-1 | | | |
| TLT'S P-2 | 10X7 | .486 | 617 | 300 | - 188 | 725 | 352 | |
| DF-4 | | | | | | | · · | |
| MAINT. P-2 | 6" Ø | .196 | 306 | 60 | 0.0 | <u></u> | 0 | (1,2,5) |
| DF-5 | | | | | | | | - |
| SHIPPING P-2 | 6X6 | .196 | 255 | 50 | | | | (2,3) |
| | | | | | | | | |
| | | | | | | | | |
| | | | | ·•· | | | | |
| | | | | | | | | |
| | | | | | | | | - |
| | | | | | | | 1 | |
| - | | | | . | : | | | |


⁽¹⁾ INLETS FOUND OPEN ENDED AND TAPED OFF.

⁽²⁾ FAN FOUND IN OFF POSITION.

⁽³⁾ FAN DOES NOT RUN.

⁴⁾ FAN NO LONGER SERVES TOILETS. CURRENTLY SERVICES KITCH. AREA. TOILETS TIED NTO CEF.

⁽⁵⁾ FAN WAS ORIGINALLY DESIGNED TO BE O.A. SUPPLY.





Appendix B

04:28

7/2002

Fig. 100 (1935)

9186820134

ACME ENGINEERING

02 PAGE


Sones and work the cibelle an enoun in


| Sirve I Sirve I | orm es 7 | On t | | eric | 4114 | nce | one The | ១៩ ៤ ខ្ន | | | | | | | | | 水 特學和 | | | | | |
|--------------------|--------------|--------------|----------|-----------------------------|-------------|----------------|----------------------|----------------------|------------------|----------------|------------------|----------------|------------------|---------------|--|--|----------|---------------------------------------|-----------|----------|------------|---------------------|
| EFRIE | | | | | | OFS | ÉPŮ | WE | NS | SI | il io | PH E | 500 | ĦΕ | | | | | | | 1 | n dan sa |
| KODEL | FAN: | MIN. XAM | | 0 | | .12 | | .25 | | .37 | | .50 | | .75 | 0" | 1.00 | 10" | 1.50 | ıa" | 2.00 | KO" | EST. CHIP WT. |
| 40. | ПРМ | SPEED | НР | СЕМ | анр | OFM | вкр | CFM* | вне | СРИ | BHP | CFM | эне | CITM | внр | GFM | BHP | PTM | BHP | CFM | ӨНР | |
| PN100F | 286 414 | 2246 3251 | ٧, | 4400 6460 | .08 .23 | 3430 5760 | .11 .28 | 8020 | .33 | 4110 | .36 | | | | | | | | | - | | 330 |
| PN30013 | 321 473 | 2521 2714 | V, | 5010 7380 | .11 .54 | 4100 6770 | .15 .40 | 2840 6140 | .17 | B490 | .51 | 46010 | .93 | | | | | | | | | 337 |
| PNJOOH | 9 5 0 | 3139 4310 | 3/, | 6230 8580 | ,20 .53 | 5500 8000 | .25 .60 | 4740 7530 | .30 .47 | 3640 8980 | .32 .73 | 6426 | .79 | 471D | .82 | | | | | | | 340 |
| P Naoo J | 438 604 | 3440 4743 | 1 | 5830 9420 | .27 .70 | 8170 8950 | .32 .78 | 5490 8470 | .38 .85 | 4720 7970 | .42 | 3990 7470 | A1 1.00 | 6300 | 1,10 | 3460 | .95 | | | | | 343 |
| PNOOK | 486 | 8817 | 11/1 | 7580 10450 | .36 .95 | 7000 10020 | 43 | 68 20 9590 | .49 | 5780 9150 | .54 1,21 | 4950 8710 | ,57 1.29 | 7780 | 1.43 | สรอง | 1.50 | | | | | 395 |
| PN300L | 670 545 | 5282 4280 | 7. | 6500 | .51 | 7970 | .58 | 7440 10970 | .65 | 6890 10580 | ,72 1.64 | 6311 00101 | .77 1.73 | 4520 8390 | .79 1.90 | 8649 | 2,05 | B470 | 2,00 | | | 361 |
| PN300M | 752 982 | 5908 5120 | 3 | 117 3 0 10170 | .88 | 11350 9730 | .96 | 9290 | 1.05 | 8840 | 0.13 | 82B0 | 1.21 | 7419 11100 | 1.34 | 6000 10380 | 1.38 | 8620 | - | | | 366 |
| PN365G | 843 248 | 23(B) | 1/2 | 12150 6250 | .14 | 17810 4710 | .18 | 12470 2590 | .19 | 12130 | | | 2.33 | 11100 | 7.02 | 10000 | 4.74 | 1000 | 1.70 | | | 445 |
| PN365H | 36! 286 | 3449 2733 | 7 | 9100 7210 | | 5860 | .26 | 7000 4390 | .29 | 5800 | | 4240 | .96 | | | | | <u> </u> | | | | 44.9 |
| | 41 <i>f</i> | 2819 2819 | <u> </u> | 18510 7440 | - | 9990 6120 | | 8650 4750 | .32 | 7780 | | 6700 | 38 | | <u> </u> | | | | | | <u></u> | 451 |
| PN365J | 445 358 | 4252 3373 | ļ | 11220 | .78 .40 | 10320 7800 | | 94BG | + | 9480 | رمضم يبيميا | 7740 3800 | 1.05 .52 | 5340 | 1,04 | | | | | - | | 483 |
| PNSSSK | 520 423 | 49 F8 | 17, | 13110 | | 12330 9720 | + | 11800 | + | 10900 7950 | - | 10200 6930 | 1,57 | 8600 | 1.68 | 6500 | 1.66 | P.E | F- 1 | | <u> </u> | 470 |
| PN865L | 571 | 5458 4854 | 2 | 14400 | 1.63 | 12700 | 1,70 | 13000 | 1.78 | 12330 10510 | 1.88 | 11690 9790 | | 10360 9100 | ·} | 8740 5850 | 2.22 | - | - | - | } | 484 |
| PN365M | 5D8 656 | 6588 | 3 | 16540 | 2.45 | 15920 | 2.54 | 15310 | 2.62 | 14720 | 2,72 | 13880 | 2.84 | | 3/ | | 3,28 | 8090 | 2.2.2 | ļ | | |
| PN365N | 775 | 6118 7405 | 5 | 16140 | 4.03 | 19010 | 4.12 | 18490 | | 17980 | | | 4.42 | 1 8 800 | 4.72 | 15560 | 5.00 | 13550 | 5,45 | 11600 | 3.49 | 499 |
| PN490H | 180 252 | 2309 3232 | ₩, | 11000 15400 | .61 | B120 | .70 | 11300 | .80 | E800 | .85 | ļ | | | LITE | CP | DUM. | non | <u>}:</u> | _ | ļ | 717 |
| PN490J | 182 278 | | 1 | 11100 1 896 0 | | 9290 15030 | 1 - | 13250 | L03 | 11290 | 1.11 | 8740 | 1,10 | | 16 | ,4 | 90 | CF | M | | ļ | 720 |
| PN490K | 226 318 | | 17, | 13800 | | 11500 17700 | 1 | 9130 16100 | | 5700 14990 | 1 | 12800 | 1.66 | | | | | | | | <u> </u> | 732 |
| PN490L | 230 250 | | 2 | 14400 21350 | .50 1,62 | 12170 18800 | 1 .39 1 1.73 | 10000 19330 | 1 .68 1 1.86 | 7000 18920 | 86. 1 202 | 15460 | 2.15 | 11700 | 2.20 | | | | | | | 739 |
| PN490M | 914 400 | | 1 3 | 19150 24400 | | | 1.27 | |) 1.40 2.67 | | 1.55 1.84 | | 06.1 50.f. | | 5.27 | 13140 | 5.27 | | | | | 794 |
| PN490N | 828 475 | 4336 | 5 | 20620 28900 | 1.46 | 19020 | | 17500 | 1.70 | 15040 28900 | 1,89 | 14990 24540 | , | | | 20240 | 5.43 | 14380 | 5.43 | | | 808 |
| PN490P | 431 543 | \$529 | 71/6 | 26800 33120 | 1.01 | 25000 |) 5.14) 6.15 | 23800 | | 22500 | | 21450 | 5.61 | | 1.00 | 16300 25830 | | 21390 | 8.21 | 15900 | 8,08 | 927 |
| PN543J | 169 239 | 2400 | , | 14000 | 16. | 10620 | ,40 | 6120 | | 1 | 1,17 | 1 | 1.14 | | | | | | | | | 780 |
| PN543K | 185 279 | 2627 | 1% | 15900 | 1 .40 | 12200 | 5/3 | 8690 | 35. | | 1 1.70 | | 1.74 | | | <u> </u> | | P P P P P P P P P P P P P P P P P P P | 1 | | | 772 |
| PN543L | 200 | 2840 | 7 | 16560 | .5 L | 1366 | 1 .61 | 10580 | 96. | | | | | | 2.17 | - | 1 | | - | | | 779 |
| PN543M | 296 | 3451 | 1 | 20120 | 189, | 17701 | 1,01 | 20570 15420 | 1.16 | 12830 | 1-2.09 1-38 | 9380 | 1.21 | | | 10000 | | | - | | | 834 |
| PN543N | 341 | 4931 | 6 | 28230 25250 | 1,-7 | 2328 | 1.90 | 2142 | 2.79 2.07 | 19830 | 2,99 | 17780 | 3.39 | 12720 | | 1 | 3.32 | full section | | - | - | 839 |
| PN543P | 400 350 | 4971 | 77. | 28980 | 3,99 | 2725 | 9 4.15 9 2.52 | 25601 | 0 4.33 0 2.99 | 2410 | 1,55 3,520 | 22450 |) 4.79) 5.41 | 18940 | | 14340 | 3.62 | | | + | | 850 |
| PN543R | 460 397 | 5638 | | 3807 | | 9150 | 0 (3.74) 0 (4.06) | 29901 | 0 6.44 0 1.24 | 2840 | 1 6.66 1 5.46 | 2700 | | 24300 | | Z1000 | 7.98 | | B.29 | | | 103 |
| | 306 | 7172 | ! '"_ | 41804 | | | | 3940 | 0 8,42 | 3820 | 9 a.65 | . 371 DC | 1 8.91 | 34900 | 9.50 | 32700 | 10.10 | | | | | 3 001 |

9185820134


ACME ENGINEERING

PAGE 97





STATIC PRESSURE - Inches of water



Performance shown is for unith without succe. BHP for ball driven units does not include drive toppes.

ACME ENGINEERING

PAGE **0**5

SELT DRIVEN

04:28

CERTIFIED CFM, BHF AND SOUND VS. STATIC PRESSURE TO ESO

| 100 | AND MARKET AND | , redictor | 1 2 6 7 12 | | 11.75 60 | | 3. 33 | di pu | | ar yy. | , | | ~~, | | Z W | | - 7 () () | | marity of the |
|----------------|-----------------------|----------------------|----------------|--------------|---------------|---------------------|---------------|----------------|---------------|--------------|----------------|--------------|--------------|-------------|---------|---------------|-------------|----------------|------------------|
| į | MODEL | FAN: | MIN. MAX | <u>.</u> | 1_ | <u> του"</u> | 1.1 | 250'' | | 500" | 1 | 750′′ | 2.0 | 100 | _2,2 | 50" | 2 | 500'' | 100T. |
| 4.0 | NO. | RPM | TIP SPEED | НР | CFM | #AH! | CFM | * AHP | CFM | → BHP | CFM | ₹ ØMF | GFM | ★BHP | CFM | 大量的門 | CFM | ★ BHP | 1 |
| | PUB135F_ | 1032 1540 | 3847 5471 | 1/n | 755 | 31 | | ļ | | | <u> </u> | | | | | | | | 148 |
| | PU5135G_ | \$242 1545 | 4390 5524 | J 16 | 1420 | D.C. | 1140 | .54 | 785 | 4.5 | | | | | | | | | 150 |
| | PUE145E | 778 1878 | 2953 4843 | 14 | | <u> </u> | | | | | 1 | | | | |] | 1 | | 150 |
| | PUB145F | 91B 1970 | 3485 5223 | 1/3 | 560 | 47 | | | | | | | | | | | | | 160 |
| | PU8146G | 1149 1680 | 4362 9410 | 15 | 1545 | .60 | 1170 | <u> </u> | 696 | 48 | | | | | | | 1 | | 180 |
| | PU8145H | 1900 1910 | 4936 7263 | 3 | 207.6 | 1.84 | 1786 | .03 | 1470 | 8.2 | 1096 | 70 | 409 | | | | | | 169 |
| | PUB163E | 741 1110 | 91d2 4722 | 1.1% | | | | | | | | | | | | | | | 188 |
| | PUB163F | 835 1229 | 3352 5228 | <u> </u> | #2Q | .33 | | | <u> </u> | | <u> </u> | | | | | | | | 188 |
| y. | PU8163G | 931 1475 | 397A 6082 | ų | 1720 | .50 | 1190 | <u></u> | L | | | | | | | | | | 188 |
| | PU8163H | 1058 1577 | 4510 4510 | <u> </u> | 2270 | .78 | 1835 | 1 | 1350 | .71 | | | | | | | 1 | | 198 |
| | PUB200E | 830 820 | 2775 4294 | <u> </u> | | | <u> </u> | | | | | | | | | | | | 255 |
| ę. | PUBSOOF | 632 906 | 7,300 47,44 | ys. | | | | | | | | | | | | | | | 258 |
| i i | PUB200G | 710 1049 | 2710 5493 | ٨ | 2000 | 57_ | 1510 | ,53 | | | | | | | | | | | 288 |
| | PU8200H | B07 | 4288 6125 | 14 | 2680 | .79 | 2205 | .78 | | | | | | | | | | | 268 |
| | PUBSOON | 904 1510 | 4736 8883 | 1 | 3330 | 1.10 | 3016 | 1,11 | 2025 | 1.11 | 1909 | 1.02 | | | ** | | | | 209 |
| Š | PUB200K | 1078 1478 | 5006 7733 | 14 | 9145 3985 | ,07 1,54 | <u> 3770</u> | 1,07 | 3600 | 1.59 | 31.90 | 1,69 | 2770 | 1,56_ | 2040 | _1,41 | | | 267 |
| M. | PUBZ00L | 1184 1633 | 9556 | <u> </u> | 2756 4500 | , <u>52</u> 2.04 | 2315 4380 | 8'08 75 | 1290 4) 85 | 80. S1.5 | 3960 | 2.14 | 3694 | 7.15 | 9200 | 2,15 | 2850 | _2,00 | 277 |
| | FUB245F | 461 690 | 2957 4295 | _ <u>v</u> _ | | | | | | | | , | | | - June | | LDGG | —€•K₽ | 277 |
| 8 | PUB245G_ | 523 789 | 3588 4832 | 1/2 | | | • | | -, | | | | | • | | | | , _ | 277 |
| | PUB245H | 894 610 | 3915 5670 | 99 | 0115 | .63 | | | | | | | | | | | | | 285 |
| | FUB245J | 645 945 | 4137 6087 | 1 | 3695 | 1.02 | 3070 | 1.02 | | | | | | | | | i i | | 283 |
| 分 第一 | PUB245K | 730 1088 | 4704 6950 | 11/2 | 472R | 1,52 | 4303 | 1.54 | 3860 | 1.62 | 3145 | 1.01 | | | | | | | 287 |
| | PUB245L | 1180 | 6529 7633 | 2 | 2090 5425 | .77 1.95 | 5098 | 2,00 | 4750 | 2.02 | 4320 | a.p.g | 3789 | 2,0D | 1875 | 1.56 | | -+ | 287 |
| 7) 2) | PUB246M | 1001 1390 | 8998 8916 | | 4780 6695 | 1.64 3.00 | 4375 5650 | 1.59 3.08 | 3900 6198 | 1,45 3,14 | 3225 5915 | 1.53 3.19 | 407 0 | | AZBO | 3.27 | 1855 | 3,20 | 303 |
| | PUB300H | 395 593 | 3102 4857 | 14 | | | | | | | | | | | | | 1000 | 3,67 | 412 |
| - | FUB300J | 481 653 | 3779 5129 | 1 | 2560 | . 86 | | | | [| | | | | | | | | 413 |
| 30 | PUB300K | 853 751 | 4343 0888 | l'h | 5530 | 1.52 | 4530 | 1.60 | | | | | | | | | | | 411 |
| | PUB300L | 503 810 | 4726 0361 | 2 | SARE | 8,08 | ORBR | 2,02 | 4440 | 1,99 | 27 | EF- 1 | | | | | | | 425 |
|] _ | PUB300M | 663 027 | 9207 7200 | <u>.</u> | 3720 9180 | 1.00 | 7 G 20 | , a m2 | | | 9 (B3 | 3.01 | 4175 | 2.89 | | | | | 402 |
| _ | PUB300N | 1300 1300 | 6440 6639 | 5 | 6680 10205 | 2.13 4.93 | 5650 9865 | 2.09 5.02 | 4980 9496 | 2.06 6.09 | PDAQ. | | | | 7846 | 5,00 | 7249 | 0.02 | 479 |
| _ | PUB365H | 279 426 | 2656 4071 | 'n | | I | | | | | | | | | | North Company | 70.3 | -0.45 | 3 |
| _ | PUB366J | 113 489 | 2991 4482 | 1 | | | | | | NT | PPO | LATE | P | 65 | 50 | OF W | 1 | | 518 |
| _ | PUB365K | 975 992 | 3583 5084 | _10 | | | | | | | | | | | | | | \dashv | 519 |
| _ | PUB365L | 388 593 | 2718 3667 | -8 | 7580 | 2.22 | | | | | | | | | | | | | 517 |
| L | PUB365M | 404 477 | 4721 5469 | p p | 10100 | | 8980 | <u>2,21</u> | 0755 | 3,09 | | | | | | | | -+ | 526 |
| | PUBSESN | 900 79.9 | 8307 7825 | .5 | 9640 12992 | 3.08 5.33 1 | 5365 2345 | 3.05 5.46 1 | 5305 1520 | 2.70, | U500 | 5.40 8 | 1915 | 5.211 | 459 | 3.67 | | | 548 |
| _ | PUB490K | श्रश्च 375 | 2900 4159 | 114 | | | | | | | | | | | | 2.18.1 | | | 561 |
| L., | PUB490L | 29.9 30.3 86.5 | 3478 4857 | -3 | | | | | | | | | | | | | -+ | | 788 773 |
| | PUB480M | 410 | 3623 6598 - | | 7465 | 2.64 | | | | | | | | | | | _ | | 4 |
| ř,C | PUB490N | 50% | 5260 6478 | 5 | 8440 10705 | 8.41 5.81 1 | 1510 | 6.86 <u>0</u> | 940 | 4,7A | | | | | | _ | | | 800 / 534 |
| ĸ. | attown moles his pro- | | -al es ! !> | | - Dunini | onuu-oni | BUREAU CAN | भ्राप्त विक्र | POTTO Dett' | en tiralita | Cros of c | بالما ماها م | ب السناب | 4-12 | . 11111 | | | | <u> براستوحد</u> |

to believe to the order wathout ducts. Beloved well determined does not michigo differ loss



Appendix C

WING'S

TESTING & BALANCING CO., INC.

94 No. Branford Rd., Branford, CT 06405 203-481-4988 Fax 203-488-5634



25 Sigourney St. ATC Upgrades



REVIEWED FOR RECORDS ONLY
BY INTEGRATED SERVICES, INC.

Date 2-9-05

Invensys
Attn.: Ron Duplin
29 Kripes Road
PO Box 575
East Granby, CT 06026

January 17, 2005

Reviewed For Record

- Device's Noted Repaired
- 2) Reviseand Raturnis
- 3) Reference Tube Most Be Repaire For system TO operate Proport

Visit us on the Internet: www.wingstesting.com or e-mail us: wings@wingstesting.com
File: 25 sigourney st ATC Upgrades.

SM-1 License # 5775



94 No. Branford Rd., Branford, CT 06405 203-481-4988 Fax 203-488-5634

| Floors | Test 1 | Final |
|---------------|-----------------|-----------------|
| | Actual/Invensys | Actual/Invensys |
| 6TH FLOOR | | |
| SPACE | .20/.10 | |
| SA SPN | 1.13/1.15 | 1.13/1.14 |
| SA SPS | 1.25/1.26 | 1.25/1.26 |
| MIN. O.A. N. | .033/,03 | .030/.03 |
| MIN. O.A. S. | .038/.04 | .030/.03 |
| 5TH FL. MEZZ. | · | |
| MESS. SPACE | .08/.07 | .08/.07 |
| LOBBY SPACE | .08/.08 | .08/.08 |
| SA SPN | .77/.78 | .77/.78 |
| SA SPS | 1.06/1.07 | 1.06/1.07 |
| MIN. O.A. N. | .015/.02 | .019/.02 |
| MIN O.A. S. | .026/.03 | .029/.03 |
| 10TH FLOOR | | |
| SPACE | .18/.10 | |
| SA SPN | 1.31/1.34 | 1.30/1.30 |
| SA SPS | 1.12/1.15 | 1.14/1.14 |
| MIN. O.A.N. | .028/.03 | .031/.03 |
| MIN. O.A.S. | .030/.03 | .030/.03 |
| 9TH FLOOR | | · · · · |
| SPACE | .23/.10 | |
| SA SPN | 1.28/1.31 | 1.28/1.28 |
| SA SPS | 1.12/1.15 | 1.14/1.14 |
| MIN. O.A.N. | .031/.03 | .031/.03 |
| MIN. O.A.S. | .03/.03 | .03/.03 |
| 8TH FLOOR | · | . 333,733 |
| SPACE | .29/.10 | |
| S.A. SPN | 1.095/1.12 | 1.11/1.11 |
| SA SPS | 1.12/1.14 | 1.15/1.15 |
| MIN. O.A.N. | .030/.03 | .030/.03 |
| MIN. O.A.S. | .030/.03 | .030/.03 |



94 No. Branford Rd., Branford, CT 06405 203-481-4988 Fax 203-488-5634

| Test 1 | Final |
|-----------------|---|
| Actual/Invensys | Actual/Invensys |
| | |
| .31/.10 | |
| 1.18/1.22 | 1.21/1.21 |
| 1.12/1.14 | 1.14/1.14 |
| .028/.03 | .03/.03 |
| .024/.03 | .031/.03 |
| | |
| .04/.04 | .04/.04 |
| 1.04/1.06 | 1.04/1.06 |
| .81/.83 | .81/.83 |
| .038/.04 | .04/.04 |
| .05/.07 | .029/,03 |
| | · |
| .04/.04 | .04/.04 |
| 1.12/1.14 | 1.12/1.14 |
| 1.20/1.18 | 1.20/1.18 |
| .031/.03 | .030/.03 |
| .03/.03 | .03/.03 |
| | |
| .17/.10 | OVER RANGE (VERIFY) |
| 1.13/1.15 | 1.13/1.15 |
| 1.13/1.19 | 1.13/1.13 |
| .03/.03 | .03/.03 |
| .03/.03 | .021/.02 |
| | |
| .22/.10 | OVER RANGE (VERIFY) |
| 1.23/1.25 | 1.23/1.25 |
| 1.13/1.15 | 1.13/1.15 |
| .03/.03 | .03/.03 |
| .033/.03 | .03/.03 |
| | .31/.10 1.18/1.22 1.12/1.14 .028/.03 .024/.03 .04/.04 1.04/1.06 .81/.83 .038/.04 .05/.07 .04/.04 1.12/1.14 1.20/1.18 .031/.03 .03/.03 .17/.10 1.13/1.15 1.13/1.19 .03/.03 .03/.03 .22/.10 1.23/1.25 1.13/1.15 .03/.03 |



94 No. Branford Rd., Branford, CT 06405 203-481-4988 Fax 203-488-5634

| Floors | Test 1 | Final |
|----------------|-----------------|-----------------|
| | Actual/Invensys | Actual/Invensys |
| 19TH FLOOR (1) | | |
| SPACE/ATMOS. | +.17/+.10 | OUT OF RANGE |
| SA SPN | 1.17/1.18 | 1.17/1.18 |
| SA SPS | 1.13/1.15 | 1.13/1.14 |
| MIN. O.A. N. | .023/.02 | .02/.02 |
| MIN. O.A. S. | .009/.01 | .01/.01 |
| 18TH FL. | | |
| SPACE | +.29/+.10 | OUT OF RANGE |
| SA SPN | 1.16/1.19 | 1.21/1.20 |
| SA SPS | 1.12/1.15 | 1.13/1.13 |
| MIN. O.A. N. | .05/.05 | .05/.05 |
| MIN O.A. S. | 042/.04 | .04/.04 |
| 17TH FLOOR (2) | • | |
| SPACE | +,19/+,10 | OUT OF RANGE |
| SA SPN | 1.24/1.29 | 1.24/1.26 |
| SA SPS | 1.13/1.13 | 1.13/1.13 |
| MIN. O.A.N. | .029/.03 | .029/.03 |
| MIN. O.A.S. | .04/.04 | .04/.04 |
| 16TH FLOOR | | |
| SPACE | .02/.02 | .02/.02 |
| SA SPN | 1.29/1.30 | 1.29/1.30 |
| SA SPS | 1.17/1.17 | 1.17/1,17 |
| MIN. O.A.N. | .03/.03 | .03/.03 |
| MIN. O.A.S. | .02/.02 | .03/.03 |
| - | | |
| | | |

⁽¹⁾ ACTUAL SPACE PRESSURE = \pm .05.

⁽²⁾ ACTUAL SPACE PRESSURE = +.065



94 No. Branford Rd., Branford, CT 06405 203-481-4988 Fax 203-488-5634

| 6TH FLOOR 8TH FLOOR | 17/.17 | S ACT | UAL/INVENSYS .17/.17 |
|------------------------|---------|-------|-------------------------|
| 8TH FLOOR | | | .17/.17 |
| | 177/177 | 1 | |
| * CONTEST OOD | .17/.17 | | .17/.17 |
| 16TH FLOOR | .17/.15 | | .18/.18 |
| AVG. | .17/.16 | .17 | 7/.17 SPT = .17" |

| | TEST 1 | FINAL |
|------------|-----------------|---------------------|
| | ACTUAL/INVENSYS | ACTUAL/INVENSYS |
| 6TH FLOOR | .21/.21 | .21/.21 |
| 8TH FLOOR | .20/.20 | .20/.20 |
| 16TH FLOOR | .21/.21 | .21/.21 |
| AVG. | .21/.21 | .21/.21 SPT = .21" |

| | • , | • | | | | | | | | <u>B</u> | NB |
|------------------|----------|----------------|----------|----------------|---------------|----------------|------------------|--|------------------|-----------------|----------------------|
| ING'S TESTING 8 | BAL | ANCING | CO., IN | C., 94 NC |). BRANF | ORD RD. | , BRANFO | RD, CT (| 06405 NOT W | (10) | به المارين دور |
| | | | AIR | D)EV/(| e)=/E{(|)X RE | EPOR I | ہار ۲ | TOU | 4 .44.1- | y |
| ROJECT: | 25 SI | GOURNEY | ST. ATO | UPGRADI | ES | | DATE: | 7-15-04 | سين | | |
| /STEM/AREA SERV: | OASF | /MEZZ. 20 | TH FL. | | | | TECH: | J.F. | | | |
| LOCATION | NO. | SIZE | FREE | DESIG MIN | N CFM MAX | TEST | FIJAL | | | RESS D | |
| OASF-1 NO. | | SIGE. | | Dillia | IVIAA | <u> </u> | MIN | MAX | MIN | MAX | NOTE |
| FLR. # 19 | | 28X16 | 3.11 | 2200 | 3600 | 1956 | 1956 | 2660 | .02 | .037 | (1,2) (3) |
| 18 | | 28X16 | | 2000 | 3275 | 2985 | 1969 | 2612 | .025 | .044 | (3) |
| . 17 | | 28X16 | | 2000 | 3275 | 1978 | 1978 | 2545 | .029 | .048 | (3) |
| 16 | | 28X16 | | 2200 | 3600 | 2264 | 2264 | 2647 | .03 | .041 | (3) |
| 15 | | 28X16 | | 2200 | 3600 | 2183 | 2183 | 2183 | .04 | .04 | (3) |
| 14 | | 28X16 | | 2200 | 3600 | 2333 | 2333 | 2520 | .03 | .035 | (3) |
| 12 | | 28X16 | | 2200 | 3600 | 2027 | 2027 | 2510 | .03 | .046 | (3) |
| 11 | - | 28X16 28X16 | | 2200 2200 | 3600 | 2403 | 2403 | 2740 | .03 | .039 | (3) |
| 9 | | 28X16 | | 2200 | 3600 3600 | . 2224 2158 | 2224 2158 | 2526 | .031 | .040 | (3) |
| 8 | | 28X16 | <u> </u> | 2200 | 3600 | 2074 | 2074 | 2451 2731 | .031 | .040 | (3) |
| 7 | | 28X16 | | 2200 | 3600 | 2127 | 2127 | 2932 | .03 | .052 | (3) |
| 6 | | 28X16 | | 2200 | 3600 | 2258 | 2258 | 2856 | .03 | .048 | (3) |
| MEZZ. 2N | | 28X16 | | 1600 | 2625 | 1696 | 1696 | 1725 | .029 | .03 | (3) |
| | | | | | | | | | | | |
| AHU-1 | | 48X20 | | 0 | 0 | 0 | 0 | 0 | | | (4) |
| | | | | <u> </u> | | 7 | | | | | |
| | | | B | 17(15 | occi | YACI |) - | | | | |
| | | 7 | 59 | tel? | | · · · | 2 | | | | |
| · | | | ٠, | 1 <u>-</u> 0 1 | | 111 | | | | | |
| | | | | | B | JH | | ~~~ | | | |
| | | | | | | | | | | | |
| 1 TEN MINA | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | 7484 | | | - | | | | |
| | | | | | | | | | - | - | |
| | | | | | - | | | | | | |
| | | | | | | | | | | | - |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | · . | | | | | | | | |
| 7.5.7.7. | <u> </u> | <u> </u> | | REMA | | | _ | 2/200000000000000000000000000000000000 | 19494A\$470A4333 | Thronous | ks (Videos assertane |

⁽¹⁾ OASF-1 OPERATING @ 54 HZ 27.2 AMPS UNDER MIN. CONDITION.

⁽²⁾ OASF-2 OPERATING @ 59.6 HZ 31.7 AMPS UNDER MAX, CONDITION.

⁽³⁾ DAMPER IS 100% OPEN UNDER MAX. CONDITION.

⁽⁴⁾ DAMPER IS CLOSED 100%.

| ROJECT: | 25 SI | GOURNEY | ST. ATC | UPGRAD | ES | | DATE: | 7-15-04 | | ********* <u>*****</u> | |
|------------------|-----------|------------|---------|-------------|----------|------|-------|---------|-------|---------------------------------------|-------------|
| YSTEM/AREA SERV: | OA S | F-2/MEZZ-2 | OTH FL | R. SO. | | | TECH: | J.F. | | | |
| | | | FREE | DESIG | N CFM | TEST | FINAL | .CFM | PRESS | DIFF | _ |
| LOCATION | NO | SIZE | AREA | MIN | MAX | 1 | MIN | MAX | MIN | MAX | NOTE |
| OASF-2 SO. | | - | | | | | | | | | (1,2) |
| FLR. # 19 | | 28X16 | | 2200 | 3600 | 1424 | 2210 | 2500 | 0.025 | 0.032 | (3) |
| 18 | | 28X16 | | 2000 | 3275 | 3163 | 1891 | 3275 | 0.015 | 0.045 | (3) |
| 17 | | 28X16 | | 2000 | 3275 | 2528 | 2070 | 2738 | 0.028 | 0.049 | (3) |
| 16 | | 28X16 | | 2200 | 3275 | 2285 | 2255 | 2882 | 0.03 | 0.049 | (3) |
| 15 | | 28X16 | - :: | 2200 | 3600 | 2152 | 2152 | 2516 | 0.03 | 0.041 | (3) |
| . 14 | _ | 28X16 | | 2200 | 3600 | 2137 | 2137 | 2529 | 0.03 | 0.042 | (3) |
| 12 | | 28X16 | | 2200 | 3600 | 2488 | 2136 | 3229 | 0.021 | 0.048 | (3) |
| 11 | | 28X16 | | 2200 | 3600 | 2507 | 2186 | 3662 | 0.022 | 0.049 | (3) |
| 10 | | 28X16 | | 2200 | 3600 | 2087 | 2087 | 2951 | 0.03 | 0.06 | (3) |
| . 9 | | 28X16 | | 2200 | 3600 | 2280 | 2280 | 3561 | 0.03 | 0.074 | (4) |
| - 8 | | 28X16 | - | 2200 | 3600 | 2451 | 2234 | 3562 | 0.024 | 0.061 | (3) |
| 7 | | 28X16 | | 2200 | 3600 | 2472 | 2299 | 3562 | 0.025 | 0.06 | (3) |
| 6 | | 28X16 | | 2200 | 3600 | 2563 | 2130 | 3230 | 0.02 | 0.046 | (3) |
| MEZZ. 2S | | 28X16 | | 2100 | 3435 | 2348 | 1954 | 3120 | 0.02 | 0.051 | (3) |
| | | | <u></u> | | | | | 0120 | 0.02 | 0.001 | (3) |
| AHU-20 | | 20X46 | | 1200 | | 256 | 1042 | 2525 | | | (4) |
| | | | | | | | | | | | (4) |
| | | 7,,,,,, | | | | - | 1 | ~~~~ | | | |
| | | | | | | | V KA | 5 /1 | 1.45 | | |
| | | | | · | | | 7 140 | · (W | | | |
| | | | | | | | 15P6 | CHE | -D 17 | 17 601 | TO CF |
| | | | | | | | (| | V 19 | | W-C |
| | - | | | | | | | T W | | | <u> </u> |
| | | | | | | | | | | R21 | 3 |
| | | | | | | | | | | | - |
| | | | | | | · | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | - · | | | | |
| | | | | | <u> </u> | | | | | | · · |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | · · · · · · · · · · · · · · · · · · · | |
| | <u></u> - | | | | | | | | | | |
| | | | | | | | | | | | |

GENERAL NOTE: OUTSIDE AIR DAMPER HUNT WHILE TRYING TO MAINTAIN CFM SETPOINTS. RESOLUTION OF SENSORS = +/-

⁽¹⁾ OASF-2 OPERATING @ 44 HZ 21 AMPS UNDER MIN. CONDITION.

⁽²⁾ OASF-2 OPERATING @ 59.5 HZ 33.6 AMPS UNDER MAX. CONDITION.

⁽³⁾ DAMPER IS 100% OPEN UNDER MAX. CONDITION.

⁽⁴⁾ ACTUATOR DOES NOTWORK. DAMPER MANUALLY POSITIONED FOR TEST PURPOSES.

| | | VELO | ЭТҮР | RESS | URER | EADIN(| 3S | | |
|-----------------------|----------|------------|---------------|-------|-------|-------------|-------|-------------|-------|
| PROJECT: | | IGOURNEY S | T., ATC U | | | | DATE: | 7-6-04 | |
| LOCATION: TRAVERSE | AIR | HANDLER TO | OTALS AREA | OF: | SIGN | CENTERLINE | TECH: | S.W. & J.F. | |
| LOCATIONS | | SIZE | SQ FT. | FPM | CFM | STATIC PRES | | INAL CFM | NOTES |
| MEZZ. NORTH | | 82X22 | 12.52 | 839 | 10500 | . W/GRID | 731 | 9152 | |
| MEZZ SOUTH | | 104X28.75 | 19.11 | 743 | 14200 | W/GRID | 752 | 14370 | |
| 6 NORTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 804 | 15364 | |
| 6 SOUTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 860 | 16435 | |
| 7 NORTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 886 | 16931 | |
| 7 SOUTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 859 | 16415 | |
| 8 NORTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 852 | 16282 | |
| 8 SOUTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 877 | 16759 | |
| 9 NORTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 770 | 14715 | |
| 9 SOUTH | ļ | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 767 | 14657 | |
| 10 NORTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 874 | 16702 | |
| 10 SOUTH | | 104X28.75 | 19,11 | 759 | 14500 | W/GRID | 917 | 17524 | |
| 11 NORTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 958 | 18307 | |
| 11 SOUTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 870 | 16626 | |
| 12 NORTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 874 | 16702 | |
| 12 SOUTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 855 | 16339 | |
| 14 NORTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 883 | 16874 | |
| 14 SOUTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 948 | 18116 | |
| 15 NORTH | | 104X28.75 | . 19.11 | 759 | 14500 | W/GRID | 814 | 15555 | |
| 15 SOUTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 848 | 16205 | |
| 16 NORTH | <u> </u> | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 721 | 13778 | |
| 16 SOUTH | | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 743 | 14199 | |
| 17 NORTH | | 104X28.75 | 19.11 | 706 | 13500 | W/GRID | 836 | 15976 | |
| 17 SOUTH | | 104X28.75 | 19.11 | 706 | 13500 | W/GRID | 845 | 16148 | |
| 18 NORTH | | 104X28.75 | 19.11 | 706 | 13500 | W/GRID | 838 | 16014 | |
| | | | | REMAR | KS |]_, | 1 | . | |

| PROJECT: LOCATION: TRAVERSE | AIR | 25 SIGOURNEY ST., ATC UPGRADES DATE: 7. AIR HANDLER TOTALS TECH: S. DUCT AREA DESIGN CENTERLINE FINAL | | | | | | | | | |
|---------------------------------------|--------------|---|-------|-------|-------------|---------------------------|-----|--------------|-----|--|--|
| LOCATIONS | | SIZE | SO FT | FPM | SIGN CFM | CENTERLINE STATIC PRES | | INAL CFM | NOT | | |
| 18 SOUTH | | 104X28.75 | 19.11 | 706 | 13500 | W/GRID | 877 | 16759 | | | |
| 19 NORTH | | 104X28.75 | 19,11 | 759 | 14500 | W/GRID | 684 | 13071 | | | |
| 19 SOUTH | <u> </u> | 104X28.75 | 19.11 | 759 | 14500 | W/GRID | 691 | 13205 | | | |
| 20TH | | 32X49.5 | 11 | 545 | 6000 | W/GRID | 450 | 4950 | (1 | | |
| LOBBY AHU-1 | | 78X20 | 10.83 | 942 | 10200 | 98 | 752 | 8144 | | | |
| | | | | | | | - | | | | |
| | - | | | | | | | | - | | |
| | | | | | | | - | | - | | |
| ·- | | | | - | | | | | | | |
| | <u> </u> | | | | | | | | | | |
| | | | | | | | | | | | |
| | | · | | | | | · | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | - | | | |
| | | | | | | | | - | | | |
| | | | | | | | | | | | |
| · · · · · · · · · · · · · · · · · · · | | | | | | | | | | | |
| | ļ | | | | | | | | | | |
| · · · · · · · · · · · · · · · · · · · | | | | | | | | | | | |
| | - | | | | | | | | | | |
| | _ | | | | | | | | | | |
| | | | | | | | | | | | |
| VFD @ 89.3%. | | L | L | REMAR | KS | | l | J | | | |