

SUMMARY OF CHANGES - JULY 2023 SUPPLEMENTS TO FORM 818
EFFECTIVE FOR FDP DATES ON or AFTER NOVEMBER 16, 2023

July 2023 significant changes are summarized below:

SECTION 1.06 - CONTROL OF MATERIALS and
SECTION 1.20-1.06 - CONTROL OF MATERIALS FOR FACILITIES
CONSTRUCTION

Update to Materials Certificate (MC) information to document certifying that the materials, components and equipment furnished meet all requirements of the Contract, including the location where such material, components and equipment were produced. Deletion of requirement that Certified Test Reports and Materials Certifications be notarized.

SECTION 1.09 - MEASUREMENT AND PAYMENT and
SECTION 1.20-1.09 – MEASUREMENT AND PAYMENT FOR FACILITIES
CONSTRUCTION

Reinstated language that had been deleted which allowed for payment of eliminated item costs incurred by the contractor prior to the date the Engineer provided the Contractor with written notice of said elimination.

SECTION 6.03 – STRUCTURAL STEEL

Revisions to include AASHTO wind load design criteria for permanent and temporary work. Updated crane pick requirements to be included in Working Drawing submittals.

SECTION 9.71 – MAINTENANCE AND PROTECTION OF TRAFFIC

Revision to the requirements for Traffic Control Supervisor, to allow that qualifications or certifications from programs other than ATSSA would be reviewed for acceptance by the Department.

SECTION 18.03 – IMPACT ATTENUATION SYSTEM,
TEMPORARY IMPACT ATTENUATION SYSTEM

Incorporation of owned special provision to include requirements for concrete pad foundation at installation of “Non-Gating” type impact attenuation systems and reference the Qualified Products List for the pad details.

SECTION M.03 – PORTLAND AND HYDRAULIC CEMENT CONCRETE

Clarified timing for resistivity testing in Table M.03.02-1.

SECTION M.04 – BITUMINOUS CONCRETE MATERIALS

Minor change of Northeast Transportation Product Evaluation Program (NTPEP) to AASHTO Product Evaluation and Audit Solutions, which AASHTO says has no abbreviation.

SECTION 6.03 – METALS

Removed requirement that Certified Test Reports and Materials Certificates be notarized.

Also, the **Errata** pages include minor revisions to various other sections.