CTDOT Design-Build Bridge Bundle Rehabilitation East Hartford and Willington Project No. 171-431

East Hartford

Town Council Meeting

March 19, 2019





LOCHNER

Agenda

- Welcome and Introductions
- Project Overview
 - Project Area
 - Purpose
 - Schedule
- Bridge Specifics
 - 02366: Rt 2 WB & Governor St to Founders Bridge over I-84 EB
 - 02367 I-84 WB Exit 54 over I-84 EB
- How to Stay Informed

Project Team

Middlesex Corporation, Lochner Responsible for Design and Construction

CTDOT's Highway Division

Responsible for administering the Design Process and providing Resident Engineer Services

Design-Build Approach

An innovative approach to project delivery

- Engineer works directly for and with the Contractor to design the project
- Partnership between designer/contractor promotes innovation and reduces project costs and schedule
- Design-Builder is selected on best value (cost and qualifications)
- CTDOT defines project requirements and oversees Design-Builder
- This is the second Design-Build project in CT

Project Area




East Hartford

02369: Route 2 EB (towards Norwich and New London) (Completed in 2018)

02366: Route 2 WB & Governor Street (to downtown Hartford via Founders Bridge)

02367: I-84 WB (Exit 54 to downtown Hartford)

Bridge Components



Existing Conditions

- Bridge 02366 and 02367 were constructed in the 1960's
 - Cast in place concrete decks
 - Supports consist of simple span steel beams on concrete abutments and piers
- Superstructures exhibit deterioration, but remain safe to drive on and are regularly inspected

Project Purpose

- Repair and replace three bridges in East Hartford and one in Willington
 - Two remaining bridges to be completed this year
- Replace the deteriorated superstructures of each bridge
- Replace the substructures of bridges:

02366: Rt 2 WB & Governor St to Founders Bridge over I-84 EB

02367: I-84 WB Exit 54 over I-84 EB

Superstructure Replacement

Accelerated Bridge Construction Techniques

- Minimizes construction timeline and traffic impacts
- Steel girders paired off-site and installed at night








Substructure Replacement

GRS-IBS Abutments

- Middlesex-Lochner proposed this method for bridges 02366 and 02367
- Increases longevity of the bridges (75 years)
- Improves safety for drivers
- Reduces maintenance



GRS-IBS Abutments

Example: Killington, CT (constructed by others)




GRS-IBS Abutments

Example: Killington, CT (constructed by others)







Project Schedule - 2019

Bridge 02366: Rt 2 WB & Governor St to Founders
Bridge over I-84 EB
March through September
(Scheduled to be closed May 6, weather permitting)

Bridge 02367: I-84 WB Exit 54 over I-84 EB


March through November

(Lane closures are scheduled to begin April 23, weather permitting)

The project contract includes a \$10,000 per day fine for the Design-Builder for exceeding the project schedule.

Bridge 02366 (Route 2 Westbound)


Duration: March 2019 - September 2019



Bridge 02366

- The existing bridge is a 3-span, 2-pier bridge
- The new bridge will be single-span with no piers (GRS-IBS abutments will replace piers)






Bridge 02366

- March to September 2019
- Bridge (and 2 associated ramps) will be closed during stage 3
 - No more than 91 days
- Traffic Mitigation will include:
 - Pitkin St. off-ramp will provide a left and left-plus-right turn lane
 - Westbound Pitkin Street has been restriped to provide 2 lanes of travel from the ramp
 - Darlin Street intersection will include a right only lane for detoured traffic




Traffic Impacts – Stage 3



Bridge 02367 (I-84 WB Exit 54)

Duration: March 2019 – November 2019



Bridge 02367

- As with Bridge 02366, the existing bride is a 3span, 2-pier bridge
- The new bridge will be single-span with no piers (GRS-IBS abutments will replace piers)




Bridge 02367

Darlin Street deceleration lane and off ramp closed




- 2 of the 4 lanes of traffic on the bridge will be maintained during construction
 - HOV lane will allow general purpose traffic

Traffic Impacts – Darlin Street Detour




Traffic Impacts – Stage 3

Work on Bridge 02366 will take place concurrently with this phase of work on Bridge 02367



Traffic Impacts – Stage 4

After work on the southern half of the bridge is complete, work will switch to the northern half.




Wrap Up

- We understand Pitkin Street will experience increased traffic during construction
 - Detour sheets will be posted on the website closer to their respective start dates
- There will be an adjustment period associated with traffic becoming familiar with these detour routes
- We will be monitoring traffic throughout construction



What to Expect Next

- There is ongoing work in the project area including:
 - Installation of timber shielding on bridges to begin in April
 - Installation of GRS walls at abutments
- Weather permitting, bridge demolition will begin in late April
- Variable Message Boards will be deployed ahead of lane closures



Stay Informed

- Project website maintained throughout construction <u>https://www.ct.gov/dot/cwp/view.asp?a=4453&q=601558</u>
 Google: "ctdot project 0171-0431"
- Detour Information Sheets
- Construction look-aheads
- Quarterly newsletter to be posted on the website
- Briefings available upon request
- We will work with CTDOT to respond to all questions and comments during construction in a timely manner

CDOT Bridge Rehabilitation Project
East Hartford & Willington
Project No. 170-431

Discussion

Greg Kozma
Connecticut Department of Transportation
Gregory.Kozma@ct.gov
860-258-4615





LOCHNER