

**SECTION 11.16
ILLUMINATED SIGNS**

11.16.01--Description: This item shall consist of furnishing and installing an Illuminated Sign, of the type specified, at the location shown on the plans or as directed by the Engineer, and in conformity with these specifications.

11.16.02--Materials: The materials for this work shall conform to Article M.16.17.

11.16.03--Construction Methods: Erection of the sign shall be accomplished in a manner so as not to cause twisting, bending, deforming, or scratching of the sign or sign face. They shall be level, correctly aligned as indicated on the plans and shall be properly fastened to the structure or supports with the necessary hardware as indicated on the plans. Any sign panel damaged shall be repaired at the Contractor's expense.

11.16.04--Method of Measurement: This work will be measured for payment by the number of illuminated signs of the type and size specified, completed in place, accepted and operating.

11.16.05--Basis of Payment: This work shall be paid for at the Contract unit price each for Illuminated Sign complete in place, which price shall include mounting brackets, hardware, fittings, snap switch, all materials, equipment, paint, tools, labor, and work incidental thereto. Cable to the sign shall be paid under Article 11.13.

Pay Item	Pay Unit
Overhead Illuminated "Stop Ahead" sign	EA.
Internally Illuminated sign	EA.