

SECTION 11.30
HIGH MOUNTED INTERNALLY ILLUMINATED
FLASHING ARROW

11.30.01--Description: This item shall include furnishing and maintaining a high mounted internally illuminated flashing arrow sign, either on a trailer assembly or truck, as shown on the traffic control plans or as ordered by the Engineer and in accordance with these specifications.

11.30.02--Materials: The flashing arrow shall conform to the requirements of Part VI of the MUTCD, Advance Warning Flashing Sequencing Arrow Panels, Type C. The panel shall have the capability of both sequential and flashing operations. The bottom of the panel shall not be less than 2.1 m above the pavement. Lamp voltage shall be dimmed by 50% for nighttime use automatically.

11.30.03--Construction Methods: The Contractor shall furnish, place, operate, maintain and relocate the sign as required. When the need no longer exists for a sign, the Contractor shall dispose of it. Any signs that are missing, damaged, defaced, or improperly functioning so that they are not effective, as determined by the Engineer and in accordance with the ATSSA guidelines contained in "Quality Standards for Work Zone Traffic Control Devices," shall be replaced by the Contractor at no cost to the State.

11.30.04--Method of Measurement: This work will be measured for payment by the number of calendar days that the sign is in place and in operation. When a sign is in operation for less than a day, such a period of time shall be considered to be a full day regardless of actual time in operation.

11.30.05--Basis of Payment: This work will be paid for at the Contract unit price per day for "High Mounted Internally Illuminated Flashing Arrow," which price shall include all costs for furnishing, maintaining and disposing of a sign and all materials, labor, tools and equipment incidental thereto.

Pay Item	Pay Unit
High Mounted Internally Illuminated Flashing Arrow	Day