

SAMPLE PROJECT USED FOR PLANS

The following sample project involves replacing an existing large pipe with a three-sided (open bottom) culvert. The project is planned to be constructed in 3 stages. A water handling pipé will be used and placed within the existing pipe. This project involves a roadway overbuild in the staging, therefore, an access road is not needed for construction

The following permits are anticipated for this project: DEEP Inland Water Resources Division Flood Management Certification (IWRD FMC) General Permit for Water Resource Construction Activities (IWRD GP) US Army Corps of Engineers Category Self-Verification (USACE SV)

For this sample project, the water-handling-cofferdam was designed using a 2-year frequency discharge. The culvert was designed for a 100-year storm. The sample project falls within a mapped FEMA area with no elevation provided on the FEMA map. A 100-year storm elevation (existing) has been calculated and this elevation is used in determining the floodplain impact area. An 8 1/2" x 11" FEMA map is provided within the permit application.


Impact areas include ALL areas to be impacted due to the project construction and activities related to the project, both temporary and permanent. On this project, additional impact area was included to allow the contractor to utilize different methods and equipment. Engineering judgement should be used to determine the amount of area the contractor needs to perform the work, while trying to minimize the disturbance to the wetland resources. The designer should also evaluate utility work needed as part of the project and include any impacts due to project related utility work.

NOTE: This sample project has been altered from the actual project to produce this sample set of plans.

GENERAL NOTES:

- 1. THESE PLANS ARE INTENDED ONLY FOR ENVIRONMENTAL PERMITTING PURPOSES. THESE PLANS HOLD AUTHORITY FOR ALL ACTIVITIES CONCERNING THE REGULATED AREA. FOR DETAILED PLANIMETRIC INFORMATION AND PAYMENT REFER TO THE APPLICABLE CONTRACT DOCUMENTS.
- 2. THE DEPARTMENT OF TRANSPORTATION WILL ONLY SUBMIT REVISIONS TO DEEP AND USACE FOR CHANGES TO THE DESIGN THAT WILL AFFECT REGULATED AREAS.
- 3. FOR A DESCRIPTION OF THE WATERCOURSES, WETLANDS AND WETLAND SOILS SEE RELEVANT SECTIONS OF THE PERMIT APPLICATION.
- 4. 400 FOOT GRID BASED ON CONNECTICUT COORDINATE SYSTEM N.A.D. 1927 VERTICAL DATUM BASED ON NGVD OF 1929.
- 5. ALL CONSTRUCTION ACTIVITIES WILL BE CONDUCTED IN ACCORDANCE WITH THE DEPARTMENT'S STANDARD SPECIFICATIONS FOR ROADS, BRIDGE, AND INCIDENTAL CONSTRUCTION, FORM 817, SECTION 1.10 AND WILL ALSO FOLLOW REQUIRED BEST MANAGEMENT PRACTICES (BMPs) AND SEDIMENT AND EROSION CONTROL MEASURES IN ACCORDANCE WITH THE 2002 EROSION & SEDIMENTATION CONTROL GUIDELINES AND THE 2004 STORMWATER QUALITY MANUAL.

ENVIRONMENTAL PERMIT PLANS STATE PROJECT NO. XXXX-XXXX REPLACEMENT OF BRIDGE NO. XXXXX IN THE TOWN OF



LOCATION PLAN

1" = 500'

GUIDE FOR THE DEVELOPMENT OF THE PERMIT PLAN SET


TITLE SHEET:


- 1. LOCATION PLAN AT AN APPROPRIATE SCALE THAT SHOWS PROJECT LOCATION AND NEARBY CROSS STREETS (EX. 1"=500', 1"=1000'). FOR LATERAL PROJECTS, DEPICT BEGINNING AND END OF PROJECT (PROJECT LIMITS).
- 2. STATE OF CONNECTICUT MAP WITH TOWN SHADED AND CALL-OUT PROJECT LOCATION
- 3. GENERAL INDEX FOR "LIST OF DRAWINGS"
 4. GENERAL NOTES 1-5 (ADDITIONAL NOTES MAY BE ADDED
- AS APPROPRIATE FOR THE PROJECT) 5. SIGNATURE BLOCK FOR CONSULTANT ENGINEER, IF NEEDED.
- 6. PLAN DATE (LATEST REVISION DATE OF SHEET. DATES DO NOT NEED TO MATCH WITHIN PLAN SET)

ON ALL OTHER PLAN VIEWS:

- 1. WETLAND LIMITS BOLD (NOT SCREENED). IDENTIFY IF STATE AND/OR FEDERAL WETLANDS
- 2. SHOW CUT/FILL LIMITS AND SEDIMENTATION CONTROL SYSTEM
- (SCS). (SCS NOT NECESSARY ON PLANTING PLAN)
 3. SHOW ORDINARY HIGH WATER (OHW) BOLD 4. SHOW FLOOD LIMIT LINES ON PLAN VIEWS - BOLD.
- IDENTIFY AS APPLICABLE FOR PROJECT: A) CALCULATED ELEVATION ON A FEMA MAP GOVERNS.
- LABEL AS: "FEMA 100-YR FLOOD (CALCULATED)"
- B) OTHERWISE, SHOW HYDRAULIC ANALYSIS ELEVATION. LABEL AS: "EXISTING 100-YR FLOOD (CALCULATED)"
- C) IF NO CALCULATIONS WERE PERFORMED, SHOW MAPPED
- FEMA LINES. LABEL AS: "MAPPED FEMA 100-YR FLOOD LIMIT"
- 5. FLOW ARROWS (EXISTING AND PROPOSED)


NOTE: FOR ADDITIONAL ENVIRONMENTAL INFORMATION, SEE ALSO THE DEPARTMENT'S OFFICE OF ENVIRONMENTAL PLANNING'S PERMIT PLAN CHECKLIST FOUND ON THE WATER & NATURAL RESOURCES WEBPAGE UNDER "PERMITTING PROCESS"







PLAN DATE: MARCH 13, 2019

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE	DESIGNER/DRAFTER: CHECKED BY:	SIGNATURE/ BLOCK: PROJECT TITLE: DEDI A CEMENIT OF	TOWN:	PROJECT NO.
SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.	STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION	REPLACEMENT OF BRIDGE NO. XXXXX ROUTE X OVER A BROOK	TOWN DRAWING TITLE:	PMT-01 SHEET NO.
REV. DATE REVISION DESCRIPTION SHEET NO. Plotted Date: 6/10/2019	SCALE AS NOTED Filename:\TITLE SHEET - Proj XXX.dgn		TITLE SHEET	







THESE WATER HANDLING SCHEMATICS ARE FOUND WITHIN THE GUIDE (SEE NOTE 2) ON THE OEP WEBPAGE. FOR WATER-HANDLING-COFFERDAM MICROSTATION FILES OF THE SCHEMATICS CONTACT DOT'S EPC UNIT 0000 42-INCH TEMPORARY WATER HANDLING PIPE 3-SIDED STRUCTURE -DEWATERING BASIN 00000000 WATER-HANDLING-COFFERDAM

PROPOSED WATER HANDLING SCHEMATIC FOR PROJECT

SEE NOTE 4

WATER HANDLING NOTES:

- 1. THE CONTRACTOR SHALL MAINTAIN WATER THROUGH THE TEMPORARY WATER HANDLING SYSTEM AS REQUIRED DURING CONSTRUCTION OF THE NEW STRUCTURE.
- 2. EQUIPMENT SHALL NOT BE PERMITTED IN THE STREAM WHEN TEMPORARY WATER HANDLING SYSTEM IS NOT IN PLACE WIHOUT APPROVAL FROM THE ENGINEER.
- 3. A DEWATERING BASIN SHALL BE ESTABLISHED OUTSIDE OF THE WETLAND LIMITS.
- TEMPORARY WATER-HANDLING-COFFERDAM SHALL CONSIST OF AN APPROVED SYSTEM THAT THE CONTRACTOR ELECTS TO USE WHICH WILL SAFELY CONVEY WATER FLOWS THROUGH THE CONSTRUCTION AREA, SHALL BE ABLE TO SUPPORT CONSTRUCTION ACTIVITY AND SHALL CONFORM TO PERMITS.

ANY WATER HANDLING SCHEME DEPICTED WITHIN THE DEPARTMENT'S 'HANDLING WATER TYPICAL SCHEMATICS' MAY BE UTILIZED UNLESS SPECIFICALLY PROHIBITED. A MEANS AND METHOD FOR WATER HANDLING SYSTEM SHALL BE SUBMITTED BY THE CONTRACTOR TO THE ENGINEER FOR APPROVAL.


- 5. WATER HANDLING MEASURES SHALL NOT EXCEED IMPACT AREAS SHOWN ON THE WETLAND AND FLOODPLAIN IMPACT SHEETS OF THE PERMIT PLANS.
- 6. ANY STORM DRAINAGE DISCHARGING INTO A CONFINED WORK AREA FROM EXISTING OR PROPOSED STORM DRAINAGE PIPES SHALL BE DIVERTED OR PUMPED OUTSIDE THE CONFINED AREAS. PUMPS/PIPES SHALL BE SIZED BY THE CONTRACTOR TO HANDLE THE EXPECTED FLOWS AND BE DISCHARGED TO A STABLE LOCATION. THE CONTRACTOR SHALL SUBMIT THE MEANS AND METHODS OF HANDLING STORM DRAINAGE TO THE ENGINEER FOR APPROVAL AND IS INCLUDED AS PART OF WATER HANDLING.
- 7. IF A SHORT DURATION PUMP SYSTEM IS PROPOSED DURING LOW FLOW CONDITIONS, THE PUMP SYSTEM SHALL BE DESIGNED BY THE CONTRACTOR AND HAVE A MINIMUM CAPACITY AS SHOWN IN THE TEMPORARY HYDRAULIC TABLE. PUMP SYSTEM PLAN SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL.


BASED UPON FIELD CONDITIONS, WORK DURATION, AND EXPECTED WEATHER CONDITIONS, THE ENGINEER MAY APPROVE A CONSTRUCTION WATER HANDLING PLAN WITH LOWER PUMPING FLOWS, PROVIDED THAT THIS INCLUDES A CONTINGENCY PLAN, WHICH MINIMIZES NEGATIVE IMPACTS AND SAFELY CONVEYS LARGER FLOWS THROUGH THE WORK AREA.

TIME-OF-YEAR BMP NOTE:

REV. DATE

ANY "UNCONFINED" INSTREAM WORK WITHIN THE BROOK SHALL BE RESTRICTED TO THE PERIOD FROM JUNE 1 TO SEPTEMBER 30, INCLUSIVE.





TEMPORARY HYDRAULIC	DATA
AVERAGE DAILY FLOW	3 CFS
AVERAGE SPRING FLOW	7 CFS
2-YEAR FREQUENCY DISCHARGE	46 CFS
SHORT-TERM, LOW FLOW PUMPING TEMPORARY DESIGN DISCHARGE = 2 x AVG DAILY	6 CFS
GRAVITY FLOW BYPASS PIPE TEMPORARY DESIGN DISCHARGE = 2-YEAR FREQUENCY	46 CFS
2-YEAR WATER SURFACE ELEVATION UPSTREAM	90.62 FT
2-YEAR WATER SURFACE ELEVATION DOWNSTREAM	89.02 FT

VALUES CALCULATED BY DOT'S **HYDRAULICS** AND **DRAINAGE** UNIT OR **CONSULTANT**

SUGGESTED SEQUENCE OF CONSTRUCTION

CONSTRUCTION OF THIS PROJECT WILL BE PERFORMED BY SHIFTING TWO-WAY TRAFFIC

STAGE 1:

- 1. COORDINATE WITH UTILITY COMPANIES TO RELOCATE UTILITY POLES AND GAS MAIN.
- 2. INSTALL SEDIMENTATION CONTROL SYSTEM (SCS).
- 3. PERFORM CLEARING AND GRUBBING, AS NECESSARY.
- 4. INSTALL TEMPORARY DEWATERING BASIN. BASIN TO REMAIN THROUGH ALL STAGES.
- 5. INSTALL TEMPORARY WATER HANDLING SYSTEM INCLUDING WATER-HANDLING-COFFERDAMS AND TEMPORARY PIPE. WATER HANDLING SYSTEM TO REMAIN THROUGH ALL STAGES.
- 6. CONSTRUCT TEMPORARY ROADWAY WIDENING.

STAGE 2:

- 1. SHIFT TRAFFIC TO SOUTH SIDE OF ROADWAY. EXCAVATE AND CONSTRUCT MICROPILES, CONSTRUCT FOOTINGS ON NORTH SIDE
- 2. PARTIALLY REMOVE TOP AND SIDE PORTIONS OF EXISTING CULVERT AND CONSTRUCT THE FINAL CHANNEL OUTSIDE THE TEMPORARY PIPE.
- 3. ERECT NORTH SIDE PRECAST CONCRETE THREE-SIDED FRAME UNITS. COMPLETE WINGWALLS 1A AND 2A. CONSTRUCT ENDWALLS AND BACKFILL. COMPLETE NORTH SIDE ROADWAY CONSTRUCTION.
- 4. COORDINATE WITH EXISTING OVERHEAD UTILITIES TO RELOCATE POLES AS SHOWN PRIOR TO STAGE 3 CONSTRUCTION. COORDINATE WITH UTILITY TO RELOCATE THEIR FACILITIES TO THE PERMANENT LOCATION ALONG THE OUTSIDE OF WINGWALLS 1A AND 2A.

STAGE 3:

- 1. SHIFT TRAFFIC TO NORTH SIDE OF THE ROADWAY.
- 2. EXCAVATE AND CONSTRUCT MICROPILES. CONSTRUCT FOOTINGS ON SOUTH SIDE.
- 3. PARTIALLY REMOVE TOP AND SIDE PORTIONS OF EXISTING CULVERT AND CONSTRUCT THE FINAL CHANNEL OUTSIDE THE TEMPORARY PIPE.
- 4. ERECT PRECAST CONCRETE THREE-SIDED FRAME UNITS ON SOUTH SIDE. COMPLETE ENDWALLS AND BACKFILL. COMPLETE STAGE 3 ROADWAY CONSTRUCTION.
- 5. REMOVE THE REMAINING PORTION OF THE EXISTING CULVERT AND COMPLETE CHANNEL CONSTRUCTION.
- 6. REMOVE TEMPORARY WATER HANDLING SYSTEM. INSTALL CHANNEL BOULDERS.
- 7. COORDINATE WITH GAS COMPANY TO RELOCATE FACILITIES TO THE PERMANENT LOCATION ALONG THE SOUTH FASCIA.
- 8. PERFORM FINAL GRADING AND INSTALL PLANTINGS.
- 9. REMOVE EROSION AND SEDIMENTATION CONTROL UPON PERMANENT STABILIZATION.


STAGING/WATER HANDLING PLAN:

- 1. THE PURPOSE OF THIS PLAN SHEET IS TO SHOW THE REGULATING AGENCY THE GENERAL INTENDED SCHEME FOR CONSTRUCTION/STAGING OF THE PROJECT AND ALSO THE METHOD(S) INTENDED FOR WATER HANDLING. IT IS EXPECTED THAT MORE DETAILED PLANS WILL BE DEVELOPED FOR FINAL CONTRACT PLANS AND PLANS WILL ALSO BE SUBMITTED BY THE CONTRACTOR. IT IS INTENDED THAT THESE PERMIT PLANS BE GENERAL ENOUGH THAT LATER CONTRACT PLANS CAN COMPLY WITH THE INTENT OF THE PERMIT PLANS.
- 2. A "HANDLING WATER TYPICAL SCHEMATICS" GUIDE HAS BEEN DEVELOPED AND CAN BE FOUND ON THE OEP WEBPAGE. THE GUIDE IS ALSO REFERENCED IN AN ENGINEERING DIRECTIVE ED-2019-6 WHICH INCLUDES ADDITIONAL HANDLING WATER INFORMATION.
- 3. SEQUENCING STATES THE BASIC INFORMATION FOR CONSTRUCTION OF THE PROJECT AS IT RELATES TO REGULATED AREAS. INCLUDE GENERAL WORK IN WETLANDS/WATERCOURSES, INSTALLATION OF ANY FISHERIES ENHANCEMENTS, AND INSTALLATION OF PLANTINGS AS REQUIRED FOR THE PROJECT.
- 4. CALL-OUT SIZE OF TEMPORARY PIPE FOR GRAVITY FLOW (OR MINIMUM CHANNEL WIDTH, IF APPLICABLE). CALL-OUT THE PUMP HOSE IF PUMPING (WITHOUT HOSE SIZE). LOCATION
- OF PUMP NOT REQUIRED. 5. SHOW DEWATERING BASIN (IF NEEDED). 6. INCLUDE WATER-HANDLING-COFFERDAM DETAIL AND THE PROPOSED TOP OF WATER-HANDLING
- -COFFERDAM ELEVATION. TOP ELEVATION TO BE EQUAL TO OR SLIGHTLY ABOVE TEMPORARY DESIGN STORM ELEVATION PER PROJECT SPECIFICS. A MAXIMUM ELEVATION MAY BE SPECIFIED DEPENDING ON PROJECT REQUIREMENTS. (DETAIL IS NOT REQUIRED TO BE SANDBAGS) 7. INCLUDE TEMPORARY HYDRAULIC DATA TABLE AS APPROPRIATE FOR PROJECT.
- 8. INCLUDE ANY REGULATORY TIME-OF-YEAR (TOY) RESTRICTION AS A NOTE ON THE PLAN. 9. STATE ANY PROHIBITED ACTIONS, IE. WATER HANDLING TECHNIQUES NOT ALLOWED
- 10. PLAN DATE (LATEST REVISION DATE OF SHEET. DATES DO NOT NEED TO MATCH WITHIN PLAN SET)

ENVIRONMENTAL PERMIT PLANS

PLAN DATE: SEPTEMBER 9, 2019

BLOCK: XXX-XXX THE INFORMATION, INCLUDING ESTIMATED STATE OF CONNECTICUT QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED REPLACEMENT OF **TOWN** DRAWING NO. INVESTIGATIONS BY THE STATE AND IS **BRIDGE NO. XXXXX PMT-06** IN NO WAY WARRANTED TO INDICATE DRAWING TITLE: THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED. SCALE IN FEET **DEPARTMENT OF TRANSPORTATION** ROUTE X OVER A BROOK STAGING/ WATER HANDLING PLAN SCALE 1"=20' REVISION DESCRIPTION Filename: ...\Staging Plan - Proj XXXrev - SchematicWH.dgn SHEET NO. Plotted Date: 9/11/2019



3. THE STOCKPILE SHALL BE LOCATED OUTSIDE THE WETLAND LIMITS AND PROTECTED WITH SEDIMENTATION CONTROL SYSTEM.

1" = 5' ENVIRONMENTAL PERMIT PLANS

PLAN DATE: JUNE 8, 2016

THE INFORMATION, QUANTITIES OF WO	DESIGNER/DRAFTER: , INCLUDING ESTIMATED ORK, SHOWN ON THESE CHECKED BY:	SIGNATURE/ BLOCK:	TLE: DEDIACEMENT OF	PROJECT NO. XXX-XXX
INVESTIGATIONS B IN NO WAY WARR THE CONDITIONS	ON LIMITED BY THE STATE AND IS RANTED TO INDICATE OF ACTUAL QUANTITIES WILL BE REQUIRED. SCALE AS NOTED STATE OF CONI DEPARTMENT OF TRA	OF TRAN	BRIDGE NO. XXXXX ROUTE X OVER A BROOK DRAWING TITLE: ELEVA	
REV. DATE REVISION DESCRIPTION SHEET NO. Plotted Date: 6/10)/2019 Filename:\ElevationsRev - Proj XXX.dgn		SECI	ION PLAN

