CONNECTICUT DEPARTMENT OF TRANSPORTATION

BUREAU OF ENGINEERING AND CONSTRUCTION

OFFICE OF CONSTRUCTION DIVISION OF MATERIALS TESTING



Quality Assurance (QA) Program for Materials Acceptance and Assurance Testing Policies and Procedures

Prepared by Materials Testing Staff

Chapter 1 – Purpose	4
Chapter 2 – Division of Materials Testing Overview	5
ORGANIZATIONAL CHART	6
Project Support & Portland Cement Concrete (PS) Section District Laboratories' Operations Physical Testing Lab/Cement Precast Concrete Fabrication	7 7 7
Hot Mix Asphalt and Final Material Certification (HMA) Section Bituminous Materials Laboratory Final Materials Certification and File Retention HMA Verification HMA Density HMA Plant Acceptance	8 8 8 8 8
Independent Assurance and Field Inspection (IA) Section HMA Assurance and Dispute Resolution HMA Plant Inspection Material Certification SiteManager Structural Steel Fabrication Plant/Field Operations Consultants/Fabrication Records	8 9 9 9 9 9 9 9
Chapter 3 – Active Material Code Definitions Paint/Coatings/Markings Landscaping Materials Precast Concrete Drainage Materials Pipe Steel Reinforcement Portland Cement Concrete Prestressed/Post-Tensioned/Concrete Members Portland Cement/Chemical Anchor Joint Materials Brick and Block Metal Castings Fences Railings Structural Anchors & Bearings Structural Anchors & Bearings Steel Items- Structural Steel Highway Lighting & Traffic Control Hot Mix Asphalt Materials	10 10 12 13 14 14 15 15 15 16 17 17 18 18 19 20 20
Chapter 4 – Materials Evaluation and Testing Procedures	25
Materials Evaluation	25
Materials Testing Procedures Sampling Materials for Test Aggregates	25 25 26
Precast Concrete Production Facility Inspection Reinforced Concrete Pipe Precast Concrete Drainage Items	26 26 27
PRECAST/PRESTRESSED CONCRETE (STRUCTURAL)	29

PORTLAND CEMENT CONCRETE (ALL) Concrete Batch Plants and Delivery Vehicles	31 31
Mass. Yield. and Air Content (Gravimetric) of PC Concrete	
Assurance Report (DMT Only): MAT-224, or MAT-225, and MAT-222	
Admixtures	
Structural Steel and Welding Shop Inspection	
HOT MIX ASPHALT (BITUMINOUS CONCRETE/SUPERPAVE)	
Annual Qualification of Hot Mix Asphalt Plants	
Sampling HMA Mixtures	
HMA Inspection Personnel Assignment Procedure	
Correlation Between Production Pull and Binder Content by Ignition Method	
Mechanical Analysis of Extracted Aggregate	
Degree of Particle Coating of HMA Mixtures	
Bulk Specific Gravity of Compacted HMA Mixtures	
Preparation of Gyratory Specimens	
Maximum Specific Gravity of HMA Paving Mixtures	
Status of New Mixes, Existing Mixes From Previous Year's Production	
MIX Design / Job MIX Formula(JMF) Submittal and Change Procedure	
HMA Verification Testing Procedures	
HMA Independent Assurance Procedures	
Mix Design / Job Mix Evaluation	
HMA PPT Verification	
Volumetric and Specific Gravity Using Gyratory Compactor	
Performance Graded Asphalt Binder (PGAB)	
DENSITY OF SOIL AND SOIL - AGGREGATES	40
DENSITY OF IN-PLACE ASPHALT PAVEMENT BY THE CORE METHOD	
Chapter 5 – AMRL Document	41
Chapter 6 – Independent Assessment/Verification Program	42
Chapter 7 – Minimum Schedule for Acceptance Testing (Non-NHS)	43
Chapter 8 – Minimum Schedule for Acceptance Testing	
Chapter 9 – Minimum Schedule for Assurance Testing	57
Appendix A – Reporting Forms	A1
Appendix B – Final Materials Certification	B1
Appendix C – Sample Scope of Work for Third-Party Testing Agency	C1
Appendix D – Active Material Codes	D1
Appendix E – Certification of Portland Cement Program	E1
Appendix F – Connecticut Reference File Specifications	F1
Appendix G – Standard Operating Procedures.	G1
Index	H1

Chapter 1 – Purpose

This manual describes the organization, functions, and procedures performed by the Connecticut Department of Transportation's (Department) Division of Materials Testing (DMT) relating to sampling, testing, and inspection of materials incorporated into Department projects or State funded municipal projects. In addition, the procedures used to verify Contractor test results and the Department's independent assurance test programs are also described. These functions and procedures comply with the criteria set forth in Federal Regulation 23 CFR 637, CONSTRUCTION INSPECTION AND APPROVAL, which governs quality assurance on all federal-aid highway projects on the National Highway System.

It is the function of the DMT to predetermine in some cases, and determine prior to completion of the work in other cases, if materials used by Contractors and the Department in the construction and maintenance of transportation facilities comply with the specification requirements and plans, and to assist others within the Department with developing and maintaining materials specifications and materials-related project specifications. Occasionally, DMT personnel perform investigational work on new materials and procedures. Testing procedures utilized by DMT personnel are as specified in the current edition of the ConnDOT Standard Specifications; Standard Specifications and Methods of Sampling and Testing by the American Association of State Highway and Transportation Officials (AASHTO); the American Society for Testing and Materials (ASTM); and ConnDOT Reference Files.

The method and frequency of testing of materials used in the construction of Department projects are identified in the "*Minimum Schedule for Acceptance Testing*" and the "*Minimum Schedule for Assurance Testing*," Chapters 8 and 9 of this manual respectively. The schedules are arranged according to standard contract item nomenclature common to the Department's Standard Specifications and listing of contract items.

All contract items within the Department's highway construction management system (SiteManager) have been, and continue to be, reviewed and where appropriate have material(s) that typically require testing associated to them. Appendix D lists the material codes used in SiteManager. During the course of a project, modifications to these associations may be required on a project-by-project basis due to a changed field condition or Contractor selections. As materials are used on the project, project personnel submit a "Request for Test" at the frequency described in the minimum test schedules to the DMT to perform whatever actions are necessary to make a recommendation to the contract administrator as to the acceptability of these materials in relation to the specific contract item. These actions are typically referred to as "acceptance testing" and may include physical testing, visual inspection, and/or review of pertinent documentation for a sample of the total material used.

Actions showing that the samples meet the acceptance criteria stated within the contract specification generally would prompt a recommendation of acceptance from the DMT for that material quantity represented by the sample. Conversely, actions showing that samples do not meet the acceptance criteria stated within the contract specification generally would prompt a recommendation of rejection.

The typical percentages of test requests processed annually by the DMT are listed below in decreasing order.

Material Name	% of
Hot Mix Asphalt (All)	23
Aggregates	13
Precast Concrete (All)	20
Concrete (PCC)	33
Asphalt Binder, Emulsions Sealers	2
Reinforcing Steel & Steel Hardware	6
Structural Steel	3
Totals	100

The contract administrator, in most cases a District Engineer, is ultimately responsible for the acceptance of the total material quantity used on a project and may accept materials recommended for rejection, or reject materials recommended for acceptance, in accordance with the Department's Specifications.

Assurance testing is performed independently from acceptance testing to assure that personnel are performing the testing procedures in accordance with the applicable sampling and testing specification and that the testing equipment used is calibrated and working properly.

After all construction on a project is completed and all requests for test have been processed, a Final Materials Certificate (FMC) is issued by DMT staff that reconciles the testing for materials that are subject to testing and/or inspection and their installed quantities. Any materials that were subject to testing and were permanently incorporated into the project that were not accepted in accordance with the specifications are listed as exceptions to the project specifications.

Chapter 2 – Division of Materials Testing Overview

The Division of Materials Testing (DMT) consists of three Sections, Project Support and Portland Cement Concrete; Independent Assurance and Field Inspection; and HMA & Final Materials Certification. All are under the jurisdiction of the Division Chief for the Office of Construction (DC) and the Principal Engineer for Materials Testing (PEMT). The DC, as the Department's representative to the AASHTO Subcommittee on Materials (SOM), advises and assists in the preparation and continuous revision of AASHTO specifications used by transportation agencies throughout North America.

The PEMT maintains an association with Materials Testing Engineers of other states through AASHTO correspondence and their annual meeting and maintains a close association with the surrounding states Materials Testing Engineers through the Northeastern States Materials Engineers' Association (NESMEA). The PEMT also maintains a close relationship with professional organizations such as the New England Transportation Technician Certification Program (NETTCP); Northeast Asphalt User /Producers' Group (NEAUPG); and the Northeast Protective Coating Committee (NEPCOAT).

The DC and PEMT are responsible for administering and providing direction for the technical operations such as the personnel policies, affirmative action goals, union contracts, code of ethics, and other pertinent Department technical guidelines/policies that are brought to the attention of, and enforced by, each individual section supervisor in the DMT.

The PEMT is assisted by three Transportation Supervising Engineers (TSEs) who lead the three sections and a complement of 45 employees. The organization of the Division of Materials Testing is graphically represented in the following Organizational Chart. (Figure 1)

It is the responsibility of the TSEs to supervise the day-to-day operations of the three sections in order to assure that materials are recommended for approval or rejection and the specified sampling and testing procedures are followed. Testing results are input to SiteManager for dissemination to the appropriate construction project and District personnel. This serves as a historical record of materials tested for use on a construction project or maintenance activity and their status during the testing process.

The duties of the three TSEs also include the submission of budget, equipment, and overtime requirements; investigation of materials failures; and communication with Contractors and Engineers on materials specifications and specific project-level issues.

The DMT participates in the AASHTO Accreditation Program (AAP). This program provides accreditation for laboratories that meet strict organization, personnel, equipment, and testing proficiency requirements. The program includes the following construction materials pertinent to the Division of Materials Testing: Asphalt Cement, Performance Graded Binder, Emulsified Asphalt, HMA, HMA Aggregate, Portland Cement Concrete, and Portland Cement Concrete Aggregate.

Figure 1. ORGANIZATIONAL CHART January 2019



Division of Materials Testing Overview (cont.)

Project Support & Portland Cement Concrete (PS) Section

The PS Section is primarily involved with the operation of the satellite laboratories in each of the outlying Districts and the testing and inspection of Portland cement concrete and precast and prestressed concrete members. In conjunction with those materials, this section also performs the physical testing of steel reinforcing material and other steel-related items. A large part of the service provided by this section is the support of the active construction projects and delivering some material samples to the Central Laboratory. Visits to the project sites are commonly done to retrieve all types of samples, assist project personnel in the submittal of all samples, and to assist in the testing of materials on site, or the assurance testing of PC concrete.

The PS Section of the DMT is divided into three functional units: District Laboratories' Operations, Physical Testing Lab/Cement, and Precast Concrete Fabrication Operations.

District Laboratories' Operations

This unit oversees the operations of the three satellite District Laboratories located in each of the outlying three Districts and the Central Laboratory's District 1 Lab in Rocky Hill. These laboratories are located in each District Office within the State to expedite the sampling and testing of common materials, such as aggregates. The unit is also responsible for maintaining an active independent assurance testing program for aggregates and concrete for the satellite District Laboratories consistent with that of the Central Laboratory.

The satellite District Laboratories are primarily assigned materials sampling and testing for projects within the District in which they are located.

The principal duties of the satellite District Laboratories are as follows:

- Perform acceptance testing of fine and coarse aggregates including but not limited to gradation analysis, specific gravity, density, and unit weight.
- Determine laboratory maximum density of soils and processed aggregates.
- Inspect metal pipe and metal culvert ends at project sites.
- Inspect and sample transportation materials at quarries, gravel banks, Portland cement concrete plants, and other sources of supply for Department projects.
- Perform acceptance sampling and testing of fine and coarse aggregates.
- Observe assurance sampling and testing for aggregates and Portland cement concrete.
- Obtain samples and transport them to the Central Laboratory as needed.
- Inspect any new sources of materials.
- Assist Division of Purchasing regarding sampling and testing of road salts.

The District 1 Lab located within the Central Laboratory facility performs the same operations as the satellite District Labs with the additional task of checking the satellite District Labs' test results for aggregates using split samples and performing additional tests on fine and coarse aggregates such as soundness, resistance to degradation by abrasion and impact, specific gravity, absorption, unit weights, angularity, and elongation.

Physical Testing Lab/Cement

The responsibilities of the physical testing unit include the testing for compressive strengths of concrete cylinders, testing of drilled cores, properties of brick and block, the tensile strengths of several ferrous and nonferrous structural steel products, the Rockwell or Brinell hardness of structural steel products, the coating thickness of zinc and epoxy coated products, and evaluating weld coupons for welder certification testing. This subsection may also perform testing on new products and materials being evaluated by the Department.

Precast Concrete Fabrication

This unit acts as a liaison with precast concrete producers and project personnel to schedule on-site inspections and resolve technical and administrative issues. Inspectors in this unit are responsible for the quality assurance of prefabricated concrete products. These products include reinforced concrete pipe, precast and prestressed concrete items. The overall duties of the individual inspectors are to monitor the fabricators compliance to their own Quality Control (QC) Plan on file with the Department. At varying frequencies, the inspectors also sample

all component materials for compliance with the Department's specifications; inspect the casting beds and forms to ensure dimensional conformance to the approved drawings; observe the concrete batching operation to ascertain conformance to an approved mix design; witness plastic concrete testing; observe the concrete placement and consolidation operation; witness the compression testing of specimens; inspect the finished product for conformance to dimensional tolerances and finished appearance; and maintain complete and accurate Department records for all phases of the work. Consultants under contract to the Department are used as needed to supplement DMT personnel to meet this responsibility.

Hot Mix Asphalt and Final Material Certification (HMA) Section

The HMA Section is divided into five functional units: Bituminous Materials Lab, Final Materials Certification and File Retention, HMA Density, HMA Verification Lab, and HMA Plant Acceptance.

Bituminous Materials Laboratory

This unit is responsible for testing of various performance graded (PG) binders and other petroleum based products. HMA paving and associated products physically tested by this unit are PG Binders, emulsified asphalts and bituminous component materials used in Ultra-thin HMA. In addition, this unit reviews binder and emulsified asphalt suppliers QC Plans and other required documentation to maintain the supplier certification by AASHTO R 26 and AASHTO R 77.

Final Materials Certification and File Retention

This unit is responsible for tracking material testing data on a project to ensure that all materials permanently incorporated into the project are tested/certified in sufficient quantity and that the results are acceptable or alternative acceptance criteria are met. Upon request from the District, a final materials certificate is provided for all completed projects stating the disposition of all materials incorporated into the project. If applicable, exceptions to the project specifications are listed individually on the certificate. Examples of this certification are in Appendix B.

HMA Verification

This unit is responsible for verifying that mix designs are in compliance with project specifications and for validating Contractor data used for acceptance. Comparison testing during the paving season is performed on test specimens that are fabricated by both Contractor or DMT staff. Test records are maintained for each mixture type produced by each vendor providing materials to the Department. The HMA Verification unit also performs extraction and aggregate tests on samples and investigates new mix designs, additives, and aggregate sources.

HMA Density

The HMA Density unit performs tests on extruded core samples and processes results for payment adjustment. A report is submitted to project staff for processing. Upon request, the HMA Density Unit also assists Pavement Management by extracting core samples for evaluation during the design phase of a project.

HMA Plant Acceptance

Staff in this unit are responsible for monitoring HMA producer QC testing at the plant used for acceptance on a project-by-project basis and processing the results for payment adjustment purposes. HMA mix designs are also reviewed by staff in this unit for compliance to the project specifications and monitors changes in materials sources and the resulting mix design changes during the paving season. During the winter months, staff review producer generated QC Plans to ensure that the current specification requirements are recognized and any revisions are acceptable to the Department.

Independent Assurance and Field Inspection (IA) Section

This Section is divided into six units: HMA Assurance and Dispute Resolution, HMA Plant Inspection, Material Certification, SiteManager, Structural Steel Fabrication Plant/Field Operations, and Consultants/Fabrication Records.

This Section of the DMT is primarily responsible for assuring that fabrication, welding, and HMA testing is being performed by qualified and certified Department and/or Contractor personnel. Quality Assurance checks are performed to ensure accordance with standard test procedures and that the equipment used is in

working order and calibrated. This typically includes a review of personnel qualifications, calibration records, witnessing test procedures, and performing assurance or verification testing.

This Section is also responsible for the day-to-day administration of a consultant contract for the testing of structural steel at various out-of-state fabricators, and other seasonal inspection needs within the State; the review and processing of the consultant inspection reports; the update and maintenance of the materials module of SiteManager and interacting with construction field inspectors to revise and maintain materials testing results for individual projects; and addressing building-related issues for ConnDOT personnel within the facility.

HMA Assurance and Dispute Resolution

This unit follows an independent process from acceptance testing to ensure that material sampling and testing of HMA by Contractor and DMT personnel, is performed correctly. The process evaluates personnel sampling and testing material for compliance with established standard test procedures and evaluates the equipment used for acceptance testing for adequacy and calibration. The evaluation process generally involves witnessing personnel during the testing procedure and documenting what is observed on the "Report of Witness" (MAT-600) form. Test equipment is evaluated through calibration checks, testing split samples, or any combination of these methods. This unit is also responsible for performing HMA production dispute resolution testing when verification validation has failed and a request to dispute is made by the Contractor.

HMA Plant Inspection

This unit is responsible for quality assurance of all HMA material used on construction and maintenance projects. This is accomplished through the inspection of HMA material at the plant. All producers are required to have a field laboratory to provide a DMT inspector immediate access to test results to assure material meets the specification at the plant. In addition to the testing of HMA, the plant inspectors sample the binder; observe the production and quality control processes; inspect fine and coarse aggregates; verify batch weights, mix temperatures, and appearance; and check plant machinery and hauling vehicles for specification compliance. The supervisor of this section is responsible for daily field supervision and observation of field technicians sampling and testing techniques; performing plant and field lab inspections; notifying producers of material problems; performing verification sampling and testing; training and reviewing procedures and specifications with the field personnel; serving as a liaison between material producers and project personnel to remedy material issues; and working closely with the HMA Plant Acceptance unit for QA and investigative tasks.

Material Certification

This unit is responsible for the review of material certificates to determine if the documentation provides the information necessary to recommend acceptance of the material. Following the issuance of the Final Materials Certificate for a particular project, personnel in this unit also compile and review the project records in accordance with the Department's record retention policies so that they can be transferred to the Department's record storage facility in Newington.

<u>SiteManager</u>

Staff are responsible for updating and maintaining the materials module of the SiteManager Reporting System and interacting with construction field inspectors and DMT personnel to revise and maintain materials testing results for individual projects.

Structural Steel Fabrication Plant/Field Operations

This unit has the responsibility to assure that all materials and physical aspects of structural steel fabrication are in compliance with the applicable specifications. Duties of this unit include the review and approval of shop and field welding procedures; assistance to other Department personnel regarding welding techniques and procedures; on-site audits and review of field welding and in-state fabrication; testing and certification of Department approved welders; and any related duties as they apply to structural steel fabrication.

Consultants/Fabrication Records

DMT personnel monitor consultant contracts for structural steel fabrication inspection on a day-to-day basis. Personnel in this unit are also responsible for the review and processing of steel fabrication inspection reports and making technical recommendations to the TSE of the section.

Chapter 3 – Active Material Code Definitions

Paint/Coatings/Markings

00031 PAINT – PRIME COAT FOR STRUCTURAL STEEL 00032 (Interim), 00033 (Top), 00039 (Field)

STRUCTURAL STEEL COATINGS

Sampling: Samples of coatings are generally not required unless specified in the Special Provisions. **Procedure:** Fabricators of structural steel are responsible for making themselves aware of the entire coating specification for each individual project prior to starting the work. The DMT must be notified in advance of any coating work on structural steel for Department use. Field painting and touch-up work must conform to Standard Specifications, Article 6.03.03-38. Project personnel are responsible for submitting a MAT-100 when the material is delivered to the project site.

Specification: As specified in a Special Provision or Standard Specifications, Section 6.03 and M.07.

00054 PAVEMENT MARKING PAINT, 15-MINUTE DRY, WHITE AND YELLOW **Scope:** White and yellow pavement marking paint **Sampling:** Samples are generally not required unless specified in the Special Provisions.

Sampling: Samples are generally not required unless specified in the Special Provisions. **Procedure**: As listed in Specification(s)

Specification/Report Form(s): Federal Specification Paint TT-P-1952, Reference File No. 207D and M.07 / MAT-236, MAT-237, or MAT-240.

00060 PAINT-Waterborne Pvmnt Mark, 3-MINUTE DRY, WHITE AND YELLOW Scope: White and yellow low-heated, fast-drying pavement marking paint Sampling:Samples are generally not required unless specified in the Special Provisions. Procedure: Same as 00054 Specification/Report Form: Federal Specification Paint TT-P-1952, Reference File No. 2001 and Section M.07

/ MAT-235, MAT-238, or MAT-239.

00091 PAINT EPOXY PAVEMENT MARKINGS

Scope: White and yellow epoxy resin pavement marking paint **Sampling:** Samples are generally not required unless specified in the Special Provisions.

00097 Sand Blasting

00097 SAND BLAST DEBRIS (Toxicity Test) Scope: Sandblast debris from bridge painting. Sent to third-party laboratory for testing. Sampling and Procedure: EPA Method 1311 Specification/Report Form: Connecticut DEEP Drinking Water Remediation Standards / NA

00297 to 00303 Snow & Ice Control 00297 CALCIUM CHLORIDE (LIQUID) 00302 CALCIUM CHLORIDE Scope: Highway Maintenance use only. Sampling and Procedure: None Specification/Report Form: AASHTO M 144 / NA

00298 SODIUM CHLORIDE (INERTIAL BARRIERS)

00303 SODIUM CHLORIDE (ROCK SALT)

Scope: All sodium chloride used for snow and ice control on highways; or for use in inertial barriers.

Sampling: For snow and ice control AASHTO T 2, none for inertial barriers.

Procedure: Sieve analysis, AASHTO T 27; chemical, ASTM E 534; moisture content, AASHTO T 265. **Specification/Report Form:** For snow and ice control, ConnDOT Reference File No. 139 / MAT-208. For inertial barriers, Standard Specifications, Section 18.07 (Materials Certificate) / NA.

00302 CALCIUM CHLORIDE (TON)

Scope: All calcium chloride used for snow and ice control on highways.

Sampling: For snow and ice control AASHTO T 2, none for inertial barriers.

Procedure: Sieve analysis, AASHTO T 27; chemical, ASTM E 534; moisture content, AASHTO T 265. **Specification/Report Form:** For snow and ice control, ConnDOT Reference File No. 139 / MAT-208. For inertial barriers, Standard Specifications, Section 18.07 (Materials Certificate) / NA.

00306 GLASS SPHERES (GLASS BEADS)

NOTE: All other material codes for glass beads are inactive.

Scope: Glass spheres (glass beads) for application on pavement markings. Sampling: One sample will be provided for each Lot Number and forwarded to the DMT by the manufacturer. Procedure: AASHTO M 247

Specification/Report Form: AASHTO M 247, Type 1 and 4 / MAT-228 or MAT-229

00310 PAVEMENT MARKING, PLASTIC, PREFORMED

Scope: Pavement Marking tape used on roadway surfaces.
 Sampling and Procedure: None.
 Specification/Report Form: Standard Specifications, Section 12.12 or Special Provision

00327 WATER

Scope: For production of PCC and any other material or process.
 Sampling and Procedure: None for potable sources. For other sources, ASTM C 1602.
 Specification/Report Form: Standard Specifications, Article M.03.01-4 / MAT-230

00328 PROTECTIVE COATING

Scope: For use on Bridges Sampling and Procedure: Material Certificate review by Project Staff Specification/Report Form: Qualified Products List

Landscaping Materials

00496 FERTILIZER (Ibs) 00512 FERTILIZER (sy) Scope: Fertilizer for use in turf establishment. Sampling: None. Procedure: Standard Specifications, M.13.03 Specification/Report Form: Standard Specifications, Article M.13.03 / NA

00497 SEED

Scope: Mixtures to establish turf or grass.
Sampling: None
Procedure: Standard Specifications, Article M.13.04
Specification/Report Form: Standard Specifications, Article M.13.04 / NA

00510 PEAT

Scope: Commercially package peat from sedge, sphagnum or reed sources used on planting soil.
Sampling: None - visual inspection by project personnel.
Specification/report Form: Standard Specification, Article M.13.07 / NA
00518 SOD
Scope: Sod used for the immediate establishment of a grass surface.
Sampling: None - visual inspection by project personnel.
Procedure: Project personnel contact Landscape Design Unit
Specification/Report Form: Standard Specifications, Article M.13.08/ NA

00533 LIME Scope: For use plantings and turf establishment items. Sampling and Procedure: None Specification/Report Form: Visual inspection by project staff.

00534 MULCH – ALL TYPES Scope: For use in plantings and turf establishment items Sampling and Procedure: None Specification/Report Form: Visual inspection by project staff.

00536 PLANT MATERIALS

07547 TREE Scope: All living plant materials are to be inspected by staff from the Department's Landscape Design Unit. A MAT-100 is NOT required. Initial contact and follow up is the responsibility of project staff. Sampling: None - visual inspection by Landscape Design personnel. Procedure: Project staff contact Landscape Design Unit Specification/Report Form: Standard Specifications, Article M.13.07/ NA

00542 TOP SOIL Scope: Cut and fill material taken from the project site and used on the project site. Sampling: None - visual inspection by project personnel. Specification/Report Form: Standard Specifications, Article M.13.01 / NA

00542X TOP SOIL 00542P PLANTING SOIL Scope: Soil brought from off the project site for use under items 0949XXX furnishing and planting trees. Sampling: None. Materials Certificate and Certified Test Report submitted with MAT-100. Specification/Report Form: Standard Specifications, Article M.13.01 / NA

04776 HAY, BALED Scope: For erosion control Sampling: None Specification/Report Form: Visual inspection by Project staff

Precast Concrete Drainage Materials

00699, 1700, 1708 Reinforced Concrete Pipe 00699 REINFORCED CONCRETE PIPE 01708 PIPE – FOR UNDERDRAIN or OUTLET Scope: Plain and perforated concrete drain pipe. Sampling: Each size and type of pipe is subject to 3-edge bearing and absorption tests each spring. Procedure: AASHTO M 170 and AASHTO T 280. Specification/Report Form: Standard Specifications, Article M.08.01-7 / MAT-314

Precast Units For Drainage Structures

00800 to 01650 Precast Concrete Drainage & Misc. Refer to Appendix D for material codes

Scope: Precast concrete units to be used in the construction of drainage structures. Precast units shall include, but not be limited to, products such as box culverts, catch basins, drop inlet and manhole tops, riser sections, sumps and other appurtenances. The recommendation for acceptance of precast units is based on the manufacturer's certification that the units conform to the project specifications. Ultimate acceptance of the material should be based on receipt of the manufacturer's certification MAT-314 (PC-1) and a visual inspection by project personnel following delivery.

Pipe

01708 PIPE – FOR UNDERDRAIN OR OUTLETScope: Iron or steel pipe used for drainage Sampling and Procedure: None Specification/Report Form: M.08.01 -1/Request for test with Materials Certificate

01783 PIPE – ALUMINUM & FITTINGS & ACC. Scope: Material used for drainage Sampling and Procedure: None Specification/Report Form: M.08.01/Visual Inspection by Project Staff

01790 PIPE ARCH ALUMINUM 01807 CULVERT END – ALUMINUM 02018 CULVERT END – COATED METAL Scope: Material used for drainage Sampling and Procedure: None Specification/Report Form: M.08.01, Field inspected by Project staff / Materials Certificate in project files

01940 to 2650 PIPE (Metal, Iron, Poly, PVC)

01940 PIPE – CCM, Fittings & Accessories 01977 PIPE – ACCM & Fittings & Accessories Scope: The field inspection of metal and aluminum pipe and structural plate pipe and pipe arches. Sampling: Depending on the size of the shipment, one or two representative pieces of metal pipe, bands, and accessories are selected by DMT and inspection personnel for testing. Procedure: Procedures and measurements are shown in the "Field Inspection of Metal and Aluminum Pipe" procedure in Appendix G. Materials Certificates and Certified Test Reports are also required. Report Form: MAT-200, MAT-201, MAT-202, MAT-203, or MAT-204.

02110 PIPE – CAST IRON & FITTINGS & ACCESSORIES 02449 PIPE – COPPER & FITTINGS & ACCESSORIES 02501 DUCTILE IRON PIPE & ACCESSORIES 02724 PIPE- STEEL & FITTINGS & ACCESSORIES Scope: This section covers welded and seamless steel pipe. Sampling: ASTM A 53 and as supplemented in Standard Specifications, M.06.02. Procedure: ASTM A 53 and as supplemented in Standard Specifications, M.06.02. Specification/Report Form: Standard Specifications, Article M.06.02. / MAT-100

02600 POLYETHYLENE PIPE 02673 POLYETHYLENE PIPE FITTINGS AND ACCESSORIES **Scope:** Plastic and polyethylene corrugated pipe or tubing for use in drainage. **Sampling and Procedure:** None - visual inspection by project personnel. **Specification/Report Form:** Standard Specifications, Article M.08.01. / MAT-100.

02649 POLYVINYL CHLORIDE PLASTIC PIPE

Scope: This section covers polyvinyl chloride plastic pipe, elbows, and couplings for highway drainage.
 Sampling and Procedure: None - visual inspection by project personnel.
 Specification/Report Form: Standard Specifications, 5.13 and Article M.08.01 / NA

002731 PIPE 04178 PIPE JOINT COMPOUND Scope: Cold applied bituminous sealer for reinforced concrete pipe. Sampling/Procedure: None/None Specification/Report Form: Standard Specifications, M.08.01 / NA 03166 SHEETING POLYETHYLENE Scope: Material Used for Environmental Items Sampling and Procedure: None Specification/Report Form: Special Provision.Visual Inspection by Project Staff.

Steel Reinforcement

02995 DOWEL SPLICE SYSTEM EPOXY COATED 02997 DOWEL SPLICE SYSTEM 02998 DEFORMED STEEL BARS, EPOXY COATED 03100 DEFORMED STEEL, REINFORCING 03100-G DEFROMED STEEL.REINFORCING - GALVANIZED 03100-SS DEFROMED STEEL.REINFORCING - STAINLESS STEEL 03102-FRP REINFORCING BARS - FIBER REINFORCED PLASTIC 03138- DOWELS, STEEL

Scope: Bars for Portland Cement concrete reinforcement.

Sampling: A sample of each size bar will be submitted for each shipment as follows: All sizes-one sample per size for each 200 tons. Samples submitted for test will be cut from the shipment on the project site and will be not less than 5 ft. (1.5 m) in length. When multiple mills are the source of the bars, a sample from each source must be provided regardless if a sample for that size has already been tested.

Procedure: AASHTO T 244

Specification/Report Form: Bar reinforcement will be tested according to procedures prescribed in AASHTO M 31. Epoxy coated reinforcement shall be tested as prescribed in AASHTO M 284. Galvanized, stainless steel and FRP bars shall be tested in accordance with the special provision. Standard Specifications, Article M.06.01.

03145 WIRE AND WELDED WIRE STEEL WIRE FABRIC (MESH)

Scope: This section covers wire and welded steel wire fabric for use as concrete reinforcement. **Sampling:** A 1 yd² (0.9 m²) sample of each type will be submitted for test per 8,000 yd² (7,000 m²) of fabric used.

Procedure: AASHTO T 244 **Specification:**

- Cold-drawn steel wire: AASHTO M 32
- Welded steel wire fabric: AASHTO M 55
- Deformed steel wire: AASHTO M 225
- Welded Deformed Steel Wire Fabric: AASHTO M 221

Report Form: MAT-306 or 328

Portland Cement Concrete

03014-X Concrete Class - X 03014-SPXK Concrete Spec. Prov. (X000psi/Mpa) 03014-other 03015 – X Mix Class Designations such as "PCC04462" Scope: Fresh Portland Cement Concrete Testing Sampling: Project personnel are responsible for sampling the concrete at the point of placement.

Procedure: Sampling - AASHTO T 141, Slump - AASHTO T 119, Temperature - AASHTO T 309, Air Content - AASHTO T 152 or AASHTO T 196, Making and Curing Concrete Test Specimens in the Field - AASHTO T 23. Project personnel are responsible for filling the cylinder molds, determining air content, temperature, and slump. Cylinders must be immediately placed where they can remain undisturbed for at least 24 hours. **Assurance Report (DMT Only):** MAT-224, or MAT-225, and MAT-222

Acceptance Report (Project Personnel): MAT-308

03016 NON-SHRINK, NON-STAINING GROUT (BATCHED) 03040 NON-SHRINK GROUT (BAGGED) 03025 MORTAR Scope: Non-shrink grout. Sampling: Project personnel are responsible for reviewing the markings on the bags containing the material indicating compliance with the specifications. Procedure: Visual inspection of bag. Specification/Report Form: Standard Specifications, Article M.03.01 / NA

Prestressed/Post-Tensioned/Concrete Members

03050 CONCRETE MEMBERS - PRESTRESSED 03051 CONCRETE PILES – PRESTRESSED

Scope: Due to the critical function of precast, prestressed, and post-tensioned concrete members as loadbearing units of bridges and structures, the DMT assigns an inspector to the manufacturing plant to inspect, in detail, all phases of manufacture. Details of this inspection are provided in Chapter 4.

08042 PULL BOX – PRECAST CONCRETE 08044 RETAINING WALL – PRECAST CONCRETE 08069 PREFABRICATED BRIDGE UNITS

Scope: Precast, prestressed, and post-tensioned concrete members for use in structures.

Procedure: Precast, prestressed, and post-tensioned concrete members are inspected at the fabricating plant during fabrication and immediately prior to shipment by a representative of the DMT to ensure conformance with the requirements of the applicable specifications. Representative samples of component materials used in the manufacture of these concrete members may be sampled and tested to determine compliance with Standard Specifications. Details of this inspection are provided in Chapter 4.

Portland Cement/Chemical Anchor

03062 PORTLAND CEMENT TYPE III

03066 PORTLAND CEMENT TYPE I/II

Scope: Portland cement used in the production of concrete for Department projects.

Sampling/Procedure: All Portland cement producers are required to submit quarterly test reports to the DMT in accordance with the requirements of Appendix E, "Criteria for Acceptance of Portland Cement by Certification."

Specification/Report Form: Standard Specifications, Article M.03.01 / None

03105 CHEMICAL ANCHOR

Sampling and Procedure: No sample required. Accepted based on Department's Qualified Products List. **Specification:** Standard Specifications, Article M.03.07

Joint Materials

03092 BITUMINOUS CONCRETE JOINT/CRACK SEALER 03093 BITUMINOUS CONCRETE JOINT/CRACK FILLER 03094 JOINT SEALANTS Scope: This section covers joint sealants for use in PC concrete structures (excluding pavements). Sampling: None Procedure: DMT personnel are responsible for reviewing the Materials Certificate and Certified Test Report. Specification/Report Form: Standard Specifications, Article M.03.01 / MAT-100

03155 EXPANSION JOINT FILLER

03158 PREFORMED EXPANSION JOINT FILLER

Scope: This section covers corrosion-resistant load transfer devices, preformed expansion joint fillers, and wood joint filler.

Sampling and Procedure: None. Project staff reviews the Materials Certificate for compliance with contract specifications.

Specification/Report Form: Standard Specifications, Article M.03.01/ NA.

03432 JOINT SEALER, ELASTOMERIC COMPRESSION

03444 CLOSED CELL ELASTOMER

Scope: Elastomeric material and lubricant adhesives for use in transverse joints in concrete structures. **Sampling and Procedure:** None. Project staff reviews the Materials Certificate for compliance with contract specifications.

Specification/Report Form: Standard Specifications, Article M.17.02 / NA

04177 JOINT SEALER, CONCRETE STRUCTURE

06659 EXPANSION JOINT SEALER

Scope: Joint sealants of the hot poured type for use in all PC concrete and HMA pavements. **Sampling:** None

Procedure: None. Project staff reviews the Materials Certificate for compliance with contract specifications. **Specification/Report Form:** Standard Specifications, Article M.04.01/MAT-100

07067 EXPANSION JOINT SYSTEM

Scope: All types of expansion joint systems used with contract items 05200XX

Sampling: None

Procedure: Per Special Provision or in lieu of any testing requirement a Materials Certificate(MC) and Visual confirmation that material installed is represented by a Materials Certificate.

Specification/Report Form: None. MC should be kept in project files.

Brick and Block

03200 & 03201 Brick & Block

Project Staff must submit a Request for Test (MAT-100) indicating manufacturer. A copy of a delivery ticket or receipt from the manufacturer must be attached to the MAT-100. Should the manufacturer not be known DMT personnel may request samples from the project. Project personnel should contact DMT immediately should the manufacturer be unfamiliar to prevent substandard material from being used.

03200 MASONARY BRICK AND BLOCK (Solid)

Scope: Precast, rectangular blocks made from PC concrete. **Procedure:** ASTM C 140 and Standard Specifications, Article M.12.12. **Specification/Report Form:** Standard Specifications, Article M.12.12 / MAT-313

03201 BRICK (Clay) - RED Scope: Brick (made from clay or shale and burned) Procedure: AASHTO T 32 Specification/Report Form: Standard Specifications, Article M.08.02/ MAT-312

Metal Castings

03205 CATCH BASIN FRAME AND/OR GRATE 03209 MANHOLE COVERS & FRAMES 03211 HANDHOLE COVERS & FRAMES 03251 CATCH BASIN – ADJUSTMENT RING 03252 MANHOLE – ADJUSTMENT RING 03253 METAL CASTINGS 06566 LAWN DRAIN Scope: This section covers castings for general application in highway and bridge construction. Sampling: None. DMT personnel will review Materials Certificate. Specification/Report Form: Standard Specifications, Article M.06.02 / MAT-100

ALUMINUM CASTING, TUBING AND FITTINGS

Scope: This section covers aluminum castings, tubing and fittings for ornamental posts, traffic rail posts, bases, post connection splice bars, end caps, etc.

Specification/Report Form: Standard Specifications, Article M.06.02 / MAT-100

Fences

03300 FENCE CHAIN LINK, FABRIC Including <u>most</u> material codes up to and including 03327 FENCE, PROTECTIVE

Scope: Aluminum-coated or polyvinyl chloride-coated steel chain-link fabric, aluminum alloy fabric, galvanized metal or polyvinyl chloride-coated material or aluminum alloy posts, top and brace rails, and fittings to be used in the construction of chain-link fence.

FABRIC

Sampling: One sample of chain-link fabric at least 3 feet (1 meter) wide and the full height of the fence will be submitted to the DMT for each shipment of 100 rolls or fraction thereof.

Procedure: AASHTO T 244 and the following as applicable:

- 1. Aluminum-Coated Steel Fabric: Standard Method of Test for Weight [Mass] of coating on aluminumcoated iron or steel articles, AASHTO T 213.
- Polyvinyl Chloride-Coated Steel Fabric: Standard Specification for Poly (Vinyl-Chloride) (PVC) Coated Steel Chain Link Fence, ASTM F 668.
- 3. Aluminum Alloy Fabric: Standard Specification for Aluminum and Aluminum-Alloy Bar, Rod, and Wire, ASTM B 211.

Specification/Report Form: Standard Specifications, Article M.10.01 Fabric / MAT-303

METAL POSTS, RAILS, AND GATE

Sampling:

Gate: Submit one (1) Request for Test with a Materials Certificate for each shipment. **Metal Posts and Rails:** Submit one (1) Request for Test with a Materials Certificate for each size and type. **Procedure:** DMT personnel will review Materials Certificate **Specification/Report Form:** Standard Specifications, Article M.10.05 / MAT--100

FITTINGS

Sampling: Submit one (1) representative sample for each size and type. **Procedure**: Average thickness of coating on hot-dipped galvanized fittings shall be determined with the use of a magnetic thickness gage, ASTM Practice E 376.

Specification/Report Form: Standard Specifications, Article M.10.05 Fittings. / MAT-325.

TENSION WIRE

Sampling: Submit one (1) representative sample for each type of tension wire. **Procedure:** AASHTO T 244 and AASHTO T 213 **Specification/Report Form:** Standard Specifications, Article M.10.05 / MAT-326

WIRE FENCE

Scope: Wire fence and support posts.

Sampling: All fence components will be inspected in the field by project personnel to determine conformance to specifications. Project personnel are responsible for submitting a Request for Test, with a Materials Certificate. For treated wood posts, a certificate of treatment is also required.

Procedure: Laboratory personnel are responsible for reviewing the Request for Test and the Materials Certificate to determine conformance to applicable specifications.

Specification/Report Form: Standard Specifications, Article M.10.04 / MAT-100

03985 GEOTEXTILES

Scope: For use in highway drainage, erosion control, or sedimentation control.

Sampling and Procedure: No Sample required. Accepted based on visual inspection and the Department's Qualified Products List.

Report Form: None

Railings

03405 to 03429 Metal Beam & Bridge Rail

Refer to Appendix D for material codes

Scope: Metal beam elements attached to steel posts by various types of hardware and ending in appropriate terminal treatment for use in various highway guardrail installations.

Sampling: Physical Samples are not required. Project personnel will submit Request for Test (MAT-100) indicating the following Brand Registration, which shall be marked on each rail element, rub rail, or terminal section:

- 1. Name or brand of manufacture.
- 2. Identification symbols, or code for heat number or coating lot.
- 3. Class (A or B).
- 4. Type (1 or 2).

Procedure: DMT personnel will review the submittal for conformance to project specifications. **Specification/Report Form:** Standard Specifications, Article M.10.02 / MAT-329

03419 to 03429 Cable Guide Rail & Related

03419 CABLE GUIDE RAIL

Scope: Wire rope and fittings for use in wire rope railing supported by wood or steel posts.
 Sampling: Samples are not required. Submit a MAT-100 with a Materials Certificate.
 Procedure: DMT personnel will review the submittal for conformance to project specifications.
 Specification/Report Form: Standard Specifications, Article M.10.01 / MAT-100

03449 TIMBER GUIDE RAIL 03450 TIMBER GUIDE RAIL ANCHORAGES 03539 TIMBER PILES Scope: Material Not Included in minimum schedule for acceptance testing Sampling and Procedure: Per Special Provision Specification/Report Form: Per Special Provision

Structural Anchors & Bearings

03504 ANCHOR BOLTS
Scope: This section covers anchor bolts, nuts and washers for structural steel construction.
Sampling: One (1) bolt for each size, heat #, and shipment is required for each project. Each sample must be submitted with a Certified Test Report and Materials Certificate.
Procedure: AASHTO T 244
Specification/Report Form: Standard Specifications, Articles M.06.02 and M.15.02, / MAT-300 or 301.

03505 to 03531 Bearing Pads 03505-L BEARING PADS (Elastomeric Laminated) 03505-P BEARING PADS (Elastomeric Plain)

Scope: Laminated and non-laminated bearing pads and adhesive for use in bridge structures.

Sampling: Submitting a MAT-100 with a Certified Test Report. In addition, a copy of the approved shop drawings must be provided. One test pad must be provided for every fifty (50) pads, or portion thereof, required on a structure. If there are multiple types/sizes of pads on a structure, the test pad shall be representative of the most common type/size.

Procedure: Review the Certified Test Report and test material as required to determine conformance to the project specifications.

Specification/Report Form: Standard Specifications, Article M.17.01 / MAT-310

03540 BEARINGS, POT OR SPHERICAL

Scope: This section covers bronze or copper alloy bridge bearings or expansion plates.
 Sampling: None
 Procedure: DMT personnel are responsible for reviewing the Materials Certificate.
 Specification/Report Form: Standard Specifications, Article M.06.02 / MAT-100

Steel Items- Structural Steel

03532 PILE, STEEL SHELL 03535 PILING, STEEL SHEET Scope: Sheet piling constructed wholly or substantially of steel. No sample required. Procedure: Laboratory personnel are responsible for reviewing the Request for Test and the Materials Certificate to determine conformance to applicable specifications. Specification/Report Form: Standard Specifications, Article M.09.01 / MAT-100.

03537 STRUCTURAL STEEL

Sampling: As required during shop or field visits **Specification/Report Form:** Standard Specifications, Article M.06.02 / NA

03542 STUD SHEAR CONNECTOR 03543 STUDS - WELDED Sampling: As required during shop or field visits Specification/Report Form: Standard Specifications, Article M.06.02 / NA

03549 H-PILES, STEEL 03559 PILE POINT, STEEL 03566 STEEL PLATES Sampling: Field personnel should contact the DMT for sampling requirements. Procedure: AASHTO T 244. Specification/Report Form: Standard Specifications, Article M.09.02 / MAT-327.

03802 SPAN POLE - STEEL

Scope: This section covers all structural steel for use in riveted, bolted, or welded construction.
 Sampling: Test samples for the grade of structural steel may be specified on the plans or in the project specifications. Samples are not common. Standard Specifications, Article M.06.02 (Charpy V-notch)
 Procedure: Submit a MAT-100 when the material is delivered to the project site.
 Specification/Report Form: Standard Specifications, Section 6.03 and Article M.06.02./MAT-305 or 100.

01839 BOLT/NUT/WASHER

07392 BOLT/NUT/WASHER (STAINLESS STEEL)

07403 ROD, THREADED

08022 BOLT/NUT/WASHER (HIGH STRENGTH)

Scope: High strength bolts, nuts, and washers for use in structural steel construction. Sampling: Request for Test (one per size) with sample, Certified Test Report, and Materials Certificate. Procedure: "Standard Method of Test for Mechanical Testing of Steel Products," AASHTO T 244. Certified Test Report and Materials Certificate must show conformance to applicable specifications. Specification/Report Form: Standard Specifications, Article M.06.02 /MAT-302

03928 SIGN SUPPORT, STRUCTURAL STEEL

Scope: Fabricated sign support of various sizes made with structural steel. Sampling: None Procedure: Notify DMT of fabrication and delivery to project site Specification/Report Form: M.06.02, M.18.01, M18.02 / MAT-100

06923 STAY-IN-PLACE FORMS **Scope:** Metal forms typically used in the construction of bridge decks Sampling: None Procedure: As per Special Provision Specification/Report Form: M.03.10 / MAT-100

07351 BOLLARD Scope: Steel Bollard Sampling: None Procedure: Special Provsion Specification/Report Form:Special Provision / MAT-100

08060 DETECTABLE WARNING STRIP - (ADA) Scope: Surface warning strip or pad Sampling: None Procedure: Special Provision

Specification/Report Form: Special Provision / MAT-100

07822 NOISE BARRIER WALL

Scope: All types of walls Sampling: None **Procedure:** Materials Certificate required from proprietary walls Specification/Report Form: 9.16 / MAT-100

Highway Lighting & Traffic Control

03504 to 03766 Highway & Bridge Lighting 03807 TRAFFIC SIGNAL

Refer to Appendix D for material codes Scope: Materials used in highway illumination. Typically, the Contractor must submit catalog cuts to the Designer for approval. Refer to the "Materials Approved by Catalog Cut" section in Chapter 2. Sampling: None

Specification/Report Form: Standard Specifications, Section M.15/ NA

03801 to 03974 Traffic Control Materials (Electric)

Refer to Appendix D for material codes

Scope: Materials used in traffic control signal installations. The Contractor may use materials provided they meet the contract specifications and are approved by the Engineer/Designer.

Sampling: The contract documents will generally designate the type of material control (i.e., Certified Test Report or Materials Certificate) required. In the absence of specific requirements, the provisions of Standard Specifications, Article 1.06 apply.

Procedure: None.

Specification/Report Form: Standard Specifications, Section M.16/ NA

03801 PEDESTALS, ALUMINUM Scope: Used for mounting Highway lighting to a foundation Sampling and Procedure: None / Materials Certificate Specification/Report Form: M.16.03 / MAT-100

03806 MAST ARM ASSEMBLY Scope: Fabricated mast arm assembly Sampling: None Procedure: Notify DMT of fabrication and delivery to project site/Materials Certificate Specification/Report Form: Special Provision / MAT-100

03927 to 03974 Signs and Traffic Control Devices 03927 TRAFFIC DRUM 03933 DELINEATOR 03934 REFLECTIVE SHEETING 03943 OBJECT MARKERS Scope: Aluminum sign blanks, silk-screen ink, reflective sheeting, and object markers. Sampling: None. Procedure: AASHTO T 244, AASHTO T 65, and ASTM E 376 Specification/Report Form: Standard Specifications, Article M.18.14 / NA.

03938 SIGN FACE - SHEET ALUMINUM

03945 CONSTRUCTION SIGNS

03952 SIGN POSTS

Scope: All signs on Department projects.

Sampling: The contract documents for the project should designate the type of material documentation (i.e., Certified Test Report or Materials Certificate) required for materials used in signing installations. In the absence of specific instructions for individual projects, the method of material control shall be provisions of Standard Specifications, Article 1.06.

Procedure: Submit Request for Test with appropriate documentation. **Specification/Report Form:** Standard Specifications, Section M.18 / MAT-100

03948 TRAFFIC CONES 03956 TRAFFIC DRUMS 03970 IMPACT ATTENUATOR 07799 IMPACT ATTENUATOR PARTS/DEVICES 03974 CONSTRUCTION BARRICADE Scope: All Devices used to direct or protect traffic Sampling and Procedure: None / Visual inspection by Project staff as needed Specification/Report Form: M.18.09 and others as required/ None

Hot Mix Asphalt Materials

04003 to 04108 Hot Mix Asphalt & Bituminous Concrete 04003 Curb Mix 04029 Ultra-thin Bonded HMA Pavement (Type B) 04052,3,4 HMA Level 1,2,3 (9.5 mm / 0.375 in.) 04056,7,8 HMA Level 1,2,3 (12.5 mm / 0.5 in.) 04064,5,6 HMA Level 1,2,3 (25mm /1.0 in.) 04076,7,8 HMA Level 1,2,3 (6.25 mm / 0.25 in.)

04128 to 04148 Emulsified Asphalt

Submit a Request for Test (MAT-100) indicating the source of the material. Sources are pregualified by the DMT in accordance with AASHTO R 77. The specific refiner of the material must be indicated on the MAT-100, not the Contractor, subcontractor or vendor. Contractor, subcontractor or vendor can be noted in the comments section of the MAT-100. Table 1 includes the appropriate material codes for each grade.

Table 1. Asphalt Emulsions Material Codes and Grades						
04128 RS-1	04133 SS-1	04138 CRS-1	04142 CMS-2	04145 CSS-1H		
04147 RS-1H	04134 SS-1H	04139 CRS-2		04146 CSS-1		
		04148 CRS-1P (polymer modified)				

Table 1 Asphalt Emulsions Material Codes and Grades

Scope: Asphalt emulsions composed of a semisolid liquid asphaltic base, water, and emulsifying agent. Sampling and Procedure: AASHTO R-66 / AASHTO T 59: Testing Emulsified Asphalt Specification/Report Form: Standard Specifications, Section M.04 / MAT-402

08010 EXPANSION JOINT - Asphaltic Plug

Scope: Components, testing, and application requirements for field molded asphaltic plug material used within expansion joints on bridges with asphalt concrete overlays or PC concrete decks. Sampling: None

Procedure: ASTM D 6297 Table 1 and special provision specifications.

- 1. Thermoplastic polymeric-modified asphalt binder per manufacturer specifications.
- 2. Aggregate per manufacturer specifications.
- 3. Foam expansion joint filler per manufacturer specifications.
- 4. Steel bridge plate per manufacturer specifications.

Specification/Report Form: Special Provision / MAT-100

04199 Membrane Waterproofing

Scope: Fully-adhered built-up bituminous membrane waterproofing system for bridge decks. Sampling: None

Procedure: Materials Certificate must be stored in the Project Records.

- 1. Primer: ASTM D 41:
- 2. Asphalt: ASTM D 449, Type III:
- 3. Fabric: ASTM D 1668:
- 4. Bituminous Plastic Cement: ASTM D 2822, Type I:

Specification/Report Form: Standard Specifications, Section 7.07 / None

04207 DAMP PROOFING (PRIMER)

04208 DAMP PROOFING (SEALER)

Scope: Three asbestos-free asphalt roof coatings of brushing or spraying consistency suitable for use as waterproofing and damp proofing of concrete and concrete masonry.

Sampling and Procedure: None. Project staff reviews the Materials Certificate for compliance with contract specifications.

Specification/Report Form: Standard Specifications, Section 7.08 /NA

Aggregates

SAMPLING OF AGGREGATES

Scope: Obtaining coarse and fine aggregates at the source of supply and/or at the project site. **Sampling:** Samples are to be obtained by a representative of the Department. Samples from potential open faced banks or pits are the responsibility of the producer unless an adequate and representative stockpile has been prepared for use on Department projects. **Procedure:** AASHTO T 2

REDUCING SAMPLES OF AGGREGATE TO TEST SIZE (DMT Staff only) Scope: Reduction of large field samples of aggregate by quartering or by use of the mechanical splitter. Sampling: AASHTO T 2 Procedure: AASHTO T 248

04697 to 04902 & 08032 to 08054 Fine & Coarse Aggregate 04697 SAND MASONRY GRADING A 04700 SAND 04703 SAND FILLER 04704 SAND MASONRY GRADING B 04709 SAND (FOR TRENCHING AND BACKFILLING) 04817 STONE DUST/SCREENINGS 04819 GRAVEL BANK RUN 04820 GRAVEL FILL 04901 BEDDING MATERIAL M08.01-21 04902 BORROW

08032 SAND (WASHED) 08033 SAND (NATURAL) 08034 STONE (BROKEN/CRUSHED) 08035 GRAVEL (CRUSHED) 08036 RECLAIMED MISC. AGGREGATE - 08036X (OFF SITE) 08037 RECLAIMED WASTE - 08037X (OFF SITE) 08039 EMBANKMENT MATERIAL

Scope: Material is tested using various test methods to determine conformance to project specifications. These methods include sieve analysis, washed sieve analysis, soundness, and others listed below. <u>Reclaimed Misc. Aggregate:</u> Glass-free and clinker-free reclaimed waste, which has been crushed, graded and blended, as specified in the Contract, with natural crushed stone or gravel. Reclaimed Waste: Crushed and graded concrete removed from pavements, structures, or buildings.

Sampling: AASHTO T 2 and AASHTO T 248 Specification: Standard Specifications, Sections (M.01, M.02, M.03, M.04, M.05 or M.12) Procedures:

SIEVE ANALYSIS – AASHTO T 27 Report Form: MAT-205, MAT-206, or MAT-207.

WASHED SIEVE ANALYSIS – AASHTO T 11 Report Form: MAT-205, MAT-206, MAT-207, or MAT-223.

DEGRADATION RESISTANCE OF AGGREGATE (L.A. ABRASION TEST) – AASHTO T 96 **Report Form:** MAT-211

SOUNDNESS OF AGGREGATE (MAGNESIUM SULFATE) – AASHTO T 104 Report Form: MAT-220 or MAT-221

MOISTURE DENSITY RELATIONSHIP OF SOILS – AASHTO T 99, AASHTO T 180 **Report Form:** MAT-213, and MAT-217 or MAT-218

TOTAL EVAPORATIVE MOISTURE CONTENT OF AGGREGATE BY DRYING - AASHTO T 255

FLAT AND/OR ELONGATED PARTICLES IN COARSE AGGREGATE – ASTM D4791 Report Form: MAT-104

FRACTURED PARTICLES IN COARSE AGGREGATE- ASTM D5821 Report Form: MAT-104

BULK DENSITY (UNIT MASS) AND VOIDS IN AGGREGATE- AASHTO T 19 Report Form: MAT-104

SPECIFIC GRAVITY AND ABSORPTION OF COARSE AGGREGATE- AASHTO T 85 Report Form: MAT-219

ORGANIC IMPURITIES IN FINE AGGREGATE – AASHTO T 21 **Report Form:** MAT-206

04771 MASONRY FACING

Scope: Masonry facing stone shall be either dimensioned masonry stone or ashlar masonry stone. **Sampling and Procedure:** Field inspection of stone by project personnel unless samples are required. **Specification/Report Form:** Standard Specifications, Article M.11.01 / MAT-100.

04909 CURBING - GRANITE STONE

Scope: Granite curbing typically used on highway bridges at the bottom of parapets adjacent to the bridge deck. Shape typically has one sloped face.

Sampling and Procedure: Field inspection of stone by project personnel. **Specification/Report Form:** Special Provision / MAT-100.

04910 CURBING - GRANITE SLOPE

Scope: Granite curbing typically used on at the approaches to bridges or parking lots. Shape is typically rectangular.

Sampling and Procedure: Field inspection of stone by project personnel.

Specification/Report Form: Standard Specifications, Article M.12.07 / MAT-100.

Chapter 4 – Materials Evaluation and Testing Procedures

This chapter describes in detail the procedures used by Division of Materials Testing (DMT) personnel to develop recommendations on the conformance to specification of materials purchased by the Department for its own use or used by a Contractor in the construction or maintenance of a facility.

In addition this chapter also describes the procedures used by DMT personnel to inspect and qualify facilities that produce materials for use on a regular basis by the Department or Department contractors.

Materials Evaluation

Material Catalog Cuts

Many materials used on a project are evaluated based on catalog cuts. These materials are typically mass produced items such as louvers, bathroom fixtures, roadway lighting, and electronic equipment available from numerous manufacturers. Due to the variety of choices, the designer typically develops a specification that can be met by several of the manufacturers. The Designer is then responsible for reviewing the catalog cuts submitted by the Contractor to the Contract Administrator and determining if the contractor-selected product meets the project specification. Consequently, the DMT will not repeat the evaluation performed by the Designer and recommend acceptance or rejection of the material. A Request for Test (MAT-100) for the materials reviewed and approved or rejected by the Designer is not required. Project field personnel are responsible for verifying that appropriate materials incorporated into the project were approved by a catalog cut submittal.

Visual Inspection of Materials on Project Site

Many materials used on a project can be initially evaluated or must be evaluated daily by project staff. The acceptance of these materials is most effectively based on the visual inspection of all these materials at the project site and over the course of the entire project. Examples of these materials are, but not limited to, temporary precast concrete barrier curb, bedding material, and topsoil (from project site). The Minimum Schedule for Acceptance Testing clearly defines which materials require a formal Request for Test (MAT-100) for acceptance purposes.

Material Certificate

Many materials used on a project can be evaluated by Project or DMT staff by the review of a material certificate. The Minimum Schedule for Acceptance Testing clearly defines which material certificates require review by project or DMT staff.

Materials Testing Procedures

Materials typically used on highway projects (i.e., concrete, HMA, subbase, etc.) and also used in vertical construction are frequently tested and as such must be tested in accordance with the Minimum Schedule for Sampling Materials for Test (Minimum Schedule). A recommendation of acceptance or rejection of the material will be made by DMT personnel based on the results of this testing.

Sampling Materials for Test

Laboratory personnel regularly sample both fine and coarse aggregates, aggregate blends for roadbase applications, and other various materials used for Construction and/or Maintenance purposes. On a less frequent basis, these personnel also oversee the field sampling of aggregates and plastic PC concrete by construction inspection personnel as required for assurance purposes.

Sampling is a critical component of testing and is performed according to the applicable specification indicated under "sampling" in each section of this manual. DMT personnel collecting samples will utilize every precaution

to obtain unbiased samples that represent the nature and condition of the material to be sampled. DMT personnel are certified in the applicable sampling procedures through the New England Transportation Technician Certification Program (NETTCP) and qualified by established procedures as described in *Appendix H* to assure uniform procedures in obtaining random samples.

DMT personnel also regularly transport field samples to the central or satellite laboratories for testing. It is also important that samples are carefully handled and transported to prevent damage to the samples. Containers used to transport samples should be clean and adequate for the particular material being sampled. Furthermore, the containers should be durable and of a type and size that prevents loss, damage, or contamination of any portion of the sample.

Aggregates

Scope: Coarse and fine aggregates are obtained at the source of supply for annual qualification. Qualified sources are listed on the DMT website. Typical sampling locations include sampling from flowing aggregate streams (bins or belt discharge), conveyor belts, roadways, stockpiles, or vehicles typically used to transport material.

Sampling: Samples are to be obtained by a representative of the Department. Preliminary samples and tests for potential open faced banks or pits are the responsibility of the producer unless an adequate and representative stockpile has been prepared for testing for use on Department projects. **Procedure:** AASHTO T 2

Precast Concrete Production Facility Inspection

Reinforced Concrete Pipe

Purpose: This outline is a guide to personnel involved in the inspection of the manufacture of reinforced concrete pipe and allied products. The following factors must be considered while inspecting this material.

- Testing and inspection of the various materials selected for use.
- Proper proportioning and adequate mixing of the materials.
- Sufficient reinforcement and proper placement of reinforcement within form work.
- Proper handling, placing, and consolidating procedures.
- Proper curing of the product.

Materials inspector must become familiar with the manufacturing processes, designs, specifications, and procedures followed for any particular plant.

Scope: Reinforced concrete pipe, elliptical pipe, slotted pipe, and culvert ends may be accepted by the DMT on the basis of the manufacturer's certification. Products covered under this section include, but are not limited to, reinforced concrete pipe for use as a culvert, slotted reinforced concrete pipe for use as underdrains, and reinforced concrete culvert ends.

Annual Plant Inspection

This inspection is to ensure that a plant is capable of producing a product that meets AASHTO M 170, AASHTO M 207, and AASHTO M 175 Type II requirements, supplemented by Standard Specifications, Article M.08.01, as applicable.

Inspection MAT-324 indicates the name, address, and plant number of the manufacturer; and lists the number, make, capacity, type, and condition of all scales and seal dates, mixers, and pipe machines.

Materials: The inspector will obtain samples of cement, water, coarse aggregate, fine aggregate, admixtures, and reinforcing steel he proposed for use on the project from the manufacturer and indicate on MAT-324 the suppliers of the materials.

Sampling: All cement must be sampled at the mill and tested by an approved laboratory whose methods and equipment are regularly inspected by the Cement and Concrete Reference Laboratory. One copy of the test report certifying the acceptability of the cement shall be furnished to the Department. At the time of the annual

inspection and at any time thereafter, the inspector may obtain a sample of cement currently in use and a copy of the corresponding certified test report.

- 1. Aggregate: Samples shall be obtained from approved storage piles or bins by the inspector during the annual inspection. Additional samples shall be taken at least once every month or from each new source.
- 2. Water: Each source of supply shall be sampled annually.
- 3. Reinforcement: Samples of each size and type of reinforcement shall be taken every six months, or as required.
- 4. Admixtures: Samples of each type of admixture from each source of supply may be obtained annually or as required.

Fabrication: Reinforced concrete pipe (RCP) must meet the requirements of the contract specifications.

The inspector will observe the production process, which shall include checking the splices, spacing, and size of reinforcing at the time cages are assembled. The reinforcing shall be lapped not less than 51 mm and welded with an electric welding machine. The spacing, center-to-center, of adjacent rings of circumferential reinforcement in the cage shall not exceed 102 mm for pipe having a 102 mm wall thickness, nor exceed the wall thickness for larger pipe, and in no case shall exceed 152 mm. The cage shall contain sufficient longitudinal bars or members, extending through the wall of the pipe to maintain the reinforcement rigidly in shape and in the correct position within the form. For multiple layers, a line of circumferential reinforcement for any given total area may be composed of two layers for pipe with a wall thickness of less than 178 mm or three layers for pipe with a wall thickness of 178 mm or greater. The layers shall not be separated by more than the thickness of one longitudinal plus 6.4 mm. The multiple layers shall be fastened together to form a single rigid cage. All other specification requirements such as laps, welds, tolerance of placement in the wall of the pipe, etc., shall apply to this method of fabricating a line of reinforcement.

The reinforcing shall be free of objectionable coatings, particularly heavy corrosion prior to installation in the form. An adherent film of rust or mill scale is not considered objectionable. The reinforcement should be secure so that the placement of the concrete will not displace the steel from its proper position.

Preliminary Tests and Tests for Extended Deliveries - Sampling

As part of the yearly certification process, laboratory personnel will select RCP and witness 3-edge testing in the Spring and Fall of each year that certification is requested, two of each size pipe up through 750 mm diameter and one of each size greater than 750 mm diameter. The pipe sample shall be tested by the 3-edge bearing test as per AASHTO T 280, except as follows:

- 1. Modified or special design pipe shall be tested to the 0.3 mm (0.01 in.) load and the ultimate load requirements as per AASHTO M 170 and M 207.
- At the discretion of the Engineer, pipe of standard design, as specified in AASHTO M 170, may be tested to the 0.3 mm (0.01 in.) requirement plus 10 percent additional load in lieu of ultimate load testing. Test pipe attaining 0.3 mm (0.01 in.) crack will not be acceptable for use on Department projects.

Rejection: The manufacturer **must** isolate the rejected pipe in its yard or provide some means to clearly indicate rejected pipe. Any size pipe previously rejected must be retested.

Precast Concrete Drainage Items

The following describes the role of the DMT in monitoring the production, quality assurance, and acceptance of precast concrete units such as catch basins, manholes, and pipe.

Quality Control Manual

Each fabricator, which proposes to manufacture precast units for use by the Department shall develop and maintain a plant-specific Quality Control Manual addressing in detail the production and certification process of products for use on Department projects. This Manual shall be submitted to the Department for initial approval, and resubmitted as required due to either operational changes within the company or changes in source of materials.

Annual Plant Certification

Each plant is subject to an annual inspection by a representative of the DMT. The purpose of this inspection is to determine if the facility has the infrastructure to manufacture precast units to the Department's requirements and the personnel and procedures necessary to adhere to the Quality Control Manual specific to that facility.

The inspector may review all phases of the manufacturing process, and will document the results of his inspection by completing the information required on Inspection MAT-324 "Yearly Inspection of Precast/Prestressed Concrete Structure, and Concrete Pipe Manufacturers."

Periodic Plant Inspection

While the plant is producing precast units for the Department, an inspector from the DMT may visit the plant unannounced to perform the following inspection activities:

- 1. Ascertain that the fabrication process and equipment used in production and the test procedures, equipment and personnel employed in the manufacturer's quality control program are in continuing compliance with the specifications and the approved Quality Control Plan for that plant.
- 2. Review the manufacturer's records relative to production, testing, and shipment of the precast units for the purpose of determining that:
 - 2.1 the compressive strength, air content and slump of the concrete consistently met the requirements at time of shipping; and,
 - 2.2 the records are complete and accurate.
- 3. Sample component materials as prescribed previously under "Sampling."

Sampling

The quality of the materials used in the manufacture of precast units shall be determined by tests on samples taken on the following schedule:

Portland Cement: Cement shall conform to AASHTO M 85 or AASHTO M 240 and shall be from a source that participates in the Cement Certification Program (Appendix E). All cement shall be sampled at the mill and tested by an approved laboratory whose methods and equipment are regularly inspected by the Cement and Concrete Reference Laboratory. Test reports certifying the acceptability of the cement shall be furnished to the DMT. Cement shall be subject to sampling and testing at any time by the DMT.

Aggregate: Samples of aggregate shall be obtained from approved storage piles or bins by the inspector during the annual inspection. Additional samples shall be taken at least every month or from each new source.

Water: Each source of supply shall be sampled annually.

Reinforcement: Samples of each size and type of reinforcement shall be taken every six (6) months or as directed by the Engineer.

Miscellaneous Hardware: Manhole steps shall conform to AASHTO M 199. Sampling frequency will be determined by the Engineer. All steel frames and grates incorporated into catch basin and drop inlet tops shall bear the Independent Testing Agency Acceptance stamp.

Admixtures: Only admixtures meeting AASHTO M 194 will be considered during the mix design review.

Fabrication Process Review

During the annual inspection, the inspector will review the standard fabrication process in use at the plant to determine that the precast units are manufactured according to the requirements specified in Standard Specifications, Article M.08.02, and the approved Quality Control Manual for that plant. The following areas of the production operations are to be carefully inspected:

- Storage and handling of component materials.
- Equipment and mixing procedures, including use of approved concrete mix designs.
- Fabrication of reinforcement or reinforcing cages, where applicable.

- Dimensions, condition, and construction of forms.
- Prior to placing concrete, the positioning of reinforcing bars or cages in the forms; and in the case of catch basin or drop inlet tops, the positioning of steel frames.
- Transportation, placement, and consolidation of plastic concrete.
- Curing methods, handling and storage of units.
- Dimensions, details, surface finish, and freedom from defects of finished units.
- Proper marking and identification of units.
- Application of protective compound to surfaces of precast catch basin and drop inlet tops, which will be exposed when in service.

Review of Materials Testing by Plant Personnel

The manufacturer is required to furnish the equipment and personnel necessary to perform compressive strength tests and air content determinations to demonstrate conformance to the contract specifications and plans and to document the results of these tests in the plant records.

During the annual inspection, the inspector will review the testing equipment and procedures employed at the plant for conformance to the following requirements:

- 1. Sampling Freshly Mixed Concrete AASHTO T 41.
- 2. Making and Curing Concrete Test Specimens in the Field AASHTO T 23.
- 3. Obtaining and Testing Drilled Cores and Sawed Beams of Concrete AASHTO T 24.
- 4. Compressive Strength of Cylindrical Concrete Specimens AASHTO T 22.
- 5. Air Content of Freshly Mixed Concrete by the Pressure Method AASHTO T 52.
- 6 Slump of Hydraulic Cement Concrete AASHTO T 119.
- 7. Frequency of sampling and testing shall be Standard Specifications, Article M.08.02-4.
- 8. The compressive strength machine shall be calibrated by an approved agency at least once each twelve (12) months.
- 9. The pressure/volumetric meter is to be calibrated by the plant quality control personnel as required by the Engineer.

The inspector will witness the performance of the required tests by the manufacturer's personnel and shall designate on Inspection MAT-324 those plant employees qualified to perform the respective tests. The inspector will consult the manufacturer's Quality Control Manual for the procedure for recording test results to ensure that said records are accurate, complete, and available to a representative of the DMT upon request.

PRECAST/PRESTRESSED CONCRETE (STRUCTURAL) BEAMS/PILES/SUBSTRUCTURE

Production Inspection

The DMT will assign personnel to inspect/witness the fabrication of precast/prestressed items such as bridge girders, deck slabs, culverts, or piles. The length of the assignment will be prioritized as to the type of member being produced and the other current resource demands.

In general, any structure or component that primarily carries live load over or beneath a transportation facility will have oversight during production from the DMT or its representative.

Any structure or component that is used to primarily resist dead load such as, but not limited to, retaining walls and proprietary items such as gross particle separators may have oversight during the production time. The DMT may adjust the amount of inspection based on the reputation of the fabrication facility and the producer's daily adherence to their quality control plan.

Plant Inspection Procedure

Sampling and Frequency

The following component materials shall be sampled and tested at the frequencies listed below:

- 1. Portland cement (PC): PC shall be from an approved source. Each load shall be accepted by certification.
- 2. Aggregate: Samples from bins or stockpiles each month for each source of supply.
- 3. Admixtures: Only qualified admixtures are to be used.
- 4. Prestressing steel strand: Standard Specifications, Article M.14.01.
- 5. Post-tensioning tendons and anchorages: Sample as per Special Provisions.
- 6. Reinforcing steel: From each source, a 5 ft. (1.5 m) sample of each size for every 400 tons (181.4 mtons), with a minimum of one sample of each size from each source per project.

Inspection of Plant Facilities and Manufacturing Procedures (MAT-324)

- 1. Storage and handling of materials.
- 2. Batching, mixing, transportation and placement of concrete.
- 3. Curing method and apparatus; i.e., steam, radiant heat or other approved method including provision for recording time and temperature data during the curing cycle.
- 4. Concrete testing equipment; i.e., compression-testing machine (should be calibrated each 12 months), pressure-type air meters, cylinder molds, slump cones, unit weight apparatus and facilities for moist-curing test cylinders, ASTM C 192.
- 5. Equipment and procedure for consolidation of concrete.
- 6. Construction and capacity of casting beds.
- 7. Dimensions, condition, and construction of forms.
- 8. Method and equipment for applying prestressing or post-tensioning forces.
- 9. Method and equipment for measuring prestressing or post-tensioning forces and the procedure for measuring elongation of strands or tendons.
- 10. Construction details, accuracy, and calibration data of pressure gauges. (Gauges shall be calibrated at intervals not to exceed 6 months.)

Inspection of Casting Bed

- 1. Check cleanliness, level, and alignment of form liner.
- 2. Check position of bulkheads for proper length of units and skewed or sloped ends.
- 3. Inspect stringing of prestressing strands to ensure correct number and position of strands and location of "hold-downs."
- 4. For each strand: inspect tension, measure elongation, and check gauge reading for proper force application. Force measurement of elongation and gauge reading shall check each other and the theoretical value within 5 percent; if they do not, notify QC manager.
- 5. Witness back tensioning at the non-jacking end of deflected strands and straight strands to verify application of the required prestressing force. Standard Specifications, Article 5.14.03.
- 6. Inspect installation of post-tensioning tendons and anchorages, when applicable.
- 7. Check size, type, and location of in-place reinforcing steel, hardware, and miscellaneous steel.
- 8. Inspect condition and alignment of side forms.
- 9. Check proper bracing and anchorage of casting bed and end anchorages.

Inspection of Concrete Operations

- 1. Check identification marker for required data and placement in unit.
- 2. For deck units, inspect internal void forms for material, size, and proper installation.
- 3. Inspect concrete delivered to forms for homogeneity and uniformity of successive batches.
- 4. Witness/monitor sampling of concrete for quality control testing.
- 5. Witness slump, air tests, concrete temperature, and unit weight for conformance to specifications; accept or deem unacceptable on basis of results.
- 6. Spot-check mixing of concrete to assure that approved mix design and procedures are being used.
- 7. Inspect placement, consolidation, and finishing for conformance to specifications and QC plan.
- 8. Ensure that approved curing method is used and applied at proper time; if steam or radiant heat is used, ensure that required preset period is observed

Inspection of Fabricated Units

- 1. Inspect units to determine if they were cured uniformly. Review the time/temperature record of curing cycle for specification compliance.
- 2. Witness testing of cylinders for required concrete strength prior to removal of forms or detensioning.
- 3. After removal of side forms, inspect units for honeycomb, cracks, etc. Report major defects to supervisor for structural review by Department Bridge Design Section and or Designer.
- 4. Inspect detensioning operations for proper sequence, method, and timing of strand release.
- 5. Witness removal of units from casting bed.
- 6. Inspect completed units for as-built dimensions, camber, horizontal alignment, etc.
- 7. When applicable, witness testing of cylinders for required concrete strength prior to post-tensioning.
- 8. Witness post-tensioning operations (checking elongation of tendons and gauge readings) to assure gauge pressures and elongations are within prescribed limits.
- 9. Witness grouting of post-tensioning ducts for conformance to approved grout mix, equipment, and pumping procedure.
- 10. Witness all repairs to determine compliance with approved procedures and use of approved materials.
- 11. Witness testing of cylinders to determine concrete strength for shipping, when required, and 28-day strength for acceptance.

Report: Results of all tests and inspections shall be reported on appropriate forms. The inspector will maintain accurate records in the form of a daily log and production records of all information concerning the manufacture of each individual member. Final approval of precast, prestressed, and post-tensioned concrete members will be reported on MAT-100.

PORTLAND CEMENT CONCRETE (ALL)

Concrete Batch Plants and Delivery Vehicles

Scope: Each year, Producers must obtain certification of the plants and the hauling/mixing vehicles from the National Ready Mix Concrete Association (NRMCA)

Sampling: NA

Procedure: From NRMCA.

Report: DMT may request copies of the NRMCA inspection reports from the producer.

Compressive Strength of Cylindrical Concrete Specimens

Scope: Compression testing of molded concrete cylinders.

Sampling: Standard Method of Sampling Freshly Mixed Concrete, AASHTO T 141; Standard Method of Making and Curing Concrete Test Specimens in the Lab, AASHTO T 126.

Procedure: Refer to Standard Operating Procedure (SOP) in Appendix G

Specification/Report Form: Standard Specifications, Section 4.01 or 6.01 / MAT-308

Mass, Yield, and Air Content (Gravimetric) of PC Concrete

Scope: Determining the mass (per cubic meter or cubic foot) of plastic PC concrete delivered to project sites. The method also provides procedures for determining yield, cement content, and air content.

Sampling: Standard Method of Sampling Freshly Mixed Concrete, AASHTO T 141.

Procedure: Standard Method of Test for Mass per Cubic Meter (Cubic Foot), Yield and Air Content (Gravimetric) of Concrete, AASHTO T 121

Specification: Standard Specifications, Section 4.01 or 6.01 and M.03 or project Special Provisions.

Assurance Report (DMT Only): MAT-224, or MAT-225, and MAT-222

Acceptance Report (Project Personnel): MAT-308.

Admixtures

Scope: Project specifications normally require that an admixture shall perform the desired function without injurious effect upon the concrete. Proof of conformance to this requirement will be in the form of a certified statement from a recognized laboratory. The certified statement will contain evidence based on tests pertinent to the admixture made in the recognized laboratory by the use of concrete materials and by methods that meet requirements of current AASHTO and ASTM standards. Tests may be made on samples taken from a quantity

submitted by the Contractor for use on the project or on samples submitted and certified by the manufacturer as representative of the admixture to be supplied. A recognized laboratory is any cement and concrete laboratory approved by the Engineer and inspected regularly by the Cement and Concrete Reference Laboratory sponsored by ASTM.

Sampling: AASHTO M 154 and AASHTO M 194

Procedure: Approval of the certified statement submitted for an admixture will qualify that admixture for inclusion in the Department's Qualified Products List regarding Admixtures for Portland Cement Concrete. **Specification/Report Form:** Standard Specifications, Article M.03.01-9 / None

Structural Steel and Welding Shop Inspection

Scope: All structural steel fabricated for permanent incorporation into the project must be inspected by DMT staff during fabrication. DMT staff supplemented by consultant inspection staff can inspect any facility no matter where it is located to determine the adherence to quality control standards and project specifications. Adherence to the "Buy America" requirements of the contract is also an important aspect of this on-site inspection.

Sampling: None Documentation on material sources, quality control test results, and other appropriate topics are kept by the DMT representative until all fabrication is completed. This documentation is then forwarded to the Central Laboratory for inclusion in the project records.

Procedure: DMT staff must be notified where and when fabrication will take place so that inspection can be scheduled. The Contractor is responsible for notifying project staff, who in turn must notify the DMT. Specification/Report Form: Standard Specifications, Section 6.03/NA

HOT MIX ASPHALT (BITUMINOUS CONCRETE/SUPERPAVE)

Annual Qualification of Hot Mix Asphalt Plants

Scope: Materials, technician qualifications, mix designs procedures, and calibration records and quality control test records are evaluated annually. The Department may perform random spot inspections of any aspect of the operation during the production season to ensure compliance to all specifications.

Sampling: Sampling of materials will be done during annual site inspection.

Procedure: Plants are inspected annually in the Spring.

Report: MAT- 404

Sampling HMA Mixtures

Scope: Procedures for sampling mixtures of HMA paving material. **Sampling:** AASHTO T 168 and AASHTO R 47. Sampling is required to be performed by a NETTCP certified technician.

Report Form: None

HMA Inspection Personnel Assignment Procedure

Scope: A priority system is utilized for the daily assignments of HMA inspectors to bituminous plants. Assignments are based on the following, in order of priority:

- **Performance** review of recent plant specific test results
- Verification Sampling as required per contract specification
- Daily tonnage produced larger tonnage will get higher priority
- Random sampling as determined by the TSE

Binder Content by Ignition Method

Scope: This method of test is for the determination of the total percentage of bitumen in HMA mixtures. Sampling: AASHTO T 168 modified, AASHTO R 47. Procedure: AASHTO T 308 Report Form: MAT-408

Correlation Between Production Pull and Binder Content by Ignition Method

Scope: To monitor the difference between the target plant production binder content and the corrected binder content by ignition method using a five (5) point moving average. If two (2) consecutive differences are more than 0.3%, a new correction factor may be required for the mix.

Sampling: AASHTO T 168 modified, AASHTO R 47. Procedure:

- 1. AASHTO T 308, Asphalt Binder Content of HMA by Ignition Method
- 2. AASHTO T 329, Moisture Content of Hot Mix Asphalt by Oven Method
- 3. AASHTO R 47, Reducing Samples of HMA to Testing Size

Report Form: None

Mechanical Analysis of Extracted Aggregate

Scope: To monitor mix compliance with the specifications and job mix formula (JMF) target values. Sampling: AASHTO T 168 modified, AASHTO R 47 Procedure: AASHTO T 30 modified Report Form: MAT-412s

Degree of Particle Coating of HMA Mixtures

Scope: Degree of coating of coarse particles of aggregate in a HMA mixture in relation to the wet mixing time. When HMA is mixed, coarse particles of aggregate are the last and the most difficult to coat, and the degree of their coating may be a measure of the degree of mixing.

Sampling: AASHTO T 195 modified and AASHTO T 168 modified.

Procedure: AASHTO T 195 modified.

- 1. Only one truck load of mixture is sampled.
- 2. Sample is taken from opposite sides of the load.

Report Form: NA

Bulk Specific Gravity of Compacted HMA Mixtures

Scope: This method determines of the bulk specific gravity to determine volumetric properties of compacted HMA mixtures.

Sampling: AASHTO T 168 modified, AASHTO R 47

Procedure: AASHTO T 166: Bulk Specific Gravity of Compacted Asphalt Mixtures Using Saturated-Surface Drv Specimens

Report Form: MAT-412s

Volumetric Calculations of VMA

Scope: These methods cover the formulas used to calculate VMA. Sampling: AASHTO T 168 modified, AASHTO R 47. **Procedure:**

- 1. AASHTO M 323: Superpave Volumetric Mix Design
- 2. AASHTO R 35: Superpave Volumetric Design for Hot Mix Asphalt
- 3. AASHTO T 329: Moisture Content of Hot Mix Asphalt by Oven Method
- 4. AASHTO T 312: Preparing and Determining the Density of Hot-Mix Asphalt (HMA) Specimens by Means of the Superpave Gyratory Compactor

Report Form: MAT-412s

Preparation of Gyratory Specimens

Scope: Preparation of test specimens using the gyratory compactor. Sampling: AASHTO T 168 modified, AASHTO R 47. Procedures:

- 1. AASHTO M 323: Superpave Volumetric Mix Design
- 2. AASHTO R 35: Superpave Volumetric Design for Hot Mix Asphalt
- 3. AASHTO T 329: Moisture Content of Hot Mix Asphalt by Oven Method
- 4. AASHTO T 312: Preparing and Determining the Density of Hot-Mix Asphalt (HMA) Specimens by Means of the Superpave Gyratory Compactor

Testing of HMA materials, fabrication of gyratory molds, and theoretical, and liquid content must be started and fabricated within 1/2 hour from the time of sampling from the delivery truck and completely finished within 2 hours. Physical, volumetric and other properties shall be calculated in accordance with the contract specifications and AASHTO M 323 and AASHTO R 35.

Maximum Specific Gravity of HMA Paving Mixtures

Scope: Determination of the maximum specific gravity of uncompacted HMA paving mixtures.

Sampling: AASHTO T 168 modified, AASHTO R 47.

Procedure: AASHTO T 209 modified.

1. Water bath temperature correction shall not be utilized provided that the water bath temperature is 77 \pm 0.9°F

Report Form: MAT-412s

Production Inspection at HMA Plants

Scope: The purpose of production inspection is to monitor compliance with the quality assurance program and the specifications. The aggregate must be of uniform quality and gradation and must be fed into the plant in a uniform manner; the heating and drying of the aggregates must be uniform; the separation of the aggregates must be controlled; and the components must be combined and mixed in a uniform, consistent manner. For these reasons, the inspector must be thoroughly familiar with all phases of the manufacturing process. HMA production activities includes the following:

- 1. Process Control (PC): Typically performed by the HMA producer prior to shipment.
- 2. Quality Control (QC): The sum total of activities performed by the seller (producer, manufacture, contractors) to make sure that a product meets contract specification requirements.
- 3. Acceptance System (Acceptance/Verification Plan): All factors that comprise the Agency's determination of degree of compliance with contract requirements and value of a product. These factors include Agency sampling, testing, acceptance limits, risk evaluation, and inspection. These factors should also include validated results of contractor sampling and testing.
- 4. **Independent Assurance (IA):** IA is an unbiased and independent verification of the Quality Assurance system used as a method of determining the reliability of the test results obtained in the regular sampling and testing activities. These results are not to be used elsewhere.

Report Form: None

Duties of the HMA Plant Inspector

Scope: The inspection includes but is not limited to checking component materials in the stockpile, cold bins, hot bins; PG binder, and additive; inspection of processing, sampling; and testing the finished product for conformance to the specifications.

Sampling and Procedure: NA

Report Form: Daily Inspector Report \ MAT-108HMA

Status of New Mixes, Existing Mixes From Previous Year's Production

Scope: Each plant will have each class of HMA material evaluated based on previous year's production compliance for Va and VMA. Based on the ranking a class receives, it will determine whether the material can be produced without the prior completion of a PPT. Rankings will be provided to each HMA producer annually at the beginning of the paving season.

Sampling: NA

Procedure: Included in the Standard Specifications Section M.04 **Report Form:** None

Mix Design / Job Mix Formula(JMF) Submittal and Change Procedure

Scope: The Producer shall submit an annual JMF as specified in Article M.04.02. The JMF will be reviewed by the DC and a mix status will be provided in accordance to Article M.04.02.2.c. Based on acceptance test

results, the Contractor may be required to submit an updated JMF using MAT-429 (JMF Changes tab) for that class of material in order to continue supplying material. **Sampling:** NA **Procedure:** Included in the Standard Specifications Section M.04

Reports: JMF annual submittal MAT-429, MAT-440

HMA Verification Testing Procedures

Scope: Verification testing will be performed to validate Contractor's QC tests used for acceptance. Samples will be randomly obtained by Department personnel from the quartered field samples obtained as indicated in Section M.04.

For non-PWL lots, the ratio of verification tests to the Contractor tests will be a minimum 1 to 10. For PWL lots, the ratio of verification tests to the Contractor tests will be a minimum of 1 to 3.5. Verification samples will be tested at the Central Laboratory. QC and verification test results for Gmm, Gmb, Pb, VA and VMA will be compared using the F-test and t-test at a 0.01 significance level for PWL lots and the absolute difference for Non-PWL lots.

Sampling: All verification samples are obtained and transported to the Central Laboratory by the Contractor within 2 business days of production.

The Contractor will follow AASHTO T 168 5.2.3 for sampling and AASHTO R 47 for the mechanical splitting of the sample. The following figures demonstrate the procedure to be used.



Figure 2- First Splitting Process



Figure 3- Second and Third Splitting Processes

Procedures:

- 1. AASHTO T 308: Method for Determining the Asphalt Content of HMA by the Ignition Method.
- 2. AASHTO T 209: Theoretical Maximum Specific Gravity and Density of HMA Mixtures.
- 3. AASHTO T 166: Bulk Specific Gravity of Compacted Asphalt Mixtures using Saturated Surface- Dry Specimens.
- 4. AASHTO T 168: Sampling of Paving Mixtures.
- 5. AASHTO T 312: Preparing and Determining the Density of Hot Mix Asphalt Specimens by Means of the

Superpave Gyratory Compactor. The compaction temperature will match the sublot compaction temperature as tested at the Contractor Laboratory.

6. AASHTO T 329: Moisture Content of Hot-Mix Asphalt (HMA) by Oven Method. Should the field sample be re-heated for 1.5 hours or more, this test may be omitted.

For non-PWL lots, results will be considered validated when the

the difference of te QC and verification results falls within the tolerances in Table 4

For PWL lots, when the project estimated quantity is below 10,500 tons or when the remaining tonnage after a JMF change or after failing fata validation lot is below 10,500 tons, one data validation analysis will be performed for all the tonnage or remaining tonnage per mix design per project. The minimum number of verification tests per each data validation lot is three. Results will be considered validated when both the F-and t- tests pass.

For PWL lots with project estimated quantities over 10,500 tons, a data validation lot will include QC and verification results in three consecutive acceptance lots under the same mix design. The first data validation lot will be performed when the first three acceptance lots are completed and consecutive data validation lots will be performed each time a new acceptance lot is closed. QC and verification data from the last two acceptance lots will be rolled over to be used in consecutive data validation lots except when prior data validation lots failed. The minimum number of verification tests per each data validation lot is five. Results will be considered validated when both the F- and t- tests pass.

Should the Department be unable to validate the Contractor's acceptance test result(s) in any acceptance PWL lot, The Engineer will test the remaining verification samples in the lot and use the verification results to calculate the lot pay adjustment.

When any single result fails the F- or t- tests, HMA staff will notify IA staff. HMA staff shall review past tests specific to the type of material that failed to look for trends. The HMA staff shall contact the Contractor's Quality Control manager to notify them of the deficiency and request that the Contractor investigate.

If the Contractor request dispute resolution testing, all sublots in the disputed lot will be tested by the Independent Assurance Section and those test results will be used for the lot pay adjustment. The Department reserves the right to deny dispute resolution testing is there is a history of disputed lots that confirmed verification results or if the dispute resolution samples appear to be tampered.

Should the Department be unable to validate the Contractor's Non-PWL acceptance test result(s), The Engineer will use verification results for the pay adjustment calculation in the corresponding sublots.

Report Forms: MAT-408PWL and MAT-408NON_PWL

HMA Independent Assurance Procedures

Scope: Independent Assurance testing will be performed by the DMT. Mixture samples will be randomly obtained by Department personnel from the quartered field samples obtained as indicated in Section M.04. The ratio of independent assurance tests to the Contractor tests will be a minimum 1 to 7. Independent assurance tests for Department verification personnel will be a minimum once per month. Test results for Gmm, Gmb, and Pb will be compared using the one-to-one comparison on split sample results.

Core samples will be randomly selected for independent assurance at a ratio of 1 to 40. Test results for Gmb will be compared using a one to one comparison on the same sample specimen.

Sampling: Mixture: Samples are obtained and transported to the Central Laboratory by the Contractor and/or the DMT.

Core: Samples are randomly obtained per Section 4.06 **Procedure:**

- 1. AASHTO T 308: Method for Determining the Asphalt Content of HMA by the Ignition Method.
- 2. AASHTO T 209: Theoretical Maximum Specific Gravity and Density of HMA Mixtures.
- 3. AASHTO T 166: Bulk Specific Gravity of Compacted Asphalt Mixtures using Saturated Surface- Dry Specimens.
- 4. AASHTO T 168: Sampling of Paving Mixtures.
- 5. AASHTO T 312: Preparing and Determining the Density of Hot Mix Asphalt Specimens by Means of the Superpave Gyratory Compactor. The compaction temperature will match the sublot compaction temperature as tested at the Contractor Laboratory.
- 6. AASHTO T 329: Moisture Content of Hot-Mix Asphalt (HMA) by Oven Method. Should the field sample be re-heated for 1.5 hours or more, this test may be omitted.
- 7. AASHTO T 331: Standard Method of Test for Bulk Specific Gravity (Gmb) and Density of Compacted Hot Mix Asphalt (HMA) Using Automatic Vacuum Sealing Method

Table 2 will be used for HMA Independent Assurance comparisons. When any of the tolerances inTable 2 column D are exceeded, the Department and/or the Contractor will work together to identify the source of the discrepancy. Tolerances in Table 2 are the absolute difference in the measured values, not the percentage of the values.

TAE	TABLE 2: Independent Assurance Tolerances												
Properties		Assessm	ent Grade										
	Α	В	С	D									
	(≤)	(≤)	(≤)	(>)									
Pb	0.11	0.22	0.33	0.33									
Gmm	0.007	0.013	0.020	0.020									
Gmb (T-166)	0.007	0.015	0.022	0.022									
Gmb (T-331)	0.007	0.013	0.020	0.020									

Report Forms: MAT-600 and MAT-412s

Mix Design / Job Mix Evaluation

Scope: In order for a JMF to be approved, the properties of the aggregate components or mix shall meet the verification tolerances shown in Table 3.

Sampling: As part of the JMF submittal, the Contractor shall submit the following samples to the Division of Material Testing:

- 4 one quart cans of PG binder, with corresponding Safety Data Sheet (SDS)
- 1 50 lbs bag of RAP
- 2 50 lbs bag of plant blended virgin aggregate
- 2 10,000 kg boxed split sample material for TSR design

Procedure: Testing will be performed by the DMT to evaluate each proposed JMF and will include:

Aggregate Components Consensus Properties Verification:

- 1. AASHTO T27: Mechanical Analysis of Aggregate
- 2. AASHTO T85: Coarse Aggregate Specific Gravity
- 3. AASHTO T84: Fine Aggregate Specific Gravity
- 4. ASTM D 5821: Coarse Aggregate Angularity
- 5. AASHTO T304, Method A: Fine Aggregate Angularity
- 6. ASTM D 4791: Flat and Elongated Particles (1:5)
- 7. AASHTO T176: Sand Equivalent Mix Verification:
- 8. AASHTO T209: Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures.
- 9. AASHTO T166: Bulk Specific Gravity of Compacted Asphalt Mixtures using Saturated Surface- Dry Specimens.
- 10. AASHTO T312: Preparing and Determining the Density of Hot Mix Asphalt Specimens by means of the Superpave Gyratory Compactor
- 11. AASHTO R35: Air Voids, VMA, VFA, Density to Nini
- 12. AASHTO T283: Resistance of Compacted Asphalt Mixtures to Moisture-Induced Damage

TABLE 3: JMF EVALUATION TOLERANCES (1)												
Properties	Tolerance	Properties	Tolerance									
#200	1.0	Gmm	0.020									
#100	3.0	Gmb	0.022									
#50	3.0	Pba	0.6									
#30	4.0	PD@Ni	1.5									
#16	4.0	Gse	0.025									
#8	5.0	Gsb	0.028									
#4	5.0	Gsa	0.025									
3/8"	5.0	CAA (1 face/2 faces)	10									
1/2"	4.0	SE	15									
3/4"	4.0	FAA	0.8									
1"	3.0	F&E	5.0									
Va	1.3	TSR	15 & Minimal									
VMA	1.3		Stripping									
VFA	6.0											

⁽¹⁾Tolerance is the absolute difference in the measuredelete d values, not a percentage of the values.

Report Form: MAT-418

HMA PPT Verification

Scope: In order for a PPT to be approved by Section M.04.02.02 Option B, the properties need to be verified. Table 4 will be used to verify PPT samples. When testing a PPT sample, if any single sieve result or any of the individual volumetric results exceed the tolerances in Table 4, the PPT will be considered as failing and the mix will remain on PPT status. If the sample meets all the tolerances, the mix will be placed on "A" status.

Sampling: As part of the PPT submittal, the Contractor shall submit the following samples to the DMT:

- 2 gyratory molds
 - 1 5,000 grams of cooled loose bituminous concrete
 - 1 5,000 grams of cooled loose bituminous concrete

Procedure: Testing will be performed by the DMT to evaluate each PPT and will include:

- 1. AASHTO T 308: Method for Determining the Asphalt Content of HMA by the Ignition Method.
- 2. AASHTO T 30 modified: Mechanical Analysis of Extracted Aggregate.
- 3. AASHTO T 209: Theoretical Maximum Specific Gravity and Density of HMA Mixtures.
- 4. AASHTO T 166: Bulk Specific Gravity of Compacted Asphalt Mixtures using Saturated Surface- Dry Specimens.
- 5. AASHTO T 168: Sampling of Paving Mixtures.
- 6. AASHTO T 312: Preparing and Determining the Density of Hot Mix Asphalt Specimens by Means of the Superpave Gyratory Compactor.
- 7. AASHTO T 329: Moisture Content of Hot-Mix Asphalt (HMA) by Oven Method. Should the field sample be re-heated for 1.5 hours or more, this test may be omitted.

TABLE 4: \	/erification
Properties	Tolerances ⁽¹⁾
#200	0.7
#100	2.0
#50	2.0
#30	2.0
#16	2.0
#8	3.0
#4	3.0
3/8"	4.0
1/2"	4.0
3/4"	4.0
1"	4.0
1 1/2"	4.0
2"	4.0
Pb	0.33
Gmm	0.020
Gmb ⁽²⁾	0.011 or 0.022
Va	0.71
VMA	0.71
VFA	3.5
PD@Ni	0.71

⁽¹⁾Tolerance is the absolute difference in the measured values, not a percentage of the values ⁽²⁾0.011 if testing the same compacted specimen or 0.022 if testing a separate compacted specimen **Report Form:** MAT-412PPT

Resistance of Compacted HMA to Moisture Induced Damage

Scope: Preparation of specimens and measurement of the change of diametral tensile strength resulting from the effects of saturation and accelerated water conditioning of compacted HMA mixtures in the laboratory. This test may be performed on HMA laboratory mixture, mixtures sampled from newly loaded trucks, field pavement samples, and pavement cores.

Sampling and Procedure: AASHTO T 283 modified

Report Form: AASHTO T 283 modified Table 1, Moisture Damage Laboratory Data Sheet or MAT-428

Volumetric and Specific Gravity Using Gyratory Compactor

Scope: These methods cover the determination of volumetric and specific gravity calculations of test specimens made by Superpave gyratory compactor.

Sampling: AASHTO T 168 modified, AASHTO R 47 Procedure: AASHTO M 323, and AASHTO R 35 Report Form: MAT-412s

Performance Graded Asphalt Binder (PGAB)

Scope: PGAB suppliers are prequalified by the DMT in accordance with AASHTO R 26 modified. To maintain qualified status, suppliers must submit monthly split samples to the DMT. HMA producers must maintain a log of binder deliveries using a MAT-435 or equivalent approved ny the Engineer.

Requirements: A Certified Test Report and bill of lading representing each delivery must be provided to the producer in accordance with AASHTO R 26 modified. Upon material delivery, plant personnel shall record lot number, date, grade of binder, witnessed by, hauler name, liquid supplier, ticket number, receiving storage tank number, quantity received, and previous tank status (quantity) in the binder log

(MAT-435). The Contractor shall provide binder samples from the delivery upon request of DC. The blending of PG binder from different suppliers is not allowed unless the HMA producer submits a QC plan for this purpose.

Sampling: In accordance with AASHTO T 40

Procedure: In accordance with all AASHTO standard methods of test listed in AASHTO 332

Report Form: QC Plan / MAT-401

DENSITY OF SOIL AND SOIL - AGGREGATES

Scope: The Contractor shall determine of the in-place density of soil and soil aggregate by using a measurement device approved by the Engineer. Density measurements shall be performed where specified in the Contract.

Procedure: Field testing shall be performed in accordance with AASHTO T 310 or other approved industry standard test method. The density results obtained shall be reported as a percent of the maximum dry density as determined by AASHTO T 180 Method D.

Correlation: All gauges shall be correlated annualy prior to use on Department projects. Correlation blocks shall be provided by the Department or the gauge manufacturer. The gauge shall be correlated in accordance with manufacturer's recommendations.

Standardization: As a minimum, standardization of the gauge shall be performed daily prior to its use. This process shall be performed in accordance with the manufacturer's recommendations.

Report Form: Form CON-125

DENSITY OF IN-PLACE ASPHALT PAVEMENT BY THE CORE METHOD

Procedure: Refer to Standard Operating Procedure (SOP) in Appendix G



Chapter 6 – Independent Assessment/Verification Program

INDEPENDENT ASSESSMENT

Independent assessment of DMT methods and equipment is performed through the AASHTO Accreditation Program (AAP). This program entails on-site inspection by personnel from the AASHTO Materials Reference Laboratory (AMRL) and the Cement and Concrete Reference Laboratory (CCRL). After the inspection by AMRL or CCRL, any deficiencies noted in equipment, personnel, or procedures are addressed in a timely fashion.

In addition to the on-site inspection, AMRL and CCRL also send samples of various materials for testing (proficiency samples). The results of these tests are compared with the test results for the same material from other testing facilities. If proficiency sample results vary by more than two standard deviations, an internal investigation will be undertaken to determine what may have affected the results. This investigation will include, but not be limited to, the following: review of work sheets and data entry; equipment check; scale check; test procedure; and a review of previous proficiency test results. Corrective action is taken as soon as possible. The determination is documented and kept on file before forwarding to AMRL or CCRL.

EQUIPMENT STANDARDIZATIONS, VERIFICATIONS, CHECKS AND MAINTENANCE

Tables indicating testing equipment that is calibrated and checked according to requirements set forth by the AASHTO Accreditation Program are included in the DMT Quality Management System Manual (R-18).

Chapter 7 - Suggested Minimum Schedule of Acceptance Testing (LOTCIP)

Local Transportation Capital Improvement Program (LOTCIP)

1/22/15

Municipal Adminstered LOTCIP Projects not on National Highway System ONLY

Material Name	Unit	Test/Documentation	Frequency 1 per	Notes
Anchor Bolts	ea.	MC	project	1 per size
Asphalt Emulsions (CSS-1, RS-1 or SS-1)	gal	МС	10k	
Bituminous Concrete (HMA)	ton	D 2950 FLDT	day	See Note 3
Cement - Portland Type I/II	bag	FLDT	project	empty bag
Chemcial Anchor	lb.	QPL MC	project	
Concrete-Ready Mixed	c.y.	T22 FLDL	75	4 cylinders
Construction Signing	ea.	МС	project	
Geotextile	s.y.	QPL MC	project	
Gravel (Bank Run or Crushed)	c.y.	T27 LABT	5k	
Grout, Non-shrink	bag	МС	project	
Masonry Brick & Block (Solid)	ea.	FLDT	project	See Note 1
Pipe - Reinforced Concrete	1.f.	PC-1	project	See Note 1
Pipe (Metal & Plastic) All types	lf	МС	project	See Note 1
Pipe Arch - Aluminum	lf	МС	project	See Note 1
Precast Concrete Items (not pipe)	ea.	PC-1	Item type	
Prestressed Concrete Members	ea.	LABT	1	See Note 2 & 3
Reclaimed Misc. Aggregate	c.y.	T27/Chem Analysis	2500	See Note 5
Reclaimed Waste	c.y.	T180 LABT	50k	See Note 5
Sand (Masonry /Trenching & Backfilling)	c.y.	T27 LABT	2500	
Sheet Piling	1.f.	MC	project	See Note 4
Sign Post	ea	МС	project	See Note 1
Span Pole - Steel or Wood	ea.	MC	project	See Note 3
Steel Reinforcing Bars (Plain or Epoxy)	lb.	T244 MC	200t	
Stone (Broken/Crushed)	c.y.	T27 LABT	20k	
Structural Steel	cw	Shop Drawings	project	Notes 2, 3 & 4
Traffic Signal Equipment	ea.	MC	project	NA
Notes				
1 Material should be inspected on	the project s	ite prior to use. Suspect mar	erial should be physica	lly tested to

1	determine conformance.	ly tested to
2	QC Inspection should be provided and documented during fabrication.	
3	Contact the Department of Transportation Division of Materials Testing to determine vendor qua QA inspection availability.	lifications and
4	Documentation should be provided to determine conformance to Buy America requirements.	
5	FORM MAT-212 should be completed and provided by the Contractor prior to use of material.	

Test Method/Test Type

LABT	Laboratory Test
FLDT	Test performed in the field
	ConnDOT Qualified Products List
QPL	(http://www.ct.gov/dot/lib/dot/documents/dresearch/conndot_qpl.pdf)
PC-1	MAT-308 Required from producer with shipment
MC*	Materials Certificate

*Should comply with ConnDOT Standard Specification Section 1.06.07

Legend

Item: Standard Specification Section and the first four digits of the Contract Item number.

Title: Generally the overall subject of the Standard Specification Section and the Contract Item numbers.

Item Unit: Generally the pay unit of the Contract Item.

Material #: Code used in SiteManager and by the Division of Materials Testing to identify component materials used in Contract Items.

Material Name: Definition of the Material #.

Material Unit: Unit of Material that defines a quantity represented by a sample. Example: A sample of concrete represents 50 CY of material regardless of what the item unit is.

MAT 100: Indicates wether a Request for Test (MAT-100) is required to be submitted to the Division of Materials Testing (See Note 11. for ALT)

Sample Type: Acceptance (Prod) or Information requires a MAT-100 to be submitted. Accept (Field) does not require a MAT-100 to be submitted.

Test Method: AASHTO or ASTM test method. See below.

Test Type: Describes the test, where the test is performed, or what is required to be submitted with the MAT-100.

Responsibility: Person who performs the test.

Frequency: Number of tests required per quantity of material using the material units: (E) English (M) Metric.

1 per "quantity" indicates that **all** the quantity of each type (size/shape/composition) of material, per item, from a single vendor and manufacturer **must be represented** on a single or multiple Request for Test(s) (MAT-100). MAT-100(s) total represented quantity must match total quantity installed.

Sample Size: Size of Sample.

Test Type:

FLDT	Test performed in the field
LABT	Laboratory Test
FLABT	Field and Laboratory Testing
LMCT*	Lab Test, Mat Cert and Cert Test Report (Originals Required)
MC*	Materials Certificate (Original Required)
MCCTR*	Materials Certificate and Certified Test Report (Originals Required)
PC1	Self Certification from producer supplied per shipment
QPL	Qualified Product List
Visual	Project Inspector must visually inspect upon delivery/installation. Visual inspection
	by DMT staff denotes witnessing fabrication of material where it is being fabricated
	by Divit stati denotes withessing fabrication of material where it is being fabricated.
	Documentation of visual inspection on the project by project staff is in accordance

*Materials Certificates and Certified Test Reports must comply with Standard Specification Section 1.06.07. Note: Materials Certificates for items composed of, or containing, steel or cast iron must also indicate where the steel and cast iron was produced and fabricated.

	X=Not Standard,					мат					Freq	uency		
	A-Spec Pro		Material	Material	Material	IVIA I	Sample	Test	Test	Test	1	per	Sample S	Size
Item	Title	Unit	#	Name	Unit	100	Туре	Method	Туре	Responsibility	(E)	(M)	lbs	kg
01.01	Environmental		03166	Sheeting, Polyethylene	s.y.	NO	None	NA	Visual	Project Staff				
	Items		04XXX	Bit. Concrete (Various)	ton	NO	None	NA	Visual	Project Staff			See Note	8
			04776	Hay, Baled	ea.	NO	None	NA	Visual	Project Staff				. 0.
			04901	Bedding Material	c.y.	NO	None	NA	Visual	Project Staff				
			08044	Retaining Wall - Precast Conc.	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	1	1	NA	
02.01	Clearing & Grubbing	l.s.	00000	Labor only		NO								
02.02	Rdwy Ex, Formation of		08037X	Reclaimed Waste (OFFSITE)			Accept (Prod)	Chem(offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	72
	and Disposal	c.y.	08037	Reclaimed Waste	c.y.	YES	Information	T180	LABT	District Lab	20k	15k	160	72
	Material		08039	Embankment Material										
02.03	Structure Excavation	c.y.	00000	Labor Only		NO								
02.04	Cofferdam	l.f.	00000	None		NO								
02.05	Trench Excav	c.y.	00000	None		NO								
02.06	Ditch Excav	c.y.	00000	None		NO								
02.07	Borrow	c.y.	04902 08037X	Borrow Reclaimed Waste (OFFSITE)	c.y.	YES	Information	T180	LABT	District Lab	20k	15k	160	72
02.08	Free-Draining	c.y.	08037X	Reclaimed Waste (OFFSITE)			Accept (Prod)	Chem (Offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	72
	Material		08037	Reclaimed Waste	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160	72
			08039	Embankment Material			Information	T180	LABT	District Lab	20k	15k	160	72
02.09	Subgrade, Form	s.y.	00000	Labor Only	_	NO								
02.10 A	A Water Pollution Control	est.	03166	Sheeting, Polyethylene	l.f.	NO	None	NA	Visual	Project Staff			See Note	e 8.
			04XXX	Bit. Concrete (Various)	ton	NO	None	NA	Visual	Project Staff				
			03985	Geotextile	s.y.	NO	None	NA	QPL/MC	Project Staff			NA	
		See 0	6.01 for Portla	nd Cement Concrete materials, 06	51 for pipe	, 07.03 fo	or Riprap, and 0	9.53 for Sod.						
02.12	Subbase	c.y.	04819	Gravel (Bank Run)										
			08034	Stone (Broken/Crushed)	1		Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160	72
			08035	Gravel (Crushed)	c.y.	YES	Information	T180	LABT	District Lab	20k	15k	160	72
			08036	Recl. Misc. Agg.										
			08036X	Recl. Misc. Agg. (OFFSITE)	1		Accept (Prod)	Chem (Offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	72
02.13	Granular Fill	c.y.	All Materials	and Frequencies as listed under 02	.12, except	Lab (T1	80) and Field De	nsity (D6938) are not r	equired for	this item.				
02.14	Comp Gran Fill	c.y.	All Materials	and Frequencies as listed under 02	.12.									

	X=Not Standard, A=Spec Pro		Material	Material	Material	MAT	Sample	Test	Test	Test	Freq	uency per	Samp	ole Size
Item	Title	Unit	#	Name	Unit	100	Туре	Method	Туре	Responsibility	(E)	(M)	lbs	kg
02.16	A Pervious Structr	c.y	All Materials a	and Frequencies as listed under 02.	.12.	MEG		D 4022	FLADT	0 (11 1	100	7(т	DD
	Backfill		03014-SP-CLSM	Contolled Low Strength Material	c.y.	YES	Accept (Prod)	D 4832	FLABI	Central Lab	100	/6	1	BD
02.19	Control Sys	l.f.	03985	Geotextile	s.y.	NO	None	NA	QPL/MC	Project Staff			1	JA
			04776	Hay, Baled	ea.	NO	None	NA	Visual	Project Staff			See N	Note 8.
03.02	X Rolld Gran Base	c.y.	All Materials	and Frequencies as listed under 02.	.12, except	Lab (T18	80) and Field De	nsity (D6938) are not r	equired for	this item.		a) (1		
03.03	X Concrete Base	c.y.	03015-03540	Concrete-PCC03540	с.у.	YES	Accept (Prod)	122	FLABT	Central Lab	75(6	0)/day	4 cyl	4 cyl
03.04	Processed Aggregate Base	ton	04819 08034 08035 08036	Gravel (Bank Run) Stone (Broken/Crushed) Gravel (Crushed) Reclaimed Misc. Aggregate	c.y.	YES	Accept (Prod) Information	T27 T180	LABT LABT	District Lab District Lab	5k 20k	3.8k 15k	160 160	72 72
			08036X	Recl. Misc. Agg. (OFFSITE)			Accept (Prod)	Chem(Offsite ONLY)	MCCTR	Central Lab	2.5k	1.9k	160	72
03.05	Processed Agg	ton	Use of Stone (Broken.Crushed) with requirement	ts as listed	under 03	.04.							
04.01	Concrete Pavement	c.y.	03015-0354X	Concrete-PCC354X	c.y.	YES	Accept (Prod)	T22	LABT	Central Lab	50(4	0)/day	4 cyl	4 cyl
			Other material	s as listed under 06.01.										
04.06	Bituminous	ton	04052,3,4	Level 1,2,3 (6.25mm / 0.25 in)				Material proj	perties:		Proje	ct quant	ities ≥ 35	500 tons
	Concrete		04056,7,8 04064,5,6 04076,7,8	Level 1,2,3 (9.5 mm / 0.375 in) Level 1,2,3 (12.5 mm / 0.5 in) Level 1,2,3 (25.0 mm / 1.0 in)	ton	YES	Accept (Prod) Project p DMT 2 Project p Non-PWL. Project pers	Table M.04.03-3 personnel must register 24 hours prior to paving ersonnel must submit o Multiple days of produ can be combined on a s onnel must submit one	LABT paving ope g using PA one MAT-10 action, each ingle MAT MAT-100	Producer erations with VETRACK 00 per day for 1 under 150 tons, -100. per lot for PWL.	Use P	ercent W 1 test p ect quan No See Tabl of Spe	ithin Limi er 500 to tities <35 n-PWL le M.04.0 ccification	ts (PWL). ns 00 tons 3-2 1.
								Material density in-	place (core	es):	S	ee Secti	on 4.06.0	3-10
							Accept (Prod)	T331	LABT	Central Lab	Proje Use P 1 joi Proje Sec	of Spe ct quant ercent W 1 mat cor nt core p ect quan Simple 2 Table 4 of Spe	cification ities ≥ 35 ithin Limi e per 500 er 2000 ft. tities <35 e Average t.06-4 & cification	n. 500 tons ts (PWL). tons of joint 700 tons 4.06-5 h.
04.06	Curb Mix	ton	04003	Curb Mix	ton	YES	On	e test per every 250 tor	ns of cumula	ative production. Se	e sectio	n M.04.	03-2b.	

	X=Not Standard,										Freq	uency		
	A=Spec Pro		Material	Material	Material	MAT	Sample	Test	Test	Test	1	per	Sampl	le Size
Item	Title	Unit	#	Name	Unit	100	Туре	Method	Туре	Responsibility	(E)	(M)	lbs	kg
04.06	Emulsified		04128	RS-1, RS-1H			Accept (Prod)	M140 & M208	LABT	Central Lab		. ,		0
	Asphalt		04133	SS-1, SS-1H			Total project or	antities up to 1000 ga	llons requi	res only a Materials	≤10	00 gal	≤100	0 gal
		gal	04146	CSS-1 CSS-1H	gal	YES	Certificate	and Certified Test Re	port from c	ertified source.	N	one	No	one
		8	04147	CPS 1	8		Total project	t quantities >1000 gals	also requi	re sample(s) for	>10	00 gal	>100	0 gal
			04147	CK5-1		YES	testing which	t qualitities > 1000 gai.	vithin 15 d	avs of sampling	10k	38k1	2 ats	21
04 15	Duran Dif Laint	e V	S == 04.06 fem)	l Ditaminana Mataniala and 2.12 fan			testing, wind	in must be submitted v		ays of sampling.	TOK	JOKI	2 40	21
05.02	Pless Kli Joint	5.y.	See 04.00 101	Bituminous Materials and 2.12 for	unbound I	nateriai.								
03.02	X Temp Crossings		00000	None										
5.03	Removal of Super	1.s.	00000	N.T.										
07.04	Structure	1	00000	None										
05.04	RR Protection	nr.	00000	None		VEC	A accent (Dred)	ТЭЭ	FLADT	Control Lob	75(6	()/day	1	ar d
05.06	Retaining walls,	C.Y.	03013-A	concrete-Class (various)	C.y.	YES	Accept (Plou)	122	FLABI	Central Lab	/3(0	0)/day	4 0	2yı
05.07	Catch Basins			Water		NO	None		Visual	Project Staff			See N	ote 4
05.07	X Manholes &	ea.	01422	Concrete Section Precast	gai	NO	None	INA	v ISuai	rioject Stall			See IN	010 4.
03.00	Dron Inlets		01440A	Catch Basin - Precast (Complete	еа	YES	Accept (Prod)	NA	PC1	Central Lab	1	1	N	A
	Drop milets		01440A	Manhole - Precast (Complete)	cu.	1 25	recept (110d)	1471	101	Contrar Edu	1	1	14.	11
			03025	Mortar (prebagged)										
			03066	Cement - Portland Type I/II	bag	NO	None	NA	Visual	Project Staff			See N	ote 9.
			06552	Lime - Hydrated						5				
			03200	Concrete Masonry Unit (CMU)		VEG		NT A	LADT	0 (11 1			C N	. 12
			03201	Brick (Clay) - RED	ea.	YES	Accept (Prod)	NA	LABI	Central Lab			See No	ote 13.
			03209	Manhole Covers / Frame										
			03205	Catch Basin - Grate	ea.	YES	Accept (Prod)	NA	MC	Central Lab	1	1	See No	ote 12.
			06566	Lawn Drain Grate										
			04697	Sand (Masonry) - Grading A	C V	VES	Accept (Prod)	Т27	LART	District Lab	2.5k	1 9k	25	12
			04704	Sand (Masonry) - Grading B	C.y.	1L5	Recept (1100)	127		District Edo	2.5K	1.7K	23	12
			04819	Gravel (Bank Run)										
			08034	Stone (Broken / Crushed)	c.v.			T25	LADT	D	~1	a 01	1.00	
			08035	Gravel (Crushed)		YES	Accept (Prod)	127	LABI	District Lab	5K	3.8K	160	72
			08036	Reclaimed Misc. Aggregate					MOOTE	D	0.51	1 01	1.60	
07.00	at a .		08036X	Recl. Misc. Agg. (OFFSITE)		TIPO	Accept (Prod)	Chem (Offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	. 72
05.08	Shear Connectors	I.S.	03542	Stud Shear Connector	ea.	YES	Accept (Prod)	AWS D1.5	MCCTR	Central Lab	qua	antity	l per	size
05.09	Welded Studs	ea.	03543	Studs - Welded	ea.	YES	Accept (Prod)	AWS D1.5	MCCTR	Central Lab	qua	antity	l per	size
05.13	PVC Pipe	1.f.	02649	Pipe - PVC & Fittings & Acc.	l.f.	NO	None	NA	Visual	Project Staff			See N	ote 8.
05.14	Prestressd Conc	1.f.	03040,16	Grout	See requir	ements f	or material #0304	0 or #03016 under ite	m 06.01				_	
<u> </u>	Members		03050	Concrete Members, Prestressed	l.f.	YES	Accept (Prod)	NA	Visual	Lab & Project			See N	ote 2.
05.20	X Exp Jnt System	c.f.	07067	Exp. Joint System	l.f	NO	None	NA	MC	Project Staff				

	X=Not Standard,					мат					Frequency	
	A-Spec Pro		Material	Material	Material	IVIA I	Sample	Test	Test	Test	1 per	Sample Size
Item	Title	Unit	#	Name	Unit	100	Туре	Method	Туре	Responsibility	(E) (M)	lbs kg
2	K Asph Plug Jnt		08010-SP	Exp. Jt Asphalt Plug-Spec Pro	c.f	NO	None	NA	MC	Project Staff		See Note 5.
05.21	Elastomeric	c.i.	03040,16	Grout	See requir	ements f	for material #0304	0 or #03016 under ite	em 06.01		-	
	Bearing Pads		03505-L	Bearing Pads (Laminated)	ea.	YES						
			03505-P	Bearing Pads (Plain)	ea.	115	Accept (Prod)	NA	MCCTR	Central Lab	See Note 3.	See Note 3.
05.22	Elastomeric	l.f.	03432	Joint Seal, Elastomeric Comp	l.f.		None	NA	MC	Project Staff		NA
	Comp. Seal		03040,16	Grout	See requir	ements f	for material #0304	0 or #03016 under ite	em 06.01		-	-
06.01	Concrete for	c.y.	00804	Box Culvert, Precast Concrete	ea	YES	Accept (Prod)	NA	Visual	Lab & Project		See Note 2
	Structures		01422	Concrete Section, Precast		125	(110 u)		, iouur	240 00 110,000		500110002.
			03015-X	Concrete-PCCXXXXX	c.v.	YES	Accept (Prod)	T22	FLABT	Central Lab	75(60)/day	4 cyl
			03014-SP_K	Concrete Special Provision	5		1 ()				())	
			03040	Grout, Non-shrink	bag	NO	None	NA	Visual	Project Staff		See Note 9.
			03016	Grout (Batched)	c.y.	YES	Accept (Prod)	T106	FLABT	Central Lab		
			04177	Joint Sealer, Concrete Structure	lb.	NO	None	NA	MC	Project Staff		NA
			03158	Preformed Expansion Joint Filler	ea.	110		1.1.1		110,000 5 0011		1
			03444	Closed Cell Elastomer	l.f.	NO	None	NA	MC	Project Staff		NA
			Note: All stee	l reinforcement under 06.01 will be	e tested as o	lescribed	l in 06.02.					
06.02	Reinforcing		02995	Dowel Splice System, Epxy Ctd	ea	YES	Accent (Prod)	Т244	LMCT	Central Lab	quantity	1
			02997	Dowel Splice System	cu.	115	(i iou)	1211	Linei	Contral Euro	quantity	1
		lb.	02998	Deformed Steel Bars, Epxy Ctd	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t 180t	5ft 1.5m
			03040, 16	Grout	See requir	ements f	for material #0304	0 or #03016 under ite	em 06.01			-
			03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t 180t	5ft 1.5m
			03105	Chemical Anchor	lb.	NO	None	NA	QPL/MC	Project Staff		NA
			03138	Dowels, Steel	ea.	YES	Accept (Prod)	T244	LMCT	Central Lab	quantity	NA
			03145	Fabric, Wire and Welded Steel	s.y.	YES	Accept (Prod)	T244	LMCT	Central Lab	$60k \text{ ft}^2 6k \text{ m}^2$	$1 y d^2$ $1 m^2$
06.03	Structural Steel	cwt.	00031	Paint - Prime Coat for Struct. Stl								
			00032	Paint - Interm. Coat for Struct Stl	gal	NO	None	NEPCOAT	MC	Project Staff	quantity	NA
			00033	Paint - Top Coat for Struct Stl				www.nepcoat.or	g			
			03537	Steel, Structual	cwt.	YES	Accept (Prod)	NA	Visual	Lab & Project		See Note 2.
			01839	Bolt/Nut/Washer	ea.	YES	Accept (Prod)	TBD	LMCT	Central Lab	quantity	
			08022	Bolt/Nut/Washer, High strength	ea.	YES	Accept (Prod)	TBD	LMCT	Central Lab	quantity	
			03542	Stud Shear Connectors	See item 5	5.08.						
	N E :		03040, 16	Grout	See requir	ements f	for material #0304	0 or #03016 under ite	em 06.01	D		
06.05	Masonry Facing	s.y.	04771	Stone, Masonry	tons	NO	None	NA	Visual	Project Staff		NA
			03138	Dowels, Steel	1 Ib.	YES	Accept (Prod)	NA	LMCT	Central Lab	quantity	NA
0(0)	Comont Dala	-	Note: Mortar	components to be tested as describe	ed in 05.07							
06.06	Masonry	c.y.	4771	Stone, Masonry	c.y.	NO	None	NA	Visual	Project Staff		NA

J	X=Not Standard, A=Spec Pro		Material	Material	Material	МАТ	Sample	Test	Test	Test	Freq 1	uency per	Sample Size
Item	Title	Unit	; #	Name	Unit	100	Туре	Method	Туре	Responsibility	(E)	(M)	lbs k
			Note: Mortar	components to be tested as describ	ed in 05.07					• •	_		
06.07	Dry Rubble Masonry	c.y.	4771	Stone, Masonry	c.y.	NO	None	NA	Visual	Project Staff			NA
06.09	Repointed Masonry	s.y.	Note: All mat	terials under 06.09 will be tested as	described	in 05.07.							
06.11	Shotcrete	c.y.	Note: All mat	terials under 06.11 will be tested as	described	in 06.01.							
06.12	Curing Box	ea.	00000	None	ea.	NO	None	NA	Catalog Cut	Project Staff			See Note 8.
06.51	Culverts/Pipe	l.f.	00327	Water	gal	NO	None	NA	Visual	Project Staff			See Note 4.
			00699	Pipe - R.C. & Fittings & Acc.	l.f.	YES	Accept (Prod)	NA	PC1	Central Lab	si	ze	See Note 7.
			various	Pipe (Metal) All types	l.f.	YES	Accept (Prod)	NA	MC	District Lab	<i>d</i> 119	ntity	See Note 8
			01783	Pipe -Alum & Fitting & Acc.	l.f.	YES	None	NA	MC	Project Staff	qua	niny	Bee Note 8.
			03066	Cement - Portland Type I/II	bag	NO	None	NA	Visual	Project Staff			See Note 9.
			03040	Grout, Non-shrink	See requir	ements f	or material #03040) under item 06.01					
			03016	Grout (Batched)	c.y.	YES	Accept (Prod)	T106	FLABT	Central Lab			1
			04704	Sand (Masonry) - Grading B	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	2.5k	1.9k	25 1
			04901	Bedding Material	c.y.	NO	None	NA	Visual	Project Staff			Se Note 8.
			04819	Gravel (Bank Run)						2			
			08034	Stone (Broken / Crushed)	C V	YES	Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160 7
			08035	Gravel (Crushed)	c .y.	125	neeept (need)	12,					1
			08036	Reclaimed Misc. Aggregate									
			08036X	Recl. Misc. Agg. (OFFSITE)	c.y.	YES	Accept (Prod)	Chem(Offsite)	MCCTR	District Lab	2.5k	1.9k	160 7
06.52	Culvert Ends	ea.	00823	Culvert End - Reinforced Conc	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	qua	ntity	NA
			Note: All non	-precast materials that may be used	d for 06.52	items are	listed under 06.51	and must be tested	at the same	frequency.			
06.53	Clean Drng Sys	ea.	00000	None		NO					1		
07.01	Drilled Shafts	l.f.	0306X	Cement (Type)		NO	None	NA	Visual	Project Staff			See Note 9.
			03100	Deformed Steel, Reinforcing		YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft 1.:
			03016	Grout (Batched)		YES	Accept (Prod)	T106	FLABT	Central Lab			
			03532	Pipe, Steel Shell		YES	Accept (Prod)	NA	MC	Central Lab	qua	ntity	NA
			02724	Pipe, Steel & Fit & Acc.		YES	Accept (Prod)	NA	MC	Central Lab	qua	ntity	NA
			02600	Pipe, Polyethylene & Fit & Acc.		NO	None	NA	Visual	Project Staff			See Note 8.
07.02	Piles	lb.	03040	Grout, Non-shrink	See requir	ements f	for material #03040) under item 06.01					
			03549	H-Piles, Steel	ton	YES	Accept (Prod)	NA	MCCTR	Central Lab	See N	Jote 1.	See Note 1.
			3559	Pile Point, Steel	ea.	YES	Accept (Prod)	NA	MCCTR	Central Lab	qua	ntity	NA
				•									
07.03	Riprap		04819	Gravel (Bank Run)									
	(all types)	c.y.	08034	Stone (Broken/Crushed)	c.y.	NO	None	NA	Visual	Project Staff			See Note 8.

1	X=Not Standard, A=Spec Pro		Material	Material	Material	MAT	Sample	Test	Test	Test	Frequen 1 per	Frequency 1 per Sa		
Item	Title	Unit	#	Name	Unit	100	Тупе	Method	Type	Responsibility	(\mathbf{E})	m	lhs	ko
Item	The	Ome	08035	Gravel (Crushed)		100		Methou	1,10	Responsibility	(1) (1	.,1)	105	<u> </u>
07.04	Gabions	c.y.	03546	Gabions	ea.	YES	Accept (Prod)	NA	MC	Central Lab	quantity	y	1	NA
07.05	Slope Paving	s.y.	08031	To Be Determined.										
07.06	Micropiles	ea.	See materials	listed under 07.01										
07.07	Membrane													
	Waterproofing	s.y.	04199	Membrane Waterproofing	s.y.	NO	None	NA	MC	Project Staff	quantity	y		
	(Woven Glass)													
07.08	Dampproofing	s.v.	04207	Dampproofing Primer	gal	NO	None	NA	MC	Project Staff	quantity	v		
			04208	Dampproofing Sealer	0				-	. .	1	,		
<u>07.11</u>	X Cone Crib Wall	-	08031	To Be Determined.		1	r				1		1	
07.13	Permanent Steel													
07.14	Temp Steel	a f	02525	Diling Steel Sheet	1.£	VES	A agant (Brad)	NIA	MCCTD	Control Lab	quantit	7	r	NT A
07.14	Sheet Piling	5.1.	03335	Filling, Steel Sheet	1.1.	165	Accept (Flou)	INA	MCCIK	Central Lab	quantity	y	1	NA
07.15	Sheet I milg													
07.12	Earth Ret Syst	s f	07627	Reinforced Earth Wall	63	VES	A geomt(Prod)	NA	MC	Lab and Project	quantit	7	See	Note 8
07.17	Crushed Stone	ton	08034	Stone (Broken/Crushed)	ca.	TLS	Accept(110d)	INA	MC	Lab and Project	quantit	y	3661	Note 8.
07.20	for Slope	ton	08034	Gravel (Crushed)	C V	NO	None	NA	Visual	Project Staff			See 1	Note 8
	Protection		08035	Gruver (erusileu)	<i>c.y.</i>	110	i tone	1111	Vibuui	i tojeet stall			5001	1010 0.
07.32	Conc. Block	S.V.	03200	Concrete Masonry Unit (CMU)	See requir	ements f	for material #032	00 under item 05.07.						
	Slope Prot.	lb	03025	Mortar	See requir	ements f	or material #030	25 under item 05.07.						
07.51	Underdrain and	l.f.	01708	Pipe - For Underdrain or Outlet	See requir	ements f	or Pipe, Metal (A	All types) under item 06	.51.					
	Outlets		03985	Geotextile	s.y.	NO	None	NA	QPL/MC	Project Staff			1	NA
			04901	Bedding Material	c.y.	NO	None	NA	Visual	Project Staff			1	NA
			02649	Pipe - PVC & Fittings & Acc.	l.f.	NO	None	NA	Visual	Project Staff			See 1	Note 8.
07.55	Geotextile	s.y.	03985	Geotextile	s.y.	NO	None	NA	QPL/MC	Project Staff			1	NA
08.03	Paved Ditches	s.y.	04003	Curb Mix	See requir	ements u	inder 04.06.							
	and Channels		04819	Gravel (Bank Run)										
			08034	Stone (Broken/Crushed)										
			08035	Gravel (Crushed)	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	5k 3	.8k	160	72
			08036	Reclaimed Misc. Aggregate										
			08036X	Recl. Misc. Agg. (OFFSITE)			Accept (Prod)	Chem(Offsite ONLY)	MCCTR	District Lab	2.5k 1	.9k	160	72
08.11	Concrete	1.f.	01511	Curb, Precast	l.f.	YES	Accept (Prod)	NA	PC1	Central Lab	quantity	y	1	NA
	Curbing		03015-03X	Concrete PCC03XXX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75 (50	4 cyl	4 cyl
			03155	Expansion Joint filler	l.f.	NO	None	NA	MC	Project Staff			ז	NA
			03158	Preformed Expansion Joint Filler	s.f.								1	
08.13	Stone Curbing	l.f.	04909	Curbing, Granite Stone	l.f.	NO	None	NA	Visual	Project Staff			1	NA

	X=Not Standard, A=Spec Pro		Matarial	Maturial	M-4	MAT	Same la	Track	T 4	Track	Frequency	German La State
Item	Title	Unit		Name	Unit	100	Sample	1 est Method	Test	Test Responsibility	$(\mathbf{F}) (\mathbf{M})$	Sample Size
08.14	Reset Stone					100	1 ypc	Wittindu	турс	Responsibility		ibs kg
	Curbing	l.f.	00000	None		NO	None					
08.15	Bit. Conc. Lip	l.f.	04003	Curb Mix	See requir	ements u	nder 04.06.					
	Curbing	gal	04128,47	RS-1 or RS-1H	See requir	ements u	nder 04.06.					
08.16	X Granite Slope Curbing	l.f.	04910	Curbing, Granite Slope	l.f.	NO	None	NA	Visual	Project Staff		NA
08.18	Prtctve Cmpnd for Bridges	s.y.	00328	Protective Coating	gal	NO	None	NA	QPL/MC	Project Staff		NA
08.21	Precast Concrete	l.f.	00895	Concrete Barrier, Precast	l.f.	YES	Accept(Prod)	NA	PC1	Central Lab	size	See Note 7.
	Barrier Curb		03015-04X	Concrete-PCC04XXX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75 60	4 cyl 4 cyl
08.22	Temp Precast Conc. Barrier	l.f.	00865	Concrete Barrier, Precast, Temp	l.f.	NO	None					
09.01	A Bollard	ea.	07351	Bollard, Steel	ea.	YES	Accept (Prod)	NA	MC	Central Lab	quantity	NA
09.04	Metal Br Rail	1.f.	03429	Metal Bridge Rail System	l.f.	YES	Accept(Prod)	NA	MC	Lab and Project	quantity	See Note 2.
09.05	Stone Wall Fence	1.f.	00000	None		NO	None			5	1 2	
09.06	Wire Fence	l.f.	03326	Fence - Wire, Posts & Hardware	l.f.	YES	Accept(Prod)	TBD	MC	Central Lab	quantity	NA
09.10	Metal Beam Rail	l.f.	03406	Metal Beam Rail System	l.f.	YES	Accept (Prod)	NA	MC	Central Lab	quantity	NA
09.11	Metal Beam Rail	ea.	01435	Anchor, (Precast)	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	quantity	NA
	Anchorages		03405	Metal Beam Rail, Anchorages for	ea.	YES	Accept (Prod)	NA	Visual	Lab and Project	quantity	See Note 2.
			03015-033X	Concrete PCC033XX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75 60	4 cyl 4 cyl
			03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t 180t	5ft 1.5m
09.12	Remove and Reset Posts,	l.f.	08031	To Be Determined.		TBD						
09.13	Chain Lnk	1.f.	03309	Fence, Chain Link	l.f.		Accept(Prod)	NA	MC	Central Lab	quantity	3 lf 1m
	Fence		03310	Fence, Chain Link, Post for	ea.	YES			LABT			1 1
			03320	Fence, Hardware & Acc.	ea.	125						1 1
				(Chain Link)								
09.14	Metal Handrail	1.f.	03414	Metal Handrail	l.f.	YES	Accept(Prod)	NA	MC	Lab and Project	quantity	See Note 2.
09.16	Noise Bar Wall	s.f.	07822	Noise Barrier Wall	s.f.	YES	Accept (Prod)	NA	MC	Central Lab	quantity	NA
09.18	Three-Cable	ea.	03015-033X	Concrete PCC033XX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75 60	4 cyl 4 cyl
	Guide Railing		03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t 180t	5ft 1.5m
	(I_Beam Posts)		03419	Cable Guide Rail	l.f.		A acout (Drod)	NA	MC	Control Loh	quantity	NA
	& Anchorages		03421	Cable Guide Railing Anchorage	ea.	YES	Accept (Prod)	INA	MC	Central Lab	quantity	INA
09.21	Concrete	s.f.	01467	Slab, Precast	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	quantity	NA

	X=Not Standard, A=Spec Pro					MAT	<i>.</i> .				Frequency			
Itom	Title	Unit	Material #	Material	Material	100	Sample	Test	Test Type	Test Responsibility	I p (F)	oer (M)	Sample	e Size kα
Item	Sidowalka		π 02008	Deformed Steel Dorg, Enviry Ctd	116	YES	A scoret (Dred)	T244	Турс	Control Lob	(E) 200+	1904	50	1.5m
	Sidewalks		02998	Deformed Steer Bars, Epxy Ctu	10.	VES	Accept (Plod)	1244			2001	1800		1.311
			03015-044X	Concrete-PCC044XX	c.y.	TES VEG	Accept (Prod)	122	FLABI	Central Lab	75	60	See No	te 14.
			03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft	<u>1.5m</u>
			03145	Fabric, Wire & Welded Steel	s.y.	YES	Accept (Prod)	T244	LABT	Central Lab	$60 \text{k} \text{ft}^2$	6k m²	1yd²	1 m ²
			03158	Preformed Expansion Joint Filler	s.f.	NO	None	NA	MC	Project Staff			See No	ote 1.
			04819	Gravel (Bank Run)										
			08034	Stone (Broken/Crushed)			Accept (Prod)	Т27	LART	District Lab	5k	3.84	160	72
			08035	Gravel (Crushed)	c.y.	YES	Accept (110d)	127	LADI	District Lab	Л	J.0 K	100	12
			08036	Reclaimed Misc. Aggregate										
			08036X	Recl. Misc. Agg. (OFFSITE)			Accept (Prod)	Chem (Offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	72
			08060	Detectable Warning Strip	ea.	NO	None	NA	QPL/MC	Project Staff	qua	ntity		
09.22	Bituminous	s.y.	0405X	HMA S 0.375	ton	YES	Accept(Prod)	TBD	FLDT	Project Staff	day	day	NA	4
	Concrete		0/1810	Gravel (Bank Run)										
	Concrete		04017		-		Accept (Prod)	Т27	LART	District Lab	51	3.84	160	72
	Driveway		08035	Gravel (Crushed)	c.y.	YES	Accept (110d)	127	LADI	District Lab	JK	J.OK	100	12
			08036	Reclaimed Misc. Aggregate										
	2		08036X	Recl. Misc. Agg. (OFFSITE)			Accept (Prod)	Chem (Offsite ONLY) MCCTR	District Lab	2.5k	1.9k	160	72
09.24	Concrete Ramp/Driveway	c.y.	See materials	listed under 06.01 and 06.02.										
09.25	Pvmnt for Railing		04003	Curb Mix	See requir	ements u	inder 04.06.							
09.30	Object Marker	ea.	03943	Object Marker	ea.	NO	None	NA	QPL/MC	Project Staff	qua	ntity	<i>a</i>	
00.20	Sweening for	ea.	03952	Sign Post	ea.	YES	Accept(Prod)	TBD	MC	Central Lab	qua	ntity	See No	ote 1.
09.39	Dust Control	hr.	00000	None		NO	None							
09.41	X Service Bridges	ea.	08031	To Be Determined.	-									
09.42	Calc Chloride Dust Control	ton	00302	Calcium Chloride	gal	NO	None	NA	Visual	Project Staff			NA	4
09.44	Topsoil	s.y.	00542X	Topsoil (from offsite)	c.y.	YES	Accept (Prod)	NA	MCCTR	Central Lab	1k	765	NA	ł
			00542	Topsoil (from project)	c.y.	NO	None	NA	Visual	Project Staff				
09.45	X Wildflowers	lb.	00000	None	116	ALT	None	NA	La	ndscape Design Unit	Approv	al	See No	te 11.
09.46	Liming Dug Shaltar	ton	00533	Lime To Do Dotomain ad	ID.	NU	Inone	NA	Visual	Project Stari			NA	1
09.4/	Dus Shellel	ea.	08031	To be Determined.		IBD								

_	X=Not Standard,					мат					Frequ	iency	y		
	A=Spec Pro		Material	Material	Material	MAI	Sample	Test	Test	Test	1 p	ber	Sample Size		
Item	Title	Unit	#	Name	Unit	100	Туре	Method	Туре	Responsibility	(E)	(M)	lbs kg		
09.49	Planting and	ea.	00327P	Water (plantings)	gal	NO	None	NA	Visual	Project Staff			NA		
	Mulching		00510	Peat	c.y.	NO	None	NA	Visual	Project Staff			NA		
	Trees, Shrubs		00533	Lime	ton	NO	None	NA	Visual	Project Staff			NA		
	Vines		00496	Fertilizer	lb.	NO	None	NA	МС	Project Staff			See Note 10.		
	and		00536	Plant Materials		ALT	None		Lan	dscape Design Unit	Approv	al	See Note 11.		
	Groundcover		00542P	Topsoil - plantings (no turf estab)	c.y.	YES	Accept (Prod)	NA	MCCTR	Central Lab	1k	765	NA		
	Plants		07547	Tree		ALT	None		Lan	dscape Design Unit	Approv	al	See Note 11.		
09.50	Turf	s.y.	00327P	Water (plantings)	gal	NO	None	NA	Visual	Project Staff			NA		
	Establishment		00496	Fertilizer	lb.	NO	None	NA	MC	Project Staff			See Note 10.		
	Erosion Control		00497	Seed	lb.	NO	None	NA	МС	Project Staff			See Note 10.		
			00533	Lime	lb.	NO	None	NA	Visual	Project Staff			NA		
			00534	Mulch - All Types	lb.	NO	None	NA	Visual	Project Staff			NA		
			00542	Topsoil (from project)	c.v.	NO	None	NA	Visual	Project Staff			NA		
			00542X	Topsoil (from offsite)	c.y.	YES	Accept (Prod)	NA	MCCTR	Central Lab	1k	765	NA		
			3985	Geotextiles	s.y.	NO	None	NA	QPL/MC	Project Staff			NA		
09.53	Sodding	s.y.	00518	Sod	s.y.	NO	None	NA	МС	Project Staff			See Note 11.		
		_		Other materials as listed in 09.50.						5					
09.76	Barricade Warning Lights	day	03603	Warning Lights	ea.	NO	None	NA	Visual	Project Staff			NA		
09.77	Traffic Cone	ea.	03934	Reflective Sheeting	s.f.	NO	None	NA	QPL/MC	Project Staff			NA		
			03948	Traffic Cones	ea.	NO	None	NA	Visual	Project Staff			NA		
09.78	Traffic Drum	ea.	03934	Reflective Sheeting	s.f.	NO	None	NA	QPL/MC	Project Staff			NA		
			03927	Traffic Drums	ea.	NO	None	NA	Visual	Project Staff			NA		
09.79	Construction	ea.	03934	Reflective Sheeting	s.f.	NO	None	NA	QPL/MC	Project Staff			NA		
	Barricades		03974	Construction Barricade	ea.	NO	None	NA	MC	Project Staff					
09.81	42 in. Traffic	ea.	03934	Reflective Sheeting	s.f.	NO	None	NA	QPL/MC	Project Staff			NA		
	Cone		03948	Traffic Cones	ea.	NO	None	NA	Visual	Project Staff					
10.01	Trenching and	1 f	04901	Bedding Material	c.y.	NO	None	NA	Visual	Project Staff			See Note 8.		
	Backfilling	1.1.		Other materials as listed elsewher	re.	-									
10.02	Light Standards		01432	Foundation (Precast)	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	size		See Note 7.		
	and Traffic		03015-033X	Concrete PCC033XX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75	60	4 cyl 4 cyl		
	Control		03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft 1.5m		
	Foundations		03504	Anchor Bolts	ea.	YES	Accept (Prod)	TBD	LMCT	Central Lab	qua	ntity	1 per size		
			03711	Ground Rod	ea.	NO	None	NA	Visual	Project Staff			NA		
10.03	Light Standards	ea.	03704	Light Standard	ea.	YES	Accept (Prod)	TBD	MC	Central Lab	qua	ntity	See Note 6.		
10.04	Roadway Luminaire	ea.	07645	Luminaire	ea.	NO		Cataloo Cut - I	Designer						

	X=Not Standard, A=Spec Pro		Matarial	Matorial	Matarial	MAT	Frequency Sample Test Test 1 per					Sampla Siza
Item	Title	Unit	Wrater fai #	Name	Unit	100	Туре	Method	Type	Responsibility	(E) (M)	lbs kg
10.06	Underbridge				22	NO		Catalog Cut	Designer	I J		
	Luminaire	ea.	07645	Luminaire	ea.	NO						
10.08	Elec. Conduit	l.f.	03693	Conduit & Fittings (all types)	l.f.	NO	No Request for Te	est - Catalog Cut -	Designer			
10.09	Cast Iron Junction Box	ea.	03724	Junction Box & Cover	ea.	YES	Accept (Prod)	NA	MC	Central Lab	quantity	NA
10.10	Conc Handhole	ea.	01462	Handhole & Cover, Precast	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	size	See Note 7.
10.11	4" Drain Pipe	l.f.	01708	Pipe - For Underdrain or Outlets	l.f.	NO					•	
10.12	Single Conductor	l.f.	08031	To Be Determined.		TBD		Catalog Cut	- Designer			
10.14	Cable In Duct	l.f.	08031	To Be Determined.		TBD						
10.15	Grounding	l.f.	03709	Ground Wire	l.f.	NO	None	NA	Visual	Project Staff		NA
	Conductor		03711	Ground Rod	ea.	NO	None	NA	Visual	Project Staff		NA
10.17	Service Entrance & Cabinet	ea.	00000	None	_	NO	Catalo	og Cut	Desi	gner of Record		
10.18	Navigation Light	ea.	08031	To Be Determined.		TBD		Catalog Cut	- Designer			
11.01	Pole Anchor	ea.	08031	To Be Determined.		TBD						
11.02	Pedestals	ea.	03801	Pedestals, Aluminum	ea.	NO	None	NA	Visual	Project Staff		NA
11.03	Span Pole	ea.	03802	Span Pole - Steel	ea.	YES	Accept(Prod)	NA	MC	Central Lab	quantity	See Note 2 & 6.
11.04	X Mast Arm		03806	Mast Arm Assembly	ea.	YES	Accept(Prod)	NA	MC	Central Lab	quantity	See Note 2 & 6.
11.05	Traffic Signals	ea.	03766	Traffic Signal Equipment	ea.	NO		Catalog Cut	Dogionar			
			03807	Traffic Signal	ea.	NO		Catalog Cut	- Designer			
11.06	Signal	ea.	00000									
11.07	Pedestrian Push Button	ea.	00000									
11.08	Controllers	ea.	00000									
11.10	X Press. Veh. Det.		00000	None		NO	Catalo	og Cut	Desi	gner of Record		
11.11	Loop Detector & Sawcut	ea.	00000									
11.12	Mag. Veh. Det.	ea.	00000									
11.13	Control Cable	l.f.	00000									
11.14	A Msngr Spn Wire	l.f.	00000									
11.15	Illum Signs	- 00	00000									
11.16	A Alt. Flsh Sig for Wrnng Sgns	ea.	00000	None		NO	Catalo	og Cut	Desi	gner of Record		

1	X=Not Standard, A=Spec Pro		Material	Material	Material	MAT	Sample	Test	Test	Test	Frequ 1 p	ency er	Sample	Size
Item	Title	Unit	#	Name	Unit	100	Туре	Method	Туре	Responsibility	(E)	(M)	lbs	kg
11.18	Rmvl/ Relo Traff Sig. Equip	l.s.	08031	To Be Determined.		TBD								
11.30	High Mounted Inter Illum. Flashing Arrow	day	00000	None	-	NO	Catalo	og Cut	Desig	ner of Record				
11.31	Changeable Message Sign / Remote Controlled Sign	day	03764	Sign (Variable Message)	ea.	NO	None	NA	МС	Project Staff			NA	
12.00	Gen. Clauses for Hwy Signing		00000	None		NO								
12.01	Ohead Sign Sup.	ea.	03928	Sign Support, Structural Steel	ea.	YES	Accept(Prod)	NA	MC	Central Lab	quan	itity	See Note 2	2 & 6.
12.02	Overhead Sign	ea.	03015-X	Concrete PCC03XXX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75	60	4 cyl	4 cyl
	Support		03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft	1.5m
	Foundation		03504	Anchor Bolts	ea.	YES	Accept (Prod)	TBD	LMCT	Central Lab	quan	itity	1 per si	ize
			03711	Ground Rod	ea.	NO	None	NA	Visual	Project Staff			NA	
12.03	Side Mntd Sign Fndtn	ea.	All Materials	and Frequencies as listed under 12	.02.									
12.04	Sign Panel Overlay	s.f.	00000	None		NO	None	NA	Visual	Project Staff			NA	
12.05	Delineators	ea	03933	Delineator	ea.	NO	None	NA	QPL/MC	Project Staff			NA	
	a:	ou.	03952	Sign Post	ea.	YES	Accept(Prod)	TBD	MC	Central Lab	quan	itity	See Not	e 1.
12.07	Sign Face - Extrdd Alum.	s.f.	03938	Sign Face, Sheet Aluminum	s.f.	NO	None	NA	QPL/MC	Project Staff			NA	
12.08	Sign Face -	s.f.	03938	Sign Face, Sheet Aluminum	s.f.	NO	None	NA	QPL/MC	Project Staff			NA	
10.00	Sheet Alum.	ea.	03952	Sign Post	ea.	YES	Accept (Prod)	NA	MC	Central Lab	quan	itity	See Not	e 1.
12.09	Painted Pvmnt	1.f.	00060	Paint Wtrbrn Pvmt Mrk (3 min)	gal	NO	None	NA	MC	Project Staff	4		See Not	e 5.
	Markings	lb.	00306	Glass Spheres	lb.	NO	None	NA	MC	Project Staff				
12.10	Epoxy Pavmnt,	l.f.	00091	Paint - Epoxy Pvmt Markings	gal	NO	None	NA	MC	Project Staff				_
	Symb and Lgnds	s.f.	00306	Glass Spheres	lb.	NO	None	NA	MC	Project Staff			See Not	e 5.
12.11	Removal of Pvmnt Markings	s.f.	00000	None		NO	None							
12.12	Temp Pvmnt Mrkng Tape	l.f.	00000	None		NO	None							
12.14	Black Mrkng Tape	l.f.	00206	Preformed Black Marking Tape	l.f.	NO	None	NA	МС	Project Staff			NA	

	X=Not Standard, A=Spec Pro		Matarial	Material	Matarial	MAT	Sample	Test	Test	Test	Frequency 1 per	Sample Size
Item	Title	Unit		Name	Unit	100	Type	Method	Tyne	Responsibility	(\mathbf{F}) (\mathbf{M})	lhs kg
12 15	X Tublr Sign Sup	ea		ictural Steel requirements	Unit	100	Type	Mictilou	турс	Responsionity		105 Kg
12.16	X Black Epoxy	cu.	500 00.05 But									
12.10	Resin Pymnt	l.f.	00091	Paint - Epoxy Pymt Markings								
	Mrkings Symble		000071		gal	NO	None	NA	MC	Project Staff		See Note 5.
	and Lgnds	s.f.	00091	Paint - Epoxy Pymt Markings								
12.20	Constr. Signs -											
	Encap. Lens	s.f.	03945	Construction Signing	s.f.	NO	None	NA	QPL/MC	Project Staff		NA
	Refl Sheeting			<u> </u>						2		
13.00	X Utilities		Util	lities Special Provisions		NO	None					
18.01	X Repair Impact					TRD						
	Att Sys.		08031	To Be Determined.		TDD						
18.02	Sand Barrels	ea.	04915	Sand (Inertial Barriers)	lbs	NO	None	NA	Visual	Project Staff		See Note 8.
18.03	Imp Att Sys.	ea.	03970	Impact Attenuator	ea.	NO	None	NA	QPL/MC	Project Staff	quantity	NA
18.06	Att Sys.	hr.	03970	Impact Attenuator	ea.	NO	None	NA	MC	Project Staff	quantity	NA
18.07	Temp Impact	ea.	00298	Sodium Chloride, Interial Barriers	lb.	NO	None	NA	MC	Project Staff		NA
	Atten Sys.		03970	Impact Attenuator	ea.	NO	None	NA	QPL/MC	Project Staff	quantity	NA
~			4700	Sand	c.y.	NO	None	NA	MC	Project Staff		NA
Gener	al Note: Materials u	ised w	ithin an item n	ot referenced in the table must be to	ested as spe	ecified in	the special provi	sion for that item, or a	as they wou	ld be typically tested	with other item	s. Should neither
Natas				provide direction	n, contact t	ne Divisi	on of Materials 1	esting for assistance.				
Notes	Sample may be requ	uired d	lenending on so	surce of material DMT personnel	will reques	t sample	from project if n	eeded				
2	Notify Division of N	Materi	als Testing price	or to fabrication to schedule plant i	spection S	Submit R	equest for Test at	fter items are inspecte	d by projec	t staff upon delivery		
3	Submit one test pad	per 5	0 of the same to	when we are portions thereof. If there are	less than 5	50 pads to	otal and more that	n one type, submit the	type with t	the greatest quantity.		
4	DO NOT submit a	Reque	st for Test unle	ss the water is non-potable. Water	may be tes	sted if dra	wn from a suspe	ct source. (1qt/1 lt sar	nple if need	led - 1 per project)		
5	Confirm Batch # on	Mate	rials Certificate	e matches information provided on	Qualified N	Materials	List (QML). Con	ntact DMT for direction	on.	1 1 5 /		
6	Material Certificate	must	indicate confor	mance for entire assembly includir	ig, but not l	limited to	, base, shaft, brad	cket arm, galvanized o	coating and	deflection testing (if	required).	
7	Mat-100 can contai	n mult	iple sizes, each	size on the project must be docum	ented with	a MAT-	100. Total project	et quantity per size do	es not requi	ire testing.		
8	If assistance is need	led, no	tify District La	boratory to schedule a field inspec-	tion.							
9	Project staff should	verify	bags used are	labeled as meeting ASTM C150; n	nortar must	meet C1	714 or C387; Lin	ne must meet C207; C	Grout must i	meet C1107.		
10	Material Certificate	may ł	be substituted f	or affadavit.								
11	Send request for ins	pectio	n to Landscape	e Design Unit, Newington Room 3	401 NWA	(860) 59	4-3336					
12	PC1 for item will co	over fr	ames and grate	s if incorporated into precast items	. Material (Certificat	ion applies when	material is not integra	al with a pro	ecast item.		
13	Delivery Ticket clea	arly lis	ting the manuf	acturer of the bricks and blocks is	required. U	Jnfamilai	r sources should	not be used, contact I	OMT for con	nfirmation.		
14	Represented quantit	y can	be adjusted bas	sed on field testing results. Contac	t DMT for	direction						

Chapter 9 - Minimum Schedule for Assurance Testing

Legen	d								
Item: St	andard Specification Section and the fir	st four digits of	the Contract Item number. Colum	n also includ	es section he	adings		<u></u>	
Title: Ge	enerally the overall subject of the Stand	ard Specificatio	n Section and the Contract Item n	umbers.					
Materia	Code: Code used in SiteManager and	by the Division	of Materials Testing to identify co	mponent mat	erials used in	Contract Item	IS		
Materia	Name: Definition of the Material #								
Test Ty	Describes where the test is perform	ed							
Sample	Resp: Who performs the sampling								
Frequer	ncy: Number of tests required per quan	tity of material u	ising the sample units.						
Sample	Units: Units of the amount of material	represented by	a single sample or test.						
Sample	Size: Size of Sample								
		Material		Tost	Туро	Sample	Freq.	Freq	Sample
Item	Title	Code(s)	Material Name	1631	iype	Resp.	1 per	Units	Size
							•		
	Earthwork								
02.02	Roadway Excavation, Formation of	08037	Recl. Waste						
	Embankment and Disposal of	08037X	Recl. Waste (OFFSITE)	Fie	eld	Central Lab	50000	tons	na
	Surplus Material	08039	Embankment Material						
02.03	Structure Excavation	08037	Recl. Waste						
		08037X	Recl. Waste (OFFSITE)	Fie	eld	Central Lab	50000	tons	na
		08039	Embankment Material				50000		
02.07	Borrow	04902	Borrow	FIE	eld	Central Lab	50000	tons	na
02.12	Subbase	04819	Gravel (Bank Run)			District Lob	50000	tana	00 lba
		08034	Stone (Broken/Crushed)	Labo	ratory	District Lab	20000	tons	20108
		08035	Bool Mico Agg	Labo	alory	Central Lab	30000	tons	na
		08036X	Reci. Misc. Agg.						
		000307	Redi. MISC. Agg. (OFFSITE)			Project			
03.03	Concrete Base	03014-PAV	Concrete-Pavement (3500psi/25MPa)	Fie	eld	Personnel	2500	c.y.	na
03.04	Processed Aggregate Base	04819	Gravel (Bank Run)						
		08034	Stone (Broken/Crushed)						
		08035	Gravel (Crushed)	Labo	ratory	District Lab	30000	tons	80 lbs
		08036	Recl. Misc. Agg.		, ,	Central Lab	30000	tons	na
		08036X	Recl. Misc. Agg. (OFFSITE)						
03.05	Processed Aggregate	04819	Gravel (Bank Run)						
		08034	Stone (Broken/Crushed)			District Lab	30000		80 lbs
		08035	Gravel (Crushed)	Labo	ratory	Central Lab	30000	tons	na
		08036	Recl. Misc. Agg.						
		08036X	Recl. Misc. Agg. (OFFSITE)						

		Material		Teet	Tuno	Sample	Freq.	Frea	Sample
ltem	Title	Code(s)	Material Name	Test	туре	Resp.	1 per	Units	Size
Surfac	e Courses or Pavements								
04.01	Concrete Pavement	03014-X 03015-X	Concrete PCC 0XXXX	Fie	eld	Project Personnel	2500	c.y.	4 cyl na
04.06	Bituminous Concrete	04003	Curb Mix					ea	
		04052,3,4,5	HMA, Level 1,2,3 (9.5 mm / 0.375 in)						
		04056,7,8,9	HMA, Level 1,2,3 (12.5 mm / 0.5 in)						
		04060,1,2,3	HMA, Level 1,2,3 (19.0 mm / 0.75 in)	Density ¹	Laboratory ²	Central Lab	40		
		04064,5,6,7	HMA, Level 1,2,3 (25.0 mm / 1.0 in)						
		04068, 9, 70, 71	HMA, Level 1 (37.5 mm / 1.5 in)						
		04076, 7, 8, 9	HMA, Level 1,2,3 (6.25 mm / 0.25 in)						
	Structures								
05.06	Retaining Walls, Endwalls and Steps	03014-X 03015-X	Concrete-PCC OXXXX	Fie	eld	Project Personnel	2500	c.y.	na
06.01	Concrete for Structures	03014-X 03015-X	Concrete-PCC OXXXX	Fie	eld	Project Personnel	2500	c.y.	na
Notes:								1	
1	Test performed on Core samples usir	Ig AASHTO T-33	31.						
2	Test performed: AASHTO T-30; T-16	6; T-209; T-308;	T-312						

Appendix A - Forms

Form	Name	Spec
MAT-100	Request for Test	
MAT-103	Report of Rejected Material	
MAT-104	Report of Test of Miscellaneous Material	
MAT-106	DMT Contact List	
MAT-107	Quality Assurance – Notable Observation	
MAT-108	Daily Work Report	
MAT-108HMA	Daily Work Report (Hot Mix Asphalt)	
MAT-108PCC	Daily Work Report (Precast Concrete)	
MAT-109	Core Sample Documentation	
MAT-110	Welding Operator Qualification Record	
MAT-111	Welding Certification Application	
MAT-112	Welding Call In Report	
MAT-200	Report of Test of Metal Pipe (Steel)	
MAT-202	Report of Test of Perforated Metal Pipe	
MAT-203	Report of Test of Structural Plate and Pipe Arches	
MAT-204	Report of Test of Culvert End	
MAT-205	Report of Tests of Bank Run Gravels or Processed Aggregate	
MAT-206	Report of Test of Sand	
MAT-207	Report of Test of Coarse Aggregate	
MAT-208	Report of Test of Rock Salt	
MAT-209	Report of Test of Calcium Chloride	
MAT-211	Report of Test of L.A. Abrasion	
MAT-213	Report of Test of Moisture/Density (Proctor)	
MAT-217	Worksheet: Moisture Density (Proctor) 6" mold	
MAT-218	Worksheet: Moisture Density (Proctor) 4" mold	
MAT-219	Worksheet for Specific Gravity and Absorption of Coarse Aggregate	
MAT-220	Worksheet for Soundness of Fine Aggregate - AASHTO T-104	
MAT-221	Worksheet for Soundness of Coarse Aggregate- AASHTO T-104	
MAT-222	Assurance Report: Material Testing Personnel and equipment in the field.	
MAT-224	Assurance Report: Plastic PC Concrete	
MAT-225	Assurance Report: Plastic PC Concrete (Metric)	
MAT-228	Report of Test: Glass Beads	
MAT-229	Report of Test: Visi Beads	
MAT-235	Report of Test: Paint-Solvent White &Yellow Pav. Mark (FastDry)	
MAT-236	Report of Test: Paint-Solvent White &Yellow Pav. Mark (Reg.Dry)	
MAT-239	Report of Test: Paint - Waterborne White & Yellow Paint (Fast Dry)	
MAT-240	Report of Test: Paint - Waterborne White & Yellow Paint (Reg. Dry)	
MAT-241	Independent Assurance Report: Concrete Fine Aggregates	
MAT-242	Independent Assurance Report: Concrete Coarse Aggregate	
MAT-243	Independent Assurance Report: Subbase & Processed Agg Base	
MAT-244	Independent Assurance Report: Plastic PC Concrete	
MAT-245	Report of Test – Aggregate Variation Limits	

MAT-246	Tracking Report: Asphaltic Plug Joint	
MAT-248	Tracking Report: Payement Marking Materials	
MAT-300	Report of Test: Anchor Bolts (Straight)	
MAT-301	Report of Test: Anchor Bolts (w/Hook)	
MAT-302	Report of Test: Hex Bolt	
MAT-303	Report of Test: Chain Link Fence Fabric	4.58
MAT-304	Report of Test: Reinforced Concrete Pipe	
MAT-305	Report of Test: Steel Bars and Shapes	
MAT-306	Report of Test: Steel Fabric Reinforcement	
MAT-307	Report of Test: General Tensile Strength	
MAT-308	Report for Test on Cylinders	
MAT-308A	Report of Test on Cylinder Diameter	
MAT-309	Report of Test: Masonry Concrete Units	4.48
MAT-310	Report of Test: Elastomeric Bearing Pad	
MAT-312	Report of Test: Clay Brick	4.48
MAT-313	Report of Test: Concrete Block for Slope Protection	
MAT-314	Certification of Precast Concrete Prod.	
MAT-316	Report of Test: Portland Cement (All Types)	4.05
MAT 323	Report of Test: Steel Strand	4.25
WAT-324	prestress/precast concrete and pipe manufacturers	
MAT-325	Report of Test: Chain Link Fence Hardware	
MAT-326	Report of Test: Chain Link Fence Tension Wire	
MAT-327	Report of Test: H-Piles and Wide Flange Shapes	
MAT-328	Report of Test: Deformed Steel Wire for Concrete Reinforcement	
MAT-329	Vacant	
MAT-330	Guideline: Visual Inspection of Reinforcing Steel	
MAT-401	Report of Test: Asphalt Binder	
MAT-402	Report of Test: Emulsified Asphalts	
MAT-404	Field Report: Bituminous Concrete Plant Inspection	
MAT-406	Field Report: Inspection of HMA Field Laboratory	
MAT-407	Field Report: Plant and Laboratory Deficiency Report	
MAT-408	Field Report: QA Verification Form	
MAT-412cm	Report of Test: Bituminous Curb Mix Quality	
MAT412s	Report of Test: Bituminous SuperPave Quality (2 sided)	
MAT-412s-ppt	Report of Test: Bituminous SuperPave Quality (Pre-Production Trial)	
MAT-412ut	Report of Test: Bituminous Ultrathin Quality	
MAT-417	Worksheet: Random Lot Selection at Plant	
MAT-418	Worksheet: Job Mix Formula Verification	
MAT-419	Template: Quality Control Plan for Fine Aggregate. used in HMA.	
MAT-429cm	Template: Job Mix Formula (curb mix)	
MAT-429s	Template: Job Mix Formula (SuperPave)	
MAT-429ut	Template: Job Mix Formula (Ultrathin)	

MAT-433	Worksheet: Ignition Oven Correction	
MAT-438NonPWL	Worksheet: Daily Plant Adjustment (Non-PWL Lots)	
MAT-438PWL	Worksheet: Daily Plant Adjustment (PWL Lots)	
MAT-440	Field Report: Producer Facility Mix Design Status	
MAT-600	Report of Witness Test – HMA Independent Assurance	

State of Connecticut Department of Transportation Material Test Report

SAMPLE ID							
REVISED SAMP	LE ID						
Material Code							
Material Descripti	on						
Sample Date							
Sampled By							
Source of Supply							
Producer/Supplie	r Code						
Material Rep Qty							
Sample Unit				REMARKS			
Sample Test Type	e						
Acceptance Meth	od Type						
Control Type							
Control Number							
Sample Taken Fr	om						
Purpose/Intended	l Use						
Location of Samp	le						
Plant ID / TYPE			1				
Plant Name							
Contract Number							
District Number							
Federal Aid Num	ber						
Field Office Phon	e Number						
Sample Status							
Date of Assigned	Status						
Creator User ID							
Project Number	Item Code	САТ	Item	Description	Material Rep Qty		

The MAT-100 must accompany all samples and documentation submitted to the Division of Materials Testing. The form is normally produced electronically through CMR/SiteManager. All samples other than PC concrete cylinders must have a MAT-100 attached or included so that the sample can be tracked by DMT personnel. Samples or documentation received without a MAT-100 may be returned to the project or discarded without any action by the DMT.

STATE OF CONNECTICUT - DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING

MAT-103 REV 11/16	REPORT	OF REJE	CTED MATERIA	AL.		
Project Number		ITEM # (If multipl	e, only list first from MAT-100)			Date
Material	Sample ID.					I
Source of Material	Quantity Represented		Reason for Rejection			
Complete section 1 OR 2.	See below fo	or instruc	tions.			
1. ACTION TAKEN - DOES NOT	INCLUDE RE	TESTING TH	HE SAME MATERIA robe. Swiss Hammer)	AL WIT	H A DIFFEREN	IT TEST METHOD.
New Sample	Source	.,	Sample ID.			Sample Status
Material Replaced	Source		Sample ID.			Sample Status
Signature						
Inspector				Print		
Project Engineer	ningar			Print		
Town Official/Title (municipal p	roiects only)			Print		
				•		
2. ACCEPTANCE OF REJECT	ED MATERIA	L WITHOU	T ACTION		Sectio	n Applied
In accordance with ConnDOT \$ 1.06.04, the non-complying ma	Standard Spec terial is hereby	ifications Se accepted b	ection 1.06.02 or by the District.		1.06.02	1.06.04
Signature/Print					Che	ck one
Inspector				Print		
Project Engineer				Print		
District or Assistant District Eng	gineer			Print		
Town Official/Title (Municipal Proje	cts Only)			Print		
For acceptance by Section 1.00	6.02, all the fol	lowing crite	ria must be met.			
1. Results of prior and subsequent satisfactory.	series of tests	of the materia	al or materials from t	he sam	e source or sou	urces are found
2. The incidence and degree of no reasonable limits.	n-conformance	with the Cont	tract requirements ar	e, in th	e Engineer's jud	lgement, within
3. The Contractor, in the Engineer	s judgement, ha	ad diligently e	exercised material co	ontrols o	consistent with g	ood practices.
4. No adverse effect on the value of	or serviceability	of the comple	eted work could resu	lt.		
For acceptance by Section 1.00 must be described below.	6.04, any credi	its, allowand	es, warranties, or	other o	conditions of a	cceptance
Orig - Division of Materials Te	esting	Copy -Dist	rict Copy	/ - Proi	ect Records	

Report of Rejected Material (MAT-103) Instructions

The Report of Rejected Material form serves the following purpose:

1. Identify the project and material that did not meet specification.

2. Report action taken (if any) **which only includes retesting** the material with an additional sample and achieving acceptable results or **removing** and replacing the deficient material with acceptable material. When such an action is taken, the MAT-103 provides the DMT with information on how rejected material was addressed. Signatures are required in this section to acknowledge the rejection and the action taken.

Please Note: Portland Cement (PC) Concrete is recommended for acceptance or rejection based on concrete cylinder test results at 28 days of age. Windsor Probe or Swiss Hammer results are for information only and will not override the test cylinder results at 28 days regardless of when they are performed. The PC concrete will be listed as an exception to the specifications on the Final Materials Certificate unless the District accepts the concrete using the acceptance criteria described below.

3. In the case where no action was taken, the District may formally accept the non-complying or deficient material in accordance with Sections 1.06.02 or 1.06.04. Signatures in this section are intended for formal acceptance of the non-complying or deficient material by the District. In the case where a Town Official or Consulting Engineer accepts material, if the District agrees, it must formally concur with the signatures. The DMT may still take exception to the District acceptance and list the material as an exception to the specification on the Final Materials Certificate if it is unable to concur.

MAT-104 REPORT OF TEST MISCELLANEOUS MATERIAL

STATE OF CONNECTICUT	DATE	PROJECT/SAMPLE NO.
DEPARTMENT OF TRANSPORTATION		
BUREAU OF HIGHWAYS	LABORATORY NO.	
REPORT OF TEST OF MISCELLANEOUS MATERIAL		
MAT 104 Revised July 2003		
RECONNENDED FOR	DEMADYC	
RECOMPENDED FOR	REMARKS	

The MAT-104 will be used by DMT personnel to report the results of testing on materials that are not otherwise covered by any specific reporting form.

CONNECTICUT DEPARTMENT OF TRANSPORTATION

Mat 106 Contact List

10

REV 04/16

RE	PRESENTATIVE (DMT - Rocky	/ HIII)			
MATERIAL TO BE TESTED					
MATERIALS		STAFF Telephone (86			
AGGREGATES (COARSE & FINE)		See District Labs Below*			
BRICK, CONCRETE BLOCK, CONCRETE CYLINDER R	ESULTS	email:	(860)		
	MARK BROTHWELL	Mark.Brothwell@ct.gov	258 - 0378		
CALCIUM CHLORIDE. FERTILIZER. PAINT (TRAFFIC).	SODIUM CHLORIDE.				
	DANIEL GUZZO	Daniel.Guzzo@ct.gov	258 - 0339		
CEMENT (TYPE I, I/II, III), GROUT					
	MOSES MARINO	Moses.Marino@ct.gov	258 - 0379		
CERTIFICATIONS, PIPE – PLASTIC					
	STEPHEN MANN	Stephen.Mann@ct.gov	258 - 0344		
CHAIN LINK FENCE, GUARD RAIL, STEEL ITEMS (REE	BAR, BOLTS, ETC.)				
	MARK BROTHWELL	Mark.Brothwell@ct.gov	258 - 0378		
CONCRETE MIX DESIGNS (NON-STANDARD), PRECA	ST/ CONCRETE, BOX CULVER	RTS			
	DANIEL GUZZO	Daniel.Guzzo@ct.gov	258 - 0339		
CONCRETE MIX, (STANDARD) MIXES (Check SiteMana	ger Terminal Server Materials F	older)			
	CHARLES GARDON	Charles.Gardon@ct.gov	258 - 0717		
CORROGATED METAL PIPE		See District Labs Below*			
CRACK SEALERS, JOINT SEALERS, MEMBRANES					
	DANIEL GUZZO	Daniel.Guzzo@ct.gov	258 - 0339		
FENCE, CHAINLINK, GUARD RAIL					
	MARK BROTHWELL	Mark.Brothwell@ct.gov	258 - 0378		
HOT MIX ASPHALT					
HMA PLANT – DMT Office	DAVID HOWLEY	David.Howley@ct.gov	258 - 0350		
HMA Plant Operation's / Field Inspection	DAVID PARILLO	David.M.Parillo@ct.gov	258 - 0389		
HOT MIX ASPHALT (Density Accentance by Cores)		David.Howley@ct.gov	258 - 0350		
		Andrew Bednar@ct.gov	258 0708		
STRUCTURAL STEEL/WELDING/COATINGS		<u>, indion.boundi.gor</u>	230-0700		
		David M Parillo@ct gov	258 _ 0380		
CERTIFICATIONS/ PRECAST CONCRETE CATCH BAS	INS. MANHOLES and TOPS. P	PIPE – REINFORCED CONCRETE	230-0303		
	STEPHEN MANN	Stephen Mann@ct.gov	258 - 0344		
FINAL MATERIAL CERTIFICATION		<u></u>	230-0344		
		Laura Pelletier@ct.gov	258 - 0323		
			250-0525		
SITEMANAGED			258 - 0350		
		David M Parilla@at apy	050 0000		
	DAVID PARILLO		258 - 0389		
AGGREGATES and RIP RAP, PIP	E, METAL, ALUMINUM CORRI	UGATED See District Labs Below*			

DISTRTICT 1		DISTRICT 3			
Justin Labossiere	(860) 258 - 0335	Steve Parkosewich	(203) 389 - 3128		
DISTRICT 2		DISTRICT 4			
Mark Tice	(860) 537 - 8935/36	Gerald Smith	(203) 591 - 3739		

 $S:\label{eq:list_contact_list_2016.doc} S:\label{eq:list_contact_list_2016.doc} S:\label{eq:list_2016.doc} S:\label{eq$

CONNECTICUL HOLEXAGO	STATE OF CONNECTICUT Department of Transportation Division of Materials Testing 280 West Street Rocky Hill, CT 06067			NOTABLE OBSERVATION MAT-107 Rev. 12/16
Project Number		District:		Date:
Project Descript	ion:		Prime Contractor:	
Producer/Suppli	er:		P/S Location:	

QA Firm:

QA Inspector:

THE FOLLOWING OBSERVATION(S) AND/OR DISCREPANCY(IES) WAS/WERE NOTED:

Photos Attach	ed:	YES			lf ves num	ber of photos:			
Verbally provid	ded to:	. 20		of	n y oo, num	ser er prietee.	on		
			Name		Com	pany/Project		Date	
Distribution:	Project E	ngineer (District)		Inspector:	Drint			
	Project N Supervis	lanager (District)			Pfillt			
	Principal	Enginee	(DMT)			Signature			

If you have any questions or require further information, please contact the Division of Materials Testing as noted below: Email: <u>DOT.MatTesting@ct.gov</u> • Tel: (860) 258 – 0321 • Fax: (860) 258 – 0399

CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING DAILY WORK REPORT MAT-108

Rev. 12/16

DATE	INSPECTOR

PLANT / PROJECT LOCATION	PROJECT #	MATERIAL	MATERIAL QUANTITY

COMMENTS / DEFICIENCIES:

TRAVEL INFORMATION						
Enter Start and End times for time from and to work station or home.						
Start:	End:					
Enter Start and End times for actual time at the plants or projects.						
Start:	End:					

CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING HMA INSPECTOR'S REPORT MAT-108 HMA

REV. 12/16

Р	LANT #:				_		DATE:					
PRODUCER	NAME:				STATE INSPECTOR:							
LOC	CATION:				PL	ANT TE	CHNICIAN:					
Project #	Route	Town	Material Code	Material Description	RAP	WMA	Contract	Mix Status On Departure	State Test	Load #	IA	Load #
COMMEN	TS / DE	FICIENCIES	:									
	SHTO 1	ESTS WITH	ESSED		\checkmark	ADD	DITIONAL	INFORMATIO	N			
 T 168 - Sampling Bituminous Mixtures R 47 - Sample Reduction T 312 - Preparation of Gyratory Sample T 308 - Asphalt Content - Ignition Sample T 209 - Theoretical Maximum Gravity (Gmm) T 30 - Sieve Analysis T 166 - Bulk Specific Gravity (Gmb) T 255 - Moisture Content 						Verify p Verify p Verify th Inspect Testing Check t Inspect Technic	lant settings a roper PG Bin- ne use of anti- aggregate an equipment is he temperatu haul units for ian performe	are in accordance w der in accordance w strip if required by d RAP stockpiles. functioning propert re of the mix. proper canvas cov d Quality Control te	vith JMF. vith JMF JMF. ly. ers and r sting (ag	& Contra elease a gregates	ct. gents. , HMA	, etc.).
Enter	Start &	End times from	m and to v	work station o	o <mark>r ho</mark> m	ie.		Tota	al Shift	Hours		
Start:			End:					Regular	r Hours:			
E	Enter St	art & End time	es for actu	al time at Pla	nt.			Overtime	Hours:			
Start:			End:					Vacation / Si	ick / PL:			

STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING PORTLAND CEMENT CONCRETE (PCC) INSPECTOR'S DAILY WORK REPORT MAT-108 PCC

Rev. 12-16

PLANT INFORMATION			
DATE:			
PLANT NAME:			
LOCATION:			
PLANT MANAGER & PHONE NUMBER:			
INSPECTOR'S NAME:			
PROJECT #:			

ITEM BEING INSPECTED					
ITEM DESCRIPTION:					
FORM INSPECTED BY:					
DID FORM MEET REQUIREMENTS?	Yes	No			
NON CONFORMANCE:					
REMARKS:					

CONCRETE POUR				
TIME:				
TEMP. OF CONCRETE:				
TEMP. OF BUILDING:				
AIR:				
SLUMP:				
DID CONCRETE POUR MEET REQUIREMENTS?	Yes	No		
NON CONFORMANCE:				
REMARKS:				

WITNESS CYLINDER BREAKS				
BREAKS:				
DID BREAKS MEET REQUIREMENTS?	Yes	No		
NON CONFORMANCE:				
REMARKS:				

END OF DAY REMARKS

TRAVEL INFORMATION				
Enter Start and End times for time from and to work station or home.				
Start:	End:	_		
Enter Start and End times for actual time at the plants or projects.				
Start:	End:	—		

Core Sample Documentation Mat - 109 Rev 4/14

STATE OF CONNECTICUT **DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING**

Security ID Tag:

SEAL NO. 1: _____

SEAL NO. 2: _____

Project No.:	Route:
Town:	District No.:
Paving Contractor:	HMA Plant:
HMA Mix Size: Level:	Lift Thickness:
Inspector:	Project Phone Number:

Core Sample Label	Date Paved	Date	Base Material			Offset	
Lot (M or J)# - # FORM 816 Section 4.06.03	(If paving at Night, date before midnight applies)	Cored			Bridge Number (if applies)	Station Number	(ft)
Do any of the Core Sample(s) above complete a lot(s)? Yes No							

If "Yes", list the Lot(s):

Inspector Signature

Contractor Rep. Signature

If you have any questions or require further information,

280 West Street, Rocky Hill, CT 06067 Tel: (860) 258 - 0350 or Tel: (860) 258 - 0340 A12

OR THAT	
OF THE	

State of Connecticut Department of Transportation Division of Materials Testing 280 West Street Rocky Hill, Ct 06067 MAT-110

WELDER AND WELDING OPERATOR QUALIFICATION RECORD

PHOTO

MAT-110						
Welder's Name:		Identification	No.:			
Address:	Idress: City:					
State:	Zip Code:	Telephone No.:				
Email Address:	Test Site:					
	WELDING PERFORMANCE QU	ALIFICATION TEST RE	CORD			
Welding process:	🗌 Manua	al 🗌 Semi-au	utomatic	Machine		
Position:	(Flat, horizontal, o	overhead or vertical – if v	ertical, state	e whether upward or downward)		
In conformance with WPS No.						
Material Specification:	Thickne	ess range this qualifies:				
	FILLER M	IFTAI				
Specification No.:	Class	ification:				
Describe filler metal (if not cov	ered by AWS specification):					
Is backing used?	· · · · · · · · · · · · · · · · · · ·					
Filler metal diameter and trade	name:	Flux for SAW or gas	for GMAW	or FCAW-G:		
	VISUAL INSPECTION	(6.26.1 OR 9.21.1)				
Appearance:	Undercut:	Piping	g porosity:			
	GUIDED BEND TE	EST RESULTS				
Туре	Result	Туре		Result		
Test Conducted By:		Laboratory Test No.:				
Per:		Test Date:				
	FILLET TEST	RESULTS				
Appearance:		Fillet Size:				
Fracture Test Root Penetration	n:	Macroetch:				
	(Describe the location, nature, and size or	r any crack or tearing of the s	specimen.)			
Test Conducted By:		Laboratory Test No.:				
Per:		Test Date:				
	RADIOGRAPHIC T	EST RESULTS				
Film Identification Results	Remarks	Film R	Results	Remarks		
		Identification				
Test Witnessed Bv:		Test No.				
Per:	Per: Test Date:					
We the undersigned certify th	at the statements in this record are correct a	and that the welds were pre	epared and te	ested in conformance with the		
Authorized Rv						
		Date:				
	If you have any questions or require f	urther information place	se contact			
Thomas Lvnch at Tel: (860) 258-0329 or Ionathan Boardman at Tel: (860) 258-0327						

Email: <u>DOT.WelderCertification@ct.gov</u> or Fax: (860),258-0399 / 280 West Street, Rocky Hill, CT 06067



Listed below are the requirements necessary to obtain or renew a Welder Certification Card from the Connecticut Department of Transportation (ConnDOT), which is needed in order to weld on ConnDOT projects.

- 1. New applicants must receive a Welder Qualification Test from an approved Contractor listed on page 2. ConnDOT also reserves the right to require a Welder Qualification Test at any time.
- 2. The Welder Certification card must be carried on the welder's person whenever welding is performed on ConnDOT Projects and is prohibited to be used as certification for other business.
- 3. The Welder Certification card shall remain the property of ConnDOT and as such reserves the right to revoke any Welder Certification at any time.
- The Welder Certification must be updated by emailing <u>DOT.WelderCertification@ct.gov</u> or calling 860-258-0374 every six months after the date of issue or six months from the date of the last valid update. A Welder must be performing welding on ConnDOT projects to be updated.
- 5. Only authorized representatives of ConnDOT shall update the Welder Certification. Unauthorized updating of the Welder Certification shall be cause for revocation. To schedule updates with ConnDOT, please contact Mr. Thomas Lynch or Mr. Jonathan Boardman as noted below.

For a Welder Certification card to be issued or re-issued, the following conditions must be met:

- Adherence to the requirements stated above.
- Completion of the contact information form below along with an attached current photo and forwarded to ConnDOT in <u>one</u> of the following ways:
 - a. Mail form and hard copy photo to: Connecticut Department of Transportation, Central Laboratory, 280 West Street, Rocky Hill, CT 06067 Attention: Thomas Lynch
 - b. Email form and digital photo to: DOT.WelderCertification@ct.gov

Contact Information:

		FILLABLE FORM (Blue	Area)		
Full Name:					
	Last		First		М.І.
Address:					
	Street Address				Apartment/Unit #
	City			State	ZIP Code
Mailing Address:					
(IF DIFFERENT)	Street Address				Apartment/Unit #
	City			State	ZIP Code
Home Phone:		Alternate Phone:		Cell Phone:	
Email:			PLEASE	PROVIDE AN EMA	AIL ADDRESS

Any questions can be directed to:

Thomas Lynch Connecticut Department of Transportation Central Laboratory 280 West Street, Rocky Hill, CT 06067 Email: <u>Thomas.Lynch@ct.gov</u> Phone: (860) 258-0329; Fax: (860) 258-0399 Jonathan Boardman Connecticut Department of Transportation Central Laboratory 280 West Street, Rocky Hill, CT 06067 Email: <u>Jonathan.Boardman@ct.gov</u> Phone: (860) 258-0327; Fax: (860) 258-0399
STATE OF CONNECTICUT Department of Transportation

Division of Materials Testing 280 West Street Rocky Hill CT 06067 860-258-0374

Welder Qualification Testing Agencies

Agency	CONTACT PERSON	TELEPHONE NUMBER
Asnutuck Community College (AC) 170 Elm Street Enfield, CT 06782	Steven Goodrow	(860) 253-3189
Materials Testing Inc.(AA)55 Laura StreetNew Haven, CT 06512	Bill Soucy	(203) 468-5216
Naugatuck Valley Community College(NV)750 Chase ParkwayWaterbury, CT 06708	Sharon Lutkus	(203) 596-8743
National Welding Lab & Inspection, LLC (NW) 3 Stacey Lane Enfield, CT 06082	Rick Munroe	(860) 394.7461
Weldtech(WT)P.O Box 168Peru, Vermont 05152	John Acosta	(860) 303-8695
Iron Worker(IW)Local - 1549 Locust StreetHartford, CT 06114	Joseph M. McGloin	(860) 246-7353

Any question about this list may be directed to:

Mr. Thomas Lynch Connecticut Department of Transportation Division of Materials Testing Materials Tech III Phone: 860-258-0329 Email: <u>Thomas.Lynch@ct.gov</u>

NNECTIO	State of Connecticut
CON CON	Department of Transportation
	Division of Materials Testing
EL E	280 West Street
TA TRANSE	Rocky Hill, Ct 06067
or the	MAT-112

Date Call Received:				Certi	fication Nu	mber:
Full Name:						
Address:	First		Last			Apartment/Unit #
	City				Stato	Zin Code
Cell Phone:	Chy	Home Phone:			Jale	
=mail: Current / Past Projec	*-					
Sullent / Fast Flojed	<u> </u>					
				Contact Name:		
				Phone Number:		
 Cell phone Email addr 	ress if they have one.					
Departm Division 280 Wer Rocky H MAT-11	of Connecticut ent of Transportation of Materials Testing st Street lill, Ct 06067 2		V	VELDER'S CAL	L IN RE	PORT
Date Call Received:				Certi	fication Nu	mber:
Full Name:						
Address:	First		Last			
	Street Address					Apartment/Unit #
	City			5	State	Zip Code
Cell Phone:		Home Phone:				
Email:						
Current / Past Projec	t:					
				Contact Name:		
				Phone Number:		
 Make sure you 1. Certificatio 2. Address if 3. Cell phone 	u ask for the following n Number. it has changed. number.	information:		L		

4. Email address if they have one.

KIND OF MATERIAL	State of Connecticut	Date	Project #			
SOURCE OF SUPPLY	Bureau of Engineering & Construction	Sample ID #				
LOCATION OF SOURCE OF SUPPLY	MAT-200					
SAMPLE TAKEN FROM						
	Nominal Size of Pipe (inches/mm):					
LOCATION OF						
	Thickness of Steel (inches/mm):					
SAMPLED BY	Type of Seam:					
DATE SAMPLED	Thickness of Asphalt (inches/mm):					
USING AGENCY	Paved Invert (inches/mm):					
QUANTITY PRESENTED	Type of Coupling Bands (inches/mm):					
PURPOSE FOR WHICH MATERIAL WILL	Thickness of Steel - Bands (inches/mr	n):				
BEUSED	Width of Coupling Bands (inches/mm)	:				
	Corrugation or Helical Rib Size (inche	s/mm):				
SAMPLE RECEIVED	NOTE: Aluminized Steel Dine does not		half agating or payed invert			
	NOTE: Alumnized Steel Fipe does not	require aspi	lait coating of paved invert			
	Person P	erforming Inspec	tion (Initials):			
DATE MATERIAL WILL BE USED	Recommended For: Remarks:					
WHERE MATERIAL WILL BE USED						
	Division of Materials Testing					

PERFORATED METAL PIPE (Steel)

KIND OF MATERIAL			Date	Project #
	State of Connecticu	ut		
SOURCE OF SUPPLY	Department of Transpor	tation	Sample ID #	
	Inspection Report	of		
LOCATION OF SOURCE OF SUPPLY	Perforated Metal Pi	De la		
	MAT-202			
SAMPLE TAKEN FROM		<i>,</i> ,		
	Nominal Size of Pipe (inche	s/mm):		
LOCATION OF	Thickness of Steel (inches/	mm):		
SAMPLED BY	Type of Seam:			
	Number of Rows of Perfora	tions:		
DATE SAMPLED	Diameter of Perforations (in	iches/mm):		
	Height of Uppermost Rows	of		
	Perforations Above bottom	of		
QUANTITY PRESENTED	Invert (inches/mm):			
PURPOSE FOR WHICH MATERIAL WILL	Chord Length of Unperforat	ted		
BE USED	Segment (inches/mm):			
	Type of Coupling Bands:			
SAMPLE RECEIVED	Thickness of Steel Bands (inches/mm):		
	Width of Coupling Bands (in	nches/mm):		
DATE MATERIAL WILL BE USED	Corrugation or Helical Rib S	Size (inches/m	nm):	
		Person Per	forming Inspection (initia	ale) ·
		r erson r er	forming inspection (mite	aisj
WHERE MATERIAL WILL BE USED				
	Decommonded For Dom	arka		
	Recommended For Rema	ains		
	Division of Materials	Testing		

STRUCTURAL PLATE AND PIPE ARCHES

KIND OF MATERIAL	State of Conr	necticut	Date	Project #			
SOURCE OF SUPPLY	Department of Tra	ansportation	Sample ID #				
LOCATION OF SOURCE OF SUPPLY	Inspection Report Plate and Pipe MAT-20	of Structural Arches					
SAMPLE TAKEN FROM	Stool 🗌	Aluminizod St					
LOCATION OF	Nominal Size of Struc	tural Plate (inches	s/mm):				
SAMPLED BY	Thickness of Plates (i	nches/mm):					
DATE SAMPLED	Diameter of Perforation	ons (inches/mm):					
USING AGENCY	Size of Corrugations	or Helical Ribs (in	ches/mm):				
QUANTITY PRESENTED	Location of Longitudi	nal Bolt Holes:					
	Location of Circumfe	rential Bolt Holes:					
PURPOSE FOR WHICH MATERIAL WILL BE USED	Center of Bolt Hole to	Edge of Plate:					
	Type of Coating:						
SAMPLE RECEIVED							
		Perso	on Performing Inspectio	on (initials) :			
DATE MATERIAL WILL BE USED	Recommended For	Remarks					
WHERE MATERIAL WILL BE USED							
	Division of Mat	terials Testing					

CULVERT END

KIND OF MATERIAL	State of Connecticut	Date	Project #			
SOURCE OF SUPPLY	Department of Transportation Bureau of Engineering & Construction	Sample ID #				
LOCATION OF SOURCE OF SUPPLY	Inspection Report of Culvert End MAT-204					
SAMPLE TAKEN FROM	Steel 🔲 Aluminized S	teel 🗌 Aluminur	n 🗌			
LOCATION OF	Nominal Size of Pipe (inches/mm):					
SAMPLED BY	Thickness of Sheet (inches/mm):					
	Thickness of Asphalt (inches/mm):					
DATE SAMPLED	Dimension "B" (inches/mm):					
USING AGENCY	Dimension "H" (inches/mm):					
	Dimension "L" (inches/mm):					
QUANTITIFRESENTED	Dimension "W" (inches/mm):					
PURPOSE FOR WHICH MATERIAL WILL BE USED	Attachment System:					
	Edge Reinforcement:					
SAMPLE RECEIVED	Type of Seam:					
	NOTE: Aluminized Steel Pipe does not r	equire asphalt coatin	g or paved invert.			
DATE MATERIAL WILL BE USED	Recommended For: Remarks:					
WHERE MATERIAL WILL BE USED						
	Division of Materials Testing					

T27/C136

Non-cumulative RETAINED MASSES

			2 1/2″					
			63 mm					
5″			2″					
125 mm			50 mm					
3 1/2″			1 1/2″					
90 mm			37.5 mm					
1 1/2″			1″					
37.5 mm			25 mm					
3/4″			3/4″					
19 mm			19 mm					
1/4″			1/4″					
6.3 mm			6.3 mm					
PAN			PAN					

1//		4/4"					
1/4		1/4					
6.3 mm		6.3 mm					
No. 10		No. 10					
2.0 mm		2.0 mm					
No. 40		No. 40					
425 μm		425 μm					
No. 100		No. 100					
150 μm		150 μm					
No. 200		No. 200					
75 μm		75 μm					
PAN		PAN					

KIND OF MATERIAL	DEP	STATE				DATE	PROJECT#			
SOURCE OF SUPPLY	BUREAU REPOR	OF ENG	INEERING &		RUCTION RAVELS	SAMPLE ID #				
LOCATION OF SOURCE OF SUPPLY	SIEVES	% PASS	SIEVES	% PASS	% WE	AR & LAB NO.	MAXIMUM DENSITY			
SAMPLE TAKEN FROM	5″ 125 mm		5″ 125 mm		-					
LOCATION OF	3 1/2″ 90 mm		3 1/2″ 90 mm		SOUNDNESS LOSS & LAB NO. OPTIMUM MOISTUR					
SAMPLED BY	2 1/2" 63 mm		2 1/2″ 63 mm							
DATE SAMPLED	2″ 50 mm		2″ 50 mm		% LIQUID ASPHALT					
	1 1/2″ 37.5 mm		1 1/2" 37.5 mm		PLASTIC	TY & LAB NO. (PL	ASTIC OR NON-PLASTIC)			
QUANTITY REPRESENTED	1″ 25 mm		1″ 25 mm							
PURPOSE FOR WHICH MATERIAL WILL BE USED	3/4″ 19 mm		3/4″ 19 mm		RECOMM	IENDED FOR:				
	1/4″ 6.3 mm		1/4″ 6.3 mm							
DATE MATERIAL WILL BE USED	No. 10 2.0 mm		No. 10 2.0 mm		REMARK	'S:				
WHERE MATERIAL WILL BE USED	No. 40 425 μm		No.40 425 μm							
DATE SAMPLED	No. 100 150 μm		No. 100 150 μm							
	No. 200 75 μm		No. 200 75 μm		Person Perf	orming Test (Initia	ls):			
	Div	ision of	Materials [•]	Testing						

	<u>T11</u>	/C11	7						-	T11/C11	7		
ORIGINAL MASS				gm				ORI	GINAL MASS			gm	
LESS WASHED MA	ss			gm				LES	S WASHED MAS	s		gm	
MASS OF SILT				gm				MAS	S OF SILT			gm	
SILT				%				SIL	г			%	
T27/C136						T27/0	136						
	RETAI	NED	IND.RETAINED	PASSING	RETAINED		RETAINE	ED	IND.RETAINED	PAS	SING	RETAINED	
	MAS	S	%	%	%		MASS		%		%	%	
5/8″						5/8	3″						
16.0 mm						16.0 m	m						
1/2″						1/:	2″						
12.5 mm						12.5 m	m						
3/8″						3/8	3″						
9.5 mm						9.5 m	m						
No. 4						No. 4							
4.75 mm					-	4./5 m	m						
NO. 8						NO. 8	-						
2.30 mm						2.30 m							
1 18 mm						1 18 m	m						
No. 30						No. 30							
600 um						600 um							
No. 50						No 50							
300 um						300 um							
No. 100						No. 100							
150 um						150 um							
PAN						PAN							
TOTAL MASS				F.M.		TOTAL MASS	5			F.M.			
KIND OF MATERI	AL				STATE OF C	ONNECTICI	JT	D	ATE		PROJEC	Γ#	
				DEP	ARTMENT OF	TRANSPOR	TATION						
SOURCE OF SUP	PLY			BUREAU	OF ENGINEE	RING & CON DE SAND	STRUCTION MAT-206	SA	MPLE ID #				
LOCATION OF SC	OURCE OF	SUPPL	Y				с с		GARDNER COL	OR STAND	ARD) T21	/C40	
				PASSING SIEVE	PERCENT	PERCENT	U	NDE	R #11	(OVER #	±11 🔲	
SAMPLE TAKEN	FROM			1/2″	,								
				12.5 mm	1			CON	IPRESSIVE S	STRENGT	H (MP	a)	
LOCATION OF				3/8* 9.5 mm						7 day	/	28 day	
SAMPLED BY				No. 4			SAMPLE SAND						
DATE SAMPLED				4./3 mm			OTTAWA SAND						
DATE OAM EED				No. 8 2.36 mm			of that is daily						
USING AGENCY				No. 16			PERCENT OF O	TTAW	Α				
QUANTITY REPR	ESENTED			No 00			RECOMMENDE) FOR					
				ю. зо 600 µm									
PURPOSE FOR W	HICH MAT	FERIAL	WILL BE USED	No 50			1						
				300 μm									
DATE MATERIAL	WILL BE	USED		No. 100			REMARKS						
				150 μm									
WHERE MATERIA	AL WILL B	EUSED											
				SILT %									
					Division of	Matorialo To	Pe Pe	rson	Performing Te	est (initials):		
1						materials 16	oung						

	Non-cum	nulative RE	AINED	MASSE	S				
NO. 3		NO	6				N	0.8	
2 1/2"									
63 mm		"				1/0//			
50 mm	25 mm	1				12.5 mm			
1 1/2″	3/4	7				3/8″			
37.5 mm	19 mn	۱				9.5 mm			
1 1/4"	1/2	~				No. 4			
31.5 mm	12.5 mm 3/8	1 ″				4.75 mm			
25 mm	9.5 mm	1				2.36 mm			
1/2″	No. 4	1				No. 16			
12.5 mm	4.75 mm	1				1.18 mm			
PAN	PAN	•				PAN			
NO 4			67		11				
NO. 4		<u>NO.</u>	<u>67</u>		— n				
50 mm									
1 1/2″	1″								
37.5 mm	25 mm								
1 1/4"	3/4″								
31.5 mm	19 mm 1/2"		-	-					
25 mm	12.5 mm								
3/4″	3/8″								
19 mm	9.5 mm								
1/2″ 12.5 mm	NO. 4 4 75 mm								
3/8″	4.75 min								
9.5 mm	2.36 mm								
PAN	PAN					PAN			
						DATE		PPO JECT #	
	DEPAR.		207 RANSPO	RTATIO	N	DAIL			
SOURCE OF SUPPLY				ESTING		SAMPLE ID	#		
	DIVISI	REPORT OF TEST OF COARSE AGGREGATE							
	REPORT O	F TEST OF C	OARSE	AGGRE	GATE				
LOCATION OF SOURCE OF SUPPLY	REPORT O	F TEST OF C			GATE	PERCENTA	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY	REPORT O SQUARE MESH SIEVES	F TEST OF C	OARSE		GATE	PERCENTA	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM	REPORT O SQUARE MESH SIEVES 2 1/2"				GATE	PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm	F TEST OF C	OARSE A		GATE	PERCENTA	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2"	F TEST OF C	OARSE A		GATE	PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm	F TEST OF C			GATE	PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2"	F TEST OF C			GATE	PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm	F TEST OF C	ECARSE /			PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4"		ECARSE /			PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm			AGGRE		PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm					PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 1" 25 mm			AGGRE		RECOMMEN	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 1" 25 mm 3/4"					PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 1" 25 mm 3/4" 19 mm					PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 1" 25 mm 1'' 37.5 mm					PERCENTA SOUNDNES RECOMMEN	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 3/4" 19 mm 1/2" 2.5 mm					REMARKS	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 3/4" 19 mm 1/2" 3/8" 9.5 mm					REMARKS	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED DATE MATERIAL WILL BE USED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 3/4" 19 mm 1/2.5 mm 3/8" 9.5 mm No. 4					RECOMMEN	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED DATE MATERIAL WILL BE USED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 3/4" 19 mm 1/2.5 mm 3/8" 9.5 mm No. 4 4.75 mm					PERCENTA SOUNDNES	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED DATE MATERIAL WILL BE USED WHERE MATERIAL WILL BE USED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 25 mm 3/4" 19 mm 1/2" 3/8" 9.5 mm No. 4 4.75 mm No. 8 2 6 mm					REMARKS	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED DATE MATERIAL WILL BE USED WHERE MATERIAL WILL BE USED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 3/4" 19 mm 1/2" 3/8" 9.5 mm No. 4 4.75 mm No. 8 2.36 mm					REMARKS	GE OF WEAR		
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED DATE MATERIAL WILL BE USED WHERE MATERIAL WILL BE USED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 3/4" 19 mm 1/2" 3/8" 9.5 mm No. 4 4.75 mm No. 8 2.36 mm No. 16 1.18 mm					PERCENTA SOUNDNES RECOMMEN	GE OF WEAR	est (initials):	
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED DATE MATERIAL WILL BE USED WHERE MATERIAL WILL BE USED SAMPLE RECEIVED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 3/4" 19 mm 1/2".5.5 mm 3/4" 9 mm 3/4" 9 mm 3/8" 9.5 mm No. 4 4.75 mm No. 8 2.36 mm No. 16 1.18 mm No. 100					PERCENTA SOUNDNES RECOMMEN	GE OF WEAR	est (initials):	
LOCATION OF SOURCE OF SUPPLY SAMPLE TAKEN FROM LOCATION OF SAMPLED BY DATE SAMPLED USING AGENCY QUANTITY REPRESENTED PURPOSE FOR WHICH MATERIAL WILL BE USED DATE MATERIAL WILL BE USED WHERE MATERIAL WILL BE USED SAMPLE RECEIVED	REPORT O SQUARE MESH SIEVES 2 1/2" 63 mm 2" 50 mm 1 1/2" 37.5 mm 1 1/4" 31.5 mm 3/4" 19 mm 1/2.5 mm 3/4" 19 mm 1/2.5 mm 3/8" 9.5 mm No. 4 4.75 mm No. 8 2.36 mm No. 16 1.18 mm No. 100 150 µm					PERCENTA SOUNDNES RECOMMEN	GE OF WEAR	est (initials):	

Rock Salt

Sample Weight	1/2 inch	% passing
ml AgNO ₃ Sample	3/8 inch	% passing
Wt of Standard	# 4	% passing
ml AgNO ₃ Standard	# 8	% passing
% NaCl	# 30	% passing
Salt Wt	Pan	
Dry Salt Wt	Project #	Sample ID#
% moisture	Date	Analyst

Specification Reference

Standard Specification _

Supplemental Specification

Project Specification _____

Other

Person Accepting Technical Responsibility

Name: Title:

Specification: Reference File 139 - AASHTO M143, Type 1 (except sections 9.1.2 and 11.2) Methods: M143 Rapid, T27, T265	State of Cor Department of T Bureau of Engineerin Report of Test	nnecticut ransportation g & Construction of Rock Salt	Date Sample ID #	Project #				
Lab use only	. MAT-2	208						
Material #		<u>Spec</u> .		Results				
	% NaCl	95 % min						
Vendor #	Moisture	3% max						
Date Sampled	% Passing ½ inch	100						
Destination Code	% Passing 3/8 inch	95 – 100						
Material Quantity	% passing # 4	20 – 90						
Material Unit	% passing # 8	10 – 60						
	% passing # 30	0 – 15						
Date Received	Р	erson Performing	Test (initials): _					
C or M	Becommended For	Pomarka						
Dates	Recommended For							
Division of Materials Testing								

Calcium Chloride

Project #	Sample ID #
Date	Analyst
Sample Wt.	
N KmnO₄	
ml KmnO₄	
CaCl Factor	
% CaCl	

Specification Reference

Standard Specification _____

Supplemental Specification

Project Specification _____

Other ____

Person Accepting Technical Responsibility

Name: ______ Title:

Specification: AASHTO M144 via Form 815 Section (9.42.02) Methods: AASHTO T143, ASTM E449 Lab use only Material #	State of Co Department of T Bureau of Engineerin Report of Test of C MAT-	nnecticut Fransportation ng & Construction alcium Chloride 209	Date Sample ID #	Project #				
Vendor #								
Date Sampled	Grade	<u>% CaCl</u>						
Destination Code	Grade 1	min. 77%						
Material Quantity	Grade 3	min. 90%	% CaCl					
Material Unit		11111. 34 /0						
Date Received								
Batch #			Person Performing Test	(initials) :				
C or M	Recommended For	Remarks						
Dates								
Division of Materials Testing								

	Pass. (inches/mm)	Ret. (inches/mm)				
Class A:	1 ½ (37.5)	1 (25) -		+ 12 (1.7mm)		
	1 (25)	³ ⁄4 (19) -				
	³⁄₄ (19)	½ (12.5) -		+ 12 (1.7mm)		
	½ (12.5)	3/8 (9.5) -			I	fotal of +12 (1.7mm)
	T	Fotal Weight =		Total Wt		
			r	Minus +12 (1.7mm)		otal of –12 (1.7mm)
Class B:	³⁄₄ (19)	½ (12.5) -				
	1⁄2 (12.5)	3/8 (9.5) -				
	1	Fotal Weight =				
			Total	of -12 (1.7)mm) = Total Weight	=	=%
A: 1250 ea B: 1250 ea	ch required size ch required size	– 12 spheres – 11 spheres			Dust = _	
KIND OF MAT	FERIAL		State of C	connecticut	Date	IN-HOUSE
KIND OF MAT	TERIAL SUPPLY	De	State of C epartment of	connecticut Transportation	Date	IN-HOUSE TEST
KIND OF MAT SOURCE OF LOCATION O	TERIAL SUPPLY F SOURCE OF SUPP	De Bureau PLY Rej	State of C epartment of u of Enginee port of Test o & Soundnes	Connecticut Transportation ring & Construction of L. A. Abrasion ss MAT-211	Date Sample ID #	IN-HOUSE TEST
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK	TERIAL SUPPLY F SOURCE OF SUPP KEN FROM	Bureau PLY Rej	State of C epartment of u of Enginee port of Test & Soundnes Clas	Connecticut Transportation ring & Construction of L. A. Abrasion ss MAT-211 S Wear, %:	Date Sample ID #	IN-HOUSE TEST %
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK	TERIAL SUPPLY F SOURCE OF SUPP KEN FROM	De Bureat PLY Rej	State of C epartment of u of Enginee port of Test of & Soundnes Clas Soun	Connecticut Transportation ring & Construction of L. A. Abrasion SS MAT-211 S Wear, %: dness, % Loss (if applicab	Date Sample ID #	IN-HOUSE TEST
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK LOCATION O	TERIAL SUPPLY F SOURCE OF SUPP KEN FROM F	De Bureau PLY Rej	State of C epartment of u of Enginee port of Test of & Soundnes Clas Soun (It	Connecticut Transportation ring & Construction of L. A. Abrasion as MAT-211 S Wear, %: dness, % Loss (if applicab f Soundness reported, at	Date Sample ID # Ide):	IN-HOUSE TEST
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK LOCATION O SAMPLED BY	TERIAL SUPPLY F SOURCE OF SUPP CEN FROM F	De Bureau PLY	State of C epartment of u of Enginee port of Test of & Soundnes Clas Soun (It	Connecticut Transportation ring & Construction of L. A. Abrasion ss MAT-211 S Wear, %: dness, % Loss (if applicab f Soundness reported, at	Date Sample ID # Ide): ttach workshee	IN-HOUSE TEST
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK LOCATION O SAMPLED BY DATE SAMPL	TERIAL SUPPLY F SOURCE OF SUPP KEN FROM F (LED	De Bureau PLY	State of C epartment of u of Enginee port of Test of & Soundnes Clas Soun (It	Connecticut Transportation ring & Construction of L. A. Abrasion ss MAT-211 S Wear, %: dness, % Loss (if applicab f Soundness reported, at Material #	Date Sample ID # Ide): Itach workshee	IN-HOUSE TEST
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK LOCATION O SAMPLED BY DATE SAMPL USING AGEN	TERIAL SUPPLY F SOURCE OF SUPP CEN FROM F (LED CY	De Bureau Rej	State of C epartment of u of Enginee port of Test of & Soundnes Clas Soun (It	Connecticut Transportation ring & Construction of L. A. Abrasion ss MAT-211 S Wear, %: dness, % Loss (if applicab f Soundness reported, at Material #	Date Sample ID # Ide): ttach workshee	IN-HOUSE TEST
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK LOCATION O SAMPLED BY DATE SAMPL USING AGEN QUANTITY P	TERIAL SUPPLY F SOURCE OF SUPP CEN FROM F C LED CY RESENTED	De Bureau Rej	State of C epartment of u of Enginee port of Test of & Soundnes Clas Soun (It	Connecticut Transportation ring & Construction of L. A. Abrasion ss MAT-211 S Wear, %: dness, % Loss (if applicab f Soundness reported, at Material a Vendor #	Date Sample ID #	IN-HOUSE TEST
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK LOCATION O SAMPLED BY DATE SAMPL USING AGEN QUANTITY PI PURPOSE FO WILL BE USE	TERIAL SUPPLY F SOURCE OF SUPP CEN FROM F C CY RESENTED DR WHICH MATERIA	De Bureau Rej	State of C epartment of u of Enginee port of Test of & Soundnes Clas Soun (It	Connecticut Transportation ring & Construction of L. A. Abrasion ss MAT-211 S Wear, %: dness, % Loss (if applicab Soundness reported, at Material 3 Vendor #	Date Sample ID #	- % - % t.)
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK LOCATION O SAMPLED BY DATE SAMPL USING AGEN QUANTITY PI PURPOSE FO WILL BE USE	TERIAL SUPPLY F SOURCE OF SUPP CEN FROM F C CY RESENTED DR WHICH MATERIA		State of C epartment of u of Enginee port of Test of & Soundnes Clas Soun (It	Connecticut Transportation ring & Construction of L. A. Abrasion ss MAT-211 S Wear, %: dness, % Loss (if applicab Soundness reported, at Material # Vendor #	Date Sample ID #	- % - % t.)
KIND OF MAT SOURCE OF LOCATION O SAMPLE TAK LOCATION O SAMPLED BY DATE SAMPL USING AGEN QUANTITY PI PURPOSE FO WILL BE USE SAMPLE REC DATE MATER	TERIAL SUPPLY F SOURCE OF SUPP CEN FROM F C CY RESENTED DR WHICH MATERIA D CEIVED RIAL WILL BE USED	De Bureau Rej	State of C epartment of u of Enginee port of Test of & Soundnes Clas Soun (If	Connecticut Transportation ring & Construction of L. A. Abrasion ss MAT-211 S Wear, %: dness, % Loss (if applicab Soundness reported, at Material a Vendor #	Date Sample ID #	IN-HOUSE TEST

T96/C131 Los Angeles Abrasion Test

MOISTURE/DENSITY

State of Cor Department of T	nnecticut ransportation	Date	Project #				
Bureau of Engineering Report of Test of M MAT 2	g and Construction loisture/Density 213	Sample ID #					
AASHTO	T180 🗌 🛛 ASTM						
Maximum Dens (Kg/cu.m-Lbs/cu	ity J.ft)						
Optimum Moisture							
	Person Perforn	ning Test (initials) :					
Recommended For	Remarks						
Information							
Division of	Materials Testing						

Connecticut Department of Transportation Moisture Density Data Computation Sheet MAT-217 - 6" Mold

Date Tested				1	2	3	4
Project No.			Soil & Tare				
Sampled From			Tare				
Sampled By			Wet Weight				
Date Sampled				X	Х	Х	Х
Type of Material			Volume	13.33	13.33	13.33	13.33
Tested By			Wet Density				
			W.C.				
Sample ID No.			Dry Density				
% Stone Replaced	lbs.		Wet	500	500	500	500
Maximum Density =	pcf	kg/m ³	Dry				
Optimum Moisture =	%		W.C.				





Connecticut Department of Transportation Moisture Density Data Computation Sheet MAT-218 - 4" Mold

Date Tested				1	2	3	4
Project No.			Soil & Tare				
Sampled From			Tare				
Sampled By			Wet Weight				
Date Sampled				Х	Х	Х	Х
Type of Material			Volume	30	30	30	30
Tested By			Wet Density				
			W.C.				
Sample ID No.			Dry Density				
% Stone Replaced	lbs.		Wet	500	500	500	500
Maximum Density =	pcf	kg/m³	Dry				
Optimum Moisture =	%		W.C.				





SPECIFIC GRAVITY AND ABSORPTION OF COARSE AGGREGATE – T 85/C127 DIVISION OF MATERIALS TESTING - MAT-219

Source:	Location:			
Tested By:	Date:			
SAMPLE #		1	2	3
Mass of SSD Sample + Basket in Air				
Less Mass of Basket in Air				
Mass of SSD Sample	В			
Mass of Saturated Sample in Water + Basket in Water				
Less Mass of Basket in Water				
Mass of Saturated Sample in Water	C			
Mass of SSD Sample	B			
Less Mass of Saturated Sample in Water	С			
Loss in Mass (Volume of SSD Sample)	B - C			
Mass of Oven-Dry Sample + Pan				
Less Mass of Pan				
Mass of Oven-Dry Sample in Air	А			
Mass of SSD Sample in Air	В			
Less Mass of Oven-Dry Sample	А			
Mass of Water (Volume of Permeable				
Voids)	B - A			
	•			
Mass of Oven-Dry Sample	A			
Less Mass of Saturated Sample in Water	С			
Loss in Mass (Volume of Oven-Dry Sample)	A - C			
Pulk Specific Crewity	A			
	B - C			
Bulk Specific Gravity (SSD Basis)	B-C	-		
Annarent Specific Gravity	A	<u> </u>		
	A - C			
Absorption %	B - A A x 100	-		
		1		

Connecticut Department of Transportation - Division of Materials Testing Fine Aggregate Soundness Worksheet T104/C88 - MAT-220

Kind of Material:	Source:	Tech/Eng. Initials:
Date Sampled:	Location:	Date Completed:

	Original Gra	ding (Plus #4)		Sample Sizes For Original Grading Soak – Dry Schedule					
Sieve In(mm)	Retained Mass	Pass & Ret. %	% Pass	Note:			Date in Sol.	Time	Date in oven
			100						
1/2 (12.5)									
3/8 (9.5)				Grading	of Original	Sample			
#4 (4.75)				Pass	Ret. On				
#8 (2.36)				3/8 (9.5)	#4 (4.75)	%			
#16 (1.18)				#4 (4.75)	#8 (2.36)	%			
#30 (600 μ)				#8 (2.36)	#16 (1.18)	%			
#50 (300 μ)				#16 (1.18)	#30 (600 μ)	%			
Totals		100		#30 (600 μ)	#50 (300 μ)	%			

Total 100

(Required Sample Not Less Than 100g For Each Size)

Passing	Retained	Actual Mass	Mass Before Test Grams.	Mass After Test Grams.	Loss in Grams	Loss in %	Grading of Orig. Sample	Weighted Average %
3/8 (9.5)	#4 (4.75)							
#4 (4.75)	#8 (2.36)							
#8 (2.36)	#16 (1.18)							
#16 (1.18)	#30 (600 μ)							
#30 (600 μ)	#50 (300 μ)							

Connecticut Department of Transportation - Division of Materials Testing Coarse Aggregate Soundness Worksheet T104/C88 - MAT-221

Kind of Material:	Source:	Tech/Eng. Initials:
Date Sampled:	Location:	Date Completed:

	Original G	rading (Plus	#4)		Sample Sizes For Original Grading					ę	Soak ·	– Dry Schedule			
Sieve	Retained	Pass 8	× %												
ln(mm)	Mass	Ret. %	Pass		#			lbs. (kg)		Date	in Sol.		Date	Da	ate in oven
			100		#			lbs. (kg)							
2 ½ (63)					#			lbs. (kg)							
2 (50)					#			lbs. (kg)							
1 ½ (37.5)					Total			lbs. (kg)							
1 (25)					Grad	ling of Orig	gina	al Sample							
3/4 (19)					Pass	Ret. O	n								
1/2 (12.5)					2 ½ (63) 1 ½ (37.	.5)	%							
3/8 (9.5)					1 ½ (37.5)	3/4 (19)	%							
# 4 (4.75)					3/4 (19)) 3/8 (9.5	5)	%							
Totals		100			3/8 (9.5) #4(4.7	5)	%							
	I	100			0.0 (0.0	Total	-)	100							
Sieve Size	e Not Le Tha	ess (n	Consisting of	A N	ctual Iass	Mass Befor Test Grams	e S.	Mass After Test Grams.	L Ö	oss in Frams	Loss ir %	1	Grading o Orig. Samp	of ole	Weighted Average %
2 ½ to 1 ½	V ₂ E00		3000 2 (50)												
(63) (37.	.5) 5000	20	00 1½ (37.5)												
1 ½ to ¾	4 150	0 /	1000 1 (25)												
(37.3) (1	3)		500 % (19)												
³ / ₄ to 3/8	B 100	0 6	70 ½ (12.5)												
(19) (9.	5)	3	30 3/8 (9.5)												
3/8 to # 4	4 200		00 # A (A 75)												

300

(9.5) (4.75)

300 # 4 (4.75)

CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING ASSURANCE REPORT: FIELD TESTING PERSONNEL AND EQUIPMENT MAT-222

Project Number:

Date:

Location:

Inspected By:

] Consultant

State

Name of Inspector(s) Certification(s) (NETTCP, ACI, Etc.) and Certification #s

 Required Testing Equipment

 Air Meter
 Thermometer

 Slump Cone
 Small Tools (scoops, measures, etc.)

 Tamping Rod (24" ok for all)
 Sampling Receptacle

 Strike Off Bar (1/8 x 3/4 x 12)
 Cylinder Curing Box (operating to manufacturer specs)

 Mallet (1.25 ± .5 lbs)
 Strike Off Curing Box (operating to manufacturer specs)

Air Meter Calibration Date:

Remarks/Observations

Form Completed By

District lab

CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING ASSURANCE REPORT

PLASTIC PC CONCRETE - MAT-224

DATE:	PROJECT NUMBER:
CLASS OF CONCRETE:	PROJECT LOCATION:
TRUCK NUMBER:	CONCRETE PRODUCER:
CYLINDER NUMBERS:	PRODUCER LOCATION:
MIX TEMP. (T309/C1064):	NOTE: COMPLETED MAT 222 MUST BE ATTACHED TO THIS REPORT
0	

BATCH MASS PER CUBIC METER									
	CEMENT lb.	OTHER	SAND +% Moisture lb.	STONE	STONE	STONE	TOTAL MIXING WATER lb.	TOTAL MASS lb.	
ACTUAL									
MIX DESIGN									
TOLERANCE	± 1%	± 1%	± 2%	± 2%	± 2%	± 2%	\pm 1% (Central Mix)		

<u>AIR TEST (T</u>	152/C231) (side by si	de check of test e	SLUMP TEST (T119/C143)			
TIME TAKEN	PROJECT TEST RESULTS	TIME TAKEN	COMPARISON TEST RESULTS	TIME TAKEN	TOTAL WATER PER BATCH (gal.)	AMOUNT OF SLUMP
	% air		% air			
TOLERANCE -	results should not o	differ by more th	ian 1 %			

UNIT MASS (T121/C138)								
		-	=	<u>•</u>	=			
TIME TAKEN	MASS OF MEASURE & SAMPLE Ib.	MASS OF MEASURE Ib.	NET MASS OF CONCRETE Ib.	VOLUME OF MEASURE (ft ³)	MASS PER CUBIC METER Ib./ ft ³			

<u>YIELD (T121/C138)</u>								
		.	=	••	=	÷	=	
TIME TAKEN	TOTAL BATCH WEIGHT Ib.	UNIT WEIGHT lb./ ft ³	YIELD PER BATCH (ft ³ / batch)	BATCH SIZE (y ³)	YIELD PER CUBIC YARD (ft ³ / y ³)		RELATIVE YIELD	
						27		

Witnessed By	(Print Name)	Project Inspector	(Print Name)
Ciamatura		Cianoturo	
Signature		Signature	

CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING ASSURANCE REPORT

PLASTIC PC CONCRETE (METRIC) - MAT-225

DATE	PROJECT NUMBER:
CLASS OF CONCRETE	PROJECT LOCATION:
TRUCK NUMBER	CONCRETE PRODUCER:
CYLINDER NUMBERS	PRODUCER LOCATION:
MIX TEMP. (T309/C1064)	NOTE: COMPLETED MAT 222 MUST BE ATTACHED TO THIS REPORT
0	

BATCH MASS PER CUBIC METER									
	CEMENT kg	OTHER	SAND +% Moisture kg	STONE	STONE	STONE	TOTAL MIXING WATER kg	TOTAL MASS kg	
ACTUAL									
MIX DESIGN									
TOLERANCE	± 1%	± 1%	± 2%	± 2%	± 2%	± 2%	± 1% (Central Mix)		

AIR TEST (T152/C231) (side	by side check	SLUMP TEST (T119/C143)			
TIME TAKEN	PROJECT TEST RESULTS	TIME TAKEN	COMPARISON TEST RESULTS	TIME TAKEN	TOTAL WATER PER BATCH (L)	AMOUNT OF SLUMP
	% air		% air			
TOLERANCE -	- results should not	differ by more t	han 1 %			

UNIT MASS (T121/C138)									
		-	=	÷	=				
TIME TAKEN	MASS OF MEASURE & SAMPLE kg	MASS OF MEASURE kg	NET MASS OF CONCRETE kg	VOLUME OF MEASURE (m ³)	MASS PER CUBIC METER kg / m ³				

YIELD (T121/C138)					
			=	•	=
TIME TAKEN	TOTAL MASS OF BATCH kg	MASS PER CUBIC METER kg / m ³	YIELD PER BATCH (m ³ / batch)	BATCH SIZE (m ³)	RELATIVE YIELD

Witnessed By

(Print Name)

Project Inspector

(Print Name)

Signature

Signature

Glass Beads

	0.0		
Grams	% Passing	Moisture Resistance	
# 20		Imperfect Wt	
# 30		Round Wt	
# 40		% Perfect	
# 50		Refractive index	
# 80		Date	
# 100		Analyst	
Pan		Project #	
Totals		Sample ID #	

Specification Reference

Standard/Project Specification _____

Supplemental Specification

Other _____

Person Accepting Technical Responsibility

Name: _____

Title:

Specifications: AASHTO M 247 Type 1 (via Form 815 M.07.03), and Federal Specification TT-8-1325C (contract for glass beads) Methods: In accordance with above specifications.	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of Glass Beads MAT-228			Date Sample ID #	Proj	ect #	
Lab use only	<u>% Passing</u>	<u>Type</u>	<u>1A</u>	<u>Type</u>	<u>1B</u>	<u>Resi</u>	<u>ilts</u>
	# 20	100					
Vendor #	# 30	75 – 9	95	100			
Date Sampled	# 40			90 – 1	00		
	# 50 15 – 35		35	50 - 75	5		
Destination Code	# 80			0 - 5			
Material Quantity	# 100	0 – 5	5				
Material Unit	% Porfect		> 70%				
Date Received			- 1078				
Batch #	Moisture Resista	ince					
C or M	Refractive Index		> 1.50				
Dates	Person Pe			erson Pe	rforming Test (initials):	
	Recommended	For	Remarks				
Division of Materials Testing							

Visi Beads

	% Retained	Project #
# 10		Sample ID #
# 12		Date
# 14		Analyst
# 16		
# 18		
# 20		
pan		

Specification Reference

Standard Specification _____

Supplemental Specification

Project Specification _____

Other _____

Person Accepting Technical Responsibility

Name: _____

Title: _____

Specifications: Form 815 M.07.22, Specification for Large Beads (via contract for glass beads), and Reference File 199 – (beads for epoxy resin pavement markings). Methods: In accordance with above	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of Visi Beads MAT-229		Date Sample ID #	Project #	
specifications. Lab use only	<u>% Retained</u>	Specs.		<u>Results</u>	
Material #	#10	0			
Vendor #	# 12	0 – 5			
Date Sampled	# 14	5 – 20			
	# 16	40 – 80			
Destination Code	#18	10 – 40			
Material Quantity	# 20	0 – 5			
Material Unit	Pan	0 – 2			
Date Received	Persor		n Performing Test (initials	5) :	
C or M	Recommended For	Remark			
Dates					
Division of Materials Testing					

Water

Appearance	Color
рН	Water Factor
ml Silver Nitrate	Chlorides
Project #	Sample ID #
Date	Analyst

Specification Reference

Standard Specification _	
--------------------------	--

Supplemental Specification

Project Specification _____

Other _____

Person Accepting Technical Responsibility

Name: _____

Title: _____

			Date	Project #
Specification: Form 815 M.03.01-4 Methods: In accordance with	State of Conn	ecticut nsportation		
AASHTO T26	Bureau of Engineering	& Construction	Sample ID #	
Note: If tests indicate unfavorable	Report of Test	of Water		
If tests indicate unfavorable results, further testing may be required. (T107, T131, or T154 and T106, or other recommended tests in cooperation with Concrete/Steel Section)	Appearance Color pH (T26, range 4.5 – Chloride Ion Concent	u 8.5) tration (D512) Person Remarks	Performing Test (initials)	·
	Division of Ma	terials Testing		

White & Yellow Fast Dry, Solvent Based Pavement Markings

Color ^(Fed. 595 – 33538)	Dry times (ASTM D 711)	% Pigment (ASTM D 3720)
Contrast Ratio ^(Fed. Test 141-4121))	Direct Reflect. ^(Fed. Ref. 141-6121)	1 (100) =
Viscosity @ 77 ^(ASTM D 562)	Weight /Gal ^(ASTM D 1475)	2 (100) =

Specification Reference

Standard Specification _____

Supplemental Specification

Project Specification _____

Other ____

Person Accepting Technical Responsibility

Name: _____

Title: _____

Specification: M.07.21 (814A) for 3 minute dry paint Method: FTMS #141	State o Department Bureau of Engin	f Coni of Tra eering	necticut ansportation a & Construction	Date	Project #		
Material #	Report of Test of White & Yellow Fast Dry Solvent Based Pavement Markings MAT-235		Sample ID #				
vendor #		Wh	iite	Yellow			
Date Sampled	Viscosity	80 – 1	00 KU	80 – 100 KU			
Destination Code	Dry Time	- 3 ו	min.	3 min.			
Material Quantity	Direct Reflectance	8	5% +	50 % +			
Material Unit	Color			Visual			
	Contrast Ratio	0).96 +	0.96 +			
Date Received	Weight/Gal	1	1.8 +	11.8 +			
Batch #	% Pigment	5	5% +	55% +			
C or M				Person Performing Test (initials) :		
Dates	Recommended F	or	Remarks				
Division Chief – Division of Materials Testing							

White & Yellow Regular Dry Solvent Based Pavement Markings

Weight/Gal ^(ASTM D 1475)	Viscosity @ 77 ^(ASTM D 562)	% Pigment (ASTM D 3720)
Direct Reflect. (Fed. Ref. 141-6121)	Contrast Ratio ^(Fed.Test 141-4121)	1 (100) =
Dry times (ASTM D 711)	Color ^(Fed. 595 – 33538)	2 (100) =

Specification Reference

Standard Specification

Supplemental Specification

Project Specification

Other

Person Accepting Technical Responsibility

Name:

Title:					
Specification: M.07.20 (814A) for 15 minute dry paint Method: FTMS #141	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of White & Yellow Regular Dry Solvent Based Pavement Markings		Date	Project #	
Material #			Sample ID #		
Vendor #		Whi	te	Yellow	
Date Sampled	Viscosity	70 – 8	30 KU	70 – 80 KU	
Destination Code	Dry Time	- 15 m	nin. 5% +	15 min. 50 % +	
Material Quantity	Color	Visu	ual	Visual	
Material Unit	Contrast Ratio	0.	96 +	0.96 +	
Date Received	Weight/Gal	12	.8 +	11.4 +	
Batch #	% Pigment	50	J% +	50% +	
C or M	Recommended F	or	Remarks		initiais)
Dates					
	Division Chief	– Divi	sion of Materials 1	Testina	

Fast Dry White & Yellow Waterborne Paint

% Non Volatile ^(ASTM D 2697)	% Pigment ^(ASTM D 3723)	Color test ⁽⁵⁹⁵⁻³	3538 yellow)	Scrub Resist. ^(ASTM D 2486)
1	1 (100)=	Flash Point ^{(Rei}	f. 200G)	Dry times ^(ASTM D 711)
	、			•
(100) =		Flexibility ^{(Fed T}	est 141c-6223)	Viscosity @ 77 ^(ASTM D 562)
	2(100)=			
2		Dry Opacity ^{(Fe}	ed. Test 141c-4121)	
	Avg	Wt/Gal @ 77 ^{(A}	STM D 1475)	(X)(0.10) = lbs/gal
		cup – cup & sai	mple = X	
(100) =				
Specification Refer	ence			
Standard Specification				
Project Specification				
Other				
Person Accepting Technical Respo	onsibility			
Name:				
Title:				
Specification: M.07.21 (Note: for next maintenance contract review delete reference file 200 and refer	to Bureau of Engineering	cticut sportation	Date	Project #
M.07.21 as the spec)	Report of Fast Dry W	nite & Yellow	Sample ID #	E
Material #	MAT-239	raint		
Vendor #	Viscosity (80 – 90 KU)		Dry Time (-120 s	ec)
Date Sampled	Flexibility (NO Flaws) Weight/Gal. (12.5 +)		Color (visual) Lead (-0.06%)	
Destination Code	Dry Opacity (0.96 +)	F	Pigment (58-63)	
Motorial Quantity	Nonvolatile (76% +)		Scrub Resistanc	e (500+)
	Flash Point (145°F+)			
Material Unit				
Date Received		Person Perform	ning Test (initials) :	
Batch #	Recommended For R	emarks		
C or M				
Dates				
	Division of Ma	terials Testing		

Regular Dry White & Yellow Waterborne Paint

% Non Volatile ^(ASTM D 2697)		% Pigment ^{(AST}	M D 3723)	Color test ^(595-13538 yellow)
		70 Fightent		
1 2		_		
		1 (100)=	Flexibility ^(Fed Test 141c-6223)
		•(100)-	i loxionity
		_		
		2	(100)=	Flash Point ^(Ref. 207)
			.()	
(100) =	(100) =			
		Viscosity @ 77	, (ASTM D 562)	Dry times ^(ASTM D 711)
Wt/Gal @ 77 ^(ASTM D 1475) (X)((0.10) = Ibs/gal			
cup – cup & sample = X	, , ,	Dry Opacity ^{(Fe}	d.Test 141c-4121)	
Specification Deference				
Standard Specification				
Standard Specification				
Project Specification				
Other				
Person Accepting Technical Responsibility				
Name:				
Title:	Otata af Oas		Data	Drain at #
maintenance contract review delete	Department of T	ransportation	Date	Project #
reference file 207 and refer to M.07.20 as the spec)	Bureau of Eng	gineering &		
Method: FTMS #141	Constru	ction	Sample ID #	
Material #	Yellow Water	guiar Dry white &		
	MAT-2	240		
Vendor #	Viscosity (75 – 85 KU)		Drv Time (-15 m	nin)
Date Sampled	Elexibility (NO Elaws)		Color (visual)	,
Date Sampled	Weight/Gal (12.5.+)		Dry Time (15 m	
Destination Code				
Motorial Quantity	Nonvolatilo (70% +)		Diamont (50.60	
	Flash Point (145°E+)		Fightent (50-60	
Material Unit	Soruh Pasiatanaa (500+		Freeze/Thaw (
Data Danaimat	Scrub Resistance (5001)	/	Treeze/Thaw (-	
Date Received				
Batch #		Pers	son Performing	Test (initials):
C or M				
	Recommended	Remarks		
Dates				
	Division of	Materials Testing		

State of Connecticut Department of Transportation Division of Materials Testing MAT-241 Independent Assurance Program Evaluation Report Concrete Aggregates – Fine Aggregates

Purpose: This form is for evaluation of assurance testing of concrete aggregates. In accordance with the minimum requirements for testing, concrete aggregates are sampled and tested for acceptance purposes randomly on a biweekly basis, and assurance testing of these processes is required each ten tests. This assurance testing evaluates in-house (not directly related to the projects) sample reducing and gradation analysis of concrete aggregates tested at various satellite locations utilizing various equipment and personnel. See MAT 245 for assurance testing criteria.

Assurance Testing Period (Dates): From: To:						
Number of assurance tests	Number of assurance tests	Percentage of assurance tests not meeting	Was corrective action taken and noted for tests			
ponomod.	criteria.	assurance criteria.	not meeting criteria?			
	Distric	t II Lab				
District III Lab						
	District	IV Lab				
Totals for Concrete Aggregate Assurance Testing in the Period						

NOTES:

State of Connecticut Department of Transportation Division of Materials Testing MAT-242 Independent Assurance Program Evaluation Report Concrete Aggregates – Coarse Aggregates

Purpose: This form is for evaluation of assurance testing of concrete aggregates. In accordance with the minimum requirements for testing, concrete aggregates are sampled and tested for acceptance purposes randomly on a biweekly basis, and assurance testing of these processes is required each ten tests. This assurance testing evaluates in-house (not directly related to the projects) sample reducing and gradation analysis of concrete aggregates tested at various satellite locations utilizing various equipment and personnel. See MAT 245 for assurance testing criteria.

Assurance Testing Period (Dates): From: To:						
Number of assurance tests performed.	Number of assurance tests not meeting assurance	Percentage of assurance tests not meeting	Was corrective action taken and noted for tests			
·	criteria.	assurance criteria.	not meeting criteria?			
	Distric	t II Lab				
	District III Lab					
	District	IV Lab				
Totals for Concrete Aggregate Assurance Testing in the Period						

NOTES:

State of Connecticut Department of Transportation Division of Materials Testing MAT-243 Independent Assurance Program Evaluation Report Subbase and Processed Aggregate Base

Purpose: This form is for evaluation of assurance testing of Subbase and Processed Aggregate Base. In accordance with the minimum requirements for testing, roadbase aggregates are sampled and tested for acceptance and assurance processes. To meet project related minimum testing requirements, project personnel notify the District Laboratories for required acceptance and assurance testing of these materials. The process starts at the project site, where laboratory personnel witness and critique the sampling procedure at the site. Laboratory acceptance testing is then performed and split samples are sent to the Central Laboratory for in-house (not directly related to the projects) assurance testing, which evaluates sample reducing and gradation analysis of the materials tested at various satellite locations utilizing various equipment and personnel. See MAT 245 for assurance testing criteria.

Assurance Testing Period (Dates): From: To:						
Number of assurance tests performed.	Number of assurance tests not meeting assurance criteria.	Percentage of assurance tests not meeting assurance criteria.	Was corrective action taken and noted for tests not meeting criteria?			
	District II Lab					
District III Lab						
	District	IV Lab				
Totals for Subbase & Processed Aggregate Base Assurance						
Testing in the Period						

NOTES: _____

State of Connecticut Department of Transportation Division of Materials Testing MAT-244 Independent Assurance Program Evaluation Report Plastic PC Concrete

Purpose: This form is for evaluation of assurance testing of plastic PC concrete. In accordance with the minimum requirements for testing, plastic PC concrete is required to be sampled and tested by project personnel for required acceptance and assurance testing. After notifying project staff of the need for required assurance testing, laboratory personnel evaluate the sampling and testing procedure, verify that adequate and calibrated testing equipment is utilized and readily available, and verify use of qualified personnel for NHS projects. Side-by-side air content testing is performed to validate project test equipment. When requested, technical expertise is also provided to the project personnel during the subject assurance testing. Forms MAT 222 and MAT 224 (MAT 225 for metric projects) are required to be completed by laboratory personnel during the assurance testing, and if testing deficiencies are encountered, they are noted. NOTES: 1) This form does not evaluate the projects on an individual basis for conformance to minimum acceptance and assurance testing requirements as specified in the "Schedule of Minimum Requirements for Sampling Materials for Test." As stated above, this form is for evaluation of the assurance testing of plastic PC concrete. 2) Comparison concrete specimens are not required to be fabricated by laboratory personnel are not required to be fabricated by laboratory personnel requirements as provided in the "Schedule of Minimum Requirements for Sampling Materials for Test." As stated above, this form is for evaluation of the assurance testing of plastic PC concrete. 2) Comparison concrete specimens are not required to be fabricated by laboratory personnel are not required to be fabricated by laboratory personnel are not required to be fabricated by laboratory personnel are not required to be fabricated by laboratory personnel concrete specimens are not required to be fabricated by laboratory personnel concrete specimens are not required to be fabricated by laboratory personnel concrete

Assurance Testing Period (Dates): From: To:						
Number of assurance tests performed.	Number of assurance tests noting any testing deficiencies.	Percentage of assurance tests noting testing deficiencies.	Was the project notified via memorandum of any testing deficiencies?			
District I Lab						
District II Lab						
	District	III Lab				
	District	IV Lab				
Totals for Plastic PC Concrete Assurance Testing in the Period						

NOTES:

STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING AND CONSTRUCTION DIVISION OF MATERIALS TESTING MAT-245

AGGREGATE ASSURANCE SAMPLES – VARIATION LIMITS

If assurance samples tested at the Central Laboratory vary from the samples tested at the District Laboratories by more than the percent shown below, the cause of the variations shall be investigated. These limits were derived from historical experience, along with engineering expertise.

NO. 4 AGGREG	ATE	NO. 6 AGGREGATE NO. 67 AGGREGATE		NO. 8 AGGREGATE			
37.5 mm (1 1/2")	- 4.0	19.0 mm (3/4")	- 4.0	19.0 mm (3/4")	- 4.0	9.5 mm (3/8")	- 5.0
25.0 mm (1")	- 9.0	12.5 mm (1/2")	- 6.0	9.5 mm (3/8")	- 3.0	4.75 mm (#4)	- 5.0
19.0 mm (3/4")	- 6.0	9.5 mm (3/8")	- 3.0	4.75 mm (#4)	- 3.0	2.36 mm (#8)	- 3.0
9.5 mm (3/8")	- 3.0	4.75 mm (#4)	- 3.0	2.36 mm (#8)	- 3.0	1.18 mm (#16)	- 3.0

CONCRETE SAND		SUBBASE		PROCESSED AGGREGA	TE BASE
4.75 mm (#4)	- 3.0	37.5 mm (1 1/2")	- 6.0	19.mm (3/4")	- 6.0
2.36 mm (#8)	- 6.0	6.3 mm (1/4")	- 6.0	6.3 mm (1/4")	- 6.0
1.18 mm (#16)	- 10.0	2.0 mm (#10)	- 6.0	425 μm (#40)	- 5.0
600 μm (#30)	- 10.0	425 µm (#40)	- 5.0	150 μm (#100)	-4.0
300 µm (#50)	- 9.0	150 µm (#100)	- 4.0		
150 µm (#100)	- 4.0	75 μm (#200)	- 3.0		
F.M. – 0.40					
SILT – 1.5					

CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING (DMT) TRACKING REPORT: PAVEMENT MARKING MATERIALS

MAT-248	Rev. 11/16
Date:	
Company:	
Material:	

Batch/ Lot #	Quantity

Remarks/Observations:

DMT Tracking Number: DMT XXXXXXXX

Form Completed By:

Recommendation Made For This Material:

Choose an item.



	GALVANIZATION oz/ft ² (g/m ²)					
	BOLT NUT WASHE					
	Mils (µm)	Mils (µm)	Mils (µm)			
SUM						
AVE.						
AVE x 1.7						
(AVE x7.067)						







THK. =

PROJECT NUMBER:	MAT-300	DATE		MATE	RIAL CODE
SAMDI E NIIMBER	STATE OF CT D.O.T.	I AR #		- 3	504
SAMIFLE NOWIDER.	DIV. OF MATERIALS	LAD #		-	
	REPORT OF TEST:				
	ANCHOR BOLTS				
	(STRAIGHT)				
	ITEM	BOLT	SPEC.	NUT	WASHER
					1
ן רדיו	SIZE (Nom. Dia.)				
	GRADE				
KTION TIFICAT DVISION EPTING ONSIBII	AREA in ² (mm ²)				
CIPICA CIFICA L SPEC AL PRC N ACCI	HARDNESS				
FICAJ RD SPE AENTA C SPECI PERSO ENICAL	EST. T.S. psi (MPa)				
PECI PPLEN PPLEN HER	GALV. oz/ft ² (g/m ²)				
ST/ SUI PR(Begin Test End Test	Tested By	REMARKS		-
	Recommendations		_		
	1		- 1		

DIVISION CHIEF - MATERIALS TESTING



	GALVANIZATION oz/ft ² (g/m ²)							
	BOLT	NUT	WASHER					
	Mils (µm)	Mils (µm)	Mils (µm)					
SUM								
AVE.								
AVE x 1.7 (AVE x7.067)								



THK. =

THK. =

PROJECT NUMBER:	MAT-301 STATE OF CT D.O.T.	DATE		MATERIA	MATERIAL CODE			
SAMPLE NUMBER:	DIV. OF MAT. TESTIN REPORT OF TEST: ANCHOR BOLTS (WITH HOOK)	G LAB #		3	504			
FICATION REFERENCE RD SPECIFICATION AENTAL SPECIFICATION SPECIAL PROVISION PERSON ACCEPTING HNICAL RESPONSIBILITY	ITEM	BOLT	SPEC.	NUT	WASHER			
	SIZE (Nom. Dia.)							
	GRADE							
	AREA in ² (mm ²)							
	HARDNESS							
	EST. T.S. PSI (MPa)							
SPECI ANDA JPPLEN COJECT COJECT	GALV. Oz/ft ² (g/m ²)							
	RECOMMENDED	FOR	REMARKS					
NAMI								
c:\jwh\forms\Anchor Bolt with Hook combo.doc								
DIVISION CHIEF – MATERIALS TESTING								


	GALVANIZATION oz/ft ² (g/m ²)								
	BOLT	NUT	WASHER						
	Mils (µm)	Mils (µm)	Mils (µm)						
SUM									
AVE.									
AVE x 1.7 (AVE x7.067)									



THK. =

PROJECT NUMBER:	MAT-302DATEMATERIASTATE OF CT D O T				ERIAL CODE
SAMPLE NUMBER:	DIV. OF MATERIA TESTING REPORT OF TEST HEX BOLTS	LS LAB #			
	ITEM	BOLT	SPEC.	NUT	WASHER
ال ٢٠	SIZE (Nom. Dia.)				
EINCH II N N N N N N N N N N N N N N N N N N	GRADE				
ZEFEF ATION IFICA1 DVISIO DVISIO EPTINC	AREA (mm ²)				
IJON I CIFIC/ L SPEC L SPEC AL PR(N ACC)	HARDNESS				
FICAT RD SPF fENTA SPECI PERSOI	EST. T.S. (MPa)				
SPECI ANDA PPLEM HER ITECF	GALV. (g/m ²)				
ST SU	Begin Date End Date	Tested By	REMARKS		
NAME					
			·		
			DIVISI	ION CHIEF – MAT	FERIALS TESTING

MAT-303

PROJECT NUMBER:	MAT-303 STATE OF CONNECTICU	Т	PROCESSING DATE	MATERIAL CODE
SAMPLE NUMBER:	DEPARTMENT OF TRANSPORT DIVISION OF MATERIALS TES REPORT OF TEST: CHAIN LINK FENCE FABR	TATION STING LIC	LABORATORY NO.	- 3300
			Actual	Specification
	Height of Fabric, inches (mm	n)		As specified on plans or spec. prov.
	Gage of Wire		No. 9 gage	
PTING	Size of Mesh, inches (mm)			2-inch (50 mm) mesh
TION RI TION IFICATIO WISION NACCE L RESPC	Edge of Finish			Knuckled
ECIFICA ECIFICA AL SPEC JAL PRC PERSC CHNICA	Tensile Strength, psi (MPa)			See above
<u>SI</u> JARD SI JEMENT LEMENT CT SPEG R R	Weight of Coating, oz/ft ² (g/n	m ²)		See above
STANI SUPPL PROJE	BEGIN DATE END DATE	TESTED BY	REMARKS	
NAME :	RECOMMENDATION	1		
			DIVISION CH	IEF – MATERIALS TESTING

MAT-304 REPORT OF TEST: REINFORCED CONCRETE PIPE (Reduced for inclusion in manual)

Sour	ce ar	nd Lo	catic	n of	Fine Aggree	gate	Supply	/:																
Source and Location of Coarse Aggregate Supply:																								
Test	s Witr	nesse	ed by	<i>ı</i> :																				
											Mach	nine Re	eadings											
RCP	RCP	RCP	RCP	Slot	Method of	Date	Date	Age	Req'd	Req'd	Req'd	Actual	Actual	Actual	Actual	Core	Absp.	Req'	d Reinf.	Actu	al Reinf.	Remarks	Status	
Size	Length	Class	Wall		Manufacture	Cast	Broken	I	.01Crack	.0 1+10 %	Ultimate	Visible	.01Crack	.01+10%	Ultimate			(iı	n²/ft)	(ir	n²/ft)			
(in.)	(ft)			(Y/N)				(days)	(lbs.)	(lbs.)	(lbs.)	(lbs.)	(lbs.)	(lbs.)	(lbs.)	(Y/N)	(%)	i	0	i	0			

PROJECT NUMBER:	MAT-305	DATE		MATERIAL CODE			
SAMPLE NUMBER:	STATE OF CONNECTICUT DEPT. OF TRANSPORTATION DIV. OF MATERIALS TESTING REPORT OF TEST: STEEL BARS AND SHAPES	LAB #					
	Size						
	Grade						
	Area, in ² (mm ²)						
CE	Load, lbf (kN)						
KEN REN	Y.P., psi (MPa)						
ISIO ISIO ISIO	Load, lbf (kN)						
N RH CATI ACU CATI ACU CATI	T.S., psi (MPa)						
CIFION CIFION AL PION N AC	Elong. (%)						
CAJ SPE FECL FECL RSO	Cold Bend						
ARD MEN T SF PE CHN	Epox, mils (µm)						
AND PEC	Test No.						
STA SUI PRO OTIO	Begin Test End Test	Tested By	REMARKS				
NAME :	Recommendations						
			DIVISION CH	IEF – MATERIALS TESTING			

Tables From ASTM A 82 Steel Wire, Plain, For Concrete Reinforcement

Table 1 Tension Test Requirements							
Tensile strength, min, ksi (MPa)	80 (550)						
Yield strength, min, ksi (MPa)	70 (485)						
Reduction of area, min, %	30^{4}						

^{*A*}For material testing of 100 ksi (690 MPa) tensile strength, the reduction of area shall be not less than 25%.

Table 2 Tension Test Requirements (Material for Welded Wire Reinforcement)

	Size W1.2	Smaller than Size W1.2
	and Larger	
Tensile strength based on wire nom. area, min, ksi (MPa)	75 (515)	70 (485)
Yield strength based on wire nom. Area, min, ksi (MPa)	65 (450)	56 (385)
Reduction of area, min, %	30^{4}	30^{4}

⁴For material testing over 100 ksi (690 MPa) tensile strength, the reduction of area shall be not less than 25 %.

Table 4 Permissible Variation in Wire Diameter									
Size Number	Nominal Diameter,	Permissible Variation Plus and Minus, in.							
	in. (mm)	(mm)							
Smaller than W5	Under 0.252 (6.40)	0.003 (0.08)							
W5 to W12, incl	0.252 (6.40) to 0.391 (9.93), incl	0.004 (0.10)							
Over to W20, incl	Over 0.391 (9.93) to	0.006 (0.15)							
	0.505 (12.83), incl	0.000 (0.13)							
Over W20	Over 0.505 (12.83)	0.008 (0.20)							

PROJECT NUMBER:	MAT	-306		PRO	CESSING DA	TE	MATERIAL CODE	
SAMPLE NUMBER:	STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: PLAIN WIRE FOR WELDED WIRE FABRIC				ORATORY N	0.	3145	
		Hori	zontal	Hori Sj	zontal pec.	Vertical	Vertical Spec.	
	Spacing (in.)			-				
	Size Number							
ENCE GG	Act. Diam. (in)							
REFER TION DN CEPTIN SPONSII	Nom. Area (in ²)			-				
ZATION ZATION CCIFICA COVISIC SON AC	Load (lbf)			-				
PECIFIC PECIFIC AL SPE CIAL PI PER	T.S. (psi)							
<u>S</u> JARD S EMENT EMENT CT SPE C TI	Condition			-				
STANI SUPPL PROJE OTHEI	BEGIN DATE END I	DATE	TESTED	BY	REMARKS			
NAME :	RECOMMENDATION							
	·				D	IVISION CHIEF –	MATERIALS TESTING	

PROJECT NUMBER:	N State	MAT-307 E OF CONNECTICU	PRC	CESSING DATE		MA	FERIAL CODE	
SAMPLE NUMBER:	DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: GENERAL TENSILE STRENGTH							
	Size							
	Grade							
	Area (in ²)							
	Load (lbf)							
BRENCE N NG SIBILITY	Y.P. (psi)							
	Load (lbf)							
I REF N ATIO ION CEPT CEPT	T.S. (psi)							
TION ATIO DIFIC OVIS OVIS N AC	Elong. (%)							
FICA CIFIC SPEG L PR L PR L PR CIFICA	Cold Bend							
PECIA PECIA PECIA PECIA	Galv (mils)							
ZARD ARD EME1 EME1 CT SH	Test No.							
STANE SUPPL PROJE	BEGIN DATE	END DATE	TESTED B	Y	REMARKS			
NAME : TITLE:	RECOMMENDAT	ΠΟΝ			-			
					DIVIS	ION CHIEF -	- MATE	RIALS TESTING

Г

State of Connecticut - Department of Transportation Division of Materials Testing 280 West Street, Rocky Hill, CT 06067

REPORT OF TEST ON PORTLAND CEMENT CONCRETE CYLINDERS

.

							MAI	308 REV. 10/16
Sample ID:					Curi	ng Box Used?	🗌 YES 🗌 N	O (Check one)
					Sour	rce/Location		
Structure/Location:					Sam	pled From:		
(Where concrete was placed.)					(i.e.ch	nute/pump)		
Item Number:*					Sam	pled By:		
Item Quantity:**					Item	Units:		
Material Quantity***					Unit			J.M (Check one)
Brand of Cement:					Teste	ed By:		
Required Strength:					Cont	tractor:		
Field Test Results			Test 1			Test 2	(Required if ma	terial fails test 1.)
Air (ASTM C173/C231)				J				
Conc. Temp. (ASTM C10	64)			> *			> *	
Slump (ASTM C143)								
Date Sampled:				* Me	asur	ed at point of	placement.	
Specimen ID:		(1)	(2)	(3)		(4)	(5)	(6)
Age(s) Requested:	· · · · · ·	(-)	(=/	(0)		(-)	(*)	
Date Received:								
Date Tested:								
Age Tested:								
			4	in. cylind	er			
Average Diameter:****								
Area :								
			6	in. cylind	er			
Average Diameter:****								
Area:								
Maximum Load:								
(AASHTO T-22) Compressive					\rightarrow			
Strength:(PSI/Mpa)								
Fracture Type: (a-e)								
Status:								
NOTES:								
*Item Number : Contract Item	under	which Cor	ntractor is being p	aid for cond	crete th	hat is represented	by sample.	
**Item Quantity: Amount of co of cylinders submitted.	**Item Quantity: Amount of concrete/Number of items represented by sample in pay units for that contract item. It is never the number of cylinders submitted.							
*** Material Quantity: Amount m ³) for structures and 50 CY (of Con 40 m³) f	crete repr or pavem	esented by samp ent. It is never the	le. Mininun e number o	n Sche f cylind	edule for Test requ ders submitted.	iires one sample	every 75 CY (60

*****Average Diameter: Value is taken from MAT-308A.

CONNECTICUT DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING AND CONSTRUCTION DIVISION OF MATERIALS TESTING

DIVISION OF WATERIALS TESTING

DAILY CONCRETE CYLINDER DIAMETER LOG

MAT-308A

Rev. 10-12-16

DATE				
Month:	CYLINDER	CYLINDER	CYLINDER	AVERAGE DIAMETER OF
Year:	DIAMETER #1	DIAMETER #2	DIAMETER #3	THE THREE CYLINDERS
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				

Compression Units

#1	#2	#3
#1	#2	#3
	#1	#1 #2 #1 #2 #1 #2

Oven Dry Density (D), $lb/ft^3 = [W_d/(W_s-W_i)] \ge 62.4$ Oven Dry Density (D), $kg/m^3 = [W_d/(W_s-W_i)] \ge 1000$ Absorption, $lb/ft^3 = [(W_s-W_d)/(W_s-W_i)] \ge 62.4$ Absorption, $kg/m^3 = [(W_s-W_d)/(W_s-W_i)] \ge 1000$ Net Volume (V_n), ft^3 or mm³ = W_d/D Average Net Area (A_n), $in^2 = (V_n \ge 1728)/H$ Average Net Area (A_n), $mm^2 = V_n/H$

PROJECT NUMBER:	MAT-309		PROCESSING D	ATE	MATER	RIAL CODE	
SAMPLE NUMBER:	DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: MASONRY CONCRETE UNITS/BRICK			LABORATORY	NO.		
		#1	#2	#3	Ave.	Spec. Ave.	Spec. Ind.
	Height, in (mm)						
ZENCE NG BILITY	Length, in (mm)						
ON REFEH DN CATION SION ACCEPTIN RESPONSI	Width, in (mm)						
ECIFICATI CIFICATIO SPECIFIC AL PROVIS PERSON PERSON	Comp. Strength, psi (MPa)						
SPI SARD SPE EMENTAI CT SPECL C C	Absorption, lb/ft ³ (kg/m ³)						
STANE SUPPL PROJE	BEGIN DATE END	DATE	TESTED BY	Y REMARK	Ś		·
NAME :	RECOMMENDATION						

Durometer Readings 1.	Identification Conn.:
2.	Proj. No.:
3.	Manufacturers I.D.:
4.	Pad Type No.:
5.	Month and Year:
Average =	Bridge Number:
	Lot Number:

Pad Number:

PROJECT NUMBER:	MAT-310	DATE	MATERIAL CODE
SAMPLE NUMBER:	STATE OF CT D.O.T. DIV. OF MAT. TESTING REPORT OF TEST: ELASTOMERIC BEARING PAD	LAB #	3505
	PA	D DATA	SPECIFICATIONS
	Size		
	Slope		
	Spacing (Lam.)		
	No. & Thickness		-
SFEF ON CAT CAT CAT ISION	Edge Cover		
N RE CCIFI CCIFI CCEP	Elast. Layer		
CIFIC CIFIC	Comp. Strain		
CAJ VTAL FECL/ RSO	Duro. Hardness		
ARD MEN T SP PE CHN	Shop Drawing		
SPE(AND, AND, AND, AND, AND, AND, AND, AND,	Cert. Test Report		
STA SUI PRC OT	Test Date Report Date	Tested By Remarks	
E: TE	Recommendation		
NAN NAN			
	1		
		DIVI	SION CHIEF – MATERIALS TESTING

MAT-311 (Deleted)

MAT-312

Compression Units

Specimen:	#1	#2	#3	#4	#5
Gross Area (A), in ² (mm ²)					
Maximum Load (W), lbf (N)					

Absorption Units

Specimen:	#1	#2	#3	#4	#5
Saturated Weight 5-h boil(W_b),					
lb (kg)					
Oven Dry Weight – Final (W_d) ,					
lb (kg)					

Compressive Strength, psi = W/A

Absorption, $\% = 100(W_b - W_d)/W_d$

PROJECT NUMBER:	MA STATE OF CO	Г-312	CUT		PROCESSING DATE				MATER	LIAL CODE
SAMPLE NUMBER:	DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: CLAY BRICK			LABORATORY NO.						
		#1	#2	#3		#4	#5	Ave	Spec. Ave.	Spec. Ind.
	Depth, in (mm)									
ENCE G BILITY	Length, in (mm)									
ON REFER N ATION SION ACCEPTIN LESPONSII	Width, in (mm)									
ECIFICATI CIFICATIC SPECIFIC AL PROVIS PERSON	Strength, psi (MPa)									
SPF SARD SPE LEMENTAI LEMENTAI CCT SPECL	Absorption by 5- hour boiling (%)									
STANI SUPPL PROJE	BEGIN DATE END	DATE	TEST	TED BY	ľ	REMA	ARKS			
NAME TITLE	RECOMMENDATION									
							DIVI	SION CHIE	EF – MATERIA	LS TESTING

MAT-313



PROJECT NUMBER:	MAT-313 PROCES		CESSING I	DATE	MATERIAL CODE		
SAMPLE NUMBER:	DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: CONCRETE BLOCK FOR SLOPE PROTECTION		ABORATORY NO.		3197		
		SAMPL	E1 S	SAMF	PLE 2	SAMPLE 3	SPEC.
	L, Length, inches (mm)						16 +/- ½ in 406 +/- 12.5 mm
	W, Width, inches (mm)						8 +/- ½ 203 +/- 12.5 mm
FERENC N PTING NSIBILIT	H, Height, inches (mm)						4 +/- ½ 100 +/- 12.5 mm
TION RE FICATIO VISION N ACCEI L RESPO	A, Area, in ² (mm ²)						
PECIFICA ECIFICA AL SPECI IAL PRO PERSO SCHNICA	Load, lbf (N)						
<u>SI</u> JARD SP JEMENT/ JEMENT/ CT SPEC R TE	Stength, psi (MPa)						3000 psi 21 MPa
STANI SUPPL PROJE	BEGIN DATE	END DATE	TESTED I	ЗY	REMARK	S	
NAME : TITLE:	RECOMMENDATIO	DN	1				
						DIVISION CHIEF – I	MATERIALS TESTING

CERTIFICATION OF PRECAST CONCRETE PRODUCTS MAT-314 (PC-1)

STATE OF CONNECTICUT

DATE OF SHIPMENT

REV. 1/15

DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING 280 West Street , Rocky Hill CT 06067-3502

<u>Project Personnel:</u> Submit with Request for Test **AFTER** visual inspection on project site.

List one type of product per cast date per line.

DISTRIBUTION: Original to Lab, Copy to	Project Engineer, Copy to be kept by Manufacturer.
MANUFACTURER	LOCATION

SHIPPED TO: (Contractor's Name)		PROJECT NO	. OR PURCHASE ORDER NO.	
Description of Produ	icts	Cast Date	Quantity	
-				
Remarks				
This document certifies that all the products listed above conform to all applicable Department and project				
specifications, including but not limited	to the "Buy America" requ	uirements regard	ding all steel components.	
	Authorized Agent of Mani	uiacturer		
Signed:			Date:	

MAT-315 (Deleted)

MAT-316

SAMPLE	SPECIFICATION REFERENCE
BRAND	SUPPLEMENTAL SPECIFICATION
ТҮРЕ	PROJECT SPECIAL PROVISION
IN LAB	PERSON ACCEPTING
<u>42 Kgs. Bag</u>	IECHNICAL RESPONSIBILITY
	NAME
GAL CAN OTHER	
OTHER	111LE

	FULL	
DATE TO CHEM. RM.	CHEMICAL	PROJECT #
DATE RESULTS RETURNED	FINENESS ONLY	SAMPLE #

Mat 316	AASHTO M – 85					LAB NO.
Mat-510		(ASTN	I C – 1	50)		
REPORT OF	TEST: POR	FLAND CEM	ENT (ALL TYPES)		
PHYSICAL SEC	CTION TEST I	RESULTS		CHEMICAL SE	CTION TE	ST RESULTS
TEST	LAB RESULT	AASHTO SPEC.		TEST	LAB RESULT	AASHTO F SPEC.
AIR CONTENT %		12 MAX.		FINENESS SoCm/Gm		2600 - 4200
				SiO ₂ %		NONE
AUTOCLAVE EXPANSION %		.80 MAX		Al ₂ O ₃ %		NONE
COMPRESSIVE STRENGTH				Fe ₂ O ₃ %		NONE
1 Day <u>MPa</u> PSI		NONE		MgO %		6.0 MAX.
3 Day <u>MPa</u> PSI		12 MPa Min. 1740 PSI Min.		SO ₃ %		a) 3.0 MAX. b) 3.5 MAX.
7 Day <u>MPa</u> PSI		19 MPa Min. 2760 PSI Min.		LOSS ON IGNITION %		3.0 MAX.
				INSOLUABLE RESIDUE %		0.75 MAX.
				C ₃ S %		NONE
TIME OF SETTING				C ₂ S %		NONE
VICAT, MIN		45 to 375		C ₃ A %		NONE
				a) WHEN C ₃ A < b) WHEN C ₃ A > NOTES:	8% 8%	,
RECOMMEN	JDED FOR:	·		REMARKS:		

MAT-316 - Page 2 CEMENT	TYPE	LAB NO				
T – 106 C – 109 DATE:	T – 137 TIME: C – 185					
CUBES MADE:	AIR CC	NTENT				
AGE	WATE	R %				
DATE	WATE	R ml				
1.	FLOW	2⁄0				
2.	GROSS	WT				
3.	- CUP V	VT				
AVG	= NET	WT				
	FACTO	R				
	NET W FACTC	T* R				
	AIR CO	NT %				
DATE						
T-107 C-151 AUTOCLAV	E T-129 C-187	T-129 C-187 NORMAL CONSISTENCY				
TIME BARS MADE	WATE	۲%				
BARS MEASURE	WATE	R ml				
SWITCHES ON	PENET mm	RATION				
VENT CLOSED						
295 PSI	T-131 C-191	VICAT – TIME	OF SET			
ADD 3 HOURS		MADE	INITIAL			
SWITCHES OFF	TIME (DF DAY				
DOWN 1 ½ HRS	HR: MI	N				
COOL 30 MIN	MINUT	ES				
AFTER STEAM						
BEFORE STEAM						
DIFFERENCE						
% EXPANSION						

Description	Sample #1	Sample #2	Sample #3	Specifications
Overall Diam. Across Crowns, in (mm)				
Diameter of Exterior Wire #1, in (mm)				
Diameter of Exterior Wire #2, in (mm)				
Diameter of Exterior Wire #3, in (mm)				
Diameter of Exterior Wire #4, in (mm)				
Diameter of Exterior Wire #5, in (mm)				
Diameter of Exterior Wire #6, in (mm)				
Diameter of Center Wire, in (mm)				
Diff Betwn. Center & Any Ext. Wire, in (mm)				
Pitch, in (mm)				
Load @ 1% Extension, lbf (kN)				
Breaking Load, lbf (kN)				
Breaking Strength, psi (MPa)				
No. Wires Broken				
Type of Break				
Location of Break				
Length Meas. @ 1% Extension, "A", in (mm)				
Length Meas. @ Breaking Load, "B", in (mm)				
Total Elongation Under Load (%)				

Total Elongation Under Load = (100%)[(B-A)/A] + 1%

PROJECT NUMBER:	N	/IAT-323		PRO	CESSING DAT	Έ	MATERIAL CODE	
SAMPLE NUMBER:	STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: STEEL STRAND		LABORATORY NO.).	3148		
				S	ample 1	Sample 2	2 Sample 3	
	Reel No.							
	Heat No.							
	Diameter of Str	rand, in (mm)						
	Min. Ext. Wire	Diameter, in (m	m)					
EREN	Center Wire Di	ameter, in (mm)						
N REF	Diff in Diamete	er of Center Wire	e, in (mm)					
ATION TION IFICA VISIC N AC	Total Area of 7	Wires, in. ² , mm	2					
IFICA IFICA SPEC L PRC DERSC	Load @ 1% Ele	ongation, lbf (kN	[)					
SPEC SPEC SPEC TTAL	Total Elongatio	on (%)						
DARD EMEN CT SP	Breaking Load	, lbf (kN)						
TANE UPPL THER	BEGIN DATE	END DATE	TESTED BY	Y	REMARKS			
NAME:	RECOMMENDAT	TION						
	·				Dľ	VISION CHIEF -	- MATERIALS TESTING	

Field Report: Inspection of Prestressed, Precast and Reinforced Concrete Pipe Manufacturers

Date:	Inspection by:			
Phone:				
Fax No:				
E-Mail:				
Plant Name				
Address				
Plant Manager				
NPCA Certified				
Items of Manufacture				
	MIXERS			
<u>Manufacturer</u>	<u>Type</u>	<u>Capacity</u>		
	PIPE MACHINE	S		
Manufacturer	Туре	Sizes		
	<u>- 11-</u>			
	CALIBRATION of SC	AT FS		
Scala	Data of Calibration	Calibration Company		
State	Date of Calibration	Canbration Company		
Cement				
Aggregate				
Water				
Other				
	TESTING EQUIPM	ENT		
Testing Machine	Date of Calibration	Calibration Company		
3-Edge				
Compression				
Concrete Testing Equip.	Condition	Calibration Info. Available		
Air Meter				
Slump Cone				
Thermometers				

MAT-324		TDAL DEDCAMMEL	Page 2 of 2
	PLANI QUALITY CON	I KOL PERSONNEL	
Employee	ACI / PCI Certified	<u>NETTCP Conc. Tech.</u>	
Additional remarks			
	SOURCE of CEMENT A	AND POZZOLANS	
	AGGREGATES A	ND WATER	
<u>Material</u>	<u>Source</u>	<u>Size</u>	
	SOURCE OF CATCH BASIN	FRAMES AND GRATES	
	REINFORCI	EMENT	
Domestic Steel			
Foreign Steel Onsite			
	ADMIVTI	IDES	
	Manufacturers of	Admixtures	
<u>Name</u>	<u>Type</u>		
	Q.C. PLAN DEF	ICIENCIES	

-Caps -Caps Carriage Bolt/Nut Bands Bands Bands Bands Carriage Matter Carriage Bolt/Nut Carriage Bo	D E T H L D E T F L Bracket Truss Rod/Nut Coupling L C Bracket Truss Rod/Nut Stretcher Bar 3/4"x1/4"x1 Tightener Brace Rail 1.5/8"x 1½"x L Tightener	C READINGS A	Mils) READINGS (M	(11s)
PROJECT NUMBER:	MAT-325	PROC	CESSING DATE	MATERIAL CODE
SAMPLE NUMBER:	STATE OF CONNECTION DEPARTMENT OF TRANSPO DIVISION OF MATERIALS ' REPORT OF TEST: CHAIN LINK FENCE HARI	CUT ORTATION LABO TESTING DWARE	ORATORY NO.	3320
	ITEM	Galv. Oz/in ² (g/m ²)	ITEM	Galv. Oz/in ² (g/m ²)
SPECIFICATION REFERENCE STANDARD SPECIFICATION SUPPLEMENTAL SPECIFICATION PROJECT SPECIAL PROVISION OTHER OTHER PERSON ACCEPTING TECHNICAL RESPONSIBILITY NAME : TITLE:	BEGIN DATE END DATE RECOMMENDATION	TESTED BY	REMARKS	
			DIVISION CHIEF	– MATERIALS TESTING

PROJECT NUMBER:	MAT-326 STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: CHAIN LINK FENCE TENSION WIRE		PROCESSING DATE		MATERIAL CODE
SAMPLE NUMBER:					
			Actual	S	Specification
NCE	Gage of Wire				
ATION REFERE ATION CIFICATION OVISION ON ACCEPTINC AL RESPONSIBI	Tensile Strength, psi (MPa)				
SPECIFIC ARD SPECIFIC EMENTAL SPE CT SPECIAL PR PERS TECHNIC	Weight of Coating, oz/ft ² (g/m ²)				
STAND SUPPLJ PROJEG OTHER	BEGIN DATE END DATE	TESTED F	BY REMARKS		
NAME :	RECOMMENDATION				
					MATEDIALS TESTING

MAT-326



PROJECT NUMBER:	MAT-327 STATE OF CONNECTICUT DOT	POST DA	ΓΕ LAB #		MAT. CODE 3549
SAMPLE NUMBER:	REPORT OF TEST: H-PILES AND WIDE FLANGE SHAPES	DATE RE	ECEIVED	RECE	IVED BY
				Specifi	cation
	Item	Sample	U.S. Cu	st. (in)	Metric (mm)
	b, flange width			+ 1/4 - 3/16	+ 4 - 3
				+1/4	+6
	d, depth			-3/16	-5
TION FICATI FICATI VISION EPTING	t _f , flange thickness				
ION R DIFICA SPECI L PRO L PRO N ACCF RESPC	t _w , web thickness				
TCAT D SPEC ENTAL SPECIA SPECIA ERSON NICAL	wt/ft		+	-/-2.5%	+/-2.5%
CUP DAR OF COLLE	Tensile Strength		Gr. 36: 5	8-80	Gr. 36: 400-550
	(ksi, MPa)		Gr. 50: 6	5-95	Gr. 50: 450-655
STA STA OTIO	Begin Date End Date Tester	By RI	EMARKS		
UTE WE					
NAA NAA					
		1			
			DIVISI	ON CHIEF –	MATERIALS TESTING

ASTM A 496 Steel Wire, Deformed, for Concrete Reinforcement

Table 4 Tension Test Requiren	nents (Material for Welded Wire Reinforcement)

	psi (MPa) min
Tensile strength	80000 (550)
Yield strength	70000(485)

Section 9 Permissible Variation in Weight

9.1 The permissible variation in weight of any deformed wire is +/-6% of its nominal weight. The theoretical weights shown in Table 1, or similar calculations on unlisted sizes, shall be used to establish the variation.

PROJECT NUMBER:	MAT-328		PROCESSING DATE		MATERIAL CODE
SAMPLE NUMBER:	DEPARTMENT OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: DEFORMED STEEL WIRE FOR CONCRETE REINFORCEMENT		LABORATORY N	NO.	3145
		Horizontal	Horizontal Spec.	Vertical	Vertical Spec.
	Spacing (in.)				
	Size Number				
ENCE G G BILITY	Unit Wt. (lb/ft)				
REFER TION DN CEPTIN SPONSII	Nom. Area (in ²)				
ZATION ZATION CIFICA CUFICA SON AC AL RES	Load (lbf)				
PECIFIC PECIFIC AL SPE CIAL PI PERS	T.S. (psi)				
<u>S</u> JARD S EMENT EMENT CT SPE CT SPE C	Condition				
STANI SUPPL PROJE OTHEH	BEGIN DATE END D.	ATE TESTED	BY REMARKS		
NAME :	RECOMMENDATION				
			Ľ	DIVISION CHIEF – 1	MATERIALS TESTIN

STATE OF CONNECTICUT - DEPARTMENT OF TRANSPORTATION

Division of Materials Testing280 West Street, Rocky HillCT 06067-3502Guideline for the Visual Inspection of Reinforcing SteelMAT-33010/16

Connecticut Department of Transportation Standard Specifications Section 1.06 **Control of Materials** requires that, "All permanently incorporated steel and iron used in the construction of the project must have been produced and fabricated in the United States." This restriction applies to reinforcing steel used in all permanent construction for the project, both on and off the project site.

Producers of reinforcing steel are required to identify their products by rolling into the surface of the bar using designated letters, numbers and/or symbols for the mill, bar size, type of steel, and in some cases the grade of steel. To assist project inspectors in interpreting the markings, the following figures are provided. Should there be questions or concerns, please contact Mark Brothwell at the Division of Materials Testing @ (860) 258-0378.



Laboratory: Central Lab Rocky Hill, CT	State of Connecticut Department of Transportation						
Sample Date Tested:	Bureau of Engineering & Highway Operations						
Kind of Material:	Report of Test: Asphalt Binder MAT-401						
Source of Supply:	Standard Specifications CON	NDOT: MO	4 Bit. Conc	rete, AASH	то мз20 /	AND AASH	TO M332
Location of Source or Supply:	Procee	dures in co	nformace v	vith AASH1	FO R-29		
Sample Taken From:							
Source of Supply:	Rocky Hill Binder Results						
Location of:							
Sampled By:	Original Binder	_					Specification
Date Sampled:	SG @ 25°C				-	-	
Using Agency: ConnDOT	Temperature (°C)	58	64	70	76	82	
Quantity Represented:	Viscosity (Pa-s) @ 135°C						max. 3
Lot Number:	Viscosity (Pa-s) @ 165°C						
Tank Number:	Mixing Temperature Range						
Sample Received:	Compaction Temperature Range						
Remarks:	Complex Modulus, G* (kPa)	L					
1	Phase Angle (δ)						
	Original G*/sin δ @ T°C						min. 1
	RTFO Binder		·				
Binder True Grade	Mass change (%)						-1 to +1
	Temperature (°C)	58	64	70	76	82	
High Temp	Complex Modulus, G* (kPa)						
Inter Temp	Phase Angle (δ)			1			
Low (BBR)	RTFO G*/sin δ @ T°C						min. 2.2
T(S)-T(m)	RTFO Jnr 3.2 (kPa ⁻¹) @ T°C		<u> </u>	<u> </u>			max. 4.5 (S), 0.5 (E)
I	RTFO R3.2 @ T°C			1			
	RTFO Jnr 0.1 (kPa−1)@ T°C			1			
	RTFO Jnr Diff (%) @ T°C			1			max. 75
	Modified by an acceptable elastomeric polv?	1	1	1	1		Yes (E)
	PAV Binder	•	<u> </u>	<u> </u>	•		
	Temperature (°C)	34	31	28	25	22	
	Complex Modulus, G* (kPa)	1	1	1			
	Phase Angle (δ)	1	+	1			
	PAV G* sin δ @ T°C	1	+	1			max. 5000 (S). 6000 (F)
	Temperature (°C)	-6	-12	-18	-24		
	PAV BBR Stiffness (MPa) @ T°C	+	+	+			max. 300
	PAV BBR m-value @ T°C	1	+	1			min. 0.3
	Failure Stress	1	+	1			
	Failure Strain (%)	1	+	1			min. 1
			1	1	1		

Laboratory: Central Lab Ro	cky Hill, CT
Sample Date Tested:	
Kind of Material:	
Source of Supply:	
Location of Source or Supply	<i>'</i> :
Sample Taken From:	
Source of Supply:	
Location of:	
Sampled By:	
Date Sampled:	
Using Agency: ConnDOT	
Quantity Represented:	
Lot Number:	
Mat-100:	
Sample Received:	
Remarks:	

State of Connecticut Department of Transportation

Bureau of Engineering & Highway Operations

Report of Test: Emulsified Asphalt MAT-402

Standard Specifications CONNDOT: M.04 Bit. Concrete, AASHTO M 140 AND AASHTO M 208

Procedures in conformace with AASHTO T 59 and AASHTO T 49

Rocky Hill Emulsified Asphalt Results

Residue by Evaporation

Set	1	2	3	4	Specification
M _{br} Beaker + Rod + Screen (if used) weight, g					
M _{brr} Beaker + Rod + Screen (if used) + residue, g					
Residue, %					
Residue by Evaporation, %					*

* Residue by distillation limits: For RS-1, RS-1h, CRS-1 and CRS-1h, min 60; SS-1, SS-1h, CSS-1 and CSS-1h, min 57

Penetration at 77°F

Trial	1	2	3	Specification
Penetration at 77°F				
Average Penetration				*
Difference between highest and lowest				**

Mass per Gallon

Measure Mass, g					
Measure and Emulsio					
M _e , mass in measure at 77°F g					
D_e , density of the emulsififed asphalt, lb/gal at 77 and 60 °F					
0 and 0					
Specific Gravity of emulsififed asphalt, 60/60					

* Requirement for testing on residue by distillation: For grades RS-1h, SS-1h, CRS-1h and CSS-1h, 40-90; RS-1 and CRS-1, 90-150; SS-1 and CSS-1, 90-250

** For Penetration 0-49, max. 2; 50-149, max. 4; 150-249, max. 12

Sieve Test

Trial	1	2	Specification
M _{spr} Mass of Sieve, Pan, and Residue, g			
M _{sp} Mass of Sieve and Pan, g			
Sample Retained, %			0.10

Producer:		Location:		
Inspected By:		Date:		
The mixing plant used in	n the preparation of bituminous	concrete shall conform	to the followi	ng requirements:
Plant Type:	Batch		um	
Aggregates:	Capacit	У		Capacity
ТҮРЕ	SOURCE OF SUPPLY	ТҮР	Έ	SOURCE OF SUPPLY
Trap Rock		🗌 Crushe	d Gravel	
1/4"		1/4"		
3/8 "		3/8 "		
1/2"		1/2"		
3/4"		3/4"		
1 "		1"		
1 1/4"		1 1/4"		
Natural Sance	I	☐ Stone S	Sand	
Screenings		☐ Other		

<u>Cold E</u>	lins:		
	Number of cold feed storage b	ins (m	ninimum of 4 required)
	Scalping Screens		
<u>Dust F</u>	Return:		
Met	nod of Introduction:	Bag	House Options:
	Pneumatic		Reversible Screw
	Screwed		Knockout Box
	Separate Bin		Other:
<u>Hot Bi</u>	ns:		
	Number of compartments (min	imum	of 3 required)
	Overflow pipes		
	Snug fitting gate:		
<u>Miscel</u>	laneous:		
	Individual belt feeders		
	Vibrating pan		
	Electronic belt weighing devices	for a	ggregates and RAP
	Belt scale accurate to +/- 0.5%		
	Means for diverting aggregate or	n conv	veyor belt before dryer
	Interlocking system of feeders a	nd co	nveyors
	RAP capability		
	Moisture compensating device		
	WMA Technology Device:		
<u>Aspha</u>	It Delivery System:		
	Spray Bar Pressure System (Bat	ch)	
	Spray Bar Gravity Fed System (E	Batch)	
	Measures accurately to within +/	-0.1%	of the total weight of mixture
	Delivers conholf comont in this		

- Delivers asphalt cement in thin, uniform sheet full width of the mixer:
- Interlock to halt production

Liquid Asphalt Storage Tanks:

Lines to be separated or equipped with a reverse pump to eliminate contamination

Thermostatically controlled with a thermometer in bulkhead

Sampling valves located in lower half of an end bulkhead and on mixer supply line.

Agitation system to ensure homogenous state

Number of storage tanks on site:

Tank Number:	Tank Capacity:	Type of Asphalt:

Hot Storage Silos:

Number of Silos:



Type of Heat:

Cone Hot Oil

Cone Electric

Silo Number	Capacity	Brand	Manufacturer

The silos shall be equipped with a light or indicator to show when the level of material reaches the top of the discharge cone.

Automation and Recordation of Bituminous Concrete Plant:

The plant shall be equipped with an automated digital weighing, cycling, and monitoring system installed with displays located in full view of the operator.

Batch Recording

The automatic proportioning system shall be capable of consistently delivering materials within the full range of batch sizes with the following tolerances:

Each Aggregate Component: <u>+</u>1.5% of individual of cumulative target weight for each bin

Mineral Filler: <u>+0.5%</u> of the total batch

Bituminous Material: <u>+</u>0.1% of the total batch

Zero Return (Aggregate): <u>+</u>0.5% of the total batch

Zero Return (Bituminous Material): <u>+</u>0.1% of the total batch

An asterisk (*) shall be automatically printed next to any batch weight(s) exceeding tolerances shown below.

Equipment shall monitor the batching sequence of each component of the mixture and produce a printed record.

A printed character shall automatically be printed on the batch plant printout when the automatic batching sequence is interrupted or switched to auto-manual or manual during proportioning.

Plant Scales:

Scales will be checked and sealed by the Weights and Measures Division at least annually and more often if deemed necessary to ensure their accuracy.

Ten standard 50 lb. (22.7 kg.) test weights for checking plant scales.

	Seal Dates
Plant Scale:	
Truck Scale:	
Silo(s):	

D.E.P. Operating Permit (Obtain Copy)

Batch/Drum/Delivery Ticket:

All vendors producing bituminous concrete for the State of Connecticut must have their truck-weighing scales, silo scales, and mixing plant automated so as to provide a detailed ticket containing the following information:

State of Connecticut printed on ticket
Name of producer and Identification of the Plant or specific storage silo if used
Date and time
Mixture designation; Mix type and level*
If WMA technology is used, the additive name and dosage rate or water injection rate must be listed
Net weight of material (Including RAP (Dry weight) percentage and moisture content, if used)
Tare weight of vehicle
Gross weight (equal to the net weight plus the tare weight or the loaded scale weight)
Project number, purchase order number, name of Contractor (If Contractor is other than the Producer)
Vehicle number or other means of unique identification of vehicle
Individual aggregate, RAP, and virgin asphalt max/target/min weights
Running daily total delivered and sequential load number

* **NOTE:** Curb Mixture to be used for machine-placed curbing must be shown on ticket as "**Curb Mix Only**".

Copy of Printout(s) (Plant & Delivery Ticket)

Please note any variations/comments from inspection below:

STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING

MAT-406 (REV 12-16)

BITUMINOUS CONCRETE PLANT LABORATORY – EQUIPMENT INSPECTION

Produc	cer: Location:
Inspec	tor: Date:
Contra	ctor's Representative:
	PLANT LABORATORY REQUIREMENTS
At all p ensure	points during the production season, this lab must comply with all requirements. The Producer shall that the State's representatives are given priority in the use of the laboratory.
<u>GENER</u>	AL:
	A laboratory that is equipped for performing all tests referenced in AASHTO R 35 and AASHTO M 323.
	The laboratory shall include a PC, printer, and telephone with a dedicated hard-wired phone line. The PC shall have Microsoft Office 2003 or later and a high speed internet connection with a functioning web browser with unrestricted access to https://ctmail.ct.gov. The PC shall have the most recent ConnDOT forms. This equipment shall be made available for use by the State's representative.
	The field laboratory shall have a potable water source (with documentation stating the source of the potable water) and drainage for use with testing equipment.
The fie	Id laboratory shall:
	be a separate room with minimum floor space of 300 ft ² (27.9 m ²) and a minimum counter space of 20 ft ² (1.9 m ²);
	have windows installed that allow for sufficient light and ventilation;
	have a source of fresh air from a door and/or from windows that can be opened;
	have a ventilation fan that will not adversely affect the room temperature;
	be equipped with a suitable heating and air conditioning cooling system able to maintain the temperature between 65°F and 80°F(18°C to 27°C); and
	be clean and be free of all materials and equipment not associated with the laboratory.

EQUIPMENT:

A list of laboratory equipment used in acceptance testing processes including, but not limited to, balances, scales, manometer/vacuum gauge, thermometers, gyratory compactor. The list shall include calibration and/or inspection dates in accordance with AASHTO R 18.		
Paint brush: 1 in to 1 ½ in (25 mm to 38 mm) wide.		
Hand brush: suitable for cleaning sieves.		
Two, 6 in. (152 mm) spatulas.		
Two stem thermometers for mix temperatures with a range of 50°F to 450°F (10°C to 230°C).		
Thermometers: Calibrated liquid-in-glass, total immersion type, of suitable range with gradations at least over 0.2°F (0.1°C) and a maximum scale error of 0.2°F (0.1°C) as prescribed in ASTM Specification E2.		
Vacuum pump or water aspirator for evacuation of air from the container: The vacuum pump or water aspirator shall be equipped with a needle valve to maintain constant vacuum.		
Water bath: Shall be capable of maintaining constant temperature between 20 and 30°C and constant suitable water level.		
Residual pressure manometers or vacuum gauges (Mercury manometers are not allowed for use.): See diagram below for proper placement of manometer or gauge.		
Water Value Flow of Exhausted Air and Water Vapor 2000 cc Filter Flask Pressure Manometer Vacuum Vessel Vacuum Vessel Vater 3-1000 cc Filter Flasks for Water Vapor Trap Fgure 1-Example of Correct Arrangement of Testing Apparatus Image: Construction of the standardized in the standardin the standardized		
Date manometer/gauge was last standardized:		

Page **2** of **6**

EQUIPMENT (Continued):

Superpave gyratory compactor: Capable of providing a consolidation pressure of 600 <u>+</u> 18 kPa, an internal angle of gyration of 1.16 <u>+</u> 0.02 degrees, and a speed of gyration of 30 <u>+</u> 0.5 rpm. Gyratory compactor shall be directly connected to printer.

Manufacturer's Name:

Date gyratory compactor was last standardized:

Three (3) Superpave cylindrical molds: Large enough to accommodate the following specimen requirements: 150 mm diameter, 90 to 150 mm heights. Molds shall have an inside diameter of 149.9 to 150.0 mm and be at least 250 mm high.

Extrusion jack or Arbor press: Capable of extruding compacted specimens from molds without distortion or damage.

Timer: Accurate to one-minute increments and capable of measuring from 1 min. to 60 min. The timer shall have audible alert when the time has expired.

Pans: Four (4) metal pans of adequate size to hold 5000 grams of material and for reheating gyratory sample to compaction temperature.

Mechanical agitator device: Capable of running two samples simultaneously and applying consistent agitation.

Putty knife or scraper.

Trowel or quartering device.

Eye wash station: A double (two-eye) wash station (2,000 ml minimum) or sink mounted (potable water source with documentation stating the source of the potable water) capable of cleaning both eyes simultaneously, installed in the laboratory for ready access. Contents shall be tamperproof and dated.

Solution Expiration Date:

Large scoop.

Heavy (Kraft) wrapping paper or other suitable paper.

Long handled shovel.

Five, 3 gal (12L) sample buckets.

Page 3 of 6

<u>EQUIPI</u>	MENT (C	Continued):	
	Sample splitter suitable to split aggregate samples (coarse and fine).		
	Fire extinguisher for electrical or chemical fires effective on all solvents used in the laborator		
		Date refilled or checked (within one year):	
	A 12 ft	³ forced draft oven	
		Thermostatically controlled so as to maintain temperature within <u>+</u> 5°F (3°C)	
		Temperature range of 104°F to 395°F (40°C to 200°C)	
	Ignition Oven(s)		
		Correction Factors for each ignition oven (See MAT-433)	
		Oven 1: Date Internal Balance was last standardized:	
		Oven 2: Date Internal Balance was last standardized:	
	Truck Body Release Agent		
		Brand Name:	
	Sieve Shaker		
		Motorized shaker having a horizontal sieving motion and a tapping action	
		Equipped with an automatic 0 to 30 minute timer capable of turning off the shaker	
		Brand Name:	
		Shaking Action: 🗌 Good 🗌 Fair 🗌 Unacceptable	
		Sieve retaining & hold-down: 🗌 Good 🗌 Fair 🗌 Unacceptable	
		Able to hold a 15 in. (380 mm) nest of sieves: Yes No	
		Timer accuracy: 🗌 Acceptable 🗌 Unacceptable	

Page 4 of 6

EQUIPMENT (Continued):

Sieves (U.S. Standard)

Set of 8 in. (200 mm) sieves

Set of 12 in. (300 mm) sieves

A minimum of one for each of the above sieve sizes:

Pan (may be half height)	🔲 #200 (75 μm) (may be half height)
🔲 #100 (150μm) (may be half height)	🔲 #50 (300μm) (may be half height)
🔲 #30 (600μm) (may be half height)	🗌 #16 (1.18mm) (may be half height)
🗌 #8 (2.36mm) (may be half height)	🗌 #4 (4.75 mm)
3/8" (6.3mm)	☐ ½" (9.5 mm)
☐ ¾" (19 mm)	🗌 1" (25 mm)
1 ¹ / ₂ " (37.5 mm)	2" (50mm)

Electronic Balances

Two 20 kg (42 lb) capacity scales with sufficient sensitivity to read to \pm 0.1 grams. For the AASHTO T 209 - mass determination in water method, one of the balances shall be equipped with a suitable suspension apparatus and holder to permit weighing the sample while suspended from the center of the scale plan or balance.

Brand Name	Туре	Last Calibration Date

Page 5 of 6

EQUIPMENT (Continued):

Workbench: Adequate in size			
Sampling table (minimum dimensions: 36 in. x 36 in. (914 mm x 914 mm))			
Sampling Platform or Catwalk			
	Step access and railing		
	Located a safe distance from the plant and a maximum of 75 ft (25 m) from the laboratory entrance. The platform must be as close to the laboratory as traffic patterns allow.		
	Located so that plant traffic flow is not impeded.		
	Height of platform is adequate to sample any size vehicle.		
	Platform permanently anchored.		
	Sampling platform structure: no visible weak or rotted materials.		
	General Condition: Acceptable Unacceptable		
	Sufficient lighting for night work. Describe:		

Page **6** of **6**
STATE OF CONNECTICUT **DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING** MAT-407 (REV 12-16) PLANT AND LABORATORY DEFICIENCY REPORT

Producer:	Location:	
Inspector:	Date:	
On the above date,	, the following deficiencies were found	in your Plant/Laboratory.
Item	Deficiency	Correction/Response
_1)		
2)		
3)		
4)		
5)		
6)		
7)		
8)		
9)		

Please make the necessary corrections before the first day of production and email responses to the following email address: <u>DOT.Materials-HMA@ct.gov</u>.

Failure to correct the indicated deficiencies may result in loss of State approval.

10)

QA VERIFICATION FORM FORM MAT-408

STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING AND CONSTRUCTION DIVISION OF MATERIALS TESTING

Project #:						Vendor #			
Project Date						Plant Location			
Mix Size				Level:					<u> </u>
Tech ID				QA DAT	A		QC E	DATA	
				Mi	xture Mass:		Mi	xture Mass:	
				Aggre	egate Mass:		Aggre	egate Mass:	
		Tol ±	JMF		Mass loss:			Mass loss:	
Pb by extra	ction	0.4		Pb b	y extraction		Pb b	y extraction	
Pb by ignition	oven	0.4		P	o by ignition	% 4.00	P		% ^
mm	in		IME	nassing	nassing	nassing	nassing	nassing	nassing
0.075	#200	2	UIVII	passing	passing	passing	passing	passing	passing
0.075	#200	2							
0.150	#100	2							
0.300	#30	3							
0.600	#30	4							
1.18	#16	4							
2.36	#8	6							
4.75	#4	6							
9.5	3/8"	6							
12.5	1/2"	6							
19.0	3/4"	6							
25.0	1"	6							
37.5	1- 1/2"	6							
50.0	2"	6							
	Total								
Gr	nb		Mold			Average			Average
(1) Specimen mass in a	air								
(2) Saturated Spec. ma	ss in air								
(3) Mass of speciment i	n water								
(4) Volume of specimer	n (2-3)	-							
Gmb @ Nmax (1/	(4)	0.040							
Gn	nm		Bowl			Average			Average
(A) Mass of HMA plus b	bowl								
(B) Mass of bowl in air									
(C) Mass of HMA in air	(A-B)								
(D) Mass of HMA plus b	oowl in water								
(E) Mass of bowl in wat	er								
(F) Mass of HMA in wat	ter (D-E)								
(G) Volume of HMA (C-	F)	1							
Gmm (C/	G)	0.030							

S:\MT Manual\FORM-MAT-408 QA Verification

State of Connecticut Department of Transportation Division of Materials Testing MAT-412cm revision 12/16

Project Number:					Materi	al Code:		Curb	Mix		Production Date:		
Vendor Number:					Mix Time	(Dry-Wet):					Contract:		
Plant:					Technician I	Name(Print):					Departure Tonnage:		
Location:					Test Date			Test	Date		Test	Date	
Mix Size:	9.	.5 mm 50 gy	rations		Test	Time		Test	Time		Test	Time	
Percent RAP:					Load N	lumber		Load N	umber		Load N	lumber	
Rap AC:		Total AC	AC F	Range	Truck	Temp.		Truck	Temp.		Truck	Temp.	
Production AC:			6.5	- 0.4	Sublot	Number		Sublot I	Number		Sublot	Number	
Input o	only one value f	for each test belo	w (Oven).		Plant / Sil	o Number		Plant / Sil	o Number		Plant / Si	o Number	
Correctio	on Factor / Igni	tion Oven Ticket	Informatio	on	Mixture Ma	ass on Ticket		Mixture Ma	ss on Ticket		Mixture Ma	ass on Ticket	
Test	Co	rrection Factor		Oven ID	Wt.	Loss		Wt.	Loss		Wt.	Loss	
Test 1					% I	oss		% L	oss		% I	oss	
Test 2					Temp	Comp		Temp	Comp		Temp	Comp	
Test 3					Mix M	oisture		Mix M	oisture		Mix M	oisture	
D.O.T. INSPEC	TORS ENTER	YOUR NAME	IN THE	CELLS TO	Pb by Ign	ition oven		Pb by Igni	tion oven		Pb by Ign	ition oven	
TH	IE RIGHT PEI	R TEST WITNE	SSED										
		Produ	uction										
Inch	mm	Tole	rance	JMF	Sieve	Passing	Cumm. Passing	Sieve	Passing	Cumm. Passing	Sieve	Passing	Cumm.
	ME Bindor (Content			weights			weights			weights		rassing
#200	0 075	201112111	0										
#200	0.075	2	.0										
#100	0.130		4										
#30	0.500												
#16	1 18		,										
#8	2 36		6										
#4	4 75		. 7										
3/8"	95		, 8										
1/2"	12.5		•										
3/4"	19.0												
			Tota	al Wt.									
Temperature / W	'eather			١٢	IF DATE / No	otes						1	
· · ·	Binder			Aggr	egate	1"/Other	1/2"	3/8"	RAP	Sand #1	Sand #2	Sand #3/Other	Virgin Binder
Binder Grade				So	urce								2
Binder Source	JMF C		JMF Col	d Feed %									
Antistrip Source				Plant Cold	Feed Setting								
Antistrip %	G Cold Feed S		Cold Feed Se	etting to 100%								N/A	
	WMA Techn	nology			Aggr	egate	Bin 5/Other	Bin 4	Bin 3	Bin 2	Bin 1	RAP	Virgin Binder
Technology				Only for	JMF Ho	ot Bin %							
Name				Plants	Plant Hot I	Bin Settings							
Rate (%)					Hot Bin Sett	ings to 100A	88						N/A

Project Num							Г				1	ite:	
Vendor Numl Th	nis Form h	<mark>as a revis</mark>	ion pe	nding									
Plant / Locati			- The second sec	_								onnage	
Fating													
Estima													
													-
Percent RA													
Corrected Rap												ket	
Virgin Pb:	in a star (Igniti	an Ovan Tickat Infa	rmation		Fut Maight Af	han Taat	-	Fut Mainht Aft	or Test		Fut Maight A		
Corr	ection Factor / igniti	on Oven Ticket Inid	ormation		Ext. Weight An	ter Test		Ext. weight Aft	er lest		Ext. Weight Af	terTest	
Test	Co	prrection Factor		Oven ID	Temp Comp			Temp Comp			Temp Comp		
Test 1					Mix Moisture (T 329)		Mix Moisture (T 329)		Mix Moisture	(T 329)	
Test 2					Pb by AASHTO	T 308		Pb by AASHTO	т 308		Pb by AASHTO) T 308	
Test 3					Pb from Plant/	Truck Ticket		Pb from Plant/	Truck Ticket		Pb from Plant/	/Truck Ticket	
D.O.T. INSPECTOR	S ENTER YOUR NAM	ME IN THE CELLS TO	THE RIGHT	PER TEST	Pb Difference		l	Pb Difference		L	Pb Difference		L
lash	vviii	Control	Prod Range	JMF		1	Cumm.			Cumm.			Cumm.
-		Points	for +Adj	Target	Sieve Weights	Passing	Passing (AASHTO	Sieve Weights	Passing	Passing (AASHTO	Sieve Weights	Passing	Passing (AASHTO
#200	0.075					-	T 30)			T 30)		<u> </u>	T 30)
#200	0.150											<u> </u>	<u> </u>
#50	0.300												
#30	0.600												
#16	1.18												
#8	2.36												┼───┤
#4	4.75												
1/2"	12.5										-		
3/4"	19.0												
1"	25.0												
1 1/2"	37.5												
2"	50.0		Tata	1 \ A/+									
			lota	i vvt.			1			1	<u> </u>		T
JMF Date:			P V	ba FA						-		<u> </u>	
JMF Gsb:			G	ise									
JMF Pba:			Info only: VMA(Pb ticket, Est Gsb 1 Gse)									
	Specimer	n mass in air		,									
	Saturated speci	men mass in air (I)						-					
	Less mass of spe	ecimen in water (J)								-			
	Gmb @ Ndes	(AASHTO T 166)								-		<u> </u>	
	Mass of HMA p	lus bowl in air (A)											
	Less mass	of bowl in air								1			
	Mass of	HMA in air					1			1			
	Mass of HMA p	lus bowl in water					-						1
	Less mass of H	MA in water					1			1		<u> </u>	-
	Volum	e of HMA					1			1			1
Gmm (AASHTO T 209)		JMF Gmm	0.030										
Va (100-(Gmb @ Nde	s / Gmm)*100))		1.0	4.0									
VMA (AASHTO R 35)			1.0				ļ						
VMA from calculated	Gsb / INFORMATION		Gse-(U.8/0.6)*(J From Gsb(F	=0.6 / F=0.8)		}						<u> </u>	├────
HEIGHT (Hi) @ Nin	ii l			-,									
Density to Nini										1			
HEIGHT(Hd) @ Nd	es				<u> </u>	l	ļ	l	I		I		
Temperature / Weath	er			ML	IF Changes / No	otes	4 /2"	2 /0"		Ce	C1 ***	Sand	Mineir D'
Binder Grade	Binder			Agg	ource	1 /Other	1/2"	3/8"	KAP	sano #1	sano #2	#3/Other	virgin Binder
Binder Source				JMF Co	old Feed %								
Antistrip Source				Plant Cold	Feed Setting								
Antistrip %				Cold Feed S	etting to 100%								N/A
Technology	WMA Technol	ogy		Only for	Aggre	egate	Bin 5/Other	Bin 4	Bin 3	Bin 2	Bin 1	RAP	Virgin Binder
Name				Batch	JIVIE HO Plant Hot P	Sin Settings							
Rate (%)				Plants	Hot Bin Sett	A89 100%							N/A
•													

State of Connecticut Department of Transportation MAT-412s_ppt revision 2/15 VIP and Construction 2009 and up

Ducient Number				I			I					
Project Number	This For	n has a re	vision	pendin	a						-	
Vendor Number		in flao a ro	, loioin	portain	.9							
Plant												
Location												
Mix Size:	-											
Percent RAP											-	
Percent IGAT.											-	
Rap AC	-										-	
Production AC											-	
Input o											-	
Correction	1											
lest	Ov	en		Wt	Loss		Wt.	Loss		Wt.	LOSS	
Test 1				%	Loss		% L	OSS		% L	.OSS	
Test 2				Temp	Comp		Temp	Comp		Temp	Comp	
Test 3				Mix N	loisture		Mix Mo	oisture		Mix M	oisture	
D.O.T INSPECT	ORS ENTER YOU	R NAME IN THE O	CELLS TO	Pb by Ign	ition oven		Pb by Igni	tion oven		Pb by Igni	ition oven	
ТН	E RIGHT PER TES	T WITNESSED										
			JMF									
Inch	mm	Control Points	Informati on Only	Sieve Weights	Passing	Passing	Sieve Weights	Passing	Passing	Sieve Weights	Passing	Passing
#200	0.075											
#100	0.150											
#50	0.300											
#30	0.600											
#16	1.18											
#8	2.36											
#4	4.75											
3/8"	9.5											
1/2"	12.5											
3/4"	19.0											
1"	25.0											
1 1/2"	37.5						-					
2"	50.0											
		l ota	al Wt.									
JIVIF Pba:	Creative an area	JMF Gsa:			JI	AF Gsb:			JMF G	se:		
	Specimen mas	s III dll										
	ess mass of speciment	n in water (1)										
	Volume of specifie	men (I-I)										
	Gmb @ Nmax (AAS	HTO T 166)										
	Mass of HMA plus b	owlin air (A)										
	Less mass of ho	wlin air										
	Mass of HMA	in air										
	Mass of HMA nlus h	owl in water										
	Less mass of how	l in water										
	Mass of HMA in	n water										
	Volume of H	IMA										
Gmm (AASHTO	Т 209)	0.030										
Va (100-(Gmb @ Ndes	(Gmm)*100))	1.0	4.0									
VMA (AASHTO F	R 35)	1.0										
VFA (AASHTO R	35)											
DUST/ASPHALT	=(-0.075mm/Pbe	e) 0.3	0.9									
Gse												
HEIGHT (Hi) @ N	Vini						-					
HEIGHT(Hd) @ I	Ndes											
HEIGHT(Hm) @	Nmax											
DENSITY @ Nini		Max.	06.0									
DENSITY @ Nde	5	1.0	96.0									
DENSITY @ Nma	X	iviax.	98.0			Dia 4	pt- c	pia ĉ	D1- 4	Other St	845	D'l-
				Hot Bin Pul	ls From Plant	BIN 4	BIN 3	BIN 2	BIN 1	Other Bin	КАР	ыnaer
Temn / Weather					%	Sand # 1 %		Sand #2 %		Sand #2 %		
Binder Grade			ology	Cold Face	Dulle Fre	1/2"	3/8"	Sand #1	Sand #2	Other Aga	RAP	Binder
Binder Source		Name	JUGSY	Pla	nt %	-/-	5/0		Sana #2			211001
Antistrin (%)		Rate (%		Aggregat	es Sources	C^			FA			
And strip (//)		nate (/0				5			14			

State of Connecticut Department of Transportation Division of Materials Testing MAT-412ut revision 06/13

Project Number:					Materi	al Code:	Ultra-	Thin Bond	ed HMA	Туре В	Production Date:		
Vendor Number:					Mix Time	(Dry-Wet):					Cont	ract:	
Plant:					Technician I	Name(Print):					Departure	Tonnage:	
Location:					Test Date			Test	Date		Test	Date	
Mix Size:	9.5 mm		Test	Time		Test	Time		Test	Time			
Percent RAP:					Load N	lumber		Load N	umber		Load N	Load Number	
Rap AC:		Total	AC AC R	lange	Truck	Temp.		Truck	Temp.		Truck	Temp.	
Production AC:			4.8	- 5.4	Sublot	Number		Sublot N	Number		Sublot	Number	
Input o	only one value f	for each te	est below (Oven).		Plant / Sil	lo Number		Plant / Sile	o Number		Plant / Sil	o Number	
Correctio	on Factor / Igni	tion Oven	Ticket Informatio	n	Mixture Ma	ass on Ticket		Mixture Ma	ss on Ticket		Mixture Ma	iss on Ticket	
Test	Co	rrection F	actor	Oven ID	Wt.	Loss		Wt.	Loss		Wt.	Loss	
Test 1					% I	Loss		% L	oss		% I	oss	
Test 2					Temp	Comp		Temp	Comp		Temp	Comp	
Test 3					Mix M	oisture		Mix Mo	oisture		Mix M	oisture	
D.O.T. INSPEC	TORS ENTER	YOUR	NAME IN THE O	CELLS TO	Pb by Ign	ition oven		Pb by Igni	tion oven		Pb by Ign	ition oven	
TH	HE RIGHT PEI	R TEST V	VITNESSED										
Inch	mm		Production Tolerance	JMF	Sieve Weights	Passing	Cumm. Passing	Sieve Weights	Passing	Cumm. Passing	Sieve Weights	Passing	Cumm. Passing
#200	0.075												
#100	0.150)											
#50	0.300)											
#30	0.600)											
#16	1.18												
#8	2.36												
#4	4.75												
1/4"	6.3												
3/8"	9.5												
1/2"	12.5												
3/4"	19.0												
		·	Tota	l Wt.									
Temperature / W	/eather			٦V	1F DATE / No	otes							
	Binder Agg		Aggr	egate	1"/Other	1/2"	3/8"	RAP	Sand #1	Sand #2	Sand #3/Other	Virgin Binder	
Binder Grade	S		So	urce									
Binder Source	JMF Co		d Feed %										
Antistrip Source	Plant Cold		Plant Cold	Feed Setting									
Antistrip %	Cold Feed Se		etting to 100%								N/A		
	WMA Techn	nology		<u>.</u>	Aggr	egate	Bin 5/Other	Bin 4	Bin 3	Bin 2	Bin 1	RAP	Virgin Binder
Technology				Only for	JMF Ho	ot Bin %							
Name				Plants	Plant Hot I	Bin Settings							
Rate (%)					Hot Bin Sett	ings to 10 04	91						N/A





MAT- 417 Worksheet : Random Lot Selection at Plant

RANDOM LOCATIONS BY ASTM D-3665

Immediately after the random numbers are generated, email this file to: DOT.Materials-HMA@ct.gov

Project Number:	
Vendor Number:	
Plant:	
Location:	
Lot Number:	
Material Code:	
Mix Size:	

Estimated Total Tonnage		Average Tonnage per Truck	
-------------------------	--	---------------------------	--

Production Day #	1	2	3	4	5	6	7
Date							
Actual Daily Tonnage in Lot							
Cumm. Tonnage in Lot	0						

Sublat#	Random #	Sublot		Load	Number on	Date	
Sub Lot #		Tonnage					
	0.000						
	0.000						
	0.000						
	0.000						
	0.000						
	0.000						
	0.000						

Table 1. Random Numbers Working Table

State of Connecticut Department of Transportation Division of Materials Testing - Job Mix Formula Verification Form MAT-418

Mix

Plant Information

Vendor Number:	
Plant:	
Location:	

Aggregate Properties

	JMF Target	DMT Result	Difference	Tolerance
0.075				1.0
0.15				3
0.3				3
0.6				4
1.18				4
2.36				5
4.75				5
9.5				5
12.5				4
19				4
Gsb				0.028
Gsa				0.025
SE				15
FAA				0.8

Mix Properties

Binder Content (%)

	JMF Target	DMT Result	Difference	Tolerance
Gmb				0.020
Gmm				0.022
Va				1.3
VMA				1.3
VFA				6.0
Pba				0.6
Factor				NA
Dust/Pbe				NA
Density to Nini				1.5
Gse				0.025

MAT-419 (REV 2-15) Checklist: QC Plan for FA (Reference M.04.01-2) Page 1 of 7

1. Basic Information		
	A. Origin of Materials	
1. Name and address of property owner or lessee.		
Name		
Address		

2. Name, title, and telephone number of company contact person.	
Name	
Title	
Telephone number	
-	

3. Name, title, telepho QCPFA.	one number and certifications, if applicable, of the person(s) responsible for the
Name	
Title	
Telephone number	
Certifications	
Name	
Title	
Telephone number	
Certifications	

MAT-419 (REV 2-15) Checklist: QC Plan for FA (Reference M.04.01-2) Page 2 of 7

2. Controls Implemented During Excavation	
	A. Overburden Removal
1. To what dept	th is the overburden removed?
Depth	

2. What is the r	ninimum separation between the edge of overburden and the production face?
Separation	

3. How will slo	ughed overburden be avoided?
Method of	
Avoidance	

	B. Mining Controls
1. Describe how excavation will be performed so that intended materials are being mined.	
Description	

2. Who will make the determination?	
Name	
Title	
Telephone number	
Certifications	

MAT-419 (REV 2-15) Checklist: QC Plan for FA (Reference M.04.01-2) Page 3 of 7

2. Controls Implemented During Excavation (continued)		
	B. Mining Controls (cont.)	
3. How will cle	an-out materials from old ramps, overlying lifts, striping or floor leveling be handled?	
Description		

4. What tests are being utilized to verify that intended materials are being mined?		
Description		

5. How will it be assured that your material meets all specifications as required by the latest ConnDOT		
M.04 criteria	M.04 criteria before it is shipped?	
Description		

C. Product Uniformity Controls	
thod of loading out shot rock or sand & gravel from a face to minimize non-uniformity?	

MAT-419 (REV 2-15) Checklist: QC Plan for FA (Reference M.04.01-2) Page 4 of 7

	2. Controls Implemented During Excavation (continued)
	C. Product Uniformity Controls (cont.)
2. Describe any	other procedure(s) used to minimize non-uniformity?
Description	

	3. Processing Controls
	A. Type of processing
1. Describe the	type of processing being done on the material.
Description	

2. Describe the	type of equipment used during processing.
Description	

3. Describe how non-uniformity will be minimized during aggregate processing.	
Description	
<u>L</u>	1

4. Describe how	v aggregate quality will be improved by processing.
Description	

MAT-419 (REV 2-15) Checklist: QC Plan for FA (Reference M.04.01-2) Page 5 of 7

4. Stockpiling	
A. Stockpiles	
1. Describ	be the height and width of stockpile.
Height	
Width	

2. Describe the method by which the stockpile is created (by haul unit, belt system etc.).	
Description	

3. Describe how non-uniformity will be minimized in the stockpiles.	
Description	

4. Describe how contamination will be minimized in the stockpiles.	
Description	

MAT-419 (REV 2-15) Checklist: QC Plan for FA (Reference M.04.01-2) Page 6 of 7

4. Stockpiling (continued)	
	A. Stockpiles (cont.)
5. Describe how	v the stockpiles will be monitored for non-uniformity and contamination.
(Ho	wwwill non-uniformity and contamination be visually monitored and by who?)
Description	
Who will be	
monitoring?	
1	

6. What physica	al tests will be employed to monitor quality of fine aggregate?
Description	

7. What is the n	ninimum testing frequency?
Description	

8. Who will do	the test?
Description	

MAT-419 (REV 2-15) Checklist: QC Plan for FA (Reference M.04.01-2) Page 7 of 7

Quality Control Plan for Fine Aggregates (QCPFA) used in HMA

4. Stockpiling (continued)								
A. Stockpiles (cont.)								
9. What actions will be taken when the material does not meet the requirements?								
Description								

5. Records								
A. Method								
1. What quality monitoring records are maintained?								
Description								

2. Where are the quality monitoring records maintained?								
Description								

3. Who is responsible	e for maintaining these records?
Name	
Title	
Telephone number	
Name	
Title	
Telephone number	

Please submit to the DMT via e-mail at <u>DOT.MatTesting@ct.gov</u>.

State of Connecticut Department of Transportation Division of Materials Testing

MAT - 429cm

Plant											
Location											
Plant Type/Capacity						м	X #		Cur	h Miy	
Submitted By									Cui		
Date Submitted											
Description		Size/T	Type of Agg	regate	Source o	of Supply		Source	Location		Blend Percent
CA-Aggregate 1											
CA-Aggregate 2											
CA-Aggregate 3											
CA/RAP-Aggregate 4											
FA-Aggregate 5											
FA-Aggregate 6											
FA-Aggregate 7		6		1.1.1					. .		
Description	1	Source	of Supply	Labo	ratory lem	perature Ra	anges	Production	n Temperatu	ire Ranges	
Asphalt Binder Grade				Mfg recom	mended mix	temp range		Mfg recom	imended mix t	emp range	
Antistrip Percentage	<u> </u>	M/ator i	niact rate no	Mfg recomm	n compaction	temp range	to por woig	Mfg recom	n compaction	temp range	al weight of mix
warm wix recinology		water i	nject rate pe	er weignt of t	onder or	additivera	ate per weig	nt of binder		e rate per tot	ai weight of mix
Nom. Size				Contrac	tor Data	1					
	A = = 1	4 2	1 2	0 == 0	A = = 5	A == C	A == 7	Cala	Specifi	cations	Contractor
9.5mm L1	Agg 1	Agg 2	Agg 3	Agg 4	Agg 5	Agg 6	Agg /	Calc.	Contro	l Deinte	JMF
	CA	CA	CA	CA/RAP	FA	FA	FA	JIMF	Contro	I Points	
Description								Comp.			Submitted
Blend Percent									Min %	Max %	
0.075									3.0	8.0	
0.150											
0.300									10.0	30.0	
0.600									20.0	40.0	
1.18									40.0	70.0	
2.30									40.0	70.0	
4.75									95.0	100.0	
12.5									100.0	100.0	
19.0											
25.0											
Production Virgin Pb			RA	P AC			То	tal/Targe	t AC		
Total binder in RAP						-					
Test Results			MIX	ТЕМР		COMPACT	ION TEMP			WET	
Gmm				AC Range			6.5 - 9.0		Wix Times	DRY	
Gmb - Ndes				User Notes:		-					
Gmb - Nini				-	White cells t	to be comple	ted by the Co	ontractor.			
Height-Ndes				-	Production I	Pb (w/ RAP) =	The total p	roduction bind	er in the HMA	۱.	
Height-Ndes			_	-	Contractor J	MF should re	eflect extract	ed asphalt and	d washed sieve	ed analysis.	
Height-Nini				-	List all the J	MF Changes i	n the "JMF C	Changes" sheet			
% Gmm at Nini		- Volumetric data for total asphalt co						tent.			
Gse		- Complete the % passing per each specimen up to at least the 25.0mm sieve.									
Va - Ndes				-	Add binder s	specific gravi	ty data if it d	iffers from 1.0	33.		
Ignition Oven Corr. Factor			J								
				Remarks:							

Accepted By

Date

State of Connecticut Department of Transportation Division of Materials Testing

MAT-429s rev 11/2016

Plant This For	This Form has a revision pending										
Plant Type/C											
Submitted B											
Date Submit											
Description											Percent
CA-Aggregate 1											
CA-Aggregate 2											
CA-Aggregate 3											
CA/RAP-Aggregate 4											
FA-Aggregate 5											
FA-Aggregate 6											
FA-Aggregate 7											
Description		Source of	of Supply	Tempe	erature Rang	es (Without	WMA)	Temperatu	re Ranges (V	With WMA)	
Asphalt Binder Grade				Mfg recon	nmended mix to	emp range		Mfg recom	mended mix t	emp range	
Antistrip Percentage				Mfg recom	m compaction	temp range		Mfg recom	n compaction	temp range	
Warm Mix Technology		Where W	MA Additive	is Added?	Water inject	ion or additive	e rate per wei	ght of binder	or additiv	e rate per tota	al weight of mix
Nom. Size				Contrac	tor Data						
	A	Acc. 2	Acc. 2	Acc. A	Acc. 5	Acc.C	Aca 7	Colo	Specifi	cations	Contractor
	Agg 1	Agg Z	Agg 3	Agg 4	Agg 5	Agg b	Agg 7		Cantura	Delate	JMF
	CA	CA	CA	CA/RAP	FA	FA	FA	JIMF	Contro	Points	
Description								Comp.			Submitted
Blend Percent									Min %	Max %	
0.075											
0.150											
0.300											
0.600											
1.18											
2.36											
4.75											
9.5											
12.5											
19.0											
25.0											
37.5											
50.0											
Production Virgin Pb			RAI	PAC			Tot	al/Target	: AC		
Total binder in RAP											
Gsa											
Gsb											
Test Results			MIX	TEMP		COMPACT	ION TEMP			WET	
Gmm			Minim	um AC		P	CS		IVIIX TIMES	DRY	
Gmb - Nmax				User Notes:							
Gmb - Ndes				-	White cells to	be completed	d by the Contr	actor.			
Gmb - Nini				-	Production Pt	o (w/ RAP) = TI	he total produ	iction binder ir	n the HMA.		
Height-Nmax				-	Contractor JN	1F should refle	ect extracted a	asphalt and wa	shed sieved a	nalysis.	
% Gmm at Nmax				-	List all the JM	F Changes in t	he "JMF Chan	ges" sheet.			
Height-Ndes				-	Volumetric da	ata for total as	phalt content				
Height-Nini				-	Complete the	% passing per	r each specim	en up to at lea	st the 25.0mn	n sieve.	
% Gmm at Nini				-	Add binder sp	ecific gravity	data if it differ	s from 1.033.			
Gse											
Multiplier (AASHTO R35 App. X1.2)				Remarks:							
Va - Ndes											
VMA											
VFA - Ndes											
Pba											
Pba/Pw											
Pbe				-							
Dust/Pbe											
TSR (AASHTO T283 (M))				1							
Ignition Oven Corr Sector				Acco-	tod By				P-	ato	1
ignition Oven Corr. Factor				Ассер	leu by				Da	110	
					A102						

State of Connecticut Department of Transportation Division of Materials Testing

Form-429ut rev 02-15

Plant											
Location								1.14	tra T	'hin	
Plant Type/Capacity						м	x #		ll d- I		ΠΙΫΙΑ
Submitted By						111	Λ #		Т	no R	
									• • •	pc D	
Date Submitted											
Description		Size/T	ype of Agg	regate	Source of	of Supply		Source Lo	ocation		Blend Percent
CA-Aggregate 1											
CA-Aggregate 2											
CA-Aggregate 3											
CA/RAP-Aggregate 4											
FA-Aggregate 5											
FA-Aggregate 6											
FA-Aggregate 7											
Description	[Source of	of Supply	Laboi	ratory Tem	perature Ra	anges	Production ⁻	Temperat	ure Ranges	
Asphalt Binder Grade				Mfg recom	mended mix	temp range		Mfg recomm	ended mix	temp range	
Antistrip Percentage				Mfg recomm	n compaction	temp range		Mfg recomm	compaction	temp range	
Warm Mix Technology		Water ir	nject rate pe	r weight of b	oinder or	additive ra	ate per weig	ht of binder	or additiv	ve rate per t	otal weight of mix
Nom, Size				Contra	tor Data						
Nona Size				contrat					Specif	ications	Contractor
0 5mm	Agg 1	Agg 2	Agg 3	Agg 4	Agg 5	Agg 6	Agg 7	Calc.			JMF
3.311111	CA	CA	CA	CA/RAP	FA	FA	FA	JMF	Contro	ol Points	
Description								Comp.			Submitted
Blend Percent									Min %	Max %	
0.075									4.0	7.0	
0.150									5.0	10.0	
0.500									0.0 12.0	20.0	
1 18									16.0	20.0	
2 36									21.0	32.0	
4 75									21.0	40.0	
6.5									30.0	50.0	
9.5									85.0	100.0	
12.5									100.0	100.0	
19.0											
25.0											
37.5											
50.0											
Production Virgin Pb	5.	00	RAI	P AC			Total A	C / JMF P	b Total		5.00
Total binder in RAP											
Gsa									Mix	Times	WET
Gsb									DRY		
Test Resul	ts		4	NC	4.8-5.4						
Gmm				User Notes:							
Gse				-	White cells	to be comple	ted by the c	ontractor			
Multiplier (AASHTO R35 X1.2)				-	Production	Pb (w/ RAP) =	= The total p	roduction bind	er in the HN	MA	
PDa(%)				-	Contractor J	MF should re	eflect extract	ed asphalt and	d washed si	eved analysis	5
SA (m /kg)				-	List all the Ji	VIF Changes	in the "JMF (hanges" sheet			r.
PDE (%) Tf (um)				-	In the table	on the left, p	rovide the H	MA volumetric	c data for tr	F Omm sigure	5
Draindown (%)				-	Add binder	Specific Grav	per each spe ity data if it (liffers from 1 (1992 1192	5.0mm sieve	
TSR (%)				-	, au bhiuel i	Specific OldV	ity uata II It (
Ignition Oven Corr Factor				Remarks:							
			I								
				<u>.</u>							
				Accep	ted By				D	ate	

A103

STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING IGNITION OVEN CORRECTION FACTOR SUMMARY										
REV. 12/16		IVIA	1-433							
Plant:			Location:							
State Inspector:			Date:							
Contractor's Repre	sentative:									
Ignition Oven Mak	e/Model:									
Ignition Oven ID#:										
Correction factors	are in accordance with	n AASHTO T 308.	1		Dro	wique Vo	240			
Mix	Mix Design Date	RAP (%)	Total Pb (%)	Mix Correction	Correction Factors*					
				Factor	2014	2015	2016			
4076										
4077										
4078										
4052										
4054										
4056										
4057										
4058										
4064										
4065										
4066										
Curb Mix										
Porous										
UTHMA										
RAP		100					[
Other										
* Prior to 2015, co	rrection factors were i	n accordance wit	h AASHTO T 308 (M)							

Project #	0	Day/Night	Day	Contract Year	0
Location (RT/Town)	0	PO #		Payable Tons	
Date Placed	1/0/1900	District #		Cost per ton (US\$)	
Міх	Level	Material Code	DMT ID	Min Pb	
		0			
Producer	Plant Location	Vendor #			
		0			
		Plant Adjustm	ent Detail		
Plant Test		Va Result	Va Adjustment	Pb Result	Pb Adjustment
1					
2					
3					
4					
5					
6					
AVa					
APb					
Plant Adjustment Tsd=(Ava +	- APb) X Tons		0.0000	Adjusted Tons	0.00
Cost Adjustment Tsd X Unit	Price				\$0.00
				Data entered by:	
				Checked by:	

Proj	ect #	0	Day/Night	Day	Contract Year	0
Location	(RT/Town)	0	PO #		Payable Tons	
PWL Lot Number		0	District #		Cost per ton (US\$)	
Mix	Level	Material Code	DMT ID	Producer	Plant Location	Vendor #
		0				0

Targets		4	#VALUE!									
Sublot	Production Date	AV	Pb	VMA	Lot Size	PWL (AV/Pb/	/VMA)	P (AV,	WL A /Pb/V	dj 'MA)	Production Lot PWL Adjustment
1												
2												
3												
4												
					0							
					Ű							
Average												
Standard Deviation												
Number of Results		0	0	0	Plant Adjustment Tsd= PWL Adj X Tons							
USL		5.2	#VALUE!	#VALUE!	Cost Adjustment Tsd X Unit Price							
LSL		2.8	#VALUE!	#VALUE!								
Qu												
QI												
PDu					Data entered by:							
PDI					Checked by:							

STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIAL TESTING MIX DESIGN STATUS

MAT-440 (Revised 12/16)

YEAR:

HOT MIX ASPHALT PRODUCER'S NAME AND ADDRESS

QC Plan Date

Plant Inspection Date

Laboratory Inspection Date

Ignition Oven Aggregates Correction Factor Date

МІХ	JMF DATE	STATUS	NOTES
4029 (UTHMA)			
4053			
4054			
4057			
4058			
4065			
4066			
4077			
4078			
4093			
4094			
4096			
4097			
4099			
4100			
4102			
4103			

NOTES: - Mixes in "PPT" or "U" status cannot be shipped to ConnDOT projects.

- This Form shall be posted in the plant laboratory.

- Mixes with no JMF Date have not been received for this paving season and cannot be used in ConnDOT projects.

- All the information on this Form is current to the day listed in "Date" section below.

Prepared by (print name)

Date

CONN	ECTICUT
000	
IRTIM) Es
CAVI O	TRANS?

STATE OF CONNECTICUT

Department of Transportation Division of Materials Testing 280 West Street Rocky Hill, CT 06067 Rev. 12/16

INDEPENDENT ASSURANCE

Report of WITNESS TEST MAT-600

Name (Tester):	NETTCP#:						
IA Sampled By:	Date (Witness Test):						
Location:							
Type of Material:	No.:						
AASHTO TEST METHODS WITNESSED	YES	NO	REMARKS				
T 168 – SAMPLING BITUMINOUS MIXTURES							
R 47 – SAMPLE REDUCTION							
T 308 – ASPHALT CONTENT – IGNITION OVEN							
T 30 – SIEVE ANALYSIS							
T 312 – PREPARATION OF GYRATORY SAMPLE							
T 166 – BULK SPECIFIC GRAVITY (Gmb)							
T 209 – THEORETICAL MAXIMUM (Gmm)							
T 185 – SPECIFIC GRAVITY – COARSE AGGREGATE							
T 184 – SPECIFIC GRAVITY – FINE AGGREGATE							
T 283 – MOISTURE INDUCED DAMAGE – (TSR)							
T 255 – MOISTURE CONTENT							
T 304 – UN-COMPACTED VOID CONTENT							
T 176 – SAND EQUIVALENT TEST							
BOWL WEIGHTS							
GYRATORY ANGLE							
THERMOMETER CHECK							
COMMENTS:							
WAS A SPLIT SAMPLE TAKEN YES NO SAMPLE NO.:							
SAMPLE GRADE: Pb: Sieve:	G	mb:	Gmm:				
Enter Start and End times for time from and to work station a	Total Shift Hours						
Start: End:	Start: End: End:						
			Total Overtime				
Enter Start and End times for actual time at the plant.			Hours:				
Start: End:			Vacation / Sick / PL:				

Appendix B – Final Materials Certification

A Final Materials Certificate (FMC) summarizes the results of acceptance testing of the material used on each FHWA-funded project and select state-funded projects. Materials used on these projects that require acceptance testing must be sampled and tested in accordance with the "Schedule of Minimum Requirements for Acceptance Testing," Chapter 8 of this manual. It is imperative that the represented quantity of each material with a sampling frequency of "one per quantity" or "one per x units" accumulate to or exceed the total quantity of that material used on the project. For some materials the minimum schedule does not indicate a testing frequency. In this instance, a single sample will be adequate to represent that material incorporated into the project.

In addition, the Division of Materials Testing (DMT) documents the process of materials testing on the project site by checking the sampling and testing procedures performed by inspection personnel in accordance with the "Schedule of Minimum Requirements for Assurance Testing," Chapter 9 of this manual. Testing equipment is also checked to ensure that the test results are valid. Discrepancies in this testing are investigated and rectified immediately. The DMT reports the results of this testing to the Federal Highway Administration on an annual basis.

To initiate the development of a FMC, a request from the appropriate District office staff for a FMC is sent to the DMT. Following a review of project records, DMT staff issue a memorandum to the project personnel entitled "Test Coverage Required for FINAL CERTIFICATION" that lists all testing deficiencies and rejected materials not previously documented.

It is the responsibility of the Transportation Supervising Engineers of each DMT section to identify material that did not meet the project specifications, was not documented correctly, and was permanently incorporated into the project. This is accomplished through the issuance of a FMC listing exceptions to the specifications. When all materials used on the project are sampled and found to meet the specification or are documented properly, the DMT issues a FMC without exceptions.

When tested material does not meet specification, a MAT-103 "Report of Rejected Material" form is used to document how the deficiency was addressed. This form must be completed for any rejected material samples and must include the signatures of appropriate Project and District personnel acknowledging the rejection.

Section 1 of the Mat-103 form under the heading "Action Taken" describes the physical action taken to retest or replace the material. This addresses when rejected materials were removed and replaced with acceptable material or were resampled and found acceptable. The Sample ID of the acceptable re-test is required on this form. If physical action was not taken, Section 2 of the MAT-103 must be completed.

Section 2 of the Mat-103 form under the heading "Acceptance of Rejected Material without Action" documents the acceptance of noncompliant materials or minor quantities

of untested materials in accordance with Section 1.06.02 or Section 1.06.04 of the Department's Standard Specification. Section 1.06.02 states that the Engineer may accept material or combination of materials and thereby waive noncomplying test results, provided that the following conditions are met:

- 1. Results of prior and subsequent series of tests of the material or materials from the same source or sources are found satisfactory.
- 2. The incidence and degree of nonconformance with the Contract requirements are, in the Engineer's judgment, within reasonable limits.
- 3. The contractor, in the Engineer's judgment, had diligently exercised material controls consistent with good practices.
- 4. No adverse affect on the value or serviceability of the completed work could result.

Section 1.06.04 states that the Engineer may accept a material or combination of materials provided that an equitable reduction of the payment is made. Any credits, allowances, warranties, or other conditions of acceptance must be listed.

Projects that did not perform any testing would obviously not meet the above criteria, while a project that utilized minor amounts of nonconforming material from a producer who generally meets requirements may meet the above criteria. Exception can be taken and noted on the FMC if it is determined by DMT staff and the Transportation Principal Engineer in the DMT that the alternate acceptance criteria has not been met for the materials in question.

Adequate Assurance Testing: Project related assurance testing is required as specified in the Schedule of Minimum Requirements for Assurance Testing (Chapter 9) or exceptions for deficiencies in assurance testing will be noted on the FMC as such. This testing does not include independent assurance testing that is performed within the DMT and is not directly associated with a project.

For projects classified as vertical or non-roadway: In accordance with section 1-2207 of the Construction Manual, "A FMC will not be provided by the DMT for facilities (vertical/non-roadway) projects; this information will be retained by the DMT for information only purposes."

Examples of Final Materials Certificates follow.

(THE FOLLOWING MEMORANDUM IS ADDRESSED TO THE DISTRICT ENGINEER AND IS REQUIRED FOR ALL FEDERAL AID PROJECTS.)

	STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION	subject:	FINAL MATERIALS CERTIFICATION STATE PROJECT NUMBER: [XXXX-XXXX] FAP NUMBER: [XXXX (XXX)]
	m e m o r a n d u m	date:	[Month, Day, Year]
0:	[Name] District Engineer District [X] Construction Bureau of Engineering and Construction	from:	[Name] Transportation Principal Engineer Division of Materials Testing Bureau of Engineering and Construction

THIS IS TO CERTIFY THAT:

t

Results of tests on acceptance samples indicate the materials incorporated in the construction work and the construction operations controlled by sampling and testing were in conformity with approved plans and specifications, and that such results compare favorably with the results of independent assurance sampling and testing.

Exceptions to the plans and specifications are documented in the project records and are also listed below:

NONE (or exceptions included as follows:)

Item # Description Quantity Reason

If you have any questions regarding this certification, please contact [Name], Transportation Supervising Engineer, at (860) 258-[XXXX] or [Email address].

[Author]:[Typist]/[Drive location/file name]

cc: [Name of Construction Division Chief]
[Name of Federal Billing Representatives]
[Name of Assistant District Engineer]
[Name of District OOC Liaison]
[DMT Representatives]
[DMT Author] - DMT Files
DOT FedBilling
DOT ConstD[#]

(THE FOLLOWING MEMORANDUM IS ADDRESSED TO THE DISTRICT MAINTENANCE DIRECTOR AND IS REQUIRED FOR ALL MAINTENANCE PROJECTS FUNDED WITH FEDERAL AID FUNDS.)

STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION	subject:	FINAL MATERIALS CERTIFICATION STATE PROJECT NUMBER: [XXXX-XXXX] FAP NUMBER: [XXXX (XXX)]
m e m o r a n d u m	date:	[Month, Day, Year]
0: [Name] Transportation Maintenance Director District [X] Maintenance Bureau of Engineering and Construction	from:	[Name] Transportation Principal Engineer Division of Materials Testing Bureau of Engineering and Construction

THIS IS TO CERTIFY THAT:

Results of tests on acceptance samples indicate the materials incorporated in the construction work and the construction operations controlled by sampling and testing were in conformity with approved plans and specifications, and that such results compare favorably with the results of independent assurance sampling and testing.

Exceptions to the plans and specifications are documented in the project records and are also listed below:

NONE (or exceptions included as follows:)

<u>Item # Description Quantity Reason</u>

If you have any questions regarding this certification, please contact [Name], Transportation Supervising Engineer, at (860) 258-[XXXX] or [Email address].

[Author]:[Typist]/[Drive location/file name]

cc: [Name of Construction Division Chief]
[Name of Federal Billing Representatives]
[Name of District OOC Liaison]
[DMT Representatives]
[DMT Author] - DMT Files
DOT FedBilling
DOT ConstD[#]

APPENDIX C SCOPE OF WORK FABRICATION INSPECTION For third-party testing agency

As determined by the Connecticut Department of Transportation's (Department) Division Chief, the testing agency shall provide qualified inspection and testing personnel to perform inspections, sampling, and testing of materials in the following areas:

- General Requirements
- Steel Fabrication Scope
- Structural Steel Inspection General
- Coatings Process Inspection
- Precast, Prestressed and Post- Tensioned Concrete Inspection

All inspections, sampling, and testing are to be done in accordance with applicable standards including, but not limited to, those described by the American Welding Society (AWS), National Association of Corrosion Engineers (NACE), American Association of State Highway Transportation Officials (AASHTO), and the American Society of Testing Materials (ASTM).

Personnel performing the inspection, sampling, or testing of specific materials may require certification that is administered by agencies such as the New England Transportation Technician Certification Program (NETTCP), American Concrete Institute (ACI), and others.

The purpose of this inspection, sampling, or testing is to assure conformance of the material to project specifications. As such, the Quality Assurance (QA) inspector may visually inspect, witness, sample, or test material during all phases of manufacture/fabrication/production. The primary function of the QA inspector is to assure the Engineer that the fabricator/producer is exercising adequate quality control during the entire fabrication/production process.

General Requirements

The testing agency shall:

1. Assume responsibility for the assigned inspection, sampling, or testing of materials as of the date stipulated by the Department in the formal notice to the testing agency to proceed with the work. This includes any partially completed work performed by the Department's former testing agency under the "Contract for Inspection, Sampling and Testing of Materials" concluded February 14, 2016.

- 2. Make no decisions and offer no advice or opinion to a proposed action by the manufacturer/fabricator/producer/contractor without first consulting with the Engineer. The Engineer is defined as the Division Chief or his duly authorized representative.
- 3. Provide all equipment required for the safe and comprehensive execution of the work including personal safety equipment such as clothing, hard hats, safety glasses, shoes, and gloves. This may also include appropriate means of transportation for some job classifications. All such equipment may be subject to the approval of the Engineer.
- 4. Adhere to the Travel Expense Guidelines dated April 19, 2016 for the purpose of determining travel expenses and work locations.

The Inspector shall:

1. Be certified in the applicable field and have a thorough knowledge of the State of Connecticut - Department of Transportation - Standard Specifications for Roads, Bridges and Incidental Construction (Form 816 as supplemented), and project specifications, including approved shop drawings.

Specific information on scope of work, personnel, and reporting requirements for each area are provided in the following pages.

Steel Fabrication - Scope

The testing agency shall submit to the Department of Transportation, Division of Materials Testing, 280 West Street, Rocky Hill, CT 06067, three copies of daily reports on a weekly basis, or as directed, for each Department project where inspection services were performed indicating the status of each member in fabrication and the shipping status of each completed member. Report cover sheets and the body of the reports must be generated with a word processing computer application and output on 8.5" X 11" white paper. Handwritten reports will not be accepted. The reports shall include daily notes of the testing agency's plant inspector and any nondestructive testing reports and shipping documents that were obtained during the day. These reports shall further include a daily summary of the number of hours worked. Weekly reports shall be due at the Department of Transportation's Division of Materials Testing (DMT) no later than seven days after the close of the period covered by such reports. The final weekly report submitted for a single project shall include all certified mill test reports documenting all steel used in the project work.

Due to their critical function as load-bearing units of bridges and structures, structural steel members must be constructed in strict conformance with the specifications. To assure this conformance, the DMT assigns a QA inspector to the manufacturing/fabrication plant to inspect, in detail, all phases of manufacture/fabrication. The primary function of the QA inspector is to assure the Engineer that the fabricator is exercising adequate quality control during the entire fabrication process. Should the inspector discover deficiencies or witness a lack of quality control, it is imperative that the Engineer be notified immediately so that corrective action can be initiated.

These specifications are not to be considered as covering every aspect of the testing agency's responsibilities, and they shall in no way relieve the testing agency of the responsibility for the inspection of all requirements of the plans, specifications, and special provisions that are pertinent to the work.

Structural Steel Inspection - General

The inspector shall:

- 1. Commence inspection with the beginning of fabrication and continue throughout the entire fabrication process, or as directed by the Engineer.
- 2. Throughout the fabrication, document information on standardized forms provided by the Engineer or on an acceptable substitution to the Engineer. All such documentation shall be neat and legible to the satisfaction of the Engineer.
- 3. Confirm that the proper approval has been granted for all shop drawings used during fabrication/manufacture. This should be accomplished before fabrication; however, it may be done during or after fabrication. Should the fabricator decide to commence, continue, or deliver work without proper approval; the inspector is required to immediately notify the fabricator's Quality Control (QC) Manager that the fabricator is proceeding at his own risk, and notify the Engineer that work began, is ongoing, or is being shipped without approved drawings. Inspector must note names, times, and summary of the discussion in his daily report.
- 4. Be cognizant of the conditions of fabrication including the time of delivery, desired order of shipment, and any special features in connection with delivery.
- 5. Obtain the records of the chemical and physical tests of the heat numbers of material from the mill. Review mill test reports for conformance to specifications and report status to the Engineer through daily reports.

- 6. Compare heat marks with those on the mill test reports. Should there be any doubt about the identity of correctness of the metal, samples of the metal may be taken and tested by the fabricator to ascertain conformance with the appropriate specifications.
- 7. See that material is properly identified throughout the entire fabrication process.
- 8. Conduct a surface inspection of a sample of incoming metals with attention to defects such as piping, cracks, laminations, buckles and kinks.
- 9. Observe that material not immediately used is properly stored and identified.
- 10. Ensure that no material from shop stock is used without approval or without properly documented test reports. Pitted or corroded material shall not be used.
- 11. Document the position of heat numbers in main members by means of diagrams showing member elevations and associated heat numbers.
- 12. Check a sample of cuts for neatness and trueness, and ensure that the proper method of cutting is used.
- 13. Inspect a sample of templates for accuracy.
- 14. Check a sample of splices, joints, and connections in accordance with appropriate specifications.
- 15. Check the fit and positioning of a sample of shop assemblies, and ensure that members are clearly match-marked when members that are to be field-spliced are given a shop laydown assembly.
- 16. Be present when material is being cambered or straightened by the application of heat to ensure use of proper procedures and temperature requirements. Confirm that only approved methods are being utilized.
- 17. Inspect a sample of completed work for general finish and workmanship. Check a sample of finished members for dimensions, proper section, connection locations, detailing and other related features. Measure and record on approved forms the overall length, length center-to-center of bearings, and camber of a sample of main members.

- 18. Check that surfaces of "weathering" steel and surface areas to receive protective coatings are properly prepared and that coatings are applied in accordance with specifications. The coating dates of all material shall be recorded in the daily report.
- 19. Ascertain that all welders, welding operators, and tackers have been properly qualified and that welding procedures have been properly followed. Copies of welder certifications and approved welding procedures shall be incorporated into the project records. Actual welding should be inspected regularly to ensure that the minimum temperature requirements for welding are being maintained, that the specified joint-welding procedures are being followed, and that the required preheat, interpass and postheat temperatures are being utilized.
- 20. Witness all nondestructive testing of welds and sign all reports of such testing. Ultrasonic inspection shall be witnessed and the interpretation of the results verified by the testing agency personnel, who shall be qualified NDT Level II or better in accordance with requirements of the American Society for Nondestructive Testing's Recommended Practice Number SNT-TC-1A and Supplement C, Ultrasonic Testing Method.
- 21. Check to ensure use of proper electrodes, electrode-flux combination, or grade of weld metal for the steel specified. Review materials certification for electrodes or electrode-flux combinations. Regularly inspect storage conditions and care of electrodes and flux for conformance to specifications. Check welding equipment for proper operation and proper calibration.
- 22. Perform visual inspection of a sample of completed welds and the base metals for cracks, notches, undercutting, and other defects.
- 23. Check a sample of the finished welds for proper profile and crosssection.
- 24. Prior to shipment of the material, ensure that the fabricator's QC representative has inspected the members and reviewed the shipping documents for completeness. Determining the acceptability of each piece prior to shipping is the sole responsibility of the fabricator. The testing agency shall ensure that members are marked in such a manner as to enable the Department's field representative to correlate shop inspection reports and shipping reports with the appropriate members.
- 25. Report and record all defects or problems observed, as well as all corresponding corrective action taken within their daily reports submitted to the Department.

Coatings Process Inspection

The NACE coating inspector shall fully complete a paint inspection checklist for all coated materials, take necessary samples of protective coatings for testing as directed by the Department's DMT, and permit only approved material to be The NACE inspector shall be present at the fabrication/coating shop used. during all cleaning and coating operations. The daily coating activity shall be recorded in the latest edition of the NACE Coating Inspector's log book and shall commence prior to the structural steel surface preparation. The testing agency shall be responsible for the purchase of the log books and shall provide them to each NACE inspector. At the time of material shipment from the fabricator's plant, the NACE inspector shall stamp the front page of each inspector's log book used during the coating operation. The stamped book shall indicate the inspector's NACE certification number, expiration date, printed name of the inspector, and shall be signed by the inspector. The log book(s) shall then be furnished to the Senior Fabrication Inspector to be included with the submission of the weekly reports.

Precast, Prestressed and Post-Tensioned Concrete Inspection

Due to their critical function as load-bearing units of bridges and structures, precast, prestressed, and post-tensioned concrete members must be constructed in strict conformance with the specifications. To assure this conformance, the DMT assigns a QA inspector to the manufacturing/fabrication plant to inspect, in detail, all phases of manufacture/fabrication. The primary function of the QA inspector is to assure the Engineer that the fabricator is exercising adequate quality control during the entire fabrication process. Should the inspector discover deficiencies or witness a lack of quality control, it is imperative that the Engineer be notified immediately so that corrective action can be initiated.

The inspector shall perform the following:

Sampling

The following component materials shall be sampled for testing in accordance with standard Department procedures and frequencies listed below:

- 1. <u>Portland cement:</u> Shall be from a qualified source. Each load shall be accepted by certification. Samples shall be taken as directed by the Engineer.
- 2. <u>Aggregate:</u> Samples from bins or stockpiles each month for each source of supply, or as directed by the Engineer.
- 3. <u>Admixtures:</u> Only qualified admixtures are to be used. Samples are to be taken as directed by the Engineer.

- 4. <u>Prestressing steel strand</u>: Sample each reel or coil in accordance with Standard Specifications, Article M.14.01-2.
- 5. <u>Post-tensioning tendons and anchorages:</u> Sample as per Special Provisions.
- 6. <u>Reinforcing steel:</u> From each source, a 5-foot (1.5 m) sample of each size for every 200 tons (181.4 metric tons), with a minimum of one sample of each size from each source per project.

Inspection of Plant Facilities and Manufacturing Procedures

The plant facilities shall be inspected annually or as directed by the Engineer. A form provided by the Department shall be utilized as a guide to plant facilities inspection. As a minimum, the following shall be inspected:

- 1. Storage and handling of materials.
- 2. Batching, mixing, transportation and placement of concrete.
- 3. Curing method and apparatus (i.e., steam, radiant heat or other approved method) including provision for recording time and temperature data during the curing cycle.
- 4. Concrete testing equipment (i.e., compression-testing machine should be calibrated every 12 months, pressure-type air meters, cylinder molds, slump cones, and unit weight apparatus) and facilities for moist-curing test cylinders in accordance with ASTM C 192.
- 5. Equipment and procedure for consolidation of concrete.
- 6. Construction and capacity of casting beds.
- 7. Dimensions, condition, and construction of forms.
- 8. Method and equipment for applying prestressing or post-tensioning forces.
- 9. Method and equipment for measuring prestressing or post-tensioning forces and the procedure for measuring elongation of strands or tendons.
- 10. Accuracy and calibration data of pressure gauges. (Gauges shall be calibrated at intervals not to exceed 6 months)

Inspection of Casting Bed

- 1. Check cleanliness, level, and alignment of form liner.
- 2. Check position of bulkheads for proper length of units and skewed or sloped ends, when applicable.
- 3. Inspect stringing of prestressing strands to ensure correct number and position of strands and location of "hold-downs."
- 4. For a sample of strands: inspect tension, measure elongation, and check gauge reading for proper force application. Force measurement of elongation and gauge reading shall check each other and the theoretical value shall be within 5 percent.
- 5. Witness retensioning at the non-jacking end of deflected strands and straight strands to verify application of the required prestressing force in accordance with the Standard Specifications, Article 5.14.03.
- 6. Inspect installation of a sample of post-tensioning tendons and anchorages, when applicable.
- 7. Check size, type, and location of a sample of reinforcing steel, hardware, and miscellaneous steel when placed in forms.
- 8. Inspect condition and alignment of a sample of side forms.
- 9. Check proper bracing and anchorage of casting bed and end anchorages.

Inspection of Concrete Operations

- 1. Inspect a sample of concrete delivered to forms for homogeneity and uniformity of successive batches.
- 2. Spot-check batching and mixing of concrete to assure that approved mix design and procedures are being used.
- 3. Witness/monitor sampling of concrete for quality control testing.
- Witness slump, air tests, concrete temperature, and unit weight for conformance to specifications and accept or deem unacceptable on the basis of results.
- 5. Inspect placement, consolidation and finishing of concrete for conformance to specifications and accepted concrete practices.

- 6. For deck units, inspect internal void forms for material, size, and proper installation.
- 7. Check identification marker for required data and placement in unit.
- 8. Ensure that approved curing method is used and applied at proper time. If steam or radiant heat is used, ensure that required preset period is observed.

Inspection of Fabricated Units

- 1. Inspect a sample of units to determine if they were cured uniformly. Review the time/temperature record of curing cycle for specification compliance.
- 2. Witness testing of cylinders for required concrete strength prior to detensioning or removal of forms.
- 3. Verify dimensions, details, surface finish, and freedom from defects of a sample of finished units.
- 4. Verify proper marking and identification of units.
- 5. Witness application of protective compound to surfaces of precast catch basin and drop inlet tops, which will be exposed when in service.
- 6. Catch basin, drop inlets, manhole riser sections, bases, and appurtenances that exhibit the following may be recommended for rejection:
 - 6.1 Fractures or cracks passing through the wall, except for a single end crack that does not exceed the depth of the joint.
 - 6.2 Defects that indicate imperfect proportioning, mixing, or molding.
 - 6.3 Surface defects indicating honeycombed or open texture.
 - 6.4 Any continuous crack having a surface width of 0.01 in. (0.3mm) or more and extending for a length of 1.0 ft. (300mm) or more, regardless of position in the section wall.
 - 6.5 Damaged or cracked ends where such damage would prevent making a satisfactory joint.

Reporting – As directed by a Department representative, the inspector will document test results on forms provided by the Department.
SCOPE OF WORK MATERIAL TESTING INSPECTION For Consultant third-party Testing Agency (Testing Agency)

As determined by the Connecticut Department of Transportation's (Department) Division Chief of Construction Services and Materials Testing (Division Chief), the Testing Agency shall provide qualified inspection and testing personnel to perform inspections, sampling, and testing of materials in the following areas:

- General Requirements
- Precast, Prestressed and Post-Tensioned Concrete Inspection
- HMA Plant Inspection
- Sampling Materials (i.e., Hot Mix Asphalt [HMA], aggregates) on Project Sites or Sources
- Testing In-Place Materials (HMA, aggregates) on Project Sites
- Testing Material Samples at Department Material Testing Facilities
- Inputting Test Results, Processing Request for Test (MAT-100) Forms, and Filing Documentation

All inspections, sampling, and testing are to be done in accordance with applicable standards including, but not limited to, those described by the American Welding Society (AWS), National Association of Corrosion Engineers (NACE), American Association of State Highway Transportation Officials (AASHTO), and the American Society of Testing Materials (ASTM).

Personnel performing the inspection, sampling, or testing of specific materials shall require certification that is administered by agencies such as the New England Transportation Technician Certification Program (NETTCP), American Concrete Institute (ACI), and others.

The purpose of this inspection, sampling, or testing is to assure conformance of the material to project specifications. The primary function of the Quality Assurance (QA) Inspector is to assure the Engineer that the fabricator/producer is exercising adequate quality control during the entire fabrication/production process. The Engineer is defined as the Division Chief or his duly authorized representative. As such, the QA Inspector shall visually inspect, witness, sample, or test material during all phases of manufacture/fabrication/production.

General Requirements

The Testing Agency shall:

1. Assume responsibility for the assigned inspection, sampling, or testing of materials as of the date stipulated by the Department in the formal notice to the Testing Agency to proceed with the work. This includes any partially completed work performed by the Department's former Testing Agency under the "Task Order Fabrication/Materials Inspection Services" contract that concluded February 14, 2016.

- 2. Make no decisions and offer no advice or opinion to a proposed action by the manufacturer/fabricator/producer/contractor without first consulting with the Engineer.
- 3. Provide all equipment required for the safe and comprehensive execution of the work including personal safety equipment such as clothing, hard hats, safety glasses, shoes, and gloves. This will also include appropriate means of transportation for some job classifications. All such equipment is subject to the approval of the Engineer.
- 4. Adhere to the Travel Expense Guidelines dated April 19, 2016 for the purpose of determining travel expenses and work locations.

The QA Inspector shall:

1. Be certified in the applicable field and have a thorough knowledge of the State of Connecticut - Department of Transportation - Standard Specifications for Roads, Bridges and Incidental Construction (Form 816 as supplemented), and project specifications, including approved shop drawings.

Specific information on scope of work, personnel, and reporting requirements for each area are provided in the following pages.

Precast, Prestressed and Post-Tensioned Concrete Inspection

Due to their critical function as load-bearing units of bridges and structures, precast, prestressed, and post-tensioned concrete members must be constructed in strict conformance with the specifications. To assure this conformance, the DMT assigns a QA Inspector to the manufacturing/fabrication plant to inspect, in detail, all phases of manufacture/fabrication. The primary function of the QA Inspector is to assure the Engineer that the fabricator is exercising adequate quality control during the entire fabrication process. Should the QA Inspector discover deficiencies or witness a lack of quality control, it is imperative that the Engineer be notified immediately so that corrective action can be initiated.

The QA Inspector shall perform the following:

Sampling

The following component materials shall be sampled for testing in accordance with standard Department procedures and frequencies listed below:

1. <u>Portland cement:</u> Shall be from a qualified source. Each load shall be accepted by certification. Samples shall be taken as directed by the Engineer.

- 2. <u>Aggregate:</u> Samples from bins or stockpiles each month for each source of supply, or as directed by the Engineer.
- 3. <u>Admixtures:</u> Only qualified admixtures are to be used. Samples are to be taken as directed by the Engineer.
- 4. <u>Prestressing steel strand:</u> Sample each reel or coil in accordance with Standard Specifications, Article M.14.01-2.
- 5. <u>Post-tensioning tendons and anchorages:</u> Sample as per Special Provisions.
- 6. <u>Reinforcing steel:</u> From each source, a 5-foot (1.5 m) sample of each size for every 200 tons (181.4 metric tons), with a minimum of one sample of each size from each source per project.

Inspection of Plant Facilities and Manufacturing Procedures

The plant facilities shall be inspected annually or as directed by the Engineer. A form provided by the Department shall be utilized as a guide to plant facilities inspection. As a minimum, the following shall be inspected:

- 1. Storage and handling of materials.
- 2. Batching, mixing, transportation and placement of concrete.
- 3. Curing method and apparatus (i.e., steam, radiant heat or other approved method) including provision for recording time and temperature data during the curing cycle.
- 4. Concrete testing equipment (i.e., compression-testing machine should be calibrated every 12 months, pressure-type air meters, cylinder molds, slump cones, and unit weight apparatus) and facilities for moist-curing test cylinders in accordance with ASTM C 192.
- 5. Equipment and procedure for consolidation of concrete.
- 6. Construction and capacity of casting beds.
- 7. Dimensions, condition, and construction of forms.
- 8. Method and equipment for applying prestressing or post-tensioning forces.
- 9. Method and equipment for measuring prestressing or post-tensioning forces and the procedure for measuring elongation of strands or tendons.
- 10. Accuracy and calibration data of pressure gauges. (Gauges shall be calibrated at intervals not to exceed 6 months)

Inspection of Casting Bed

- 1. Check cleanliness, level, and alignment of form liner.
- 2. Check position of bulkheads for proper length of units and skewed or sloped ends, when applicable.
- 3. Inspect stringing of prestressing strands to ensure correct number and position of strands and location of "hold-downs."
- 4. For a sample of strands: inspect tension, measure elongation, and check gauge reading for proper force application. Force measurement of elongation and gauge reading shall check each other and the theoretical value shall be within 5 percent.
- 5. Witness retensioning at the non-jacking end of deflected strands and straight strands to verify application of the required prestressing force in accordance with the Standard Specifications, Article 5.14.03.
- 6. Inspect installation of a sample of post-tensioning tendons and anchorages, when applicable.
- 7. Check size, type, and location of a sample of reinforcing steel, hardware, and miscellaneous steel when placed in forms.
- 8. Inspect condition and alignment of a sample of side forms.
- 9. Check proper bracing and anchorage of casting bed and end anchorages.

Inspection of Concrete Operations

- 1. Inspect a sample of concrete delivered to forms for homogeneity and uniformity of successive batches.
- 2. Spot-check batching and mixing of concrete to assure that approved mix design and procedures are being used.
- 3. Witness/monitor sampling of concrete for quality control testing.
- Witness slump, air tests, concrete temperature, and unit weight for conformance to specifications and accept or deem unacceptable on the basis of results.
- 5. Inspect placement, consolidation and finishing of concrete for conformance to specifications and accepted concrete practices.
- 6. For deck units, inspect internal void forms for material, size, and proper installation.

- 7. Check identification marker for required data and placement in unit.
- 8. Ensure that approved curing method is used and applied at proper time. If steam or radiant heat is used, ensure that required preset period is observed.

Inspection of Fabricated Units

- 1. Inspect a sample of units to determine if they were cured uniformly. Review the time/temperature record of curing cycle for specification compliance.
- 2. Witness testing of cylinders for required concrete strength prior to detensioning or removal of forms.
- 3. Verify dimensions, details, surface finish, and freedom from defects of a sample of finished units.
- 4. Verify proper marking and identification of units.
- 5. Witness application of protective compound to surfaces of precast catch basin and drop inlet tops, which will be exposed when in service.
- 6. Catch basin, drop inlets, manhole riser sections, bases, and appurtenances that exhibit the following shall be recommended for rejection:
 - 6.1 Fractures or cracks passing through the wall, except for a single end crack that does not exceed the depth of the joint.
 - 6.2 Defects that indicate imperfect proportioning, mixing, or molding.
 - 6.3 Surface defects indicating honeycombed or open texture.
 - 6.4 Any continuous crack having a surface width of 0.01 in. (0.3mm) or more and extending for a length of 1.0 ft. (300mm) or more, regardless of position in the section wall.
 - 6.5 Damaged or cracked ends where such damage would prevent making a satisfactory joint.

Reporting – As directed by the Engineer, the QA Inspector will document test results on forms provided by the Department.

HMA PLANT INSPECTION

The duties listed here are minimum requirements to be performed by HMA Inspectors. The daily responsibilities of an HMA Inspector shall be for elements and frequency, as specified in the contract, and will typically include, but are not limited to, the following items.

AASHTO Test Witnessed (at a Minimum)

- T 168 Sampling Bituminous Mixtures
- R 47 Sample Reduction
- T 312 Preparation of Gyratory Sample
- T 308 Asphalt Content Ignition Sample
- T 209 Theoretical Maximum Gravity (GMM)
- T 30 Sieve Analysis
- T 166 Bulk Specific Gravity (GMB)
- T 255 Moisture Content
- 1. Confirm assignment, correct specification year, and mix status (A/PT) with plant technician.
- 2. Review test data charts, past technician notes, and copies of past testing reports.
- 3. Inspect aggregates for consistency, quality, and cleanliness, and verify it was obtained from an approved source of supply.
- 4. Visually inspect stockpiles and cold-feed bins for segregation and/or contamination.
- 5. Verify that the latest JMF and HMA laboratory correction factors are available and accurate.
- 6. Verify the appropriate PG binder grade is being used for the day's production.
- 7. Inspect haul units for proper canvas covers and approved truck body release agents (no fuel oil).
- 8. Check the temperature of the mix.
- 9. Inspect the process of the batch/drum plant operations.
- 10. Check truck tickets for mix proportion, class, RAP content, moisture, and target weights.
- 11. Verify and note the status of the HMA plant. It should be running only on full automatic (not auto-manual or manual).

- 12. Retrieve all QC documentation.
- 13. Obtain random verification sample(s).
- 14. Obtain a liquid bituminous sample.
- 15. Obtain an Independent Assurance split sample.

Sampling Materials on Project Sites or Sources

The technician shall perform the following at the direction of a Department employee:

Sampling – Sample materials at a project site or source and transport such material all in accordance with applicable standards. The technician shall transport the sample to a location designated by the Department. The technician must be aware of the hazards of the project site or material sources and perform sampling in a safe manner.

Reporting – As directed by a Department representative, the inspector will document test results on forms provided by the Department. For example, HMA Inspectors shall report results on Forms MAT 412, MAT 413, and Daily Inspector Report/Form MAT 431. Pavement density and subbase density testing are reported on Forms CON 133 and CON 125.

Testing In-Place Materials on Project Sites

The technician shall perform the following at the direction of a Department employee:

Sampling – Test in-place material in accordance with applicable standards. The technician must be capable of following directions to various project and supplier sites throughout the state to independently test materials. The technician must be qualified to use the testing equipment safely and effectively. The technician must be aware of the hazards of the project site and perform testing in a safe manner.

Reporting – As directed by a Department representative, the inspector will document test results on forms provided by the Department within 24 hours. For example, HMA Inspectors shall report results on Forms MAT 412, MAT 413, and Daily Inspector Report/Form MAT 431. Pavement density and subbase density testing are reported on Forms CON 133 and CON 125.

Testing Material Samples at Department Material Testing Facilities

The technician shall perform the following at the direction of a Department employee:

Sampling – In accordance with applicable standards, assist or independently test material samples including, but not limited to, concrete cylinders, steel reinforcing bars, chains, fasteners, sand, and Portland cement in a laboratory setting. The technician shall also document the test results, input the test results into the Department's reporting system, and file the documentation as needed. Assist in the cleaning and maintenance of testing equipment and surrounding areas.

Reporting – As directed by a Department representative, the inspector will document test results on forms provided by the Department.

Inputting Test Results, Processing Request for Test (MAT-100) Forms, & Filing Documentation

The technician shall perform the following at the direction of a Department employee:

Request for Test (Form MAT-100) Processing – Through the Department's computerized construction management system (Site Manager), record test results and status of MAT-100 forms. File hardcopy versions of the MAT-100 forms in the Department's files.

Legend			
Material	Unit (Eng)	English unit of material that	
Code:		defines a quantity	
Material - The full detail description of a materia			
Full Name:	11		
Status: Type of Acceptance required	Status: Type of Acceptance required		
A: A request for test (Mat100)			
B: An alternative method for Acceptance			
(see Minimum Schedule for Acceptance Testing)			
Section: Section responsibility within the Divis	on of Materia	als Testing for material	
1: District 1 Rocky Hill 7:	Asphalt Bind	er	
2: District 2 Colchester 9:	2: District 2 Colchester 9: Physical Testing		
3: District 3 New Haven 10:	3: District 3 New Haven 10: Precast Concrete		
4: District 4 Thomaston 11:	Certification	S	
5: Chemical 15:	Structural St	eel	
6: Hot Mix Asphalt 17: Road Salts			

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
00000	NO REQUEST FOR TEST REQUIRED	NONE	В	11
00031	Paint - Prime Coat for Struct. Steel	gal	В	15
00032	Paint - Interm. Coat for Struct. Steel	gal	В	15
00033	Paint - Top Coat For Struct. Steel	gal	В	15
00039	Paint - For Field Touchup	gal	В	15
00054	Paint - Waterborne Pvmt Mark (15 Min)	gal	В	5
00060	Paint - Waterborne Pvmt. Mark (3 Min)	gal	В	5
00091	Paint - Epoxy Pavement Markings	gal	В	5
00097	Sand Blast Debris (Toxicity Test)	TEST	В	5
00297	Calcium Chloride - Liquid	gal	В	17
00298	Sodium Chloride, Inertial Barriers	lb.	В	5
00302	Calcium Chloride	ton	В	5
00303	Sodium Chloride	ton	А	17
00306	Glass Spheres	lb.	В	5
00310	Pavement Marking, Plastic, Preformed.	l.f.	В	5
00327	Water	gal	В	5
00328	Protective Coating	s.f.	В	11
00496	Fertilizer	lb.	В	5
00497	Seed	lb.	В	5
00510	Peat	c.y.	В	5
00512	Fertilizer	s.y.	В	5
00518	Sod	s.y.	В	5
00533	Lime	lb.	В	5
00534	Mulch - All Types	lb.	В	5
00536	Plant Materials	ea.	В	5
00542	Topsoil (from project)	c.y.	В	5
00542X	Topsoil (OFFSITE)	c.y.	А	5
00699	Pipe - R.C. & Fittings & Acc.	l.f.	A	10
00800	Box Culvert, Precast Concrete, 3 sided	l.f.	A	10

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
00804	Box Culvert, Precast Concrete	l.f.	А	10
00823	Culvert End - Reinforced Concrete	ea.	А	10
00865	Concrete Barrier, Precast, Temporary	l.f.	В	10
00895	Concrete Barrier, Precast	l.f.	А	10
01422	Section, Precast	ea.	А	10
01432	Foundation (precast)	ea.	А	10
01435	Anchor, Precast	ea.	А	10
01440A	Catch Basin - Precast (Complete)	ea.	А	10
01441A	Manhole - Precast (Complete)	ea.	А	10
01444	Catch Basin Riser, Precast	ea.	А	10
01458	Catch Basin Sump, Precast	ea.	А	10
01462	Handhole & Cover, Precast	ea.	А	10
01467	Slab, Precast	ea.	А	10
01491	Manhole - Riser (precast)	ea.	А	10
01499	Manhole - Base (precast)	ea.	А	10
01511	Curb, Precast	l.f.	А	10
01649	Catch Basin Top, Frame & Grate	ea.	А	10
01708	Pipe - For Underdrain or Outlet	l.f.	А	11
01783	Pipe - Aluminum & Fittings & Acc.	l.f.	В	11
01790	Pipe Arch - Aluminum	l.f.	В	11
01807	Culvert End - Aluminum	ea.	В	11
01839	Bolt / Nut / Washer	ea.	А	9
01940	Pipe - CCM & Fittings & Acc.	l.f.	A	1,2,3,4
01977	Pipe - ACCM & Fittings & Acc.	l.f.	А	1,2,3,4
02018	Culvert End - Coated Metal	ea.	А	1,2,3,4
02110	Pipe - Cast Iron & Fittings & Acc.	l.f.	А	15
02449	Pipe - Copper & Fittings & Acc.	l.f.	В	11
02501	Pipe - Ductile Iron & Fittings & Acc.	l.f.	А	15
02600	Pipe - Polyethylene & Fittings & Acc.	l.f.	В	11
02649	Pipe - PVC & Fittings & Acc.	l.f.	В	11
02673	Culvert End - Polyethylene	ea.	В	11
02724	Pipe - Steel & Fittings & Acc.	l.f.	А	15
02731	Pipe - Fiberglass & Fittings & Acc.	l.f.	В	11
02995	Dowel Splice System, Epoxy Coated	ea.	А	9
02997	Dowel Splice System	ea.	A	9
02998	Deformed Steel Bars, Epoxy Coated	lb.	А	9
03014-A-3.3K	Concrete-Class A (3300psi/22.8MPa)	C.Y.	A	9
03014-C-3.3K	Concrete-Class C (3300psi/22.8MPa)	, С.V.	А	9
03014-F-4.4K	Concrete-Class F (4400psi/30.4MPa)	C.V.	A	9
03014-SP2500	Concrete-Spec. Prov. (2500psi/18MPa)	, С.У.	А	9
03014-SP3.3K	Concrete-Spec. Prov. (3300psi/23MPa)	CY	A	9
03014-SP3K	Concrete-Spec. Prov. (3000psi/21MPa)	C.V.	А	9
03014-SP4.4K	Concrete-Spec. Prov. (4400psi/30MPa)	CY	A	9
03014-SP4500	Concrete-Spec. Prov. (4500psi/31MPa)	C.V.	A	9
03014-SP4K	Concrete-Spec. Prov. (4000psi/28MPa)	C.V.	A	9
.				-

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
03014-SP5.7K	Concrete-Spec. Prov. (5656psi/39MPa)	c.y.	А	9
03014-SP5K	Concrete-Spec. Prov. (5000psi/35MPa)	c.y.	А	9
03014-SP6.5K	Concrete-Spec. Prov. (6527psi/45MPa)	CY	А	9
03014-SP6K	Concrete-Spec. Prov. (6000psi/41MPa)	c.y.	А	9
03014-SP8K	Concrete-Spec. Prov. (8000psi/55MPa)	c.y.	А	9
03014-SP-CLSM	Concrete-Controlled Low Strngth Material	c.y.	А	9
03015-02230	PCC 2200 psi, No. 3, Exp. 0	c.y.	А	9
03015-03081	PCC 3000 psi, No. 8, Exp. 1	c.y.	А	9
03015-03340	PCC 3300 psi, No. 4, Exp. 0	c.y.	А	9
03015-03360	PCC 3300 psi, No. 6, Exp. 0	c.y.	А	9
03015-03540	PCC 3500 psi, No. 4, Exp. 0	c.y.	А	9
03015-04081	PCC 4000 psi, No. 8, Exp. 1	c.y.	А	9
03015-04460	PCC 4400 psi, No. 6, Exp. 0	c.y.	А	9
03015-04462	PCC 4400 psi, No. 6, Exp. 2	c.y.	А	9
03015-04481	PCC 4400 psi, No. 8, Exp. 1	c.y.	А	9
03015-05081	PCC 5000 psi, No. 8, Exp. 1	c.y.	А	9
03015-05560	PCC 5500 psi, No. 6, Exp. 0	c.y.	А	9
03015-05562	PCC 5500 psi, No. 6, Exp. 2	c.y.	А	9
03016	Grout - Non Shrink (Batched)	c.y.	А	10
03025	Mortar	bag	В	10
03040	Grout, Non-Shrink	bag	В	10
03050	Concrete Members, Prestressed	l.f.	А	10
03051	Concrete Piles - Prestressed	l.f.	А	10
03062	Cement - Portland Type III	bag	В	9
03066	Cement - Portland Type I/II	bag	В	10
03092	Bituminous Concrete Joint / Crack Sealer	gal	А	7
03093	Bituminous Concrete Joint / Crack Filler	lb.	А	7
03094	Joint Sealer (Hot-Applied Rubberized)	l.f.	А	7
03100	Deformed Steel, Reinforcing	lb.	А	9
03100-G	Deformed, Steel, Reinforcing Bars, Galva	lb.	А	9
03100-SS	Stainless Steel Rebar	lb.	А	9
03102-FRP	Reinforcing Bars - Fiber Reinf - Polymer	lb.	А	9
03105	Chemical Anchor	ea.	В	11
03138	Dowels, Steel	ea.	А	9
03145	Fabric, Wire & Welded Steel	s.y.	А	9
03155	Expansion Joint Filler	l.f.	В	5
03158	Preformed Expansion Joint Filler	s.f.	В	5
03166	Sheeting, Polyethylene	s.y.	В	11
03200	Concrete Masonry Unit (CMU)	ea.	В	9
03201	Brick (Clay) - RED	ea.	В	9
03205	Catch Basin - Grates	ea.	А	15
03209	Manhole Covers / Frames	ea.	А	15
03211	Handhole Covers / Frames	ea.	А	15
03251	Catch Basin - Adjustment Ring	ea.	А	15
03252	Manhole - Adjustment Ring	ea.	А	15

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
03307	Fence, Chain Link, Gate	ea.	А	9
03309	Fence, Chain Link	l.f.	А	9
03310	Fence, Chain Link, Post for	ea.	А	9
03320	Fence, Hardware & Access. (Chain Link)	ea.	А	9
03327	Fence, Protective	l.f.	А	15
03405	Metal Beam Rail, Anchorages for	ea.	А	15
03406	Metal Beam Rail	l.f.	А	15
03413	Box Beam Guide Railing	l.f.	А	15
03414	Metal Handrail	l.f.	А	15
03419	Cable Guide Rail	l.f.	А	9
03421	Cable Guide Railing, Anchorages for	ea.	А	9
03429	Metal Bridge Rail	l.f.	А	15
03432	Joint Seal, Elastomeric Compression	l.f.	В	11
03444	Closed Cell Elastomer	c.i.	В	11
03449	Timber Guide Rail	l.f.	А	15
03450	Timber Guide Rail - Anchorages	ea.	А	10
03504	Anchor Bolts	ea.	А	9
03505-L	Bearing Pads (Elastomeric Laminated)	ea.	А	9
03505-P	Bearing Pads (Elastomeric Plain)	ea.	А	9
03532	Pile, Steel Shell	l.f.	А	9
03535	Piling, Steel Sheet	l.f.	А	9
03537	Steel, Structural	cwt.	А	15
03539	Piles, Timber	l.f.	В	11
03540	Bearings, Pot or Spherical	ea.	А	15
03542	Stud Shear Connector	ea.	А	9
03543	Studs - Welded	ea.	А	9
03549	H-Piles, Steel	lb.	А	9
03559	Pile Point, Steel	ea.	А	15
03566	Steel Plates	ea.	А	15
03603	Warning Lights	ea.	В	11
03693	Conduit & Fittings (all types)	l.f.	В	11
03704	Light Standard	ea.	А	15
03709	Ground Wire	l.f.	В	15
03711	Ground Rod	ea.	В	11
03723	Rigid Metal Conduit	l.f.	В	11
03724	Junction Box & Cover	ea.	А	15
03764	Sign (Variable Message)	ea.	В	11
03766	Traffic Signal Equipment	ea.	В	11
03801	Pedestals, Aluminum	ea.	В	11
03802	Span Pole - Steel	ea.	А	15
03806	Mast Arm Assembly	ea.	A	15
03807	Traffic Signal	ea.	В	11
03927	Traffic Drum	ea.	В	11
03928	Sign Support, Structural Steel	ea.	А	15
03933	Delineator	ea.	В	11

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
03934	Reflective Sheeting	s.f.	В	11
03938	Sign Face - Sheet Aluminum	s.f.	В	11
03943	Object Marker	ea.	В	11
03945	Construction Signing	s.f.	В	11
03948	Traffic Cones	ea.	В	11
03952	Sign Post	ea.	А	9
03956	Traffic Drums	ea.	В	11
03970	Impact Attenuator	ea.	В	11
03974	Construction Barricade	ea.	В	11
03985	Geotextile	s.y.	В	11
04003	Bituminous Concrete - Curb Mix	ton	А	6
04029	Ultra-Thin Bonded HMA Pavement (Type B)	ton	А	6
04052	HMA- Level 1 (9.5 mm / 0.375 in)	ton	А	6
04053	HMA, Level 2 (9.5 mm / 0.375 in)	ton	А	6
04054	HMA, Level 3 (9.5 mm / 0.375 in)	ton	А	6
04056	HMA, Level 1 (12.5 mm / 0.5 in)	ton	А	6
04057	HMA, Level 2 (12.5 mm / 0.5 in)	ton	А	6
04058	HMA, Level 3 (12.5 mm / 0.5 in)	ton	А	6
04064	HMA, Level 1 (25.0 mm / 1.0 in)	ton	А	6
04065	HMA, Level 2 (25.0 mm / 1.0 in)	ton	А	6
04066	HMA, Level 3 (25.0 mm / 1.0 in)	ton	А	6
04076	HMA, Level 1 (6.25 mm / 0.25 in)	ton	А	6
04077	HMA, Level 2 (6.25 mm / 0.25 in)	ton	А	6
04078	HMA, Level 3 (6.25 mm / 0.25 in)	ton	А	6
04092	PMA, Level 1 (6.25 mm / 0.25 in)	ton	А	6
04093	PMA, Level 2 (6.25 mm / 0.25 in)	ton	А	6
04094	PMA, Level 3 (6.25 mm / 0.25 in)	ton	А	6
04095	PMA, Level 1 (9.5 mm / 0.375 in)	ton	А	6
04096	PMA, Level 2 (9.5 mm / 0.375 in)	ton	А	6
04097	PMA, Level 3 (9.5 mm / 0.375 in)	ton	А	6
04098	PMA, Level 1 (12.5 mm / 0.5 in)	ton	А	6
04099	PMA, Level 2 (12.5 mm / 0.5 in)	ton	А	6
04100	PMA, Level 3 (12.5 mm / 0.5 in)	ton	А	6
04101	PMA, Level 1 (25.0 mm / 1.0 in)	ton	А	6
04102	PMA, Level 2 (25.0 mm / 1.0 in)	ton	А	6
04103	PMA, Level 3 (25.0 mm / 1.0 in)	ton	А	6
04108-SP	HMA- POROUS PAVEMENT	ton	А	6
04128	RS-1	gal	A	7
04133	SS-1- Slow Setting Asphalt Emulsion	gal	А	7
04134	SS-1H - Slow Setting Asphalt Emulsion -	GAL	A	7
04138	CRS-1 (Cationic Rapid Setting Asphalt)	gal	А	7
04139	CRS-2 (Cationic Rapid Setting)	gal	A	7
04142	Cationic Emulsion (CMS-2)	gal	А	7
04145	CSS-1H - Slow Setting Ashalt Emulsion	gal	A	7
04146	CSS-1- Cationic Emulsion	gal	А	7

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
04147	RS-1H	gal	Α	7
04148	CRS-1P - Polymer Modified	GAL	А	7
04177	Joint Sealer, Concrete Structure	lb.	В	5
04199	Membrane Waterproofing	s.y.	В	7
04207	Dampproofing, Primer for	gal	В	7
04208	Dampproofing, Sealer for	gal	В	7
04697	Sand (Masonry) - Grading A	c.y.	А	1,2,3,4
04700	Sand	c.y.	А	1,2,3,4
04704	Sand (Masonry) - Grading B	c.y.	А	1,2,3,4
04749	Aggregate (Lightweight)	c.y.	А	1,2,3,4
04776	Hay, Baled	ea.	В	11
04817	Stone Dust/Screenings	ton	А	1,2,3,4
04819	Gravel (Bank Run)	c.y.	А	1,2,3,4
04901	Bedding Material	c.y.	В	1,2,3,4
04902	Borrow	c.y.	Α	1,2,3,4
04909	Curbing, Granite Stone	l.f.	В	1,2,3,4
04910	Curbing, Granite Slope	l.f.	В	1,2,3,4
06566	Lawn Drain	ea.	А	15
06659	Expansion Joint Sealer	l.f.	В	5
06923	Stay In Place Forms	l.f.	А	15
07067	Expansion Joint System	l.f.	В	5
07351	Bollard	ea.	А	15
07392	Bolt / Nut / Washer (Stainless Steel)	ea.	А	9
07403	Rod, Threaded	ea.	А	15
07547	Tree	ea.	В	5
07627	Reinforced Earth Wall	ea.	В	10
07645	Luminaire	ea.	В	11
07799	Impact Attenuator Parts/Devices	ea.	В	11
07822	Noise Barrier Wall	s.f.	В	11
08010 - SP	Exp. Jt Asphaltic Plug - SPECIAL PROV.	c.f.	В	5
08022	Bolt / Nut / Washer, (High Strength)	ea.	А	9
08032	Sand (Washed)	с.у.	А	1,2,3,4
08033	Sand (Natural)	с.у.	А	1,2,3,4
08034	Stone (Broken/Crushed)	c.y.	А	1,2,3,4
08035	Gravel (Crushed)	c.y.	А	1,2,3,4
08036	Reclaimed Misc. Aggregate (ON-SITE)	с.у.	А	1,2,3,4
08036X	Reclaimed Misc. Aggregate (OFFSITE)	c.y.	А	1,2,3,4
08037	Reclaimed Waste	с.у.	А	1,2,3,4
08037X	Reclaimed Waste (OFFSITE)	с.у.	А	1,2,3,4
08039	Embankment Material	c.y.	А	1,2,3,4
08042	Pull Box - Precast Concrete	ea.	Α	10
08044	Retaining Wall - Precast Concrete	ea.	А	10
08060	Detectable Warning Strip - (ADA)	s.f.	В	11
08069	Prefabricated Bridge Units	EACH	А	10

CONNECTICUT DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING AND CONSTRUCTION DIVISION OF MATERIALS TESTING

CRITERIA FOR ACCEPTANCE OF PORTLAND CEMENT BY CERTIFICATION

Before a cement producer is qualified to provide cement for use on Connecticut Department of Transportation (Department) projects, an authorized representative of the cement producer must agree to and comply with the following:

A. <u>QUALIFICATION</u>

- 1. The cement producer shall demonstrate that the production of cement at each mill providing material to the Department is regulated by an effective program of quality control. The cement producer shall submit a quality control plan to the Division of Materials Testing (DMT) that includes a detailed account of the quality control methods employed, the sampling and testing frequency, and testing procedures for review. Furthermore, the cement producer shall provide upon request, any documentation produced during any quality control related sampling and testing.
- 2. The testing laboratory of the cement producer shall be certified by the Cement and Concrete Reference Laboratory. Copies of the two (2) latest inspection reports shall be submitted to the DMT for review. The laboratory must be CCRL certified during any period that the mill provides material to the Department.
- 3. The cement producer shall certify the quality of the cement supplied as conforming to the requirements of the applicable specifications.

B. OPERATIONAL PROCEDURE

- 1. One (1) certified summary laboratory test report for all cement being produced shall be furnished on a monthly basis by the cement producer to the Division of Materials Testing, 280 West Street, Rocky Hill, Connecticut 06067.
- 2. Each bulk shipment to a ready mix producer, precast fabricator, or distributor shall be accompanied by a Bill of Lading that includes the following information:
 - a. Cement Producer's Name
 - b. Mill Location
 - c. Cement Carrier Number
 - d. Date Loaded
 - e. Weight of Material Contained in Carrier

- f. Silo, Bin or Lot Number of Cement, Terminals
- g. Consignee
- h. Destination
- i. Cement Type

Original BOL's must be provided to the purchaser for retention and review by the Department.

- 3. Random samples of the cement supplied may be selected and tested by the Department. Results of tests on these samples may be compared with the certified test values provided by the cement producer.
- 4. Results from bulk cement testing may also apply to bagged material from the same source.

Failure of the cement producer to comply with the requirements of the operational procedure may be considered grounds for suspending the qualification of the cement producer to provide cement on the basis of certification.

The procedure outlined above is intended to establish general guidelines for the acceptance of cement on the basis of producer qualification. However, the ConnDOT reserves the right to modify the above requirements if the best interest of the Department is served.

Appendix F – Connecticut Reference File (CRF) Specifications*

* used for Bureau of Highway Operations purchasing contracts ONLY. The following CRF's are active.

File #	Title/Description
25	Black Enamel Paint
104	Burnt Orange Enamel Paint For Trucks
139	Sodium Chloride (Rock salt)
161	Non-reflective Plastic Sheeting
163	Processed Aggregate
191	Grits
194	Premixed Sodium Chloride (Salt) And Calcium Chloride
199	Epoxy Resin Pavement Markings, Symbols and Legends
200	White and Yellow Fast-Drying Waterborne Pavement Marking Paint
207	White and Yellow Regular-Drying Waterborne Pavement Marking Paint
2007-03	Liquid Calcium Chloride Anti-icing Agent

BLACK ENAMEL PAINT

REFERENCE FILE NO. 25-G

Issued March 10, 1953 Revised November 2, 1981

GENERAL — This material shall be shipped in regulation 1—gallon metal pails. Each container shall be marked with the following: name and type of paint, net weight, batch number, date of manufacture and State of Connecticut reference file and purchase order numbers, together with name and address of the manufacturer. When so requested, samples and analyses of all pigments, oils, resins, thinners and driers used for the enamel furnished shall be supplied by the manufacturer within ten days after request is made therefore.

A certified test report containing the physical and chemical properties of the material shall be submitted with each batch shipment.

The enamel shall consist of pigments and composition ground in the required vehicle by a suitable grinding machine to the required fineness. All pigments, oils, resins, thinners and driers used shall be of the best quality, free from adulterants of any kind and shall comply with the specific requirements given below. The enamel shall not contain any lead or lead by products.

The material desired under this specification is an extremely durable, highest quality black enamel for use on highway signs, and shall be resistant to air, sun and water.

<u>COLOR</u> — The color shall be jet black, conforming to Federal Standard No. 595, Color No. 17038.

ENAMEL COMPOSITION

	IVIIIN.	IVIAX.
Carbon Black, %	3	4
Total solids, % by weight	42	-
Coarse particles retained on #325 screen based on paint, % Weight per gallon, lb.	- 7.5	0.5
Viscosity, Krebs units at 77°F.	67	77
Fitneness of grind (North Standard)	7	

PIGMENT COMPOSITION — The pigment shall be carbon black only.

.

N A A XZ

<u>VEHICLE</u> - The vehicle shall consist of a phthalic alkyd resin conforming to the requirements of Federal Specification TT—R-266, Type 3, of latest issue, with the following exceptions: Viscosity - Z maximum; Compatibility — delete raw linseed oil and mineral spirits dilution tests. The necessary quantities of suitable aliphatic, aromatic or terpene thinners and driers shall be added to yield a product conforming to all the requirements of this specification.

<u>SPECULAR GLOSS</u> - The enamel shall be flowed on a tin panel and allowed to dry for 24 hours before measuring. The specular gloss at 60° angle of incident, ASTM designation D523 of latest issue, shall be not less than 85.

<u>SETTING AND DRYING TIME</u> — This enamel shall air dry dust free within 2 hours, dry hard within 8 hours and reach full hardness within 48 hours.

<u>DRY OPACITY</u> — This enamel shall have a contrast ratio of at least 0.99 when spread at the rate of 630 sq. ft. per gallon (0.0025—inch wet film thickness).

<u>WATER RESISTANCE</u> — A film of enamel 0.002 inch thick shall be allowed to air dry for 96 hours, and then immersed in distilled water for 16 hours. It shall show no blistering or wrinkling immediately upon removal and no more than slight dulling or whitening after 2 hours recovery. After 24 hours, the gloss of the immersed portion shall be at least 90 percent of a comparison panel, which was not immersed.

<u>FLEXIBILITY</u> - A film of enamel 0.002 inch thick shall be allowed to dry for 18 hours, then baked for 72 hours at 105± 2°C, allowed to cool for 1/2 hour at 25°c (77°F), then bent over an 1/8—inch mandrel. There shall be no visible cracks when examined in a strong light at a 7—diameter magnification.

<u>SKINNING</u> — The enamel shall not skin within 48 hours in a three—quarter filled, closed container. Small amounts of anti—skinning agents, wetting agents, suspension agents and anti—drier agents may be added at the discretion of the manufacturer.

<u>WORKING PROPERTIES</u> — The enamel shall be well ground and shall show no more settling or caking than may be easily redispursed with a paddle to a homogeneous state. It shall be of good brushing consistency and shall dry to a smooth, glossy, uniform film, free from running, sagging or streaking.

BURNT ORANGE ENAMEL PAINT FOR TRUCKS (LEAD FREE)

REFERENCE FILE NO. 104-P

Issued May 17, 1945 Revised January 25, 1999

<u>INTENDED USE</u> – This specification covers a lead-free high-grade, synthetic-type high gloss enamel intended for use on trucks and other metallic motorized mechanical equipment. It is highly weather-resistant and is characterized by excellent color and gloss-retention, good drying, flexibility and freedom from aftertack. This enamel may be applied by brush or spray. It fails by mild chalking rather than by checking or cracking. The application of wax at periodic intervals will retard chalking and improve the appearance of the finish.

<u>GENERAL</u> – This material shall consist of pigments of the required fineness and composition, ground in the specified vehicle by a suitable grinding machine to the required fineness. All pigments, oils, resins, thinners and driers shall comply with the requirements below.

This enamel shall be shipped in regulation one-or five-gallon metal pails, as specified by the Purchasing Department. Each container shall be marked with the following: name and type of paint, net weight, batch number, date of manufacture and State of Connecticut Reference File and Purchase Order Numbers, together with the name and address of the manufacturer. When so requested, samples and, analyses of all pigments, oils, resins, thinners, and driers used shall be supplied by the manufacture within ten (10) days after request is made.

COLOR – Standard color chips may be viewed at the Connecticut Department of Transportation, Research and Materials Testing Laboratory, 280 West Street, Rocky Hill, Connecticut 06067. The color shall essentially match that of color Omaha Orange, DuPont #082.

VEHICLE - The vehicle for this air-drying enamel shall consist of a phthalic alkyd resin.

Necessary quantities of suitable aliphatic, aromatic or tarpene thinners and driers, or mixture thereof, shall be added to yield a product conforming to all the requirements of this specification. Small amounts of antiskinning agents, wetting agents, suspension agents and antidrier absorption agents may be added at the discretion of the manufacturer.

QUANTITITIVE REQUIREMENTS	Min.	Max.
Pigment, % by weight	16	
Vehicle, % by weight		84
Volatile matter in vehicle, % by weight		55
Coarse particles and skins retained on		
#325 sieve, % by weight of pigment		0.5
Viscosity, Krebs units at 77°F.	75	85
Specular gloss (without correction for		
diffuse reflectance)	85	
Fineness of grind (North Standard)	6	
Dry opacity (540 sq. ft. per gallon)	0.52	
Weight per gallon, lbs.	8.0	
Drying time: Dust-free setting time, hours		1
Dry hard, hours		8
Full hardness, hours		48

<u>BRUSHING PROPERTIES</u> – As received, this enamel shall be ready-mixed for use. It shall be of good brushing consistency in the packaged condition. When tested as described below, laps

shall be picked up without pulling under the brush; and the enamel shall dry to a smooth, glossy, uniform film, free from running, sagging or streaking.

Brush the evenly mixed enamel on a thoroughly cleaned, rust-free, smooth, cold-rolled steel or aluminum panel (2 ft. square) with a 2-1/2 inch paint brush, applying the enamel uniformly at an approximately spreading rate of 500 square feet per gallon. Place the panel in a nearly vertical position, allow to air dry for 24 hours and examine for defects described above.

<u>DRYING TIME</u> – A wet film, 0.0015-inch thick, shall set to a dust-free condition within one hour, dry hard and tack-free within 8-hours and reach full hardness within 48 hours.

<u>FILM FOR FLEXIBILITY, WATER-RESISTANCE AND GASOLINE-RESISTANCE</u> – Tin panels, measuring 4 by 6 inches and weighing 19 to 25 grams per square centimeter, will be used for this test. They will be thoroughly cleaned with a suitable solvent and lightly buffed with steel wool immediately before using. Apply the film with a 0.002-inch (approximately 0.004-inch gap clearance). Bird Film Applicator or any other doctor blade which produces a film of the same thickness as that produced by the Bird blade.

<u>FLEXIBILLITY</u> – Films prepared as above shall be allowed to air dry in a horizontal position for 18 hours, then baked for 168 hours at $105 \pm 2^{\circ}C$ ($221 \pm 4^{\circ}F$). After baking, condition the panel for one-half hour at $23 \pm 1^{\circ}C$ ($73.4 \pm 2^{\circ}F$) and relative humidity 50% - 4%. Bend over a 1/8 inch mandrel. Examine the coating for cracks over the area of the bend in a strong light at a 7-diameter magnification. The film of the enamel shall show no cracking.

<u>APPEARANCE OF FILM AFTER BAKING</u> – After drying and baking the panel for flexibility, the enamel film shall retain at least 75 percent of the original secular gloss value.

<u>ADHESION</u> – In testing for adhesion, use the flat portion of the panel from the flexibility test. Cut a narrow ribbon of the film from the panel by use of the sharp knife blade held at about 30 degrees from the panel. The film should cut loose in the form of a ribbon without flaking or cracking.

<u>COLOR WATER RESISTANCE</u> – After drying for 96 hours, place one of the test panels in a beaker containing approximately 2-1/2 inches of distilled water at room temperature (21 to 32°C), and allow to remain for 16 hours. Remove and allow to dry. The film shall show no blistering or wrinkling immediately upon removal from the water. There shall be no more than a slight dulling or whitening when examined 2 hours after removal of the panels and after 24 hours of air drying, the gloss of the immersed portion shall be at least 90 percent of the gloss of a comparison panel which was not immersed. The immersed and comparison panel shall be indistinguishable with regard to film hardness after the 24 hours of air drying.

<u>GASOLINE RESISTENCE</u> – After drying for 96 hours, place one of the panels in a beaker containing approximately 2-1/2 inches of gasoline conforming to Federal Specification VVG-1690, cover with a watch glass and allow to remain at room temperature (21 to 32°C), for 16 hours. Remove and allow to dry. The film shall show no blistering or wrinkling immediately upon removal of the panel, and any softening or whitening effect that may remain two hours after removal shall have completely disappeared after air drying for 24 hours. The immersed portion shall retain at least 50 percent of the gloss of a comparison panel which was not immersed.

<u>DRY OPACITY</u> – At a spreading rate of 540 square feet pr gallon, this enamel shall have a minimum dry-film contrast ratio of not less than 0.98.

<u>MISCIBILITY WITH MINERAL SPIRITS</u> – Mix thoroughly one part of mineral spirits conforming to Grade I of Federal Specification AA-2904 with eight parts of enamel by slowly adding the mineral spirits to the enamel with constant stirring. The enamel shall be completely missible with mineral

spirits. After standing 24 hours there shall be no curdling or precipitation of the vehicle. Any settling of the pigment shall be disregarded.

SKINNING – The enamel shall not skin within 48 hours in a three-quarters filled, closed container.

<u>RESIN</u> – Resin and resin derivatives shall be absent.

RECOATING – Recoating after 24 hours air drying shall produce no film irregularity.

ODOR – The odor of the wet enamel and of the dry film shall not be obnoxious.

TOXICITY – The enamel shall contain no benzol or chlorinated solvents.

<u>PARTIALLY FILLED CONTAINER</u> – After standing 30 days at a temperature between 21 and 32°C, a three-quarters filled, closed 8-ounce glass jar of the enamel shall show no livering, curdling, hard settlement or caking. Any skin formed shall be continuously and easily removed, and the enamel shall mix readily to a smooth, homogeneous state.

<u>FULL CONTAINER</u> - Upon being opened after six months of storage under warehouse storage conditions, a full, closed container shall show no livering or curding of the enamel and no more settling than can be redispersed with a paddle to a homogeneous state. There shall be no hard settlement or caking and no skinning. The viscosity shall not have increased more than an equivalent of 10 K.U. during the storage period. The enamel shall have retained its drying properties and shall dry to a full gloss finish, free from grit and seediness.

APPLICABLE FEDERAL SPECIFICATIONS AND STANDARDS -

A-A2504	Thinners; Paint, Volatile Mineral Spirits
VV-3-1690	Gasoline, Automotive
141	Paint, Varnish, Lacquer and Related Materials;
Methods of Inspection, Sampling and Testing	

SODIUM CHLORIDE (ROCK SALT)

REFERENCE FILE NO. 139R

Issued July 7, 1955

Revised June 1, 2002

Scope: This specification prescribes the composition, storage, inspection, acceptance and delivery of road salt obtained from (natural deposits/artificially produced) which is to be used for snow & ice control on highways and bridges.

<u>Requirements</u>: All road salt shall conform to AASHTO M 143 (ASTM D—632) Type 1, with the exceptions and additions stated herein. When material is not in conformance as stated herein, and the state formally agrees to accept such material, payment reduction shall apply and will be the sum of the individual reductions based on the bid price.

Inspection & Testing: At the vendor's location the stockpile shall be covered as required and the road salt shall be tested by Division of Materials Testing. The Bureau of Finance and Administration shall accept the material prior to any shipment to the State. Road salt from different origins (natural deposits/artificially produced) shall be stockpiled separately. If at any time, the purity of road salt is less than 95 percent sodium chloride, the vendor shall maintain this material in a physically separated stockpile. Once the stockpile has been accepted, material shall not be added to the stockpile without prior notification to and additional testing by the State. Failure to properly control these stockpiles may result in revocation of the award.

Material acceptance:

PURITY: The road salt requirements for material acceptance shall be as stated in AASHTO M— 143 (ASTM D—632) Type 1, except sections 9.1.2 and 11.2 will not apply. It is intended that only products meeting the specified sodium chloride content (95.0 percent or greater) will be accepted; however, at the sole discretion of the Department of Transportation, road salt having a purity of less than 95.0 percent sodium chloride content may be accepted with an adjustment in payment in accordance with Table 1.

Percent of Sodium Chloride	Percent Payment of Unit Bid Price
95.0% to 100%	100
93.0% to 94.9%	95
91.0% to 92.9%	90
90.9% & below	73

TABLE 1: Adjustment in Payment for Purity of Sodium Chloride

<u>Grading</u>: The gradation requirements for material acceptance shall be as stated below. Failure to conform to these requirements may result in rejection of the stockpile. If non-conforming material is accepted, a reduction in payment of 2 percent per screen shall be assessed for deviations in the gradation.

Sieve Size	Percent Passing by Weight
12.5 mm (1/2in.)	100
9.5 mm (3/8in.)	95 to 100
4.75 mm (No.4)	20 to 90
2.36 mm (No.8)	10 to 60
600 μm (No.30)	0 to 15

Moisture: Full payment will apply to the road salt when its moisture content does not exceed two (2.0) percent. Road salt with a moisture content greater than (2.0) percent may be accepted at the discretion of the Department, with an adjustment in weight for moisture content over 2.0 percent.

Anticaking Agent: Road salt furnished under this contract shall be free flowing and granular. All bulk road salt shall be treated with an approved conditioner, such as sodium ferrocyanide, to prevent caking while in storage. This treatment shall be prior to shipping product from the origin (natural deposits/artificially produced). This conditioner shall be visible and introduced uniformly throughout the road salt at a maximum rate of 50 parts per million or 0.0050 percent.

NON-REFLECTIVE PLASTIC SHEETING

REFERENCE FILE NO. 161-D

Issued October 19, 1962 Revised June 10, 1983

<u>Description</u>: The material shall consist of a flexible, pigmented plastic film, completely pre-coated with a solvent or heat-activated tack-free adhesive. The adhesive shall be protected by a paper liner, which shall be removable without soaking in water or other solvents.

Property Requirements:

A. Thickness: The thickness of the plastic film with adhesive shall be a minimum of 0.003 inches and a maximum of 0.0045 inches.

B. Film: The unapplied and/or applied film shall be readily processed with, and ensure adequate adhesion of, process inks recommended by the manufacturer.

1. Flexibility: The material shall be sufficiently flexible to permit application over and conform to moderately contoured surfaces.

2. Gloss: The film shall have an initial 60-degree gloss value of 35 (minimum), when tested in accordance with ASTM Method D 523, measuring at least three portions of the film to obtain uniformity.

C. Adhesive: The pre-coated adhesive shall form a durable bond to smooth, clean, corrosion- and weather-resistant surfaces, shall be of uniform thickness, non-corrosive to applied surfaces and shall have no staining effect on the film.

Adhesion: The material, applied according to Paragraph I "Preparation of Test Panels" shall have sufficient bond to prevent removal from the panel in one piece without the aid of a physical tool.

D. Exterior Exposure: The material shall withstand three years' vertical, south-facing exterior exposure in Texas, showing no appreciable discoloration, cracking, crazing, blistering, delamination or loss of adhesion. A slight amount of caulking is permissible.

E. Dimensional Stability: The material shall show no more than 1/64" shrinkage in any direction from edge of the panel when prepared in accordance with Paragraph I after being subjected to a temperature of 150° F for 48 hours.

F. Heat Resistance: The material applied according to Paragraph I, shall be heat-resistant enough to retain adhesion after one week at 150° F.

G. Solvent and Chemical Resistance: The material, when prepared in accordance with Paragraph I, shall withstand immersion in the following liquids at 70°-90° F, showing no appreciable decrease in adhesion, color or general appearance.

Liquids_		Time,
Hours		
Reference Fuel (MIL-F-8799A) (15 parts xylol – 85 parts mineral spirits by weight)	1	
Distilled Water		24
SAE #20 Motor Oil		24

H. Opacity: when applied, the material shall be sufficiently opaque to hide a contrasting black printed legend and white surface.

I. Preparation of Test Panels: Test panel shall be prepared using a $6 \frac{1}{2}$ " × $6 \frac{1}{2}$ " piece of the plastic film, applied to a clean 6" × 6" aluminum panel, pre-masked or as recommended by the manufacturer, trimmed evenly at the edge of the panel, and aged for 48 hours at 70-90°F.

J. Shelf Life Storage: The material shall withstand one year's shelf life when stored in a clean area free from exposure to excessive heat, moisture, and direct sunlight.

K. General Characteristics and Packaging: The plastic film shall be furnished in rolls, cut sheets or characters as may be specified. The film, as supplied, shall be free from ragged edges, streaks, blisters, foreign matter, or other

surface imperfections which would make it unsuitable for the intended usage, and shall be readily cut with scissors, knife, blade, shears, or other production tools. Complete and detailed instructions for mounting the plastic film shall be supplied with each package of material.

Rolls, sheets or letters shall be individually packaged in suitable containers and in such a manner that no damage or defacement may occur to the plastic film during transport to destination.

Quality Assurance: The vendor shall furnish a Certified Test Report conforming to the requirements stated herein below for all materials supplied under this specification.

1. A Certified Test Report is a document containing a list of the dimensional, chemical, and physical results obtained by an approved testing organization from an actual test of the material involved. It shall also certify that the materials meet the requirements of the specifications and shall include the following information:

- a. Description of material
- b. Connecticut Department of Transportation purchase order number.
- c. Date of manufacture.
- d. Date of testing.
- e. Name of organization to which the material is consigned.
- f. Quantity of material represented.
- g. Means of identifying consignment such as label, marking, lot number, etc.
- h. Date and method of shipment.
- i. Name of organization performing the tests.

EACH SHIPMENT SHALL BE ACCOMPANIED BY A CERTIFIED TEST REPORT. THIS REPORT SHALL STATE THAT MATERIAL FURNISHED WILL CONFORM TO THE SPECIFICATIONS IN EVERY DETAIL. The Certified Test Report shall be signed by an authorized and responsible agent for the organization supplying the material. The certificate MUST be notarized.

PROCESSED AGGREGATE REFERENCE FILE NO. 163-K

Issued: March 4, 1963 Revised: January 28, 2015

<u>Description:</u> Generally used by the Office of Maintenance as a base material for incidental work such as bike paths or ancillary paved surfaces.

Processed Aggregate shall conform to the following:

All Processed Aggregate shall conform to ConnDOT Standard Specifications, Article M.05.01, except that reclaimed material is prohibited and Medium processed aggregate shall conform to the following gradation:

Medium Processed Aggregate				
Square Mesh Sieves	Percent Passing by Weight (Mass)			
2 ½ in. (63 mm)	100			
2 in. (50 mm)	100			
1 ½ in. (37.5 mm.)	100			
1 in. (25.4 mm)	90-100			
¾ in. (19 mm)	75-100			
1⁄4 in. (6.3 mm)	30-60			
#40 (425 um)	5-25			
#100 (150 um)	3-12			

GRITS

REFERENCE FILE NO. 191-E Issued January 14, 1980 Revised June 29, 2001

REFERENCE FILE 191-E

CONNECTICUT DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING AND HIGHWAY OPERATIONS SPECIFICATION FOR GRITS

DESCRIPTION: Grits shall consist of sound, tough, durable particles of crushed or uncrushed screened stone or gravel, and shall be free from lumps of clay, soil, loam or organic matter.

MATERIAL REQUIREMENTS:

- <u>Soundness</u>: When tested for soundness with a magnesium sulfate solution using AASHTO Method T 104, the plus No. 4 fraction shall show a loss of not more than 10 percent at the end of five cycles.
- Loss on Abrasion: When tested by means of the Los Angeles Machine using AASHTO Method T 96, the plus No. 8 fraction shall show a loss on abrasion of not more than 40 percent.
- 3) <u>Flat and Elongated</u>: All plus No. 8 material shall not contain more than 15 percent of flat or elongated pieces, the longest dimensions of which exceed three times the maximum thickness.
- 4) <u>Grading:</u> The grit material shall conform to one of the gradations shown in Table 1 below. The grading will be specified on the Purchase Order.

Table 1. Fercent Passing per Orauling						
Sieve Size	Grading "A"	Grading "B"				
3/8	100	100				
#4	40-90	85-100				
#8	0-30	10-40				
#16		0-10				
#50	0-10	0-5				
#100	0-3					

	Table 1.	Percent Passing per Grading	
--	----------	-----------------------------	--

PREMIXED SODIUM CHLORIDE (Salt) AND CALCIUM CHLORIDE REFERENCE FILE NUMBER 194-E Issued March 12, 1976 Revised June 1, 1998

SCOPE:

This specification covers a premixed blend of sodium chloride (rock salt) and calcium chloride to be used for ice control on highways and bridges.

DESCRIPTION:

Sodium Chloride: The sodium chloride shall conform to the requirements of Reference File 139, latest revision.

Calcium Chloride: The calcium chloride shall conform to the requirements of AASHTO M 144, Type I.

MIXTURE:

The premix for the CONTNDOT shall be a completely uniform and free-flowing mixture of three parts sodium chloride by weight to one part flake calcium chloride by weight.

SAMPLES FOR TEST:

Before a purchase order is issued, vendor(s) awarded the contract must forward, UNBLENDED, a thirty-pound bag of sodium chloride and a ten-pound bag of calcium chloride to be used for test to the Director of Research and Materials, 280 West St., Rocky Hill, CT 06067.

GENERAL:

The State reserves the right to inspect or sample material at the place of manufacture or stockpile, or to test materials before accepting delivery.

EPOXY RESIN PAVEMENT MARKINGS, SYMBOLS AND LEGENDS

REFERENCE FILE NO. 199-C

Issued: November 1, 1985

Revised: October 30, 1995

<u>DESCRIPTION</u>: This specification covers reflectorized white and yellow two component epoxy resin to be used for pavement marking on both asphaltic and Portland cement concrete pavement surfaces. It is to be used in conjunction with a surface application of glass beads and in accordance with these requirements. Upon curing, it produces an adherent reflectorized stripe of specified thickness and width capable of resisting wear from traffic.

<u>CLASSIFICATION</u>: This specification provides for the classification of epoxy resin pavement marking system by type.

Туре І	A fast—cure material suitable for centerline, skipline and edgeline use
	under traffic conditions

- Type II A slow—cure material suitable for centerline, skipline and edgeline use under minimal traffic conditions; e.g., unopened roadways
- Type III A medium—cure material suitable for pavement marking message and transverse line work

MATERIALS -GENERAL REQUIREMENTS:

Standards - All standards herein are minimum standards.

<u>Identification</u>: Each container must bear a label with the following information thereon: Name and address of manufacturer, shipping point, grade production batch number, date of manufacture, shipping point, grade name and/or identification number, type of material, number of gallons, contract number, use intended, directions for application, and formula. Improperly labeled samples and deliveries will be rejected.

<u>Qualification of Manufacturer</u>: No material will be considered unless the firm submitting the material can meet the following conditions (these qualifications must be provided to approve a subcontractor for this work):

- a: that it has in operation a factory adequate for and devoted to manufacturer of the pavement marking material that it proposes to furnish;
- b. that it is capable of predicting batch sizes consistent with the quantities to be delivered;
- c. that it maintains a laboratory to scientifically control the product bid on to ensure accuracy and quality of formulation; and
- d. that it has produced pavement marking material over the past two (2) years with a successful application record.

<u>Certification</u>: The manufacturer shall furnish a certified test report by an independent testing laboratory prior to the start of work indicating that the material as specified has been tested in accordance with ASTM or ACI testing procedures noted in this specification. The certified test report shall indicate the results of testing for the following criteria:

Composition, Color, Adhesion Capabilities, Abrasion Resistance, Hardness, Tensile Strength, and Compressive Strength.

Additionally, infrared spectrophotometer plots for both components of the test material shall be included by the independent laboratory in the certified test report.

The manufacturer shall furnish certified test reports for each batch delivered for application at the project site. Certified test reports shall be in accordance with the State of Connecticut, Department of Transportation Standard Specifications for Roads, Bridges and Incidental Construction, Section 1.06.07 of the latest edition,

MATERIALS - DETAILED REQUIREMENTS:

<u>Epoxy Resin Material</u>: The material shall be composed of epoxy resins and pigments only. No solvents to be given off to the environment upon application to the pavement surface, nor fillers, will be allowed.

Composition:	WHITE (percent by weight) 20 <u>+</u> 2 Titanium Dioxide (ASTM D	YELLOW (percent by weight) 20 <u>+</u> 2 Chrome Yellow (ASTM
	476 Type III) 80 <u>+</u> 2 Epoxy Resins	D211 Type III) 75 <u>+</u> 2 Epoxy Resins

<u>Color</u>: The color of the WHITE material shall be no darker or yellower than color chip 17778 of Federal Standard No. 595a of the latest issue, when the material is placed in a Type EH weatherometer for a period of 500 hours and weathered according to ASTM F 42. The color of the YELLOW shall be reasonably close to color chip 13538 of the Federal Standard No. 595a of the latest issue.

<u>Adhesion Capabilities</u>: When the adhesion of the material to Portland cement concrete (the concrete shall have a minimum of 300 psi tensile strength) is tested according to American Concrete Institute Committee 503R testing procedure, the failure of the system must take place in the concrete. The concrete shall be 32 °C when the material is applied, after which the material shall be allowed to cure for 72 hours at 23 \pm 2 °C.

<u>Abrasion Resistance</u>: When the abrasion resistance of the material is tested according to ASTM C 501 with a CS-17 wheel under a load of 1000 grams for 1000 cycles, the wear index shall be no greater than 82. (The index is the weight in milligrams that is abraded from the sample under the test conditions)

<u>Hardness</u>: The Type D durometer hardness of the material shall be not less than 75 or more than 90 when tested according to ASTM D 2240 after the material has cured for 72 hours at 23 ± 2 °C.

<u>Compressive Strength</u>: The compressive strength of the material, when tested according to ASTM D 695, shall not be less than 12,000 psi after 72 hours cured at 23 ± 2 °C.

<u>Shelf Life</u>: The individual components shall not require mixing prior to use when stored for a period of 12 months.

<u>Glass Beads:</u> The moisture resistant glass beads shall meet the requirements of AASHTO M 246, except that glass spheres shall meet the gradation requirements as follows:

Grading "A"		Grading "B"	
Sieve Size	Percent	<u>Sieve Size</u>	Percent
% Passing #20	100	% Retained #10	0
% Passing #30	80—95	% Retained #12	0—5
% Passing #50	9—42	% Retained #14	5—20
% Passing #80	0—10	% Retained #16	40—80
C C		% Retained #18	10—40
		% Retained #20	0—5
		% Retained Pan	0—2

Glass beads conforming to the requirements of Grading "A" shall be applied at a rate of 25 pounds per gallon of epoxy pavement marking material.

If specified, glass beads conforming to the requirements of Grading "B" shall be applied at a rate of 12 pounds per gallon of epoxy pavement marking material, immediately followed by a scanned drop of glass beads conforming to the requirements of Grading "A" applied at a rate of 12 pounds per gallon of epoxy pavement marking material.

Traffic cones or any other acceptable method shall be used to protect the pavement marking until cured.

<u>Time To No—Track</u>: The Type I material shall be in "no—tracking" condition in 60 seconds or less.

The no-tracking condition shall be determined by actual application on the pavement of the pigmented binder at 20 mils wet, covered with glass spheres at a rate of 25 pounds per gallon. The lines for this test shall be applied with the specialized striping equipment operated so as to have the material at the manufacturer's recommended application temperature. This maximum no—tracking time shall not be exceeded when the pavement temperature varies from 50 °F to 120 °F, and under all humidity conditions, provided the pavement is surface dry.

The no-tracking time shall be determined by passing over the line with a passenger car or pickup truck in the simulated passing maneuver. A line showing no visual deposition of the material to the pavement surface when viewed from a distance of 50 feet shall be considered as showing "no— tracking" and conforming to this requirement for time to no-track.

WHITE AND YELLOW FAST-DRYING WATERBORNE PAVEMENT MARKING PAINT

REFERENCE FILE NUMBER 200-I

Revised: May 29, 2008

Scope: White and yellow fast-drying waterborne pavement marking paint to be applied to bituminous concrete and Portland cement concrete pavements. This paint shall be capable of being applied with paint striping equipment at an application temperature of 130° F to 145° F (54° C to 63° C).

General: Specifications and publications that apply are as follows:

FS: TT-P-1952 Paint, Traffic and Air Field Marking, Water Emulsion Base; Federal Test-Method Standard #141 Paint, Varnish, Lacquer and Related Materials, Methods of Inspection, Sampling and Testing; FS No. 595 Colors; and HH-R-59 Roofing Felt (Asbestos, Asphalt-saturated).

ASTM Standards: D 211-Specifications for Chrome Yellow and Chrome Orange; D 476-Specifications for Titanium Dioxide Pigments; D 562 Test for Consistency of Paints Using the Stormer Viscometer; D 869-Test for 45-deg, 0-deg Directional Reflectance Factor of Opaque Specimens by Broad Band Filter Reflectometry.

Detailed Requirements, Formulation and Manufacture: The paint shall be formulated and manufactured from first-grade raw materials and shall be free from defects and imperfections that might adversely affect the serviceability of the finished product. The materials shall not exhibit settling or jellying after storage in the sealed containers as received that will affect the performance of the products. The paint shall provide the proper anchorage, refraction and reflection for the finished glass spheres when applied as specified.

Composition: The composition of the paint shall be at the discretion of the manufacturer, provided that the finished product meets the requirements of any applicable Federal, State or Local regulations for products of this type and the requirements as follows:

1. Paint shall not contain more than 0.06% lead;

2 Total nonvolatile shall not be less than 76% by weight (mass);

3. Pigment shall be 58-63% by weight (mass);

4. Resin solids shall be composed of 100% acrylic emulsion polymer;

5. Volatile organic compounds shall not exceed 150 grams/liter, excluding water;

6. Closed-cup flash point shall not be less than 145° F (38° C);

7. Weight per gallon (mass per liter) shall not be less than 12.5 pounds/gallon (1.50 kilograms/liter) when tested in accordance with ASTM D 1475.

8. Drying time to no pick up shall be3 minutes or less when tested in accordance with ASTM D 711

Scrub Resistance: The paint shall pass test for scrub resistance when tested in accordance with ASTM D2486, Method B.

Viscosity: The consistency of the paint shall not be less than 80, nor more than 90 Kreb units when tested in accordance with ASTM D562.

Flexibility: The paint shall not show cracking or flaking when subjected to the TT-P-1952 flexibility test in which the panels used shall be tin plates that are 3 inches x 5 inches (76 millimeters x 127 millimeters) in area and 35 - 31 U.S. Gauge in thickness. The tin panels shall be lightly buffed with steel wool and thoroughly cleaned with solvent before being used for tests.

Dry Opacity: Both white and yellow paints shall have a minimum contrast ratio of 0.96. Contract ratio shall be determined by applying a wet film thickness of 0.005 inches (127 microns) to a standard hiding power chart. After drying, the black and white reflectance values shall be determined using a suitable reflectometer and the contrast ratio determined.

Bleeding: The paints shall have a minimum bleeding ratio of 0.97 when tested in accordance with FS TT-P-1952. The asphalt-saturated felt shall conform to FS HH-R-59.

Abrasion Resistance: No less than 210 liters of sand shall be required to remove paint film when tested in accordance with TT-P-1952.

Color: The paint shall not discolor in sunlight and shall maintain colorfastness throughout its life, approximately two years. Color determination shall be made without beads, after a minimum of 24 hours. Color for yellow paint shall be a visual match for 595-13538. If not a visual match, the diffuse day color of the paint shall conform to the CIE Chromaticity coordinate limits as follows:

	Х	У	X	У	X	У		ху	Brightness
<u>White:</u>	(x) 0.305	(y) 0.295	(x) 0.360	(y) 0.360	(x) 0.388	(y) 0.377	(x) 0.280	(y) 0.310	84.0
	(x)	(y)	(x)	(y)	(x)	(y)	(x)	(y)	
Yellow:	0.485	0.455	0.506	0.452	0.484	0.428	0.477	0.438	50.0

WHITE AND YELLOW REGULAR-DRYING WATERBORNE PAVEMENT MARKING PAINT REFERENCE FILE NUMBER 207- D

Revised: May 29, 2008

Scope: White and yellow regular-drying waterborne pavement marking paint that is to be applied to bituminous concrete and Portland cement concrete pavements. This paint shall be capable of being applied with paint striping equipment that does not require heating above ambient temperatures.

General: Specifications and publications that apply are as follows:

FS: TT-P-1952 Paint, Traffic and Air Field Marking, Water Emulsion Base; Federal Test-Method Standard #141 Paint, Varnish, Lacquer and Related Materials, Methods of Inspection, Sampling and Testing; FS No. 595 Colors; and HH-R-59 Roofing Felt (Asbestos, Asphalt-saturated).

ASTM Standards: D 211-Specifications for Chrome Yellow and Chrome Orange; D 476-Specifications for Titanium Dioxide Pigments; D 562 Test for Consistency of Paints Using the Stormer Viscometer; D 869-Test for 45-deg, 0-deg Directional Reflectance Factor of Opaque Specimens by Broad Band Filter Reflectometry.

Detailed Requirements, Formulation and Manufacture: The paint shall be formulated and manufactured from first-grade raw materials and shall be free from defects and imperfections that might adversely affect the serviceability of the finished product. The materials shall not exhibit settling or jellying after storage in the sealed containers as received that will affect the performance of the products. The paint shall provide the proper anchorage, refraction and reflection for the finished glass spheres when applied as specified.

Composition: The composition of the paint shall be at the discretion of the manufacturer, provided that the finished product meets the requirements of any applicable Federal, State or Local regulations for products of this type and the requirements as follows:

1. Paint shall not contain more than 0.06% lead;

2 Total nonvolatile shall not be less than 70% by weight (mass);

3. Pigment shall be 50-60% by weight (mass);

4. Resin solids shall be composed of 100% acrylic emulsion polymer;

5. Volatile organic compounds shall not exceed 150 grams/liter, excluding water;

6. Closed-cup flash point shall not be less than 145° F (38° C), and weight per gallon (mass per liter) shall not be less than 12.5 pounds/gallon (1.50 kilograms/liter) when tested in accordance with ASTM D 1475.

7. Weight per gallon (Mass per liter) shall not be less than 12.5 pounds/gallon (1.50 kilograms/liter) when tested in accordance with ASTM D 1475;

8. Drying time to no pick up shall be 15 minutes or less when tested in accordance with ASTM D 711

Scrub Resistance: The paint shall pass test for scrub resistance when tested in accordance with ASTM D2486, Method B.

Viscosity: The consistency of the paint shall not be less than 75, nor more than 85 Kreb units when tested in accordance with ASTM D562.

Flexibility: The paint shall not show cracking or flaking when subjected to the TT-P-1952 flexibility test in which the panels used shall be tin plates that are 3 inches x 5 inches (76 millimeters x 127 millimeters) in area and 35 - 31 U.S. Gauge in thickness. The tin panels shall be lightly buffed with steel wool and thoroughly cleaned with solvent before being used for tests.

Dry Opacity: Both white and yellow paints shall have a minimum contrast ratio of 0.96. Contract ratio shall be determined by applying a wet film thickness of 0.005 inches (127 microns) to a standard hiding power chart. After drying, the black and white reflectance values shall be determined using a suitable reflectometer and the contrast ratio determined.

Freeze-Thaw Resistance: After five freeze thaw cycles in accordance with ASTM D2243: 1) Evidence of settling, gelation, or coagulation in the can shall have a rating of no less than 8 (very slight). 2) The paint shall not have a change in viscosity (ASTM D562) of more than 10 Kreb units. 3) Test panel changes in hiding, gloss, speckiness, agglomeration, coagulation, or color change shall have a rating of no less than 8 (very slight).

Bleeding: The paints shall have a minimum bleeding ratio of 0.97 when tested in accordance with FS TT-P-1952. The asphalt-saturated felt shall conform to FS HH-R-59.

Abrasion Resistance: No less than 210 liters of sand shall be required to remove paint film when tested in accordance with TT-P-1952.

Color: The paint shall not discolor in sunlight and shall maintain colorfastness throughout its life, approximately two years. Color determination shall be made without beads, after a minimum of 24 hours. Color for yellow paint shall be a visual match for 595-13538. If not a visual match, the diffuse day color of the paint shall conform to the CIE Chromaticity coordinate limits as follows:

	Х	y	X	У	X	У		ху	Brightness
<u>White:</u>	(x) 0.305	(y) 0.295	(x) 0.360	(y) 0.360	(x) 0.388	(y) 0.377	(x) 0.280	(y) 0.310	84.0
	(x)	(y)	(x)	(y)	(x)	(y)	(x)	(y)	
Yellow:	0.485	0.455	0.506	0.452	0.484	0.428	0.477	0.438	50.0

Liquid Calcium Chloride Anti-icing Agent

REFERENCE FILE Number 2007-3

Issued August 1, 2007

Scope: This reference file consists of the specification for Liquid Calcium Chloride Anti-icing Agent, which is to be used with Sodium Chloride for snow and ice control by the Connecticut Department of Transportation (Department).

The supplier shall furnish a Certified Test Report and Materials Certificate as detailed below for each batch delivered to the Department.

The Certified Test Report is a document containing a list of the dimensional, chemical, metallurgical, electrical and physical results obtained from a physical test of the materials involved, and shall certify that the materials being supplied meet the requirements of this specification. Such Report shall also include the following information:

- (1) Description of materials
- (2) Date of manufacture
- (3) Date of testing
- (4) Name of organization to which the material has been consigned, if applicable
- (5) Quantity of material represented, such as batch, lot, group, etc.
- (6) Means of identifying the consignment, such as label, marking, lot number, etc.
- (7) Date and method of shipment
- (8) Name of organization performing tests

The Certified Test Report shall be signed by a duly-authorized and responsible agent for the organization manufacturing the materials, and the signature must be notarized.

A Materials Certificate is a document certifying that the materials, components and equipment furnished conform to all requirements of this specification. Such Certificate shall also include the following information:

(1) Quantity of material represented, such as batch, lot, group, etc., and certified test report identification number representing materials being delivered

- (2) Quantity of material represented by the certificate
- (3) Means of identifying the consignment, such as labels, lot numbers, etc.
- (4) Date and method of shipment

The Materials Certificate shall be signed by a duly-authorized and responsible agent for the organization supplying the material, and the signature must be notarized.

The supplier shall be responsible for all testing and materials certificates.

<u>Samples:</u> The ConnDOT representative may take one gallon sample at start, and one gallon prior to the end of delivery, Samples must be taken directly from the truck.

References to the web site of the Pacific Northwest Snowfighters Association (PNSA) of British Columbia, Idaho, Montana, Oregon and Washington (<u>http://www.wsdot.wa.gov/partners/pns/default.htm</u>) are exclusively to the 2007 <u>testing method(s)</u> that the Department's Division of Materials Testing will use to determine if the product meets this specification. PNSA <u>specifications</u> listed on the PNSA Web site are for information only and do not necessarily reflect requirements of this REFERENCE FILE (Number 2007_3).

ConnDOT Test Methods and Specification Limits:

ConnDOT Test #1 - Percent Concentration of Active Ingredient in the Liquid

The Product shall be 32% Calcium Chloride by weight; tolerance: ±1%, per PNSA Test Method Number 1 on page 24 of the PNSA Web site or by ASTM methods D345 and E449. It is intended that only products meeting the specified Liquid Calcium Chloride content of 31% to 33% will be accepted; however, at the sole discretion of the Department of Transportation, Liquid Calcium Chloride content lower or greater than this percent may be accepted with an adjustment in payment in accordance with table 1.

Percent of Liquid Calcium	Percent Payment of Unit Bid Price
29% to 30%	90
34% to 35%	90

At the sole discretion of the Department, Liquid Calcium Chloride content lower than 29% or greater than 35% is subject to rejection and nonpayment.

All test data shall be rounded in accordance with the latest version of **AASHTO R11**.

ConnDOT Test #2 - Weight per Gallon

Specific Gravity by ASTM D 1429 Test Method A - Pycnometer at 20°C +/- 1°C per PNSA Test Method Number 2 on page 24 of the PNSA Web site.
ConnDOT Test #3 - PH

The PH shall be between 6.0 -10.0 per PNSA Test Method Number 4 on page 24 of the PNSA Web site.

ConnDOT Test #4 - Sampling Liquid Calcium Chloride

Sampling Liquid Calcium Chloride shall be done in accordance with ASTM D345. Product shall be tested using generally accepted industry standard analytical procedures as appropriate.

ConnDOT Test #5 - Visual Inspection and Field Observations

A ConnDOT representative may perform a visual inspection `to assure that the material remains clean and free of extraneous matter, remains free from hard caking, does not segregate, and remains suitable for the intended purpose and as otherwise outlined in Section IV. <u>NOTE:</u> Purchaser may use any laboratory test method necessary to verify conclusions from visual inspections. Per PNSA Test Method Number 14 on page 25 of the PNSA Web site.

ConnDOT Test #6 - Total Arsenic, Barium, Cadmium, Chromium, Copper, Lead,Mercury, Selenium,Zinc, Phosphorus, and Cyanide

Atomic Absorption Spectrophotometry or Plasma Emission Spectroscopy as described in "Standard Methods for the Examination of Water and Waste Water," APHA-AWWA-WPCF per PNSA Test Method Number 9 on page 25 of the PNSA Web site.

A submitted product that contains any constituent in excess of the following established total concentration limits as tested in accordance with the above test shall not be acceptable. Results are stated as parts per million (ppm).

Arsenic	1.0 ppm
Barium	100.0 ppm
Cadmium	0.20 ppm
Chromium	1.0 ppm
Copper	1.0 ppm
Lead	1.0 ppm
Mercury	0.05 ppm
Selenium	5.0 ppm
Zinc	10.00 ppm
Phosphorus	250.00 ppm
Cyanide	0.20 ppm

Note: Liquid products shall be tested as received.

All laboratory results must be below the maximum concentrations listed above.

Appendix G – Standard Operating Procedures

	Version	Date	Pages
Portland Cement Concrete			
Compression Testing	V1.1	Dec 2014	G2-G6
Grout			
Compression Testing	V1.0		G7-G12
Bituminous Concrete			
In-place density using Cores	V1.1	Dec 2014	G13-G18
Steel Reinforcement			
Tensile Testing			Pending
Bend Testing			Pending
Hardness Testing			Pending
Snow and Ice Control			
Testing for Moisture of Roadway Salt	V1.0		G19

TINIUS-OLSEN COMPRESSION MACHINEVersion 1.1Standard Operating Procedure



John Giannini

Supervisor of Laboratory/Workshop

Tinius-Olsen Hydraulic Compression Tester Equip. #68-3695

Name and Function of Lab/Project

Mechanical & Electrical

Type of hazards (mechanical, electrical, chemical, biological or radiation)

Room 150

Location

Tinius-Olsen

Make

400,000 Lbf Super "L"

Model

A. Introduction/Features

- 400,000 Lbf Capacity
- Heavy-duty, ultra-stiff frame design permits testing of 6" X 12" and 4" X 8" concrete cylinders
- Side and rear safety guards ensure operator safety
- High-accuracy pressure transducer load weighing system
- HP Compaq MXL31707H6 Controller
- Wire safety cage to prevent debris from falling outside testing area.

B. Health and Safety Considerations

I. Safety devices required (e.g. machine guards, personal protective equipment, etc.)

- *SAFETY GOGGLES/GLASSES* must be worn **at all times in the lab**. Prescription glasses can be worn under the safety goggles.
- HARD TOE BOOTS/SHOES must be worn at all times while handling cylinders.

II. General Safety

- FOOD AND DRINK are not allowed in any laboratory.
- Be aware of the specific hazards associated with each lab procedure.
- Wear appropriate clothing and foot wear (NO OPEN-TOED SHOES).
- Familiarize yourself with all emergency safety equipment (eyewash, fire alarm, fire extinguishers, telephone).
- Do not leave in-progress tests unattended.
- Keep work areas Clean.

TINIUS-OLSEN COMPRESSION MACHINE 1.1 Standard Operating Procedure



Version 1.1

FIRE: Immediately **report it to a supervisor** and then exit the laboratory and building quickly via proper exit route. (Make sure you know where the exits are located.)

ACCIDENTS AND INJURIES must be reported to a supervisor. There are emergency first aid supplies available, and emergency responders are trained in basic first-aid.

THE BEST SAFETY PRECAUTIONS include **ADVANCED PREPARATION** for each laboratory and a **CLEAN ORGANIZED WORK SPACE**.

C. Operation Procedures:

The following guidelines are for persons who are authorized to use the Tinius-Olsen compression machine for ASTM C-39 & ASTM-1231. If a person is operating equipment for the first time, a competent operator of that equipment must also be present.

Power On equipment

1. Turn on the testing machine by using the power switch (LPLH-LF-CIR.9) located on the wall near the service panel to the right of the testing machine as shown in Figure 1.



Figure 1. Power Switch Location for Tinius-Olsen Compression Machine

2. Turn on computer and computer monitor using switches shown in Figure 2.



Figure 2. Computer and Monitor Power Switches

TINIUS-OLSEN COMPRESSION MACHINE Standard Operating Procedure



Version 1.1

Turn on hydraulic pump by pressing "Pump" button on handheld controller as shown in Figure 3. When leaving the area of the machine for an extended period of time (10 minutes or more) shut off pump.

1) <u>**PUMP</u>** will appear on the display (let pump warm up for about 20 seconds)</u>

2) Press "Return" button on handheld controller (the bottom compression plate will raise to specific height)



Figure 3. Handheld Controller and Compression Plates

- a. Using the computer mouse, Click on "Navigator" icon on the computer monitor
- b. Using the steps below, check that the software is configured for the proper size cylinder.

1) go to file

2) load test setting

3) #8 for 6x12 or #9 for 4x8

Test Preparation

- c. Review MAT-308 and enter project number and sample ID on "NEXT" tab
- d. Check cylinder markings for concurrence with MAT-308
- e. Type in or check appropriate cylinder size (typically 6 or 4 inches) is displayed
- f. Place test caps on bottom and top of cylinder. Caps are shown in Figure 4.
- g. Properly place specimen (centered on bottom compression plate)
- h. Place wire safety cage centered around specimen, close cage. Cage is shown in Figure 4.

TINIUS-OLSEN COMPRESSION MACHINE Standard Operating Procedure

Version 1.1



Figure 4. Wire Safety Cage and Test Caps

3. Test Procedure

4"x8" cylinders

- a. Double click on 1 in top menu bar to raise base plate until the cylinder is located ¹/₈" from top plate then click on the red STOP sign.
- b. Click on the "LOAD ZERO" icon in top menu bar (handheld controller should show zero load)
- c. Click on TEST NOW button
- d. Monitor the testing (Click on ABORT button if needed)

6"x12" cylinders

- a. Click on the "LOAD ZERO" icon in top menu bar (handheld controller should show zero load)
- b. Click on TEST NOW button
- c. Monitor the testing (Click on ABORT button if needed)
- 4. Documentation of Results
 - a. Observe how specimen broke and that no contact with wire safety cage was made.
 - b. Double check project number and sample ID, edit on "RESULTS" tab if needed.
 - c. Click on "ACCEPT" if no issues were observed. Click "DISCARD" if needed.
 - d. Record Total load and Load (PSI/Mpa) on Mat-308 from yellow highlighted information at the bottom the window.
- 5. Remove crushed specimen
 - a. Open and remove wire safety cage
 - b. Discard crushed specimen in yellow rolling metal bin.
 - c. Clean bottom plate of any debris.

TINIUS-OLSEN COMPRESSION MACHINEVersion 1.1Standard Operating Procedure



- 6. To test another specimen;
 - e. Press the "**NEXT**" tab;
 - f. Return to step 2
- 7. Clean and shutdown
 - g. Properly close "Navigator" window by clicking on [X] in top right corner.
 - h. Click on "Start" icon in lower left corner and select "SHUTDOWN" from menu.
 - i. Turn pump off using handheld controller shown in Figure 3.
 - j. Switch test equipment off by using switch shown in Figure 1.
 - k. Clean floor, pan, and plates of any debris.
 - 1. Record number of cylinders tested on Pad Usage Sheet in three ring binder located on test console.

If you ever have any doubts or questions, ASK!

Emergency Contacts:

John Giannini, Supervising Engineer, 860-258-0324

Daniel Guzzo, Transportation Engineer III, 860-258-0339

Mark Brothwell, Transportation Engineer II, 860-258-0378

FIRE/AMBULANCE/SAFETY -Emergency Response, 9-911

SATEC COMPRESSION MACHINE Standard Operating Procedure

Version 1.1

John Giannini

Supervisor of Laboratory/Workshop

SATEC SYSTEMS Hydraulic Compression Tester Equip. #68-3712 Name and Function of Lab/Project

SATEC-QC PRISM

Make

Mechanical & Electrical

Type of hazards (mechanical, electrical, chemical, biological or radiation)

Room 155

Location

Mark III Smart "C" 100QC Model

A. Introduction/Features

- 100,000 Lbs. Capacity
- Heavy-duty, ultra-stiff frame design permits testing of 2" X 2" grout cube
- Side and rear safety guards ensure operator safety
- High-accuracy pressure transducer load weighing system
- Mark III Smart "C" Indicator display Controller
- Wire safety cage to prevent debris from falling outside testing area.

B. Health and Safety Considerations

I. Safety devices required (e.g. machine guards, personal protective equipment, etc.)

- *SAFETY GOGGLES/GLASSES* must be worn **at all times in the lab**. Prescription glasses can be worn under the safety goggles.
- *HARD TOE BOOTS/SHOES* must be worn at all times while handling cubes.

II. General Safety

- FOOD AND DRINK are not allowed in any laboratory.
- Be aware of the specific hazards associated with each lab procedure.
- Wear appropriate clothing and foot wear (NO OPEN-TOED SHOES).
- Familiarize yourself with all emergency safety equipment (eyewash, fire alarm, fire extinguishers, telephone).
- Do not leave in-progress tests unattended.
- Keep work areas Clean.

See attached sheets pages 1-5



CONVECTICATION

SATEC COMPRESSION MACHINE Standard Operating Procedure



COMPRESSION MACHINE PROCEDURES



These buttons will all be explained on the next few pages.

SATEC COMPRESSION MACHINE Standard Operating Procedure





3|Page Division of Materials Testing - Room 155 Nov, 2016

SATEC COMPRESSION MACHINE Standard Operating Procedure





SATEC COMPRESSION MACHINE Standard Operating Procedure





SATEC COMPRESSION MACHINE Standard Operating Procedure







Eliana Carlson

Supervisor of Laboratory/Workshop

Handling and Testing Hot Mix Cores for Density Determination

Name and Function of Lab/Project

Mechanical & Electrical

Type of hazards (mechanical, electrical, chemical, biological or radiation)

Rooms 162 and 159

Location

Various

Make

Various

Model

A. Introduction/Features

- Procedures to be followed for the in-place density of bituminous concrete mixtures by testing cores samples
- Handling of the bituminous concrete core samples include:
 - Receiving core samples (chain of custody)
 - Organization
- Testing of the bituminous concrete core samples include:
 - Saw cutting core samples
 - Drying core samples
 - Testing for bulk specific gravity
 - Reporting
 - Core sample retention and disposal
- Equipment:
 - 5 Vacuum drying apparatus located in room 162:
 - Make: Instrotek
 - Model: CoreDry
 - 1 Automatic vacuum sealing apparatus located in Room 162
 - Make: Instrotek
 - Model: CoreLok
 - 2 Radial cutting table saws located in Room 159
 - Make: Nuova Mondial Mec
 - Model: Manta ED 120



B. Health and Safety Considerations

I. Safety devices required (e.g. machine guards, personal protective equipment, etc.)

- *SAFETY GOGGLES/GLASSES* must be worn when operating the table saw. Prescription glasses can be worn under the safety goggles.
- SAFETY EAR PROTECTION must be worn when operating the table saw.
- The operator shall keep all body parts outside the *MACHINE GUARDS* when operating the table saw
- *HARD TOE BOOTS/SHOES* must be worn at all times in the laboratory.

II. General Safety

- **FOOD AND DRINK** are not allowed in any laboratory.
- Be aware of the specific hazards associated with each laboratory procedure.
- Wear appropriate clothing and foot wear (**NO OPEN-TOED SHOES**).
- Familiarize yourself with all emergency safety equipment (eyewash, fire alarm, fire extinguishers, telephone).
- Do not leave in-progress tests unattended.
- Keep work areas Clean.

FIRE: Immediately **report it to a supervisor** and then exit the laboratory and building quickly via proper exit route. (Make sure you know where the exits are located.)

ACCIDENTS AND INJURIES must be reported to a supervisor. There are emergency first aid supplies available, and emergency responders are trained in basic first-aid.

THE BEST SAFETY PRECAUTIONS include **ADVANCED PREPARATION** for each laboratory and a **CLEAN ORGANIZED WORK SPACE**.

C. Equipment Maintenance

All maintenance operations shall follow the corresponding operator's manual.

CoreDry Maintenance:

- Change the vacuum pump oil (InstroTek part number 1520137) after 80 hours of use. A software indicator will prompt you to do so. Keep the maintenance records updated in the corresponding calibration and maintenance book.
- Change your Tank Filters (InstroTek part number 1009012) every 1 to 2 months. Keep the maintenance records updated in the corresponding calibration and maintenance book.



- Change your exhaust filter (InstroTek part number 1520084) on the vacuum pump once a year. Keep the maintenance records updated in the corresponding calibration and maintenance book.

CoreLok Maintenance:

- Weekly, check oil level, the condition of the silicon pad in lid, the condition of the silicon gasket in lid, the condition of the seal bar Teflon tape and seal element, the condition of the CoreLok lid and glass viewing window. Keep records of the oil refills in corresponding calibration and maintenance book.
- Yearly, replace vacuum oil using 10-weight synthetic oil, exhaust filter, seal element and Teflon tape of the seal bar. Keep records of these replacements in the corresponding calibration and maintenance book.

D. Operation Procedures – Handling Bituminous Concrete Core Samples:

Receipt of Cores (Chain of Custody):

The Contractor is responsible to obtain, label and transport core samples to the DMT. The Engineer will select the core locations, witness the extraction and labeling of the core samples and will complete Form MAT 109. The cores and corresponding MAT 109 will be delivered to the DMT in a secured container approved by the Engineer. Upon delivery DMT staff will:

- 1. Inspect the container and cut the security seal(s).
- 2. Verify the security seal numbers match numbers documented on MAT 109.
- 3. Check in and take possession of each core sample by comparing the labeling on the core to the sample identifications listed on the MAT 109 and inspecting each core sample for visible damage. Document discrepancies or damaged core(s) on the MAT 109. The DMT inspector will initial and date the MAT 109.
- 4. If no discrepancies exist, place cores and MAT 109 on a rack for testing.
- 5. If discrepancies or damaged samples are found, notify the room lead who will send an e-mail to the project inspector or other designated district staff detailing the observation(s).
- 6. Damaged cores shall not be tested.
- 7. If a Mat 109 or security seal(s) are not present, the room lead will send an e-mail to the project inspector or other designated district staff. The cores will be retained until such time a decision is made to test or not.
- 8. Once the observation(s) is cleared the sample(s), or replacement sample(s), will be placed on a rack for subsequent testing.

Organization:

Log in all the core samples received (including damage cores and note this in the corresponding column) in the "Tracking Cores" file located in the year folder in: S:\Verification & Cores\HMA Core Density Testing. The room lead will input an entry in the tracking file for any correspondence with project personnel.



E. Operation Procedures – Testing Bituminous Concrete Core Samples:

The following guidelines are for persons who are authorized to use the CoreDry, CoreLok and Table Saws for ASTM D 7227/D 7227M & AASHTO T 331. If a person is operating any of this equipment for the first time, a competent operator of said equipment must also be present.

Sample Preparation - Saw Cutting Core Samples:

When applicable, the core will be separated into individual lifts. This will be accomplished by slight strokes with a chisel or the use of a table saw. Care shall be taken to ensure the lift to be tested is not damaged. In general, any sample that cannot be readily separated into individual lifts by the use of a chisel or if the testing bag does not conform to the specimen in a uniform manner will be saw cut. Any remaining material that is not used for testing will be discarded. The lift will be cleaned to remove any deleterious material from the coring or sawing process.

Before operating the table saw, refer to the corresponding job hazard analysis document in Appendix A of this manual.

Sample Preparation - Drying Core Samples:

- 1. CoreDry Daily Test: Everyday, before starting operation, test the CoreDry equipment according to the equipment manual. If the test fails, notify the room lead.
- 2. Towel-dry the surface of the core and place it on its side on the wire mesh sample support (Figure 1).
- 3. Place the lid on sample chamber (Figure 2 red arrow) and press start (Figure 2 blue arrow).
- 4. When sample is dry, the unit will automatically stop and the lids can be removed.
- 5. If the sample is not dry after 45 cycles, remove the sample and place at room temperature for 15 minutes and continue drying the sample.
- 6. Between samples, remove the cold trap lid (Figure 2 green arrow) and the divider plate and wipe out the cumulate moisture using a lint free cloth. Always replace the divider before drying the next sample.





Figure 1. Placing a Core Sample in the CoreDry Sample Chamber (Instrotek CoreDry Manual)



Figure 2. CoreDry Components

Testing for Bulk Specific Gravity:

- 1. Select and inspect the bag for holes or stress points. Do not use the bag if you find holes or stress points.
- 2. Record the thickness of the core in column L in the "input" sheet in of Form MAT 438.
- 3. Weight the bag and enter this weight in column F in the "input" sheet in of Form MAT 438.
- 4. Weigh the dry sample and record the sample weight in column G in the "input" sheet in of Form MAT 438.
- 5. Check CoreLok oil level as indicated in the equipment operator manual.
- 6. Place the bag in the CoreLok Chamber and carefully place the sample inside the bag. The bag opening shall be over the seal bar (Figures 3 and 4) with approximately 1" overlap.
- 7. Close the CoreLok door and the equipment will seal the bag,
- 8. Record the weight of the sample sealed inside the bag under water in column I in the "input" sheet in of Form MAT 438. Make sure that the bag is not touching the sides or bottom of the water tank and that all entrapped air has been remove (this may be accomplished by gently shaking the bag under water).
- 9. Remove the bag and sample from the water bath, cut the bag and record the dry weight of the core in column J in the "input" sheet in of Form MAT 438. If the dry weight of the core before and after test in column J and G differ by more than 1gr, repeat the process from 1 thought 9.
- 10. All weights of shall be entered into the electronic MAT 438 between two days of testing and all the data shall be reviewed.
- 11. Notify your chain of command and obtain a quote when the stock of bags is reduced to ten boxes (1000 bags).



Version 1.1



Figures 3 and 4. CoreDry Seal bar and Sample Placement (Instrotek CoreLok Manual)

Reporting:

The percentage compaction shall be reported as the percent of the average day's production acceptance maximum theoretical gravity (Gmm) results performed in accordance with AASHTO T 209. Gmm test results determined to be invalid will not be included in the daily's average Gmm determination. The Engineer may replace the contractor's Gmm result(s) with the verification result(s). If Gmm test results are not available from acceptance testing, the Gmm shall be tested from a sample obtained by breaking down the core after the core has been tested or shall be determined from historical data.

The percent compaction of each core (sub-lot) will be determined using the following formula:

Percent compaction = 100[Gmb of core / Gmm of day's production (avg.) or Gmm core sample or historical Gmm]

All percent compaction results will be reported to the nearest 0.1 percent. The density report will automatically mark in red all individual density results that are outside the 87-95% range and that are outside +/-3.5% of the average. The cores that provide results on red will be re-tested.

The handling, testing and reporting of core samples will be monitored and reviewed by DMT supervisory staff (E3 and above) on an ongoing basis. Any change to the standard procedure, shall be approved by the SE or above prior to implementation.

Once a lot is completed the results shall be emailed by the DMT's core testing room lead to project inspection staff or other designated district staff. At no time will the DMT forward results directly to the Contractor. In general, the following shall be included in the email list:



Version 1.1

- Construction projects; Project Engineer, Project Inspector, District email, DMT chain of command.
- VIP and other Maintenance Projects; District Planners and/or other designated staff, DMT chain of command.
- Municipal Projects; Muni Team leader, Muni team inspector (if known), muni MAT 100 email, DMT chain of command.

Report Form: Form MAT 438 or other form approved by the DMT.

Core Sample Retention and Disposal:

After the specific gravity testing has been completed and reviewed by the room lead, store the tested core in the back hall rack for a two-week period. After two weeks, dispose the cores in the HMA recycling bin located in the back dock. In general cores that are below the minimum acceptable density (negative adjustment range) should be retained for a slightly longer period to allow for inspection by others. Any lot that is remove and replace will be retained until such time it is determined they are no longer needed.

If you ever have any doubts or questions, ASK!

Emergency Contacts:

Eliana Carlson, Supervising Engineer, 860-258-0325

David Howley, Transportation Engineer III, 860-258-0350

Shane St. Lauren, Transportation Technician III, 860-258-03??

FIRE/AMBULANCE/SAFETY -Emergency Response, 9-911



Division of Materials Testing

Why is roadway salt tested for moisture content?

- Roadway salt is paid for based on gross weight.
- Specifications allow 3% moisture content for full payment.
- Weight of water in excess of 3% is deducted from payment by contract administrator (Purchasing).
- Salt with excess moisture may clump and freeze, making handling difficult.

Scale Inspection/Check

- Scales must be labeled with current calibration date.
- Scale must show same reading (within 0.1 gram) when weighing the same reference weight.
- These steps must be performed before each test or if a scale has been moved.



Sample, and chain of custody, must be maintained at all times.

- Sample must be representative of the pile being tested.
- Sample must not be taken from surface of a pile.
- **<u>Do not</u>** pick out large or discolored particles.
- Take samples from no less than 3 areas of the pile.
- All equipment used in the testing process must be maintained at all times.





Connecticut Department of Transportation Equipment Needed:

Oven



Calibrated Digital Scale



Shovel / Scoop / Sample Thief

Sampling Containers/Sampling Bag



Division of Materials Testing

Page |3

•

Reference: Standard Testing Specification For (Sodium Chloride ASTM D632)

This procedure must be consistently and thoroughly followed.

Sampling:

1. Scrape aside the top layer of salt to a depth of no less than 1 inch.



Figure 1 - Preparing field sampling location



- 2. Take approximately 500 g of material to a depth of six inches.
 - Repeat steps 1 and 2 at two locations, no less than five feet from each other.



Figure 2 - Sampling

3. Place the three samples in a sample bag.



Figure 3 - Filling field sample bag



4. Sample bag must be closed tightly while transporting field sample.



Figure 4 – Securing sample bag

5. The field sample must be reduced to a minimum of 300 grams test sample using sample splitter.



Figure 5 - Sample splitter

6. Determine the mass of the test sample and a metal container of stable shape and weight, using a scale.



7. Place the test sample, within the container into the drying oven at a temperature of $230^{\circ} \pm 9^{\circ}$ F.



Figure 7 – Drying oven

- 8. Cool sample on the counter until cool to the touch, then determine the mass weight of the test sample and container.
- 9. Repeat steps 7 and 8 until test sample weight changes less than 0.1 %.
- 10. Use the following formula to determine the moisture content of the test sample.



References

Photos:

- 1. Oven "Clarkson Laboratory",
 - <u>http://store.clarksonlab.com/O4325-B.aspx</u>
- 2. Digital Scale "Scale Palace",
 - <u>https://scalepalace.com/index.php?main_page=index&manufacturers_id=6&sor</u> <u>t=20a&page=3</u>
- 3. Scoop "Cole-Palmer",
 - <u>http://www.coleparmer.com/Product/Stainless Steel Scoop 201 Grade 5 oz</u> <u>1 each/EW-07205-01</u>
- 4. Sample Thief Wilkey Industries, Inc",
 - <u>http://www.wilkeyindustries.com/sample-probe.php</u>
- 5. CTDOT Salt Shed "Ctpost",
 - <u>http://www.ctpost.com/local/article/Storms-draining-road-salt-supplies-</u> <u>straining-5222298.php</u>

✤ All other photos are property of <u>CTDOT</u>



Index

Admixtures for Portland Cement Concrete, 31 Aggregate Degradation, Resistance to, 24 Aggregate Soundness, 24 Aggregate, Bulk Density, 24 Aggregate, Flat and/or Elongated Particles, 24 Aggregate, Fractured Particles, 24 Aggregate, Inorganic Impurities in., 24 Aggregate, Mechanical Analysis for HMA, 33 Aggregate, Reducing Sample size, 23 Aggregate, Sampling, 23, 26 Aggregate, Sieve analysis, 23 Aggregate, Specific Gravity and Absorption, 24 Aggregate, Total Evaporative Moisture Content, 24 Aggregate, Voids in, 24 Aluminum, Castings, 17 Aluminum, fittings, 17 Aluminum, tubing, 17 AMRL Certification Document, 41 Anchor Bolts, Steel, 18 Anchorages, Cable Guide Rail, 18 Asphalt, Emulsified, 22 Asphaltic Plug Joint, 22 Bearing Pads, 19 Bearing Pads, Elastomeric, 19 Bearing plates, bronze or copper, 19 Bolts, Anchor, 18 Bolts, High strength Steel, 20 Bronze Bearing plates, 19 Bronze Expansion plates, 19 Bulk Specific Gravity of HMA, 33 Cable Guide Railing, 18 Calcium Chloride, 10 Cement, 15 Chain Link Fence, 17 Compression Seals, Elastomeric, 16 Concrete Block, 16 Concrete Brick, 16 Concrete Mix Design, 14 Concrete Pavement, Transverse joints, 16 Concrete Pipe inspection, 26 Concrete, Admixtures, 31 Concrete, Gravimetric test, 31 Concrete, Inspection of batch plants and truck mixers), 31 Concrete, Pipe reinforced, 26 Copper Bearing plates, 19 Copper Expansion plates, 19

Evaporative Moisture Content, Aggregate, 24 Expansion plates, Bronze or Copper, 19 Fence, Chain Link, 17 Fence, Wire, 18 Fertilizer, 11 Geotextiles, 18 Glass Beads/Spheres, 11 Grass, 11 Grout, non-shrink, non-staining, 15 HMA Plants, Annual Qualification, 32 HMA Sampling, 32 HMA, Gyratory Specimens, 33 HMA, Mix Design Submittal and JMF Change Procedure, 34 HMA, New and Existing Mixes, 34 HMA, Particle Coating, 33 HMA, Personnel Assignment, 32 HMA, Plant Inspector, 34 HMA, Production Inspection, 34 HMA, Resistance to Moisture Induced Damage, 39 HMA, VMA and Correction Factor, 33 HMA, Volumetric and Specific Gravity, 39 Hot Mix Asphalt, 21 Illumination, Highway, 20 Independent Assessment/Verification Program, 42 Joint Sealants, 15 Joints, Transverse for Concrete Pavement, 16 L.A. Abrasion, 24 Magnesium Sulfate, 24 Markers, Object, 21 Masonry Facing, 24 Maximum Specific Gravity of HMA, 34 NUCLEAR DENSITY OF SOILS / 40 Object Markers, 21 Organizational Chart, 6 Overview, Division of Materials Testing, 5 Paint, Pvmnt Marking 15 Min., 10 Paint, Trafffic 3 Min., 10 Peat, 11 Perforated Concrete Pipe, 12 Performance Graded Asphalt Binder (PGAB), 39 Piles. Steel, 19 Pipe, Concrete, 26 Pipe, Concrete Perforated, 12 Pipe, Concrete plain, 12 Pipe, plastic, 13

Pipe, polyethylene, 13 Pipe, PVC, 13 Pipe, Steel, Welded and Seamless, 13 Plain Concrete Pipe, 12 Portland Cement, 14, 15 Precast Concrete Drainage Items, 12 Precast Concrete for drainage structures, 12 Precast Concrete Structural Members, 15 Purpose, 4 Quality Acceptance Section (QAC), 7 Quality Assurance Section, 8 Rock Salt, 10 Sampling, Care in, 25 Sealers, Hot Poured, 16

Seed, 11 Signs, 21 Sod, 11 Sodium Chloride, 10 Steel, Anchor Bolts, 18 Steel, Coatings, 10 Steel, High strength bolts, 20 Steel, Reinforcing Bar, 14 Steel, Structural, 19 Steel, Welded Wire Fabric, 14 Steel, Wire, 14 Top Soil, 12 Washing, Material finer than #200 Sieve, 23 Water, 11 Waterproofing, Membrane, 22 Welding, Filler metal, 19 Wire Fence, 18