

TREE ON NORTH SIDE OF INTERSECTION
(LOOKING NORTHWEST)

CONCEPTUAL DESIGN

WINTONBURY AVENUE

RE-ALIGN EXISTING DRIVEWAY

REMOVE LARGE TREE
INSTALL LANDSCAPING BUFFER

MAINTAIN EXISTING ENTER
AND EXIT ONLY DRIVEWAYS

UTILITY POLE IMPACT

ROUTE 178
(WINTONBURY AVENUE)

CAMELOT DRIVE

R 33'
R 47'
R 65'

8'
16'
15'

SECONDARY CHURCH DRIVEWAY
(RIGHT-IN / RIGHT-OUT ONLY)

UTILITY POLE IMPACT

POTENTIAL UTILITY
POLE IMPACT

APPROXIMATE PARTIAL TAKING LINE (TYP)

IMPACTS TO UTILITY POLE, TREES & SIDEWALK

REMOVE TREES
INSTALL LANDSCAPING BUFFER

BLOOMFIELD
UNITED METHODIST

EXISTING BUS STOP

PRIMARY CHURCH DRIVEWAY
(FULL ACCESS)

EXISTING BUS STOP

ROUTE 178 (SCHOOL STREET)

PER REFERENCE (NG)

ASSUMED NORTH



JUNCTION POLE AND TREES ON SOUTHEAST CORNER
(LOOKING SOUTHWEST)

BASE MAP SOURCE:

- 2025 NEARMAP AERIAL
- CT GEODATA PORTAL PARCEL DATA

REVISION DESCRIPTION | DATE | REV.

SIGNATURE BLOCK: Tighe&Bond

DESIGNER/DRAFTER: MDS CHECKED BY: COG

0 40' 80'
HORIZONTAL SCALE
1" = 40'

CTDOT CONNECTICUT DEPARTMENT OF TRANSPORTATION

PROJECT TITLE: STATEWIDE ROUNDABOUT STUDY

TOWN(S): BLOOMFIELD

DRAWING TITLE: ROUTE 178 (WINTONBURY AVE/ SCHOOL ST) AT WINTONBURY AVE CONCEPT PLAN

PROJECT NO.: 0170-3632

DRAWING NO.: CON-4C

SHEET NO.:

LASTED SAVED BY: RCase **FILE NAME:** J:\C\C1023 CTDOT-2014 Oncall Traffic\031 - Statewide Roundabout Study\Drawings\Microstation\Contract_Plans\Bloomfiled CON-4\Route 178 at Wintonbury Ave_Plan.dgn
PLOTTED DATE: 9/2/2025