

**Rentschler Field Parking and Traffic Circulation Improvements
Project No. 3097-01
State of Connecticut
Office of Policy and Management**

Addendum 4

1. With regard to Item 7, Question 17 in Addendum 2, please note the following change: (Deleted text is struck through; added text is underlined.)

Q17. We believe it was specified that materials from one section could not be reused in another section, i.e. materials from the Recreation Field cannot be moved to the North Klondike and vice versa. Please clarify

Sheet PS-1 and PS-2 identify the locations where polluted soil may be reused, specifically oriented toward re-use in the originating area, followed by similar areas as designated in the notes for each location. Prioritization and sequencing of work in the areas of those volumes will likely promote material balancing. ~~Recreation Field material is considered polluted soil and may only be reused within the Recreation Field dimensions.~~ Earthwork within the Recreation Field is expected to result in excess soil which is believed to be polluted soil. Much of that material is expected to be topsoil. OPM has determined that the excess Recreation Field material may be reused within the North Klondike area, where fill is required. If, after all fill has been placed within the North Klondike, there remains excess polluted soil from the Recreation Field, such material shall be managed in accordance with the 'Notice to Contractor – Excavated Material Management'. The Contractor is reminded; however, that excess non-polluted clean fill will be the responsibility of the Contractor, in accordance with the terms of Form 816. Contractor is also reminded that UTC will conduct soil remediation activities within the Recreation Field in coordination with the project. That remediation must be completed before soil from that area may be relocated ~~within the parcel~~. The location of the intended UTC remediation is shown on Sheet No. LA-1.

2. Comments received by OPM suggest that some confusion exists about statements that were made at the prebid meetings regarding site balance. Please refer to the response in Item 7, Question 3 in Addendum 2, reprinted below. **Bidders are reminded that in the event oral and written responses have been provided to questions, the written responses prevail.**

Q3. Is the site balanced?

Prospective bidders are expected to perform their own earthwork calculations and base their lump sum bids accordingly. Refer to Section 2.02 of the technical specifications, Special Provision '0207001A – Borrow' and the 'Notice to Contractor – Excavated Material Management'.