

SUMMARY OF CHANGES
JANUARY 2021 SUPPLEMENTS TO FORM 818
EFFECTIVE FOR FDP DATES AFTER JUNE 1, 2021

Significant changes in each Section are summarized below:

SECTION 1.05 – CONTROL OF THE WORK

Added Subarticle 1.05.19 that requires contractors erecting new structural steel (bridge beams, girders and trusses) and fabricated (overhead and cantilever) sign supports to possess an appropriate AISC Steel Erector Certification.

SECTION 1.20-9.80 – CONSTRUCTION SURVEYING FOR FACILITIES CONSTRUCTION

Incorporated new section to address surveying for Facilities Construction that was previously a special provision in Facilities Construction projects. Changes include Class T-2 survey replaced with Class A-2, and “Existing Building Location Survey” replaced with “Improvement Location Survey.”

**SECTION 4.06 – BITUMINOUS CONCRETE and
SECTION M.04 – BITUMINOUS CONCRETE MATERIALS**

Subgroup revisions including taking pavement cores within 3 days of paving (with some exceptions) and other minor revisions were incorporated.

SECTION 4.07 – RUMBLE STRIPS, REMOVAL OF RUMBLE STRIPS

Combined and updated owned special provisions for Rumble Strips and Removal of Rumble Strips, incorporated as new Section 4.07.

SECTION 6.03 – STRUCTURAL STEEL

Added option for cold cambering to be allowed on certain rolled beams.

SECTION 10.18 – NAVIGATION LIGHT

SECTION M.15 – HIGHWAY ILLUMINATION

Deleted Section 10.18 and corresponding Subarticle M.15.16 (Navigation Light) due to use of special provisions for site-specific lighting needs.

SECTION 11.12 – MAGNETIC VEHICLE DETECTOR

SECTION M.16 – TRAFFIC CONTROL SIGNALS

Deleted Section 11.12 and corresponding Subarticle M.16.13 (Magnetic Vehicle Detector) due to outdated equipment specified and use of special provisions.