

**SECTION 11.06  
PEDESTRIAN SIGNAL**

**11.06.01--Description:** This item shall consist of furnishing and installing a "Walk-Don't Walk" pedestrian signal of the type specified at locations shown on the plans or as indicated by the Engineer in conformity with these specifications.

**11.06.02--Materials:** The materials for this work shall conform to the requirements of Article M.16.07.

**11.06.03--Construction Methods:** Each completely assembled "Walk-Don't Walk" pedestrian signal unit shall normally be installed as follows:

Each pedestrian signal shall be erected vertically in accordance with the specific type of mountings shown on the plans. Each signal face shall be pointed in the direction of the approaching pedestrian traffic it is to control.

During construction, and until the signals are placed in actual operation, the signal housing shall be hooded. In no case shall the signal project beyond the curb, and it shall be at least 300 mm behind the curb.

**11.06.04--Method of Measurement:** The quantity to be paid for under these items will be the number of completed, installed and accepted pedestrian signals of the type specified.

**11.06.05--Basis of Payment:** This work will be paid for at the Contract unit price each for "Pedestrian Signal," of the type specified which price shall include all materials, housing, lamp socket, lamp, lens, visor, miscellaneous fittings and parts, equipment, paint and painting, labor and work incidental thereto.

Pay Item	Pay Unit
Pedestrian Signal (Type)	EA.