

**SECTION 7.25  
BAGGED STONE**

**7.25.01--Description:** This item shall consist of furnishing and placing crushed stone or gravel in burlap bags at the inlet ends of weep holes in structures to the dimensions indicated on the plans or as ordered by the Engineer.

**7.25.02--Materials:** The materials for this work shall conform to the following requirements:

(a) The crushed stone or gravel shall conform to the grading requirements of Article M.01.01 for No. 3 or No. 4 coarse aggregate or a mixture of both.

(b) The bag shall be of burlap and shall be large enough to contain loosely 0.03 m<sup>3</sup> of the granular material.

**7.25.03--Construction Methods:** Approximately 0.03 m<sup>3</sup> of the crushed stone or gravel shall be enclosed in the burlap bag which shall then be securely tied at the neck with cord or wire so that the enclosed material is contained loosely. The filled bags shall be stacked at the weepholes to the dimensions shown on the plans or as directed by the Engineer. The bags shall be unbroken at the time pervious material is placed around them, and bags which are broken or burst prior to or during the placing of the pervious material shall be replaced at the expense of the Contractor.

**7.25.04--Method of Measurement:** The quantity of bagged crushed stone or gravel shall be based on the actual number of bags, of 0.03 m<sup>3</sup> each, completed and accepted, within the neat lines shown on the plans or as ordered by the Engineer.

**7.25.05--Basis of Payment:** This work will be paid for at the contract unit price per bag for "Bagged Stone," complete in place, which price shall include all materials, equipment, tools and labor incidental thereto.

Pay Item	Pay Unit
Bagged Stone	Bag