

SECTION 1.10 ENVIRONMENTAL COMPLIANCE

**In Article 1.10.03--Water Pollution Control:
BEST MANAGEMENT PRACTICES**

Add the following after Required Best Management Practices Number 13:

14. Staging, laydown areas and servicing and fueling of equipment on Site are prohibited unless further coordination is done with the Department according to the following specifications. The Contractor shall submit documentation to the Engineer for further approval by the Department's Office of Environmental Planning (OEP) certifying adherence to these conditions as part of the initial Project submittals. Any work that is anticipated to require ground disturbance or any storage of material for more than twenty four (24) hours in a single location must be identified.

If staging, laydown areas and/or servicing and fueling of equipment are required, the Contractor shall submit, under the initial Project submittals, detailed site plans showing the locations of any staging, laydown, and/ or servicing and fueling areas to the Engineer for approval by the OEP including submittal of a narrative of the Contractor's Best Management Practices for staging, refueling, and a checklist for site cleanup should a spill occur. If it is determined by the OEP that the Project location falls within a sensitive area, the Contractor must adhere to all special requirements and best management practices provided by the OEP.