

SBA

Filed by:

*Kri Pelletier, Property Specialist - SBA Communications  
134 Flanders Rd., Suite 125, Westborough, MA 01581  
508.251.0720 x 3804 - kpelletier@sbsite.com*

August 11, 2016

Melanie A. Bachman  
Acting Executive Director  
Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051

**Notice of Exempt Modification**

**1 Deerfield Lane, Ansonia, CT 06401**

**N 41° 21' 3.06"**

**W 73° 02' 57.6954"**

**AT&T #: 10126685\_LTE / CT2359**

Dear Ms. Bachman:

AT&T currently maintains nine (9) antennas at the 148-foot level of the existing 170-foot Monopole Tower at 1 Deerfield Lane. The tower is owned by SBA Towers IV, LLC. The property is owned by Macabee Properties, LLC (Property Listing Report attached.) AT&T now intends to swap three (3) existing GSM Antennas with three (3) new LTE antennas. These antennas would be installed at the 148-foot level of the tower. The full scope of work is as follows:

Remove:

- None

Remove and Replace:

- (3) GSM antennas removed and replaced with (3) LTE antennas
- (3) RRU 11s removed and replaced with (3) RRU 32s

Install:

- (3) RRU 32
- (1) DC6 Squid
- (3) Bias Ts

Existing Equipment to Remain (including Entitlements):

- (3) RRU 12-B2
- (3) RRU A2
- (3) LTE Antennas
- (3) UMTS Antennas
- (1) DC-6 Squid
- (12) coax – 1-5/8"
- (1) 1/2 " fiber
- (2) 3/4" DC
- (6) Diplexers

- (6) TMAs
- (3) T-Arms

The tower was approved by the CSC in Case/Docket 340 on April 9, 2008, calling for a monopole no taller than necessary to provide proposed telecommunications services, sufficient to accommodate the antennas of T-Mobile and other entities, and not to exceed 170'. The tower was to provide space for any City of Ansonia and Town of Woodbridge public safety services. All antennas were to be attached with T arms and the Certificate Holder was to provide a recalculated report of RF power density, to be submitted to Council, if there were to be a change in density above levels calculated and provided pursuant to the Decision and Order (attached.)

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. §16.50j-72(b)(2). In accordance with R.C.S.A. § 16.50j-73, a copy of this letter is being sent to the Honorable David S. Cassetti, Mayor of the City of Ansonia, as well as the property owner, Macabee Properties, LLC. (Separate notice is not being sent to tower owner, as it belongs to SBA.)

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. §16.50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modification will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modification will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading with certain modifications.

For the foregoing reasons, AT&T respectfully submits that the proposed modifications to the above-referenced telecommunication facility constitute an exempt modifications under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,



Kri Pelletier  
Property Specialist  
SBA COMMUNICATIONS CORPORATION  
134 Flanders Rd., Suite 125  
Westborough, MA 01581  
508.251.0720 x3804 + T  
508.366.2610 + F  
203.446.7700 + C  
kpelletier@sbsite.com

Attachments

cc: The Honorable David S. Cassetti—as elected official  
*City of Ansonia, 253 Main Street, Ansonia, CT 06401*  
Macabee Properties, LLC—as property owner  
*11 Hemlock Hollow Road, Woodbridge, CT 06525*



### POWER DENSITY

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Powerwave 7770	Make / Model:	Powerwave 7770	Make / Model:	Powerwave 7770
Gain:	11.4 / 13.4 dBd	Gain:	11.4 / 13.4 dBd	Gain:	11.4 / 13.4 dBd
Height (AGL):	148.3 feet	Height (AGL):	148.3 feet	Height (AGL):	148.3 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power(W):	120 Watts	Total TX Power(W):	120 Watts	Total TX Power(W):	120 Watts
ERP (W):	2,140.89	ERP (W):	2,140.89	ERP (W):	2,140.89
Antenna A1 MPE%	0.49 %	Antenna B1 MPE%	0.49 %	Antenna C1 MPE%	0.49 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	CCI OPA-65R-LCUU-H6	Make / Model:	CCI OPA-65R-LCUU-H8	Make / Model:	CCI OPA-65R-LCUU-H8
Gain:	11.65 / 14.85 dBd	Gain:	12.55 / 14.85 dBd	Gain:	12.55 / 14.85 dBd
Height (AGL):	148.3 feet	Height (AGL):	148.3 feet	Height (AGL):	148.3 feet
Frequency Bands	700 MHz / 1900 MHz (PCS)	Frequency Bands	700 MHz / 1900 MHz (PCS)	Frequency Bands	700 MHz / 1900 MHz (PCS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power(W):	240 Watts	Total TX Power(W):	240 Watts	Total TX Power(W):	240 Watts
ERP (W):	5,420.52	ERP (W):	5,824.55	ERP (W):	5,824.55
Antenna A2 MPE%	1.32 %	Antenna B2 MPE%	1.47 %	Antenna C2 MPE%	1.47 %
Antenna #:	3	Antenna #:	3	Antenna #:	3
Make / Model:	CCI HPA-65R-BUU-H6	Make / Model:	CCI HPA-65R-BUU-H8	Make / Model:	CCI HPA-65R-BUU-H8
Gain:	12.65 / 15.25 dBd	Gain:	14.05 / 15.55 dBd	Gain:	14.05 / 15.55 dBd
Height (AGL):	148.3 feet	Height (AGL):	148.3 feet	Height (AGL):	148.3 feet
Frequency Bands	850 MHz / 2300 MHz (WCS)	Frequency Bands	850 MHz / 2300 MHz (WCS)	Frequency Bands	850 MHz / 2300 MHz (WCS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power(W):	180 Watts	Total TX Power(W):	180 Watts	Total TX Power(W):	180 Watts
ERP (W):	5,124.05	ERP (W):	5,831.65	ERP (W):	5,831.65
Antenna A3 MPE%	1.06 %	Antenna B3 MPE%	1.24 %	Antenna C3 MPE%	1.24 %

Site Composite MPE%	
Carrier	MPE%
AT&T – Max per sector	3.21 %
T-Mobile	1.55 %
Clearwire	0.13 %
Verizon Wireless	2.04 %
MetroPCS	0.40 %
Site Total MPE %:	7.33 %

AT&T Sector A Total:	2.87 %
AT&T Sector B Total:	3.21 %
AT&T Sector C Total:	3.21 %
Site Total:	7.33 %



Property Information

Property Location	1 DEERFIELD LA
Owner	MACABEE PROPERTIES LLC
Co-Owner	
Mailing Address	11 HEMLOCK HOLLOW RD WOODBIDGE CT 06525
Land Use	104 4 Family
Land Class	R
Zoning Code	AA
Census Tract	
Sub Lot	
Neighborhood	
Acreage	16.2
Utilities	Public Water,Septic
Lot Setting/Desc	Level
Survey Map	
Additional Info	

Photo



Sketch



Primary Construction Details

Year Built	1958
Stories	1
Building Style	Family Flat
Building Use	Residential
Building Condition	Below Average
Floors	Carpet
Total Rooms	12

Bedrooms	5 Bedrooms
Full Bathrooms	4
Half Bathrooms	0
Bath Style	Average
Kitchen Style	Average
Roof Style	Flat
Roof Cover	Tar + Gravel

Exterior Walls	Concr/Cinder
Interior Walls	Plaster
Heating Type	Hot Water
Heating Fuel	Oil
AC Type	None
Gross Bldg Area	9364
Total Living Area	5367



Valuation Summary (Assessed value = 70% of Appraised Value)

Item	Appraised	Assessed
Buildings	177400	124200
Extras	0	0
Outbuildings	52900	37100
Land	275300	104390
Total	505600	265690

Outbuilding and Extra Items

Type	Description
Cell Tower	1.00 UNITS
Garage poor	1200.00 S.F.
Barn 1 St	384.00 S.F.
Stable	800.00 S.F.
Shed	800.00 S.F.

Sub Areas

Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
First Floor	5367	5367
Garage	160	0
Utility, Storage, Unfinished	1984	0
Crawl space	1749	0
Porch, Enclosed, Unfinished	104	0
Total Area	9364	5367

Sales History

Owner of Record	Book/ Page	Sale Date	Sale Price
MACABEE PROPERTIES LLC	435/ 195	12/28/2005	0
GELERTNER JOEL & CHERYL	316/ 863	12/2/1998	235000



**1 DEERFIELD LA**



**MBL : 1000002000**  
**Owner : MACABEE PI**  
**Acres : 16.2**  
**Zoning : AA**

[Details](#) [Quick Map](#) [Summary Card](#) [Birds!](#)

Generate Abutter List:



## RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

AT&T Existing Facility

Site ID: CT2359

Ansonia Deerfield Ln  
1 Deerfield Lane  
Ansonia, CT 06401

**August 10, 2016**

**EBI Project Number: 6216003523**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general public allowable limit:	<b>7.33 %</b>



August 10, 2016

AT&T Mobility – New England  
Attn: Cameron Syme, RF Manager  
550 Cochituate Road  
Suite 550 – 13&14  
Framingham, MA 06040

## Emissions Analysis for Site: **CT2359 – Ansonia Deerfield Ln**

EBI Consulting was directed to analyze the proposed AT&T facility located at **1 Deerfield Lane, Ansonia, CT**, for the purpose of determining whether the emissions from the Proposed AT&T Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 700 and 850 MHz Bands are approximately  $467 \mu\text{W}/\text{cm}^2$  and  $567 \mu\text{W}/\text{cm}^2$  respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 2300 MHz (WCS) bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.





Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## CALCULATIONS

Calculations were done for the proposed AT&T Wireless antenna facility located at **1 Deerfield Lane, Ansonia, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since AT&T is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 UMTS channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 2 UMTS channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 3) 2 LTE channels (700 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 5) 2 GSM channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 6) 2 LTE channels (2300 MHz (WCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.



- 7) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 8) For the following calculations the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antennas used in this modeling are the **Powerwave 7770, CCI OPA-65R-LCUU-H6, CCI HPA-65R-BUU-H6, CCI OPA-65R-LCUU-H8 and the CCI HPA-65R-BUU-H8** for transmission in the 700 MHz, 850 MHz, 1900 MHz (PCS) and 2300 MHz (WCS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 10) The antenna mounting height centerlines of the proposed antennas are **148.3 feet** above ground level (AGL) for **Sector A**, **148.3 feet** above ground level (AGL) for **Sector B** and **148.3 feet** above ground level (AGL) for Sector C.
- 11) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general public threshold limits.



## AT&T Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	<b>1</b>	Antenna #:	<b>1</b>	Antenna #:	<b>1</b>
Make / Model:	Powerwave 7770	Make / Model:	Powerwave 7770	Make / Model:	Powerwave 7770
Gain:	11.4 / 13.4 dBd	Gain:	11.4 / 13.4 dBd	Gain:	11.4 / 13.4 dBd
Height (AGL):	<b>148.3 feet</b>	Height (AGL):	<b>148.3 feet</b>	Height (AGL):	<b>148.3 feet</b>
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power(W):	120 Watts	Total TX Power(W):	120 Watts	Total TX Power(W):	120 Watts
ERP (W):	2,140.89	ERP (W):	2,140.89	ERP (W):	2,140.89
Antenna A1 MPE%	<b>0.49 %</b>	Antenna B1 MPE%	<b>0.49 %</b>	Antenna C1 MPE%	<b>0.49 %</b>
Antenna #:	<b>2</b>	Antenna #:	<b>2</b>	Antenna #:	<b>2</b>
Make / Model:	CCI OPA-65R-LCUU-H6	Make / Model:	CCI OPA-65R-LCUU-H8	Make / Model:	CCI OPA-65R-LCUU-H8
Gain:	11.65 / 14.85 dBd	Gain:	12.55 / 14.85 dBd	Gain:	12.55 / 14.85 dBd
Height (AGL):	<b>148.3 feet</b>	Height (AGL):	<b>148.3 feet</b>	Height (AGL):	<b>148.3 feet</b>
Frequency Bands	700 MHz / 1900 MHz (PCS)	Frequency Bands	700 MHz / 1900 MHz (PCS)	Frequency Bands	700 MHz / 1900 MHz (PCS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power(W):	240 Watts	Total TX Power(W):	240 Watts	Total TX Power(W):	240 Watts
ERP (W):	5,420.52	ERP (W):	5,824.55	ERP (W):	5,824.55
Antenna A2 MPE%	<b>1.32 %</b>	Antenna B2 MPE%	<b>1.47 %</b>	Antenna C2 MPE%	<b>1.47 %</b>
Antenna #:	<b>3</b>	Antenna #:	<b>3</b>	Antenna #:	<b>3</b>
Make / Model:	CCI HPA-65R-BUU-H6	Make / Model:	CCI HPA-65R-BUU-H8	Make / Model:	CCI HPA-65R-BUU-H8
Gain:	12.65 / 15.25 dBd	Gain:	14.05 / 15.55 dBd	Gain:	14.05 / 15.55 dBd
Height (AGL):	<b>148.3 feet</b>	Height (AGL):	<b>148.3 feet</b>	Height (AGL):	<b>148.3 feet</b>
Frequency Bands	850 MHz / 2300 MHz (WCS)	Frequency Bands	850 MHz / 2300 MHz (WCS)	Frequency Bands	850 MHz / 2300 MHz (WCS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power(W):	180 Watts	Total TX Power(W):	180 Watts	Total TX Power(W):	180 Watts
ERP (W):	5,124.05	ERP (W):	5,831.65	ERP (W):	5,831.65
Antenna A3 MPE%	<b>1.06 %</b>	Antenna B3 MPE%	<b>1.24 %</b>	Antenna C3 MPE%	<b>1.24 %</b>

Site Composite MPE%	
Carrier	MPE%
AT&T – Max per sector	<b>3.21 %</b>
T-Mobile	1.55 %
Clearwire	0.13 %
Verizon Wireless	2.04 %
MetroPCS	0.40 %
<b>Site Total MPE %:</b>	<b>7.33 %</b>

AT&T Sector A Total:	2.87 %
AT&T Sector B Total:	3.21 %
AT&T Sector C Total:	3.21 %
<b>Site Total:</b>	<b>7.33 %</b>



## AT&T Highest Calculated Sector Values:

AT&T _ Max Values (Sectors B & C)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
AT&T 850 MHz UMTS	2	414.12	148.3	1.47	850 MHz	567	0.26%
AT&T 1900 MHz (PCS) UMTS	2	656.33	148.3	2.33	1900 MHz (PCS)	1000	0.23%
AT&T 700 MHz LTE	2	1,079.32	148.3	3.83	700 MHz	467	0.82%
AT&T 1900 MHz (PCS) LTE	2	1,832.95	148.3	6.51	1900 MHz (PCS)	1000	0.65%
AT&T 850 MHz GSM	2	762.29	148.3	2.71	850 MHz	567	0.48%
AT&T 2300 MHz (WCS) LTE	2	2,153.53	148.3	7.65	2300 MHz (WCS)	1000	0.76%
						Total*:	3.21%

NOTE: Totals may vary by .01% due to summing of remainders



## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general public exposure to RF Emissions.

The anticipated maximum composite contributions from the AT&T facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general public exposure to RF Emissions are shown here:

AT&T Sector	Power Density Value (%)
Sector A:	2.87 %
Sector B:	3.21 %
Sector C:	3.21 %
AT&T Maximum Total (per sector):	3.21 %
Site Total:	7.33 %
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **7.33 %** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Tower Engineering Solutions**

Phone (972) 483-0607, Fax (972) 975-9615  
8445 Freeport Parkway, Suite 375, Irving, Texas 75063

---

## **Post-Mod Structural Analysis Report**

**Existing 169 ft SABRE Monopole**

**Customer Name: SBA Communications Corp**

**Customer Site Number: CT13071-A**

**Customer Site Name: Woodbridge**

**Carrier Name: AT&T**

**Carrier Site ID/ Name: CT2359 Tenant Site Name Ansonia Deerfield Lane FA#**

**Site Location: 1 Deerfield Lane**

**Ansonia, Connecticut**

**New Haven County**

**Latitude: 41.350750**

**Longitude: -73.049250**

### **Analysis Result:**

**Max Structural Usage: 95.4% [Pass]**

**Max Foundation Usage: 100.0% [Pass]**

**Report Prepared By : Uma S Atluri**



## Introduction

The purpose of this report is to summarize the analysis results on the 169 ft SABRE Monopole to support the proposed antennas and transmission lines in addition to those currently installed. Any existing modification listed under Sources of Information was assumed completed and was included in this analysis.

The proposed modification by **TES** listed under Sources of Information was considered completed and was included in this analysis.

## Sources of Information

<b>Tower Drawings</b>	Sabre, DWG # 08-01016-PE, dated 1/7/2008
<b>Foundation Drawing</b>	Sabre, DWG # 08-01016, dated 1/30/2008
<b>Geotechnical Report</b>	JGI Eastern, Inc., Project # J2085109, dated 1/29/2008
<b>Existing Modification</b>	TES, Project # 17022, dated 9/1/2015:TES, Project # 19194, dated 12/9/2015
<b>Proposed Modification</b>	<b>TES</b> Job # 22848

## Analysis Criteria

The analysis was performed in accordance with the requirements and stipulations of the ANSI/TIA/EIA 222-F. In accordance with this standard, the structure was analyzed using **TESPoles**, a proprietary analysis software. The program considers the structure as an elastic 3-D model with second-order effects and temperature effects incorporated in the analysis. The analysis was performed using multiple wind directions.

<b>Basic Wind Speed Used in the Analysis:</b>	85.0 mph (fastest mile) (Equivalent to 105 mph 3-second Gust wind speed)
<b>Basic Wind Speed with Ice:</b>	74 mph (fastest mile) with 1/2" radial ice concurrent
<b>Operational Wind Speed:</b>	50 mph + 0" Radial ice
<b>Standard/Codes:</b>	ANSI/TIA/EIA 222-F / 2005 Connecticut State Building Code

## Existing Antennas, Mounts and Transmission Lines

The table below summarizes the antennas, mounts and transmission lines that were considered in the analysis as existing on the tower.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
1	167.0	3	Ericsson - AIR B2A B4P - Panel	(3) T-Arms w/Commscope VSR-MS-B stabilizer Pipe	(12) 1 5/8" (1) 1 5/8" Fiber	T-Mobile
2		3	Ericsson - AIR B4A B2P - Panel			
3		3	Commscope - LNX-6515DS - Panel			
4		3	Ericsson S11B12-RRU			
5		3	Ericsson KRY 112 144/1-TMA			
6	157.0	3	ALU RRH2X60-AWS RRH	(3) T-Arms	(6) 1 5/8"* (12) 1 5/8" (1) 1 5/8" Fiber (1) 1/2"	Verizon
7		1	Antel BXA-70063/6CF - Panel			
8		4	Decibel - DB846F65ZAXY - Panel			
9		2	Decibel - DB846H80E-SX - Panel			
10		1	GPS			
11		6	Andrew - HBX-6517DS-VTM - Panel			
12		1	RFS DB T1-6Z-8AB-OZ Distribution Box			
13	2	Swedcom - SLCP 2x6014F - Panel				
-	150.0	6	Ericsson RRUS-11-RRU	(3) T-Arms	(12) 1 5/8" (1) 1/2" Fiber (Rosenberger 10mm FB-L98B- 002 fiber Trunk) (2) 3/4" DC (WR-VG122ST- BRDA 12 gauge DC)	AT&T
		1	Raycap DC6-48-60-18-8F-Surge Suppersor/Squid			
-	148.0	6	Powerwave 7770 - Panel	(3) T-Arms	(12) 1 5/8" (1) 1/2" Fiber (Rosenberger 10mm FB-L98B- 002 fiber Trunk) (2) 3/4" DC (WR-VG122ST- BRDA 12 gauge DC)	AT&T
		1	Cci OPA-65R-LCUU-H6 - Panel			
		2	Cci OPA-65R-LCUU-H8 - Panel			
		6	Powerwave LGP21401 TMA-TMA			
		3	Ericsson RRUS 12-B2-RRU			
		3	Ericsson RRUS A2 Module - RRUS			
		6	Powerwave LGP13519 Diplexer-Diplexer			
27	127.0	3	Samsung - 2.5GHz RRH BTS	(3) T-Arms	(4) 1/2" (3) 1/4" (3) 5/16" (3) 5/8"	Clearwire
28		3	Argus - LLPX310R - Panel			
29		3	Andrew - VHLP2-11 - Dish			
30		1	Andrew - VHLP800-11 - Dish			

\*lines outside of the pole



## Proposed Carrier's Final Configuration of Antennas, Mounts and Transmission Lines

Information pertaining to the proposed carrier's final configuration of antennas and transmission lines was provided by SBA Communications Corp. The proposed antennas and lines are listed below.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
14	148.0	3	Powerwave 7770 - Panel	(3) T-Arms	(12) 1 5/8" (1) 1/2" Fiber (Rosenberger 10mm FB-L98B- 002 fiber Trunk) (2) 3/4" DC (WR-VG122ST- BRDA 12 gauge DC)	AT&T
15		1	Cci OPA-65R-LCUU-H6 - Panel			
16		2	Cci OPA-65R-LCUU-H8 - Panel			
17		1	CCI HPA-65R-BUU-H6 - Panel			
18		2	CCI HPA-65R-BUU-H8 - Panel			
19		6	Powerwave LGP21401 TMA			
20		3	Ericsson RRUS-11-RRU			
21		3	Ericsson RRUS 12-B2-RRU			
22		3	Ericsson RRUS A2 Module - RRU			
23		3	Ericsson RRUS 32-RRU			
24		6	Powerwave LGP13519 Diplexer			
25		2	Raycap DC6-48-60-18-8F-Surge Supperssor			
26		3	Powerwave 1001940-Bias Ts			

All proposed transmission lines are considered running inside of the pole shafts.

## **Analysis Results**

The results of the structural analysis, performed for the wind and ice loading and antenna equipment as defined above, are summarized as the following:

	Pole shafts	Anchor Bolts	Base Plate	Reinforcement Plate
Max. Usage:	<b>95.4%</b>	<b>89.2%</b>	<b>76.8%</b>	<b>80.9%</b>
Pass/Fail	<b>Pass</b>	<b>Pass</b>	<b>Pass</b>	<b>Pass</b>

## **Foundations**

	Moment (Kip-Ft)	Shear (Kips)	Axial (Kips)
Analysis Reactions	4188.6	33.8	51.7

The foundation has been investigated using the supplied documents and soils report and was found adequate. Therefore, no modification to the foundation will be required.

## **Operational Condition (Rigidity):**

Maximum twist and sway of the microwave dishes under the operational wind speed as specified in the Analysis Criteria are listed in the table below:

Elevation (ft)	Antenna / Dish	Carrier	Twist (deg)	Sway (deg)
148.0	Various- Panels	AT&T	0.002	2.210
127.0	Andrew - VHLP2-11 - Dish	Clearwire	0.002	1.951
127.0	Andrew VHLP800-11 - Dish	Clearwire	0.002	1.951

It is recommended that the carriers review the twist and sway values of the microwave dishes.

## **Conclusions**

Based on the analysis results, the structure and its foundation will be adequate to safely support the existing and proposed equipment and meet the minimum requirements per the design ANSI/TIA/EIA 222-F standards under a basic wind speed of 85 mph no ice and 74 mph with 1/2" radial ice after the following proposed modification is successfully completed.

- Proposed modification design drawing by **TES** Job # 22848

**Pre-Mod Installation Determination**

We have also checked this tower to determine if the proposed AT&T equipment loading can be installed prior to the completion of the required modifications. We ran a reduced wind loading case as required by TIA-1019 considering a construction period of no more than 6 months.

The tower and foundations passed, so the Carrier can proceed and install their proposed loading prior to the mods completion. Please be aware that this approval is being provided and is based on the method outlined in TIA-1019. This approval is not a blanket approval and there is still a risk that the tower will experience a wind event that cannot be predicted by TIA-1019 or our Engineers. In the event of an unforeseen wind event, Tower Engineering Solutions will not be liable nor responsible for damage to the tower or the Carriers equipment. Additionally, the tower cannot go beyond the 6 month construction period without the modifications being completed. If the modifications cannot be completed within 6 months from the completed installation of the Carrier's proposed equipment, TES must be notified immediately for further review.

## Standard Conditions

1. This analysis was performed based on the information supplied to **(TES) Tower Engineering Solutions, LLC**. Verification of the information provided was not included in the Scope of Work for **TES**. The accuracy of the analysis is dependent on the accuracy of the information provided.
2. The analysis is based on the presumption that the tower members and components along with any existing reinforcement items have been correctly and properly designed, manufactured, installed and maintained.
3. All the existing structural members were assumed to be in good condition with no physical damage or deterioration associated with corrosion.
4. An initial tension of 10% of the break strength on all the existing guy wires was assumed in all the structural analyses of guyed towers unless different values were provided by the client. **TES** cannot take responsibility for the deviations in the analysis results because of differences in the initial tension forces of the existing guy wires.
5. Secondary component or connection secondary components, welds and bolts are assumed to be able to carry their intended original design loads. **TES** cannot take responsibility for verification of the adequacy on the connections, bolts and welds present in the structure.
6. The analyses will be performed based on the codes as specified by the client or based on the best knowledge of the engineering staff of **TES**. In the absence of information to the contrary, all work will be performed in accordance with the latest relevant revision of ANSI/TIA-222. If wind speed or/and ice loads are different from the minimum values recommended by the EIA/TIA-222 standard or other codes, **TES** should be notified in writing and the applicable minimum values provided by the client.
7. The configuration of the existing mounts, antennas, coax and other appurtenances were supplied by the customer for the current structural analysis. **TES** has not visited the tower site to verify the adequacy of the information provided. If there is any discrepancy found in the report regarding the existing conditions, **TES** should be notified immediately to evaluate the effect of the discrepancy on the analysis results.
8. The client will assume responsibility for rework associated with the differences in initially provided information, including tower and foundation information, existing and/or proposed equipment and transmission lines.
9. If a feasibility analysis was performed, final acceptance of changed conditions shall be based upon a rigorous structural analysis.

# Usage Diagram - Max Stress 95.4% at 47.0ft

**Structure:** CT13071-A-SBA  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69


6/21/2016



Page: 1

Dead Load Factor: 1.00  
 Wind Load Factor: 1.00


**Load Case : 85 mph Wind with 0 in Ice**



**Iterations:** 27

52 Allowable Stress  
50 Resulting Stress

*Copyright © 2016 by Tower Engineering Solutions, LLC. All rights reserved.*



## Structure: CT13071-A-SBA

**Type:** Tapered  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.00 (ft)

**Base Shape:** 18 Sided  
**Taper:** 0.20003

6/21/2016

Page: 2



### Shaft Properties


Seq	Length (ft)	Top (in)	Bottom (in)	Thick (in)	Joint Type	Taper	Grade (ksi)
1	47.00	46.78	56.18	0.438		0.20003	65
2	53.50	38.08	48.78	0.375	Slip	0.20003	65
3	53.50	28.88	39.58	0.250	Slip	0.20003	65
4	30.00	24.00	30.00	0.188	Slip	0.20003	65

### Discrete Appurtenances

Attach Elev (ft)	Force Elev (ft)	Qty	Description	Carrier
167.00	167.00	3	AIR B2A B4P	T-Mobile
167.00	167.00	3	AIR B4A B2P	T-Mobile
167.00	167.00	3	Ericsson KRY 112 144/1	T-Mobile
167.00	167.00	3	Ericsson S11B12	T-Mobile
167.00	167.00	3	LNx-6515DS	T-Mobile
167.00	167.50	3	T-Arms/Commscope	T-Mobile
157.00	157.00	3	ALU RRH2X60-AWS RRH	Verizon
157.00	157.00	1	BXA-70063/6CF	Verizon
157.00	157.00	4	DB846F65ZAXY	Verizon
157.00	157.00	2	DB846H80E-SX	Verizon
157.00	157.00	1	GPS	Verizon
157.00	157.00	6	HBX-6517DS-VTM	Verizon
157.00	157.00	1	RFS DB T1-6Z-8AB-OZ	Verizon
157.00	157.00	2	SLCP 2x6014F	Verizon
157.00	157.00	3	T-Arms	Verizon
150.00	150.00	1	Collar Mount	AT&T
148.00	148.00	1	CCI HPA-65R-BUU-H6	AT&T
148.00	148.00	2	CCI HPA-65R-BUU-H8	AT&T
148.00	148.00	1	Cci OPA-65R-LCUU-H6	AT&T
148.00	148.00	2	Cci OPA-65R-LCUU-H8	AT&T
148.00	148.00	3	Ericsson RRUS	AT&T
148.00	148.00	3	Ericsson RRUS 32-RRU	AT&T
148.00	148.00	3	Ericsson RRUS A2 Module	AT&T
148.00	148.00	3	Ericsson RRUS-11-RRU	AT&T
148.00	148.00	3	Powerwave 1001940-Bias	AT&T
148.00	148.00	3	Powerwave 7770	AT&T
148.00	148.00	6	Powerwave LGP13519	AT&T
148.00	148.00	6	Powerwave LGP21401	AT&T
148.00	148.00	2	Raycap	AT&T
148.00	148.00	3	T-Arms	AT&T
127.00	127.00	3	2.5GHz RRH BTS	Clearwire
127.00	127.00	3	LLPX310R	Clearwire
127.00	127.00	3	Sector Frames	Clearwire
127.00	127.00	3	VHLP2-11	Clearwire
127.00	127.00	1	VHLP800-11	Clearwire

### Linear Appurtenances

Elev From (ft)	Elev To (ft)	Placement	Description	Carrier
0.00	167.00	Inside	1 5/8" Coax	T-Mobile
0.00	167.00	Inside	1 5/8" Fiber	T-Mobile
0.00	157.00	Inside	1 5/8" Coax	Verizon
0.00	157.00	Outside	1 5/8" Coax	Verizon
0.00	157.00	Inside	1 5/8" Fiber	Verizon
0.00	157.00	Inside	1/2" Coax	Verizon
0.00	148.00	Inside	1 5/8" Coax	AT&T



**Structure: CT13071-A-SBA**

**Type:** Tapered  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.00 (ft)

**Base Shape:** 18 Sided  
**Taper:** 0.20003

6/21/2016

Page: 3



0.00	148.00	Inside	1/2" Fiber	AT&T
0.00	148.00	Inside	3/4" DC Power	AT&T
0.00	127.00	Inside	1/2" Coax	Clearwire
0.00	127.00	Inside	1/4" Coax	Clearwire
0.00	127.00	Inside	5/16" Coax	Clearwire
0.00	127.00	Inside	5/8"	Clearwire
99.25	109.25	Outside	1" Reinforcing plate	
89.25	99.25	Outside	1" Reinforcing plate	

**Anchor Bolts**

Qty	Specifications	Grade (ksi)	Arrangement
16	2.25" 18J	75.0	Cluster

**Base Plate**

Thickness (in)	Specifications (in)	Grade (ksi)	Geometry
3.0000	61.3	60.0	Clipped

**Reactions**

Load Case	Moment	Shear	Axial
85 mph Wind with 0" Ice	4188.6	33.8	42.9
73.61 mph Wind with 0.5" Ice	3350.9	26.9	51.7
50 mph Wind with 0" Ice	1451.7	11.7	42.9


# Structure: CT13071-A-SBA - Coax Line Placement

Type: Monopole  
Site Name: Woodbridge  
Height: 169.00 (ft)

6/21/2016



Page: 4





## Shaft Properties

**Structure:** CT13071-A-SBA  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016

Page: 5



Sec. No.	Shape	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Overlap (in)	Weight (lb)
1	18	47.000	0.4375	65		0.00	11,335
2	18	53.500	0.3750	65	Slip	75.00	9,329
3	18	53.500	0.2500	65	Slip	60.00	4,908
4	18	30.000	0.1875	65	Slip	45.00	1,629
<b>Total Shaft Weight:</b>							<b>27,200</b>

### Bottom

### Top

Sec. No.	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Taper
1	56.18	0.00	77.40	30386.58	21.23	128.41	46.78	47.00	64.35	17459.0	17.44	106.92	0.200030
2	48.78	40.75	57.61	17053.51	21.53	130.08	38.08	94.25	44.87	8058.91	16.49	101.54	0.200030
3	39.58	89.25	31.21	6097.74	26.50	158.31	28.88	142.7	22.71	2351.56	18.96	115.50	0.200030
4	30.00	139.0	17.74	1992.41	26.80	160.00	24.00	169.0	14.17	1015.22	21.16	128.00	0.200030

### Additional Steel

Elev From (ft)	Elev To (ft)	Qty	Description	Fy (ksi)	Fu (ksi)	Offset (in)	Intermediate Connectors	Spacing (in)	Termination Connectors	Spacing (in)	Lower Qty	Upper Qty
							Description		Description			
91.25	99.25	3	LNP LP6X100-G-10TT	65	80	0.00	5/8" Hollo Bolt	23.00	5/8" Hollo Bolt		9	10
99.25	107.2	3	LNP LP6X100-G-10TT	65	80	0.00	5/8" Hollo Bolt	23.00	5/8" Hollo Bolt		9	9

## Loading Summary

**Structure:** CT13071-A-SBA  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016

Page: 6



### Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
1	167.00	AIR B2A B4P	3	91.50	6.58	0.86	129.20	6.970	0.86	0.00	0.00
2	167.00	AIR B4A B2P	3	90.40	6.58	0.86	128.10	6.970	0.86	0.00	0.00
3	167.00	Ericsson KRY 112 144/1	3	11.00	0.41	0.50	14.10	0.550	0.50	0.00	0.00
4	167.00	Ericsson S11B12	3	51.00	3.31	0.50	75.70	3.890	0.50	0.00	0.00
5	167.00	LNx-6515DS	3	50.30	11.41	0.84	115.60	12.340	0.84	0.00	0.00
6	167.00	T-Arms/Commscope VSR-MS-B	3	340.00	6.75	0.75	420.00	10.500	0.75	0.00	0.50
7	157.00	ALU RRH2X60-AWS RRH	3	60.00	3.96	0.50	80.10	4.230	0.50	0.00	0.00
8	157.00	BXA-70063/6CF	1	17.00	7.73	0.70	57.60	8.540	0.70	0.00	0.00
9	157.00	DB846F65ZAXY	4	21.00	7.05	0.93	0.00	0.000	0.93	0.00	0.00
10	157.00	DB846H80E-SX	2	16.00	5.01	1.10	0.00	0.000	1.10	0.00	0.00
11	157.00	GPS	1	10.00	1.00	1.00	18.00	1.250	1.00	0.00	0.00
12	157.00	HBX-6517DS-VTM	6	18.70	5.30	0.75	46.20	6.010	0.75	0.00	0.00
13	157.00	RFS DB T1-6Z-8AB-OZ Distribution B	1	19.00	3.74	0.67	35.80	3.960	0.67	0.00	0.00
14	157.00	SLCP 2x6014F	2	20.00	7.21	0.89	70.40	7.880	0.89	0.00	0.00
15	157.00	T-Arms	3	350.00	8.00	0.75	420.00	10.500	0.75	0.00	0.00
16	150.00	Collar Mount	1	100.00	3.00	1.00	450.00	5.000	1.00	0.00	0.00
17	148.00	CCI HPA-65R-BUU-H6	1	51.00	10.36	0.85	108.40	10.580	0.85	0.00	0.00
18	148.00	CCI HPA-65R-BUU-H8	2	68.00	13.30	0.79	137.00	13.900	0.79	0.00	0.00
19	148.00	Cci OPA-65R-LCUU-H6	1	73.00	10.36	0.79	134.00	10.850	0.79	0.00	0.00
20	148.00	Cci OPA-65R-LCUU-H8	2	88.00	12.98	0.79	162.00	13.580	0.79	0.00	0.00
21	148.00	Ericsson RRUS 12-B2-RRU	3	58.00	3.67	0.50	75.70	3.890	0.50	0.00	0.00
22	148.00	Ericsson RRUS 32-RRU	3	77.00	1.93	0.50	86.20	2.100	0.50	0.00	0.00
23	148.00	Ericsson RRUS A2 Module	3	21.20	1.86	0.50	31.40	2.150	0.50	0.00	0.00
24	148.00	Ericsson RRUS-11-RRU	3	50.00	2.94	0.60	66.00	3.140	0.60	0.00	0.00
25	148.00	Powerwave 1001940-Bias Ts	3	2.00	0.08	0.50	1.40	0.130	0.50	0.00	0.00
26	148.00	Powerwave 7770	3	35.00	5.88	0.73	0.00	6.530	0.73	0.00	0.00
27	148.00	Powerwave LGP13519 Diplexer-Duple	6	5.30	0.34	0.50	8.00	0.470	0.50	0.00	0.00
28	148.00	Powerwave LGP21401 TMA	6	14.10	1.29	0.50	21.20	1.530	0.50	0.00	0.00
29	148.00	Raycap DC6-48-60-18-8F-Surge Supp	2	32.80	1.47	0.67	49.50	1.670	0.67	0.00	0.00
30	148.00	T-Arms	3	350.00	8.00	0.75	420.00	10.500	0.75	0.00	0.00
31	127.00	2.5GHz RRH BTS	3	33.00	1.82	0.73	44.90	2.090	0.73	0.00	0.00
32	127.00	LLPX310R	3	28.60	4.83	0.69	54.50	5.360	0.69	0.00	0.00
33	127.00	Sector Frames	3	500.00	15.00	0.75	700.00	21.500	0.75	0.00	0.00
34	127.00	VHLP2-11	3	27.00	4.68	0.90	55.00	5.050	0.90	0.10	0.00
35	127.00	VHLP800-11	1	48.00	8.43	1.00	97.00	8.920	1.00	0.10	0.00
<b>Totals:</b>			<b>96</b>	<b>7,758.20</b>			<b>10,944.70</b>				

### Linear Appurtenances

Bottom Elev. (ft)	Top Elev. (ft)	Description	No Ice		Ice		Exposed
			Weight (lb/ft)	CaAa (sf/ft)	Weight (lb/ft)	CaAa (sf/ft)	
0.00	167.00	(12) 1 5/8" Coax	12.00	0.00	12.00	0.00	Inside
0.00	167.00	(1) 1 5/8" Fiber	1.20	0.00	1.20	0.00	Inside
0.00	157.00	(12) 1 5/8" Coax	12.00	0.00	12.00	0.00	Inside
0.00	157.00	(6) 1 5/8" Coax	6.00	0.20	15.00	0.30	Outside

## Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
0.00	157.00	(1) 1 5/8" Fiber		1.20	0.00		1.20	0.00		Inside	
0.00	157.00	(1) 1/2" Coax		0.75	0.00		0.75	0.00		Inside	
0.00	148.00	(12) 1 5/8" Coax		12.00	0.00		12.00	0.00		Inside	
0.00	148.00	(1) 1/2" Fiber		0.72	0.00		0.72	0.00		Inside	
0.00	148.00	(2) 3/4" DC Power		1.60	0.00		1.60	0.00		Inside	
0.00	127.00	(4) 1/2" Coax		3.00	0.00		3.00	0.00		Inside	
0.00	127.00	(3) 1/4" Coax		0.12	0.00		0.12	0.00		Inside	
0.00	127.00	(3) 5/16" Coax		0.30	0.00		0.30	0.00		Inside	
0.00	127.00	(3) 5/8"		0.52	0.00		0.52	0.00		Inside	
99.25	109.25	(1) 1" Reinforcing plate		0.00	0.17		0.00	0.27		Outside	
89.25	99.25	(1) 1" Reinforcing plate		0.00	0.17		0.00	0.27		Outside	
<b>Totals:</b>				<b>7,956.29</b>			<b>9,369.29</b>				

## Shaft Section Properties

**Structure:** CT13071-A-SBA  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 8



**Increment Length:** 5 (ft)

Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in^2)	Ix (in^4)	W/t Ratio	D/t Ratio	Fy (ksi)	Fb (ksi)	Weight (lb)	Additional Reinforcing			
											Area (in^2)	Ixp (in^4)	Iyp (in^4)	Weight (lb)
0.00		0.4375	56.180	77.403	30386.6	21.23	128.41	65	52	0.0				
5.00		0.4375	55.180	76.014	28780.1	20.83	126.13	65	52	1305.1				
10.00		0.4375	54.180	74.625	27231.3	20.43	123.84	65	52	1281.5				
15.00		0.4375	53.180	73.236	25739.1	20.02	121.55	65	52	1257.8				
20.00		0.4375	52.179	71.848	24302.4	19.62	119.27	65	52	1234.2				
25.00		0.4375	51.179	70.459	22920.2	19.22	116.98	65	52	1210.6				
30.00		0.4375	50.179	69.070	21591.5	18.81	114.70	65	52	1187.0				
35.00		0.4375	49.179	67.681	20315.1	18.41	112.41	65	52	1163.3				
40.00		0.4375	48.179	66.292	19090.0	18.01	110.12	65	52	1139.7				
40.75	Bot - Section 2	0.4375	48.029	66.084	18910.6	17.95	109.78	65	52	168.9				
45.00		0.4375	47.179	64.904	17915.2	17.60	107.84	65	52	1773.0				
47.00	Top - Section 1	0.3750	47.529	56.123	15766.0	20.94	126.74	65	52	823.4				
50.00		0.3750	46.929	55.408	15171.7	20.66	125.14	65	52	569.3				
55.00		0.3750	45.928	54.218	14214.7	20.19	122.48	65	52	932.6				
60.00		0.3750	44.928	53.028	13298.8	19.71	119.81	65	52	912.3				
65.00		0.3750	43.928	51.837	12423.2	19.24	117.14	65	52	892.1				
70.00		0.3750	42.928	50.647	11586.8	18.77	114.47	65	52	871.8				
75.00		0.3750	41.928	49.456	10788.9	18.30	111.81	65	52	851.6				
80.00		0.3750	40.928	48.266	10028.4	17.83	109.14	65	52	831.3				
85.00		0.3750	39.927	47.076	9304.6	17.36	106.47	65	52	811.1				
89.25	Bot - Section 3	0.3750	39.077	46.064	8717.4	16.96	104.21	65	52	673.5				
90.00		0.3750	38.927	45.885	8616.4	16.89	103.81	65	52	196.8				
91.25	RB1	0.3750	38.677	45.588	8449.9	16.78	103.14	65	52	326.3	18.00	4460.1	2812.1	76.6
94.25	Top - Section 2	0.2500	38.577	30.412	5644.2	25.80	154.31	65	52	774.6	18.00	4328.3	2729.4	183.7
95.00		0.2500	38.427	30.293	5578.2	25.69	153.71	65	51	77.5	18.00	4290.5	2703.4	45.9
99.25	RT1 RB2	0.2500	37.577	29.618	5213.8	25.09	150.31	65	52	433.2	18.00	4108.2	2589.1	260.3
100.00		0.2500	37.427	29.499	5151.2	24.99	149.71	65	52	75.4	18.00	4076.4	2569.2	45.9
105.00		0.2500	36.427	28.705	4746.6	24.28	145.71	65	52	495.1	18.00	3867.9	2438.5	306.2
107.25	RT2	0.2500	35.977	28.348	4571.6	23.96	143.91	65	52	218.4	18.00	3775.8	2380.9	137.8
110.00		0.2500	35.427	27.912	4363.7	23.58	141.71	65	52	263.2				
115.00		0.2500	34.427	27.118	4001.9	22.87	137.71	65	52	468.1				
120.00		0.2500	33.426	26.325	3660.8	22.17	133.71	65	52	454.6				
125.00		0.2500	32.426	25.531	3339.6	21.46	129.71	65	52	441.1				
127.00		0.2500	32.026	25.214	3216.6	21.18	128.10	65	52	172.7				
130.00		0.2500	31.426	24.737	3037.7	20.75	125.70	65	52	255.0				
135.00		0.2500	30.426	23.944	2754.7	20.05	121.70	65	52	414.1				
139.00	Bot - Section 4	0.2500	29.626	23.309	2541.3	19.48	118.50	65	52	321.6				
140.00		0.2500	29.426	23.150	2489.7	19.34	117.70	65	52	139.2				
142.75	Top - Section 3	0.1875	29.251	17.296	1845.8	26.10	156.00	65	52	378.0				
145.00		0.1875	28.801	17.028	1761.3	25.67	153.60	65	51	131.4				
148.00		0.1875	28.201	16.671	1652.8	25.11	150.40	65	52	172.0				
150.00		0.1875	27.801	16.433	1583.0	24.73	148.27	65	52	112.6				
155.00		0.1875	26.800	15.837	1417.2	23.79	142.94	65	52	274.5				
157.00		0.1875	26.400	15.599	1354.2	23.42	140.80	65	52	107.0				
160.00		0.1875	25.800	15.242	1263.3	22.85	137.60	65	52	157.4				
165.00		0.1875	24.800	14.647	1121.0	21.91	132.27	65	52	254.3				
167.00		0.1875	24.400	14.409	1067.3	21.54	130.13	65	52	98.9				
169.00		0.1875	24.000	14.171	1015.2	21.16	128.00	65	52	97.3				
<b>Total Weight</b>										<b>27200.5</b>				
											<b>1056.6</b>			

## Wind Loading - Shaft

**Structure:** CT13071-A-SBA

**Code:** EIA/TIA-222-F

6/21/2016



**Site Name:** Woodbridge

**Exposure:** C

**Height:** 169.00 (ft)

**Gh:** 1.69

Page: 9

**Base Elev:** 0.000 (ft)


**Struct Class:** II

**Load Case:** 85 mph Wind with 0" Ice

**Iterations:** 27

**Dead Load Factor** 1.00

**Wind Load Factor** 1.00



Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		0.00	1.00	18.496	31.26	397.94	0.650	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		0.00	1.00	18.496	31.26	390.86	0.650	0.000	5.00	23.200	15.08	471.4	0.0	1305.1
10.00		0.00	1.00	18.496	31.26	383.77	0.650	0.000	5.00	22.783	14.81	462.9	0.0	1281.5
15.00		0.00	1.00	18.496	31.26	376.69	0.650	0.000	5.00	22.367	14.54	454.4	0.0	1257.8
20.00		0.00	1.00	18.496	31.26	369.60	0.650	0.000	5.00	21.950	14.27	446.0	0.0	1234.2
25.00		0.00	1.00	18.496	31.26	362.52	0.650	0.000	5.00	21.533	14.00	437.5	0.0	1210.6
30.00		0.00	1.00	18.496	31.26	355.44	0.650	0.000	5.00	21.116	13.73	429.0	0.0	1187.0
35.00		0.00	1.02	18.810	31.79	351.29	0.650	0.000	5.00	20.700	13.45	427.7	0.0	1163.3
40.00		0.00	1.06	19.541	33.02	350.78	0.650	0.000	5.00	20.283	13.18	435.4	0.0	1139.7
40.75	Bot - Section 2	0.00	1.06	19.645	33.20	350.61	0.650	0.000	0.75	3.006	1.95	64.9	0.0	168.9
45.00		0.00	1.09	20.210	34.15	349.32	0.650	0.000	4.25	17.125	11.13	380.2	0.0	1773.0
47.00	Top - Section 1	0.00	1.11	20.463	34.58	348.52	0.650	0.000	2.00	7.955	5.17	178.8	0.0	823.4
50.00		0.00	1.13	20.827	35.20	352.74	0.650	0.000	3.00	11.807	7.67	270.1	0.0	569.3
55.00		0.00	1.16	21.402	36.17	349.95	0.650	0.000	5.00	19.345	12.57	454.8	0.0	932.6
60.00		0.00	1.19	21.941	37.08	346.62	0.650	0.000	5.00	18.928	12.30	456.2	0.0	912.3
65.00		0.00	1.21	22.449	37.94	342.80	0.650	0.000	5.00	18.512	12.03	456.5	0.0	892.1
70.00		0.00	1.24	22.929	38.75	338.56	0.650	0.000	5.00	18.095	11.76	455.8	0.0	871.8
75.00		0.00	1.26	23.386	39.52	333.94	0.650	0.000	5.00	17.678	11.49	454.1	0.0	851.6
80.00		0.00	1.29	23.821	40.26	329.00	0.650	0.000	5.00	17.262	11.22	451.7	0.0	831.3
85.00		0.00	1.31	24.237	40.96	323.75	0.650	0.000	5.00	16.845	10.95	448.5	0.0	811.1
89.25	Bot - Section 3	0.00	1.33	24.577	41.54	319.07	0.650	0.000	4.25	13.990	9.09	377.7	0.0	673.5
90.00		0.00	1.33	24.636	41.63	318.23	0.650	0.000	0.75	2.469	1.60	66.8	0.0	196.8
91.25	RB1	0.00	1.34	24.733	41.80	316.81	0.650	0.000	1.25	4.094	2.66	111.2	0.0	326.3
94.25	Top - Section 2	0.00	1.35	24.963	42.19	313.34	0.650	0.000	3.00	9.719	6.32	266.5	0.0	774.6
95.00		0.00	1.35	25.020	42.28	316.58	0.650	0.000	0.75	2.406	1.56	66.1	0.0	77.5
99.25	RT1 RB2	0.00	1.37	25.334	42.82	311.51	0.650	0.000	4.25	13.459	8.75	374.6	0.0	433.2
100.00		0.00	1.37	25.389	42.91	310.60	0.650	0.000	0.75	2.344	1.52	65.4	0.0	75.4
105.00		0.00	1.39	25.745	43.51	304.42	0.650	0.000	5.00	15.386	10.00	435.1	0.0	495.1
107.25	RT2	0.00	1.40	25.902	43.77	301.57	0.650	0.000	2.25	6.788	4.41	193.1	0.0	218.4
110.00		0.00	1.41	26.090	44.09	298.03	0.650	0.000	2.75	8.182	5.32	234.5	0.0	263.2
115.00		0.00	1.43	26.423	44.66	291.47	0.650	0.000	5.00	14.553	9.46	422.4	0.0	468.1
120.00		0.00	1.45	26.747	45.20	284.72	0.650	0.000	5.00	14.136	9.19	415.3	0.0	454.6
125.00		0.00	1.46	27.060	45.73	277.82	0.650	0.000	5.00	13.719	8.92	407.8	0.0	441.1
127.00	Appurtenance(s)	0.00	1.47	27.183	45.94	275.02	0.650	0.000	2.00	5.371	3.49	160.4	0.0	172.7
130.00		0.00	1.48	27.365	46.25	270.76	0.650	0.000	3.00	7.932	5.16	238.4	0.0	255.0
135.00		0.00	1.50	27.662	46.75	263.56	0.650	0.000	5.00	12.886	8.38	391.6	0.0	414.1
139.00	Bot - Section 4	0.00	1.51	27.894	47.14	257.71	0.650	0.000	4.00	10.009	6.51	306.7	0.0	321.6
140.00		0.00	1.51	27.951	47.24	256.23	0.650	0.000	1.00	2.492	1.62	76.5	0.0	139.2
142.75	Top - Section 3	0.00	1.52	28.107	47.50	252.14	0.650	0.000	2.75	6.766	4.40	208.9	0.0	378.0
145.00		0.00	1.53	28.233	47.71	252.04	0.650	0.000	2.25	5.442	3.54	168.8	0.0	131.4
148.00	Appurtenance(s)	0.00	1.54	28.398	47.99	247.52	0.650	0.000	3.00	7.125	4.63	222.3	0.0	172.0
150.00	Appurtenance(s)	0.00	1.54	28.507	48.18	244.47	0.650	0.000	2.00	4.667	3.03	146.1	0.0	112.6
155.00		0.00	1.56	28.776	48.63	236.78	0.650	0.000	5.00	11.375	7.39	359.6	0.0	274.5
157.00	Appurtenance(s)	0.00	1.56	28.881	48.81	233.68	0.650	0.000	2.00	4.433	2.88	140.7	0.0	107.0
160.00		0.00	1.57	29.038	49.07	228.98	0.650	0.000	3.00	6.525	4.24	208.1	0.0	157.4
165.00		0.00	1.58	29.294	49.51	221.08	0.650	0.000	5.00	10.542	6.85	339.2	0.0	254.3
167.00	Appurtenance(s)	0.00	1.59	29.395	49.68	217.89	0.650	0.000	2.00	4.100	2.67	132.4	0.0	98.9
169.00		0.00	1.59	29.495	49.85	214.68	0.650	0.000	2.00	4.033	2.62	130.7	0.0	97.3

## Wind Loading - Shaft

**Structure:** CT13071-A-SBA

**Site Name:** Woodbridge

**Height:** 169.00 (ft)

**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F

**Exposure:** C

**Gh:** 1.69

**Struct Class:** II

6/21/2016

Page: 10



**Totals:** 169.00

14,303.0

27,200.5

## Discrete Appurtenance Forces

**Structure:** CT13071-A-SB  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)


**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 11



**Load Case:** 85 mph Wind with 0" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 27

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa Factor	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	167.00	LNx-6515DS	3	29.395	49.678	0.84	28.75	150.90	0.000	0.000	1428.41	0.00	0.00
2	167.00	Ericsson S11B12	3	29.395	49.678	0.50	4.96	153.00	0.000	0.000	246.65	0.00	0.00
3	167.00	Ericsson KRY 112 144/1	3	29.395	49.678	0.50	0.61	33.00	0.000	0.000	30.55	0.00	0.00
4	167.00	AIR B4A B2P	3	29.395	49.678	0.86	16.98	271.20	0.000	0.000	843.36	0.00	0.00
5	167.00	AIR B2A B4P	3	29.395	49.678	0.86	16.98	274.50	0.000	0.000	843.36	0.00	0.00
6	167.00	T-Arms/Commscope	3	29.420	49.721	0.75	15.19	1020.00	0.000	0.500	755.13	0.00	377.57
7	157.00	DB846H80E-SX	2	28.881	48.809	1.10	11.02	32.00	0.000	0.000	537.98	0.00	0.00
8	157.00	ALU RRH2X60-AWS RRH	3	28.881	48.809	0.50	5.94	180.00	0.000	0.000	289.93	0.00	0.00
9	157.00	BXA-70063/6CF	1	28.881	48.809	0.70	5.41	17.00	0.000	0.000	264.11	0.00	0.00
10	157.00	DB846F65ZAXY	4	28.881	48.809	0.93	26.23	84.00	0.000	0.000	1280.07	0.00	0.00
11	157.00	RFS DB T1-6Z-8AB-OZ	1	28.881	48.809	0.67	2.51	19.00	0.000	0.000	122.31	0.00	0.00
12	157.00	GPS	1	28.881	48.809	1.00	1.00	10.00	0.000	0.000	48.81	0.00	0.00
13	157.00	HBX-6517DS-VTM	6	28.881	48.809	0.75	23.85	112.20	0.000	0.000	1164.10	0.00	0.00
14	157.00	SLCP 2x6014F	2	28.881	48.809	0.89	12.83	40.00	0.000	0.000	626.41	0.00	0.00
15	157.00	T-Arms	3	28.881	48.809	0.75	18.00	1050.00	0.000	0.000	878.57	0.00	0.00
16	150.00	Collar Mount	1	28.507	48.177	1.00	3.00	100.00	0.000	0.000	144.53	0.00	0.00
17	148.00	T-Arms	3	28.398	47.993	0.75	18.00	1050.00	0.000	0.000	863.87	0.00	0.00
18	148.00	Raycap	2	28.398	47.993	0.67	1.97	65.60	0.000	0.000	94.54	0.00	0.00
19	148.00	Ericsson RRUS 32-RRU	3	28.398	47.993	0.50	2.90	231.00	0.000	0.000	138.94	0.00	0.00
20	148.00	CCI HPA-65R-BUU-H6	1	28.398	47.993	0.85	8.81	51.00	0.000	0.000	422.63	0.00	0.00
21	148.00	CCI HPA-65R-BUU-H8	2	28.398	47.993	0.79	21.01	136.00	0.000	0.000	1008.53	0.00	0.00
22	148.00	Cci OPA-65R-LCUU-H6	1	28.398	47.993	0.79	8.18	73.00	0.000	0.000	392.79	0.00	0.00
23	148.00	Cci OPA-65R-LCUU-H8	2	28.398	47.993	0.79	20.51	176.00	0.000	0.000	984.26	0.00	0.00
24	148.00	Ericsson RRUS 12-B2-RRU	3	28.398	47.993	0.50	5.50	174.00	0.000	0.000	264.20	0.00	0.00
25	148.00	Powerwave LGP21401 TMA	6	28.398	47.993	0.50	3.87	84.60	0.000	0.000	185.73	0.00	0.00
26	148.00	Ericsson RRUS A2 Module	3	28.398	47.993	0.50	2.79	63.60	0.000	0.000	133.90	0.00	0.00
27	148.00	Ericsson RRUS-11-RRU	3	28.398	47.993	0.60	5.29	150.00	0.000	0.000	253.98	0.00	0.00
28	148.00	Powerwave 1001940-Bias Ts	3	28.398	47.993	0.50	0.12	6.00	0.000	0.000	5.76	0.00	0.00
29	148.00	Powerwave 7770	3	28.398	47.993	0.73	12.88	105.00	0.000	0.000	618.02	0.00	0.00
30	148.00	Powerwave LGP13519	6	28.398	47.993	0.50	1.02	31.80	0.000	0.000	48.95	0.00	0.00
31	127.00	VHLP800-11	1	27.183	45.940	1.00	8.43	48.00	1.455	0.000	387.27	563.49	0.00
32	127.00	VHLP2-11	3	27.183	45.940	0.90	12.64	81.00	1.455	0.000	580.50	844.63	0.00
33	127.00	Sector Frames	3	27.183	45.940	0.75	33.75	1500.00	0.000	0.000	1550.47	0.00	0.00
34	127.00	LLPX310R	3	27.183	45.940	0.69	10.00	85.80	0.000	0.000	459.31	0.00	0.00
35	127.00	2.5GHz RRH BTS	3	27.183	45.940	0.73	3.99	99.00	0.000	0.000	183.11	0.00	0.00
<b>Totals:</b>								<b>7,758.20</b>			<b>18,081.03</b>		

## Total Applied Force Summary

**Structure:** CT13071-A-SB  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)


**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 12



**Load Case:** 85 mph Wind with 0" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 27

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		502.63	1562.16	0.00	0.00
10.00		494.16	1538.53	0.00	0.00
15.00		485.70	1514.90	0.00	0.00
20.00		477.23	1491.27	0.00	0.00
25.00		468.76	1467.64	0.00	0.00
30.00		460.30	1444.01	0.00	0.00
35.00		459.49	1420.38	0.00	0.00
40.00		468.41	1396.76	0.00	0.00
40.75		69.86	207.48	0.00	0.00
45.00		409.22	1991.49	0.00	0.00
47.00		192.64	926.20	0.00	0.00
50.00		291.25	723.50	0.00	0.00
55.00		490.99	1189.63	0.00	0.00
60.00		493.30	1169.38	0.00	0.00
65.00		494.44	1149.13	0.00	0.00
70.00		494.52	1128.88	0.00	0.00
75.00		493.66	1108.62	0.00	0.00
80.00		491.94	1088.37	0.00	0.00
85.00		489.44	1068.12	0.00	0.00
89.25		413.02	891.97	0.00	0.00
90.00		78.37	235.37	0.00	0.00
91.25		130.56	390.60	0.00	0.00
94.25		313.35	928.84	0.00	0.00
95.00		77.87	116.02	0.00	0.00
99.25		441.89	651.70	0.00	0.00
100.00		77.28	113.99	0.00	0.00
105.00		515.64	752.19	0.00	0.00
107.25		229.58	334.08	0.00	0.00
110.00		273.73	404.61	0.00	0.00
115.00		467.06	725.19	0.00	0.00
120.00		460.53	711.68	0.00	0.00
125.00		453.55	698.18	0.00	0.00
127.00	(13) appurtenances	3339.42	2089.29	1408.12	0.00
130.00		266.18	397.37	0.00	0.00
135.00		438.31	651.48	0.00	0.00
139.00		344.39	511.46	0.00	0.00
140.00		85.95	186.68	0.00	0.00
142.75		235.04	508.51	0.00	0.00
145.00		190.26	238.20	0.00	0.00
148.00	(41) appurtenances	5667.17	2712.01	0.00	0.00
150.00	(1) appurtenances	309.94	278.94	0.00	0.00
155.00		408.20	440.27	0.00	0.00
157.00	(23) appurtenances	5372.46	1717.47	0.00	0.00
160.00		208.14	197.02	0.00	0.00
165.00		339.23	320.27	0.00	0.00
167.00	(18) appurtenances	4279.84	2027.87	0.00	377.57
169.00		130.68	97.25	0.00	0.00



## Total Applied Force Summary

**Structure:** CT13071-A-SB      **Code:** EIA/TIA-222-F      6/21/2016  
**Site Name:** Woodbridge      **Exposure:** C  
**Height:** 169.00 (ft)      **Gh:** 1.69  
**Base Elev:** 0.000 (ft)      **Struct Class:** II

Page: 13



<b>Totals:</b>	<u>33,775.61</u>	<u>42,914.98</u>	<u>1,408.12</u>	<u>377.57</u>
----------------	------------------	------------------	-----------------	---------------

## Resulting Forces and Deflections

**Structure:** CT13071-A-SB  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)


**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 14



**Load Case:** 85 mph Wind with 0" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 27

Elev (ft)	Lateral FX (-) (kips)	Axial FY (-) (kips)	Lateral FZ (kips)	Moment MX (ft-kips)	Torsion MY (ft-kips)	Moment MZ (ft-kips)	Deflect X (in)	Deflect Z (in)	Deflect Resultant (in)	Rotation Sway (deg)	Rotation Twist (deg)
0.00	-33.849	-42.857	0.000	-0.019	-1.382	-4188.588	0.000	0.000	0.000	0.000	0.000
5.00	-33.483	-41.183	0.000	-0.019	-1.382	-4019.346	-0.103	0.000	0.103	-0.192	0.000
10.00	-33.116	-39.534	0.000	-0.019	-1.382	-3851.935	-0.409	0.000	0.409	-0.387	0.000
15.00	-32.749	-37.910	0.000	-0.020	-1.382	-3686.357	-0.919	0.000	0.919	-0.584	0.000
20.00	-32.381	-36.312	0.000	-0.020	-1.382	-3522.615	-1.637	0.000	1.637	-0.783	0.000
25.00	-32.013	-34.739	0.000	-0.021	-1.383	-3360.713	-2.565	0.000	2.565	-0.984	0.000
30.00	-31.644	-33.191	0.000	-0.022	-1.383	-3200.652	-3.705	0.000	3.705	-1.188	0.000
35.00	-31.267	-31.668	0.000	-0.024	-1.383	-3042.436	-5.059	0.000	5.059	-1.393	-0.001
40.00	-30.825	-30.220	0.000	-0.023	-1.384	-2886.105	-6.630	0.000	6.630	-1.601	-0.001
40.75	-30.805	-29.958	0.000	-0.025	-1.384	-2862.987	-6.884	0.000	6.884	-1.633	-0.001
45.00	-30.400	-27.910	0.000	-0.025	-1.384	-2732.069	-8.419	0.000	8.419	-1.812	-0.001
47.00	-30.228	-26.934	0.000	-0.027	-1.384	-2671.270	-9.197	0.000	9.197	-1.898	-0.001
50.00	-29.996	-26.125	0.000	-0.029	-1.385	-2580.587	-10.431	0.000	10.431	-2.026	-0.001
55.00	-29.563	-24.834	0.000	-0.031	-1.386	-2430.612	-12.679	0.000	12.679	-2.261	-0.001
60.00	-29.119	-23.566	0.001	-0.034	-1.387	-2282.802	-15.173	0.000	15.173	-2.497	-0.001
65.00	-28.664	-22.322	0.001	-0.036	-1.387	-2137.211	-17.914	0.001	17.914	-2.733	-0.001
70.00	-28.202	-21.103	0.001	-0.039	-1.388	-1993.891	-20.903	0.001	20.903	-2.970	-0.001
75.00	-27.731	-19.909	0.001	-0.043	-1.389	-1852.885	-24.139	0.001	24.139	-3.206	-0.002
80.00	-27.254	-18.740	0.001	-0.046	-1.390	-1714.231	-27.621	0.001	27.621	-3.441	-0.002
85.00	-26.765	-17.604	0.001	-0.050	-1.392	-1577.964	-31.349	0.002	31.349	-3.675	-0.002
89.25	-26.328	-16.688	0.001	-0.051	-1.392	-1464.214	-34.708	0.002	34.708	-3.872	-0.002
90.00	-26.247	-16.437	0.001	-0.052	-1.392	-1444.468	-35.319	0.002	35.319	-3.908	-0.002
91.25	-26.113	-16.019	0.001	-0.054	-1.393	-1411.659	-36.350	0.002	36.350	-3.967	-0.002
94.25	-25.752	-15.085	0.001	-0.055	-1.393	-1333.321	-38.874	0.002	38.874	-4.071	-0.002
95.00	-25.694	-14.927	0.001	-0.057	-1.396	-1314.007	-39.515	0.002	39.515	-4.097	-0.002
99.25	-25.233	-14.263	0.001	-0.057	-1.397	-1204.807	-43.244	0.003	43.244	-4.281	-0.003
100.00	-25.177	-14.101	0.001	-0.060	-1.398	-1185.883	-43.918	0.003	43.918	-4.313	-0.003
105.00	-24.639	-13.328	0.001	-0.061	-1.399	-1060.000	-48.543	0.004	48.543	-4.520	-0.003
107.25	-24.407	-12.970	0.001	-0.063	-1.400	-1004.562	-50.693	0.004	50.693	-4.612	-0.003
110.00	-24.145	-12.504	0.001	-0.067	-1.402	-937.444	-53.379	0.005	53.379	-4.721	-0.004
115.00	-23.675	-11.707	0.001	-0.074	-1.404	-816.721	-58.473	0.006	58.473	-5.007	-0.004
120.00	-23.202	-10.934	0.002	-0.081	-1.406	-698.347	-63.857	0.007	63.857	-5.276	-0.005
125.00	-22.715	-10.215	0.002	-0.088	-1.407	-582.337	-69.512	0.008	69.512	-5.525	-0.005
127.00	-19.206	-8.422	0.002	0.047	0.000	-536.907	-71.844	0.009	71.844	-5.620	-0.005
130.00	-18.925	-7.996	0.002	0.042	0.000	-479.291	-75.415	0.009	75.415	-5.755	-0.005
135.00	-18.445	-7.338	0.002	0.034	0.000	-384.666	-81.543	0.010	81.543	-5.957	-0.005
139.00	-18.059	-6.838	0.002	0.027	0.000	-310.888	-86.590	0.011	86.590	-6.101	-0.005
140.00	-17.961	-6.643	0.002	0.026	0.000	-292.829	-87.869	0.011	87.869	-6.135	-0.005
142.75	-17.680	-6.140	0.002	0.022	0.000	-243.438	-91.422	0.012	91.422	-6.219	-0.005
145.00	-17.473	-5.901	0.002	0.018	0.000	-203.659	-94.363	0.012	94.363	-6.280	-0.005
148.00	-11.545	-3.817	0.001	0.013	0.000	-151.242	-98.332	0.013	98.332	-6.366	-0.005
150.00	-11.211	-3.560	0.001	0.011	0.000	-128.151	-101.004	0.013	101.004	-6.414	-0.005
155.00	-10.759	-3.159	0.001	0.006	0.000	-72.098	-107.761	0.014	107.761	-6.504	-0.005
157.00	-5.227	-2.060	0.000	0.004	0.000	-50.581	-110.486	0.015	110.486	-6.529	-0.005
160.00	-4.998	-1.886	0.000	0.003	0.000	-34.901	-114.589	0.015	114.589	-6.556	-0.005
165.00	-4.625	-1.605	0.000	0.001	0.000	-9.910	-121.456	0.016	121.456	-6.581	-0.005
167.00	-0.141	-0.082	0.000	0.000	0.000	-0.282	-124.207	0.017	124.207	-6.583	-0.005
169.00	-0.131	0.000	0.000	0.000	0.000	0.000	0.000	0.000	126.959	-6.583	-0.005

## Resulting Forces and Deflections

**Structure:** CT13071-A-SB

**Site Name:** Woodbridge

**Height:** 169.00 (ft)

**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F

**Exposure:** C

**Gh:** 1.69

**Struct Class:** II

6/21/2016

Page: 15



## Resulting Stresses

**Structure:** CT13071-A-SBA  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II


6/21/2016

Page: 16



**Load Case:** 85 mph Wind with 0" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 27

### Applied Stresses

Elev (ft)	fa Axial (Y) (ksi)	fvx Shear (X) (ksi)	fvz Shear (Z) (ksi)	fvT Torsion (ksi)	fbx Bending (X) (ksi)	fbz Bending (Z) (ksi)	fb Combined (ksi)	Fb Allow Stress (ksi)	f/Fb Stress Ratio
0.00	0.55	0.88	0.00	0.01	0.00	47.18	47.76	52.0	0.919
5.00	0.54	0.89	0.00	0.01	0.00	46.95	47.52	52.0	0.914
10.00	0.53	0.89	0.00	0.01	0.00	46.69	47.25	52.0	0.909
15.00	0.52	0.90	0.00	0.01	0.00	46.40	46.95	52.0	0.903
20.00	0.51	0.91	0.00	0.01	0.00	46.08	46.61	52.0	0.897
25.00	0.49	0.92	0.00	0.01	0.00	45.72	46.24	52.0	0.890
30.00	0.48	0.92	0.00	0.01	0.00	45.32	45.83	52.0	0.882
35.00	0.47	0.93	0.00	0.01	0.00	44.87	45.37	52.0	0.873
40.00	0.46	0.94	0.00	0.01	0.00	44.38	44.86	52.0	0.863
40.75	0.45	0.94	0.00	0.01	0.00	44.30	44.78	52.0	0.862
45.00	0.43	0.94	0.00	0.01	0.00	43.83	44.30	52.0	0.852
47.00	0.48	1.09	0.00	0.01	0.00	49.06	49.58	52.0	0.954
50.00	0.47	1.09	0.00	0.01	0.00	48.63	49.14	52.0	0.945
55.00	0.46	1.10	0.00	0.01	0.00	47.85	48.34	52.0	0.930
60.00	0.44	1.11	0.00	0.01	0.00	46.99	47.47	52.0	0.913
65.00	0.43	1.11	0.00	0.01	0.00	46.04	46.51	52.0	0.895
70.00	0.42	1.12	0.00	0.02	0.00	45.01	45.47	52.0	0.875
75.00	0.40	1.13	0.00	0.02	0.00	43.87	44.32	52.0	0.853
80.00	0.39	1.14	0.00	0.02	0.00	42.62	43.06	52.0	0.828
85.00	0.37	1.15	0.00	0.02	0.00	41.25	41.68	52.0	0.802
89.25	0.36	1.15	0.00	0.02	0.00	39.99	40.40	52.0	0.777
90.00	0.36	1.15	0.00	0.02	0.00	39.76	40.17	52.0	0.773
91.25	0.35	1.15	0.00	0.02	0.00	39.37	29.77	52.0	0.573
94.25	0.50	1.71	0.00	0.03	0.00	29.20	29.20	52.0	0.562
95.00	0.49	1.71	0.00	0.03	0.00	38.07	38.07	51.2	0.743
99.25	0.48	1.72	0.00	0.03	0.00	36.24	36.24	51.7	0.700
100.00	0.48	1.72	0.00	0.03	0.00	35.91	35.91	51.8	0.693
105.00	0.46	1.73	0.00	0.03	0.00	33.59	33.59	52.0	0.646
107.25	0.46	1.74	0.00	0.03	0.00	32.50	32.95	52.0	0.634
110.00	0.45	1.74	0.00	0.03	0.00	46.37	46.92	52.0	0.903
115.00	0.43	1.76	0.00	0.04	0.00	42.81	43.35	52.0	0.834
120.00	0.42	1.78	0.00	0.04	0.00	38.85	39.39	52.0	0.758
125.00	0.40	1.79	0.00	0.04	0.01	34.45	34.99	52.0	0.673
127.00	0.33	1.54	0.00	0.00	0.00	32.57	33.01	52.0	0.635
130.00	0.32	1.54	0.00	0.00	0.00	30.21	30.65	52.0	0.590
135.00	0.31	1.55	0.00	0.00	0.00	25.89	26.33	52.0	0.507
139.00	0.29	1.56	0.00	0.00	0.00	22.08	22.54	52.0	0.434
140.00	0.29	1.56	0.00	0.00	0.00	21.09	21.54	52.0	0.414
142.75	0.36	2.06	0.00	0.00	0.00	23.50	24.12	52.0	0.464
145.00	0.35	2.07	0.00	0.00	0.00	20.29	20.94	51.2	0.409
148.00	0.23	1.40	0.00	0.00	0.00	15.72	16.13	51.7	0.312
150.00	0.22	1.37	0.00	0.00	0.00	13.71	14.13	52.0	0.272
155.00	0.20	1.37	0.00	0.00	0.00	8.31	8.83	52.0	0.170
157.00	0.13	0.68	0.00	0.00	0.00	6.01	6.25	52.0	0.120
160.00	0.12	0.66	0.00	0.00	0.00	4.34	4.61	52.0	0.089
165.00	0.11	0.64	0.00	0.00	0.00	1.34	1.82	52.0	0.035
167.00	0.01	0.02	0.00	0.00	0.00	0.04	0.06	52.0	0.001

## Resulting Stresses

**Structure:** CT13071-A-SBA

**Code:** EIA/TIA-222-F

6/21/2016

**Site Name:** Woodbridge

**Exposure:** C

**Height:** 169.00 (ft)

**Gh:** 1.69

**Base Elev:** 0.000 (ft)

**Struct Class:** II

Page: 17



169.00	0.00	0.02	0.00	0.00	0.00	0.00	0.03	52.0	0.001
--------	------	------	------	------	------	------	------	------	-------

## Wind Loading - Shaft

**Structure:** CT13071-A-SBA  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)


**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 18



**Load Case:** 73.61 mph Wind with 0.5" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 27

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		0.00	1.00	13.871	23.44	344.62	0.650	0.500	0.00	0.000	0.00	0.0	0.0	0.0
5.00		0.00	1.00	13.871	23.44	338.48	0.650	0.500	5.00	23.617	15.35	359.9	171.8	1476.9
10.00		0.00	1.00	13.871	23.44	332.35	0.650	0.500	5.00	23.200	15.08	353.5	168.7	1450.2
15.00		0.00	1.00	13.871	23.44	326.21	0.650	0.500	5.00	22.783	14.81	347.2	165.6	1423.5
20.00		0.00	1.00	13.871	23.44	320.08	0.650	0.500	5.00	22.366	14.54	340.8	162.6	1396.8
25.00		0.00	1.00	13.871	23.44	313.94	0.650	0.500	5.00	21.950	14.27	334.5	159.5	1370.1
30.00		0.00	1.00	13.871	23.44	307.81	0.650	0.500	5.00	21.533	14.00	328.1	156.4	1343.3
35.00		0.00	1.02	14.106	23.84	304.22	0.650	0.500	5.00	21.116	13.73	327.2	153.3	1316.6
40.00		0.00	1.06	14.655	24.77	303.77	0.650	0.500	5.00	20.700	13.45	333.2	150.2	1289.9
40.75	Bot - Section 2	0.00	1.06	14.733	24.90	303.63	0.650	0.500	0.75	3.069	1.99	49.7	22.5	191.4
45.00		0.00	1.09	15.156	25.61	302.51	0.650	0.500	4.25	17.479	11.36	291.0	127.0	1900.0
47.00	Top - Section 1	0.00	1.11	15.346	25.93	301.82	0.650	0.500	2.00	8.121	5.28	136.9	59.3	882.7
50.00		0.00	1.13	15.620	26.40	305.47	0.650	0.500	3.00	12.057	7.84	206.9	87.8	657.1
55.00		0.00	1.16	16.051	27.13	303.06	0.650	0.500	5.00	19.762	12.85	348.4	143.3	1075.8
60.00		0.00	1.19	16.455	27.81	300.17	0.650	0.500	5.00	19.345	12.57	349.7	140.2	1052.5
65.00		0.00	1.21	16.836	28.45	296.86	0.650	0.500	5.00	18.928	12.30	350.1	137.1	1029.2
70.00		0.00	1.24	17.196	29.06	293.19	0.650	0.500	5.00	18.512	12.03	349.7	134.0	1005.8
75.00		0.00	1.26	17.538	29.64	289.20	0.650	0.500	5.00	18.095	11.76	348.6	130.9	982.5
80.00		0.00	1.29	17.865	30.19	284.91	0.650	0.500	5.00	17.678	11.49	346.9	127.8	959.2
85.00		0.00	1.31	18.177	30.72	280.37	0.650	0.500	5.00	17.261	11.22	344.7	124.7	935.8
89.25	Bot - Section 3	0.00	1.33	18.432	31.15	276.32	0.650	0.500	4.25	14.345	9.32	290.4	103.8	777.3
90.00		0.00	1.33	18.476	31.22	275.59	0.650	0.500	0.75	2.531	1.65	51.4	18.5	215.3
91.25	RB1	0.00	1.34	18.549	31.35	274.36	0.650	0.500	1.25	4.198	2.73	85.5	30.6	356.9
94.25	Top - Section 2	0.00	1.35	18.721	31.64	271.35	0.650	0.500	3.00	9.969	6.48	205.0	72.3	847.0
95.00		0.00	1.35	18.764	31.71	274.15	0.650	0.500	0.75	2.469	1.60	50.9	18.0	95.5
99.25	RT1 RB2	0.00	1.37	19.000	32.11	269.77	0.650	0.500	4.25	13.813	8.98	288.3	99.9	533.1
100.00		0.00	1.37	19.041	32.18	268.98	0.650	0.500	0.75	2.406	1.56	50.3	17.6	93.0
105.00		0.00	1.39	19.308	32.63	263.63	0.650	0.500	5.00	15.803	10.27	335.2	113.9	609.1
107.25	RT2	0.00	1.40	19.425	32.83	261.16	0.650	0.500	2.25	6.975	4.53	148.8	50.7	269.1
110.00		0.00	1.41	19.566	33.07	258.10	0.650	0.500	2.75	8.411	5.47	180.8	61.0	324.2
115.00		0.00	1.43	19.816	33.49	252.41	0.650	0.500	5.00	14.969	9.73	325.9	107.8	575.9
120.00		0.00	1.45	20.059	33.90	246.57	0.650	0.500	5.00	14.553	9.46	320.7	104.7	559.3
125.00		0.00	1.46	20.294	34.30	240.59	0.650	0.500	5.00	14.136	9.19	315.1	101.6	542.7
127.00	Appurtenance(s)	0.00	1.47	20.386	34.45	238.16	0.650	0.500	2.00	5.538	3.60	124.0	40.1	212.8
130.00		0.00	1.48	20.523	34.68	234.48	0.650	0.500	3.00	8.182	5.32	184.4	59.1	314.1
135.00		0.00	1.50	20.745	35.06	228.25	0.650	0.500	5.00	13.303	8.65	303.1	95.4	509.6
139.00	Bot - Section 4	0.00	1.51	20.919	35.35	223.17	0.650	0.500	4.00	10.342	6.72	237.7	74.4	395.9
140.00		0.00	1.51	20.962	35.43	221.89	0.650	0.500	1.00	2.575	1.67	59.3	18.7	157.9
142.75	Top - Section 3	0.00	1.52	21.079	35.62	218.35	0.650	0.500	2.75	6.995	4.55	162.0	50.5	428.5
145.00		0.00	1.53	21.173	35.78	218.27	0.650	0.500	2.25	5.630	3.66	130.9	40.7	172.1
148.00	Appurtenance(s)	0.00	1.54	21.297	35.99	214.35	0.650	0.500	3.00	7.375	4.79	172.5	53.1	225.1
150.00	Appurtenance(s)	0.00	1.54	21.379	36.13	211.71	0.650	0.500	2.00	4.833	3.14	113.5	34.9	147.6
155.00		0.00	1.56	21.581	36.47	205.06	0.650	0.500	5.00	11.792	7.66	279.5	84.2	358.8
157.00	Appurtenance(s)	0.00	1.56	21.660	36.60	202.36	0.650	0.500	2.00	4.600	2.99	109.5	33.2	140.2
160.00		0.00	1.57	21.777	36.80	198.30	0.650	0.500	3.00	6.775	4.40	162.1	48.7	206.1
165.00		0.00	1.58	21.969	37.13	191.45	0.650	0.500	5.00	10.958	7.12	264.5	78.1	332.3
167.00	Appurtenance(s)	0.00	1.59	22.045	37.26	188.69	0.650	0.500	2.00	4.267	2.77	103.3	30.7	129.6
169.00		0.00	1.59	22.120	37.38	185.91	0.650	0.500	2.00	4.200	2.73	102.1	30.2	127.5

## Wind Loading - Shaft

**Structure:** CT13071-A-SBA

**Site Name:** Woodbridge

**Height:** 169.00 (ft)

**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F

**Exposure:** C

**Gh:** 1.69

**Struct Class:** II

6/21/2016

Page: 19



**Totals:** 169.00

11,003.7

31,395.7

## Discrete Appurtenance Forces

**Structure:** CT13071-A-SB  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II


6/21/2016

Page: 20



**Load Case:** 73.61 mph Wind with 0.5" Ice

**Dead Load Factor**    1.00  
**Wind Load Factor**    1.00



**Iterations:** 27

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa Factor	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	167.00	LNx-6515DS	3	22.045	37.256	0.84	31.10	346.80	0.000	0.000	1158.56	0.00	0.00
2	167.00	Ericsson S11B12	3	22.045	37.256	0.50	5.83	227.10	0.000	0.000	217.39	0.00	0.00
3	167.00	Ericsson KRY 112 144/1	3	22.045	37.256	0.50	0.83	42.30	0.000	0.000	30.74	0.00	0.00
4	167.00	AIR B4A B2P	3	22.045	37.256	0.86	17.98	384.30	0.000	0.000	669.97	0.00	0.00
5	167.00	AIR B2A B4P	3	22.045	37.256	0.86	17.98	387.60	0.000	0.000	669.97	0.00	0.00
6	167.00	T-Arms/Commscope	3	22.064	37.288	0.75	23.63	1260.00	0.000	0.500	880.93	0.00	440.47
7	157.00	DB846H80E-SX	2	21.660	36.605	1.10	0.00	0.00	0.000	0.000	0.00	0.00	0.00
8	157.00	ALU RRH2X60-AWS RRH	3	21.660	36.605	0.50	6.35	240.30	0.000	0.000	232.26	0.00	0.00
9	157.00	BXA-70063/6CF	1	21.660	36.605	0.70	5.98	57.60	0.000	0.000	218.82	0.00	0.00
10	157.00	DB846F65ZAXY	4	21.660	36.605	0.93	0.00	0.00	0.000	0.000	0.00	0.00	0.00
11	157.00	RFS DB T1-6Z-8AB-OZ	1	21.660	36.605	0.67	2.65	35.80	0.000	0.000	97.12	0.00	0.00
12	157.00	GPS	1	21.660	36.605	1.00	1.25	18.00	0.000	0.000	45.76	0.00	0.00
13	157.00	HBX-6517DS-VTM	6	21.660	36.605	0.75	27.05	277.20	0.000	0.000	989.98	0.00	0.00
14	157.00	SLCP 2x6014F	2	21.660	36.605	0.89	14.03	140.80	0.000	0.000	513.43	0.00	0.00
15	157.00	T-Arms	3	21.660	36.605	0.75	23.63	1260.00	0.000	0.000	864.79	0.00	0.00
16	150.00	Collar Mount	1	21.379	36.131	1.00	5.00	450.00	0.000	0.000	180.65	0.00	0.00
17	148.00	T-Arms	3	21.297	35.993	0.75	23.63	1260.00	0.000	0.000	850.33	0.00	0.00
18	148.00	Raycap	2	21.297	35.993	0.67	2.24	99.00	0.000	0.000	80.54	0.00	0.00
19	148.00	Ericsson RRUS 32-RRU	3	21.297	35.993	0.50	3.15	258.60	0.000	0.000	113.38	0.00	0.00
20	148.00	CCI HPA-65R-BUU-H6	1	21.297	35.993	0.85	8.99	108.40	0.000	0.000	323.68	0.00	0.00
21	148.00	CCI HPA-65R-BUU-H8	2	21.297	35.993	0.79	21.96	274.00	0.000	0.000	790.47	0.00	0.00
22	148.00	Cci OPA-65R-LCUU-H6	1	21.297	35.993	0.79	8.57	134.00	0.000	0.000	308.51	0.00	0.00
23	148.00	Cci OPA-65R-LCUU-H8	2	21.297	35.993	0.79	21.46	324.00	0.000	0.000	772.27	0.00	0.00
24	148.00	Ericsson RRUS 12-B2-RRU	3	21.297	35.993	0.50	5.83	227.10	0.000	0.000	210.02	0.00	0.00
25	148.00	Powerwave LGP21401 TMA	6	21.297	35.993	0.50	4.59	127.20	0.000	0.000	165.21	0.00	0.00
26	148.00	Ericsson RRUS A2 Module	3	21.297	35.993	0.50	3.22	94.20	0.000	0.000	116.08	0.00	0.00
27	148.00	Ericsson RRUS-11-RRU	3	21.297	35.993	0.60	5.65	198.00	0.000	0.000	203.43	0.00	0.00
28	148.00	Powerwave 1001940-Bias Ts	3	21.297	35.993	0.50	0.20	4.20	0.000	0.000	7.02	0.00	0.00
29	148.00	Powerwave 7770	3	21.297	35.993	0.73	14.30	0.00	0.000	0.000	514.72	0.00	0.00
30	148.00	Powerwave LGP13519	6	21.297	35.993	0.50	1.41	48.00	0.000	0.000	50.75	0.00	0.00
31	127.00	VHLP800-11	1	20.386	34.453	1.00	8.92	97.00	1.455	0.000	307.32	447.15	0.00
32	127.00	VHLP2-11	3	20.386	34.453	0.90	13.63	165.00	1.455	0.000	469.77	683.51	0.00
33	127.00	Sector Frames	3	20.386	34.453	0.75	48.38	2100.00	0.000	0.000	1666.66	0.00	0.00
34	127.00	LLPX310R	3	20.386	34.453	0.69	11.10	163.50	0.000	0.000	382.26	0.00	0.00
35	127.00	2.5GHz RRH BTS	3	20.386	34.453	0.73	4.58	134.70	0.000	0.000	157.69	0.00	0.00

**Totals: 10,944.70**

**14,260.47**



## Total Applied Force Summary

**Structure:** CT13071-A-SB  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II


6/21/2016

Page: 21



**Load Case:** 73.61 mph Wind with 0.5" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 27

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		395.02	1778.97	0.00	0.00
10.00		388.67	1752.25	0.00	0.00
15.00		382.32	1725.54	0.00	0.00
20.00		375.97	1698.82	0.00	0.00
25.00		369.62	1672.11	0.00	0.00
30.00		363.27	1645.39	0.00	0.00
35.00		362.97	1618.68	0.00	0.00
40.00		370.38	1591.97	0.00	0.00
40.75		55.27	236.69	0.00	0.00
45.00		323.68	2156.76	0.00	0.00
47.00		152.47	1003.48	0.00	0.00
50.00		230.64	838.31	0.00	0.00
55.00		389.13	1377.90	0.00	0.00
60.00		391.39	1354.56	0.00	0.00
65.00		392.74	1331.22	0.00	0.00
70.00		393.27	1307.88	0.00	0.00
75.00		393.07	1284.54	0.00	0.00
80.00		392.21	1261.20	0.00	0.00
85.00		390.74	1237.86	0.00	0.00
89.25		330.16	1034.03	0.00	0.00
90.00		64.73	260.61	0.00	0.00
91.25		107.88	432.46	0.00	0.00
94.25		259.12	1028.19	0.00	0.00
95.00		64.44	140.79	0.00	0.00
99.25		366.08	789.82	0.00	0.00
100.00		64.09	138.30	0.00	0.00
105.00		428.17	911.14	0.00	0.00
107.25		190.95	404.98	0.00	0.00
110.00		225.91	490.33	0.00	0.00
115.00		376.09	877.96	0.00	0.00
120.00		371.51	861.37	0.00	0.00
125.00		366.58	844.78	0.00	0.00
127.00	(13) appurtenances	3128.39	2993.84	1130.67	0.00
130.00		215.66	483.48	0.00	0.00
135.00		355.74	791.91	0.00	0.00
139.00		280.08	621.83	0.00	0.00
140.00		69.92	214.38	0.00	0.00
142.75		191.37	583.75	0.00	0.00
145.00		155.10	299.14	0.00	0.00
148.00	(41) appurtenances	4711.34	3551.25	0.00	0.00
150.00	(1) appurtenances	315.85	681.87	0.00	0.00
155.00		334.25	569.51	0.00	0.00
157.00	(23) appurtenances	3093.58	2254.18	0.00	0.00
160.00		162.07	245.71	0.00	0.00
165.00		264.46	398.34	0.00	0.00
167.00	(18) appurtenances	3730.88	2804.11	0.00	440.47
169.00		102.06	127.49	0.00	0.00

## Total Applied Force Summary

**Structure:** CT13071-A-SB      **Code:** EIA/TIA-222-F      6/21/2016  
**Site Name:** Woodbridge      **Exposure:** C  
**Height:** 169.00 (ft)      **Gh:** 1.69  
**Base Elev:** 0.000 (ft)      **Struct Class:** II

Page: 22



<b>Totals:</b>	<u>26,839.29</u>	<u>51,709.69</u>	<u>1,130.67</u>	<u>440.47</u>
----------------	------------------	------------------	-----------------	---------------

## Resulting Forces and Deflections

**Structure:** CT13071-A-SB  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)


**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 23



**Load Case:** 73.61 mph Wind with 0.5" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 27

Elev (ft)	Lateral FX (-) (kips)	Axial FY (-) (kips)	Lateral FZ (kips)	Moment MX (ft-kips)	Torsion MY (ft-kips)	Moment MZ (ft-kips)	Deflect X (in)	Deflect Z (in)	Deflect Resultant (in)	Rotation Sway (deg)	Rotation Twist (deg)
0.00	-26.910	-51.673	0.000	-0.016	-1.117	-3350.934	0.000	0.000	0.000	0.000	0.000
5.00	-26.647	-49.823	0.000	-0.016	-1.117	-3216.386	-0.082	0.000	0.082	-0.154	0.000
10.00	-26.383	-48.000	0.000	-0.016	-1.117	-3083.153	-0.327	0.000	0.327	-0.309	0.000
15.00	-26.117	-46.205	0.000	-0.016	-1.117	-2951.241	-0.736	0.000	0.736	-0.467	0.000
20.00	-25.849	-44.438	0.000	-0.017	-1.117	-2820.660	-1.310	0.000	1.310	-0.627	0.000
25.00	-25.580	-42.698	0.000	-0.017	-1.118	-2691.417	-2.053	0.000	2.053	-0.788	0.000
30.00	-25.309	-40.986	0.000	-0.018	-1.118	-2563.520	-2.965	0.000	2.965	-0.951	0.000
35.00	-25.030	-39.302	0.000	-0.019	-1.118	-2436.978	-4.050	0.000	4.050	-1.116	0.000
40.00	-24.690	-37.677	0.000	-0.018	-1.118	-2311.828	-5.307	0.000	5.307	-1.282	-0.001
40.75	-24.684	-37.405	0.000	-0.020	-1.118	-2293.311	-5.511	0.000	5.511	-1.308	-0.001
45.00	-24.374	-35.212	0.000	-0.020	-1.118	-2188.404	-6.740	0.000	6.740	-1.451	-0.001
47.00	-24.247	-34.176	0.000	-0.021	-1.119	-2139.658	-7.363	0.000	7.363	-1.520	-0.001
50.00	-24.078	-33.283	0.000	-0.022	-1.119	-2066.919	-8.351	0.000	8.351	-1.622	-0.001
55.00	-23.753	-31.840	0.000	-0.024	-1.119	-1946.531	-10.151	0.000	10.151	-1.811	-0.001
60.00	-23.417	-30.422	0.000	-0.025	-1.120	-1827.769	-12.148	0.000	12.148	-1.999	-0.001
65.00	-23.072	-29.030	0.000	-0.027	-1.120	-1710.686	-14.344	0.000	14.344	-2.189	-0.001
70.00	-22.718	-27.664	0.000	-0.029	-1.121	-1595.328	-16.737	0.001	16.737	-2.378	-0.001
75.00	-22.357	-26.324	0.000	-0.031	-1.121	-1481.739	-19.329	0.001	19.329	-2.567	-0.001
80.00	-21.988	-25.011	0.000	-0.033	-1.122	-1369.957	-22.117	0.001	22.117	-2.755	-0.001
85.00	-21.608	-23.729	0.001	-0.035	-1.122	-1260.017	-25.102	0.001	25.102	-2.941	-0.002
89.25	-21.260	-22.680	0.001	-0.036	-1.123	-1168.186	-27.791	0.001	27.791	-3.099	-0.002
90.00	-21.196	-22.409	0.001	-0.037	-1.123	-1152.241	-28.280	0.001	28.280	-3.128	-0.002
91.25	-21.089	-21.959	0.001	-0.038	-1.123	-1125.746	-29.105	0.001	29.105	-3.175	-0.002
94.25	-20.792	-20.929	0.001	-0.038	-1.123	-1062.479	-31.126	0.002	31.126	-3.257	-0.002
95.00	-20.750	-20.761	0.001	-0.040	-1.124	-1046.885	-31.639	0.002	31.639	-3.278	-0.002
99.25	-20.368	-19.964	0.001	-0.040	-1.125	-958.698	-34.623	0.002	34.623	-3.424	-0.002
100.00	-20.329	-19.795	0.001	-0.041	-1.125	-943.422	-35.163	0.002	35.163	-3.450	-0.002
105.00	-19.884	-18.872	0.001	-0.042	-1.126	-841.777	-38.863	0.002	38.863	-3.615	-0.003
107.25	-19.694	-18.452	0.001	-0.043	-1.127	-797.038	-40.584	0.003	40.584	-3.688	-0.003
110.00	-19.487	-17.923	0.001	-0.046	-1.127	-742.880	-42.732	0.003	42.732	-3.774	-0.003
115.00	-19.117	-17.000	0.001	-0.050	-1.128	-645.450	-46.805	0.004	46.805	-4.000	-0.003
120.00	-18.742	-16.101	0.001	-0.055	-1.129	-549.867	-51.108	0.004	51.108	-4.213	-0.004
125.00	-18.348	-15.243	0.001	-0.058	-1.130	-456.158	-55.624	0.005	55.624	-4.408	-0.004
127.00	-15.017	-12.478	0.001	0.028	0.000	-419.462	-57.485	0.006	57.485	-4.483	-0.004
130.00	-14.792	-11.978	0.001	0.025	0.000	-374.413	-60.334	0.006	60.334	-4.588	-0.004
135.00	-14.399	-11.184	0.001	0.020	0.000	-300.456	-65.222	0.007	65.222	-4.746	-0.004
139.00	-14.080	-10.572	0.001	0.016	0.000	-242.863	-69.244	0.007	69.244	-4.858	-0.004
140.00	-14.001	-10.352	0.001	0.016	0.000	-228.783	-70.263	0.007	70.263	-4.885	-0.004
142.75	-13.769	-9.774	0.001	0.013	0.000	-190.282	-73.094	0.008	73.094	-4.951	-0.004
145.00	-13.599	-9.475	0.001	0.011	0.000	-159.301	-75.437	0.008	75.437	-4.998	-0.004
148.00	-8.599	-6.344	0.001	0.008	0.000	-118.506	-78.597	0.009	78.597	-5.066	-0.004
150.00	-8.230	-5.684	0.001	0.007	0.000	-101.307	-80.726	0.009	80.726	-5.103	-0.004
155.00	-7.850	-5.141	0.001	0.004	0.000	-60.157	-86.106	0.009	86.106	-5.176	-0.004
157.00	-4.567	-3.174	0.000	0.003	0.000	-44.457	-88.276	0.010	88.276	-5.197	-0.004
160.00	-4.384	-2.942	0.000	0.002	0.000	-30.757	-91.546	0.010	91.546	-5.221	-0.004
165.00	-4.085	-2.569	0.000	0.001	0.000	-8.837	-97.020	0.011	97.020	-5.243	-0.004
167.00	-0.113	-0.118	0.000	0.000	0.000	-0.227	-99.215	0.011	99.215	-5.245	-0.004
169.00	-0.102	0.000	0.000	0.000	0.000	0.000	0.000	0.000	101.409	-5.245	-0.004

## Resulting Forces and Deflections

**Structure:** CT13071-A-SB

**Site Name:** Woodbridge

**Height:** 169.00 (ft)

**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F

**Exposure:** C

**Gh:** 1.69

**Struct Class:** II

6/21/2016

Page: 24



## Resulting Stresses

**Structure:** CT13071-A-SBA

**Code:** EIA/TIA-222-F

6/21/2016



**Site Name:** Woodbridge

**Exposure:** C

**Height:** 169.00 (ft)

**Gh:** 1.69

**Base Elev:** 0.000 (ft)


**Struct Class:** II

Page: 25

**Load Case:** 73.61 mph Wind with 0.5" Ice

**Iterations:** 27

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



### Applied Stresses

Elev (ft)	fa Axial (Y) (ksi)	fvx Shear (X) (ksi)	fvz Shear (Z) (ksi)	fvT Torsion (ksi)	fbx Bending (X) (ksi)	fbz Bending (Z) (ksi)	fb Combined (ksi)	Fb Allow Stress (ksi)	f/Fb Stress Ratio
0.00	0.67	0.70	0.00	0.01	0.00	37.75	38.43	52.0	0.739
5.00	0.66	0.71	0.00	0.01	0.00	37.57	38.25	52.0	0.736
10.00	0.64	0.71	0.00	0.01	0.00	37.37	38.04	52.0	0.732
15.00	0.63	0.72	0.00	0.01	0.00	37.15	37.80	52.0	0.727
20.00	0.62	0.73	0.00	0.01	0.00	36.90	37.54	52.0	0.722
25.00	0.61	0.73	0.00	0.01	0.00	36.61	37.24	52.0	0.716
30.00	0.59	0.74	0.00	0.01	0.00	36.30	36.91	52.0	0.710
35.00	0.58	0.75	0.00	0.01	0.00	35.94	36.55	52.0	0.703
40.00	0.57	0.75	0.00	0.01	0.00	35.55	36.14	52.0	0.695
40.75	0.57	0.75	0.00	0.01	0.00	35.49	36.08	52.0	0.694
45.00	0.54	0.76	0.00	0.01	0.00	35.11	35.68	52.0	0.686
47.00	0.61	0.87	0.00	0.01	0.00	39.30	39.94	52.0	0.768
50.00	0.60	0.88	0.00	0.01	0.00	38.95	39.58	52.0	0.761
55.00	0.59	0.88	0.00	0.01	0.00	38.32	38.94	52.0	0.749
60.00	0.57	0.89	0.00	0.01	0.00	37.62	38.23	52.0	0.735
65.00	0.56	0.90	0.00	0.01	0.00	36.85	37.45	52.0	0.720
70.00	0.55	0.90	0.00	0.01	0.00	36.01	36.59	52.0	0.704
75.00	0.53	0.91	0.00	0.01	0.00	35.08	35.65	52.0	0.686
80.00	0.52	0.92	0.00	0.01	0.00	34.06	34.62	52.0	0.666
85.00	0.50	0.93	0.00	0.01	0.00	32.94	33.49	52.0	0.644
89.25	0.49	0.93	0.00	0.02	0.00	31.90	32.44	52.0	0.624
90.00	0.49	0.93	0.00	0.02	0.00	31.72	32.25	52.0	0.620
91.25	0.48	0.93	0.00	0.02	0.00	31.39	23.74	52.0	0.457
94.25	0.69	1.38	0.00	0.02	0.00	23.27	23.27	52.0	0.448
95.00	0.69	1.38	0.00	0.02	0.00	30.33	30.33	51.2	0.592
99.25	0.67	1.39	0.00	0.02	0.00	28.84	28.84	51.7	0.557
100.00	0.67	1.39	0.00	0.02	0.00	28.57	28.57	51.8	0.551
105.00	0.66	1.40	0.00	0.03	0.00	26.67	26.67	52.0	0.513
107.25	0.65	1.40	0.00	0.03	0.00	25.78	26.43	52.0	0.509
110.00	0.64	1.41	0.00	0.03	0.00	36.75	37.47	52.0	0.721
115.00	0.63	1.42	0.00	0.03	0.00	33.83	34.55	52.0	0.665
120.00	0.61	1.43	0.00	0.03	0.00	30.59	31.30	52.0	0.602
125.00	0.60	1.45	0.00	0.03	0.00	26.98	27.70	52.0	0.533
127.00	0.49	1.20	0.00	0.00	0.00	25.45	26.02	52.0	0.501
130.00	0.48	1.21	0.00	0.00	0.00	23.60	24.17	52.0	0.465
135.00	0.47	1.21	0.00	0.00	0.00	20.22	20.79	52.0	0.400
139.00	0.45	1.22	0.00	0.00	0.00	17.25	17.83	52.0	0.343
140.00	0.45	1.22	0.00	0.00	0.00	16.47	17.05	52.0	0.328
142.75	0.57	1.60	0.00	0.00	0.00	18.37	19.14	52.0	0.368
145.00	0.56	1.61	0.00	0.00	0.00	15.87	16.66	51.2	0.325
148.00	0.38	1.04	0.00	0.00	0.00	12.32	12.83	51.7	0.248
150.00	0.35	1.01	0.00	0.00	0.00	10.84	11.32	52.0	0.218
155.00	0.32	1.00	0.00	0.00	0.00	6.93	7.46	52.0	0.143
157.00	0.20	0.59	0.00	0.00	0.00	5.28	5.58	52.0	0.107
160.00	0.19	0.58	0.00	0.00	0.00	3.83	4.14	52.0	0.080
165.00	0.18	0.56	0.00	0.00	0.00	1.19	1.68	52.0	0.032
167.00	0.01	0.02	0.00	0.00	0.00	0.03	0.05	52.0	0.001

## Resulting Stresses

**Structure:** CT13071-A-SBA

**Code:** EIA/TIA-222-F

6/21/2016

**Site Name:** Woodbridge

**Exposure:** C

**Height:** 169.00 (ft)

**Gh:** 1.69

**Base Elev:** 0.000 (ft)

**Struct Class:** II

Page: 26



169.00	0.00	0.01	0.00	0.00	0.00	0.00	0.03	52.0	0.000
--------	------	------	------	------	------	------	------	------	-------

## Wind Loading - Shaft

**Structure:** CT13071-A-SBA  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)


**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 27



**Load Case:** 50 mph Wind with 0" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 25

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		0.00	1.00	6.400	10.82	234.08	0.650	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		0.00	1.00	6.400	10.82	229.92	0.650	0.000	5.00	23.200	15.08	163.1	0.0	1305.1
10.00		0.00	1.00	6.400	10.82	225.75	0.650	0.000	5.00	22.783	14.81	160.2	0.0	1281.5
15.00		0.00	1.00	6.400	10.82	221.58	0.650	0.000	5.00	22.367	14.54	157.2	0.0	1257.8
20.00		0.00	1.00	6.400	10.82	217.41	0.650	0.000	5.00	21.950	14.27	154.3	0.0	1234.2
25.00		0.00	1.00	6.400	10.82	213.25	0.650	0.000	5.00	21.533	14.00	151.4	0.0	1210.6
30.00		0.00	1.00	6.400	10.82	209.08	0.650	0.000	5.00	21.116	13.73	148.5	0.0	1187.0
35.00		0.00	1.02	6.509	11.00	206.64	0.650	0.000	5.00	20.700	13.45	148.0	0.0	1163.3
40.00		0.00	1.06	6.762	11.43	206.34	0.650	0.000	5.00	20.283	13.18	150.7	0.0	1139.7
40.75	Bot - Section 2	0.00	1.06	6.798	11.49	206.24	0.650	0.000	0.75	3.006	1.95	22.4	0.0	168.9
45.00		0.00	1.09	6.993	11.82	205.48	0.650	0.000	4.25	17.125	11.13	131.6	0.0	1773.0
47.00	Top - Section 1	0.00	1.11	7.080	11.97	205.01	0.650	0.000	2.00	7.955	5.17	61.9	0.0	823.4
50.00		0.00	1.13	7.207	12.18	207.49	0.650	0.000	3.00	11.807	7.67	93.5	0.0	569.3
55.00		0.00	1.16	7.406	12.52	205.86	0.650	0.000	5.00	19.345	12.57	157.4	0.0	932.6
60.00		0.00	1.19	7.592	12.83	203.89	0.650	0.000	5.00	18.928	12.30	157.9	0.0	912.3
65.00		0.00	1.21	7.768	13.13	201.65	0.650	0.000	5.00	18.512	12.03	158.0	0.0	892.1
70.00		0.00	1.24	7.934	13.41	199.15	0.650	0.000	5.00	18.095	11.76	157.7	0.0	871.8
75.00		0.00	1.26	8.092	13.68	196.44	0.650	0.000	5.00	17.678	11.49	157.1	0.0	851.6
80.00		0.00	1.29	8.242	13.93	193.53	0.650	0.000	5.00	17.262	11.22	156.3	0.0	831.3
85.00		0.00	1.31	8.387	14.17	190.44	0.650	0.000	5.00	16.845	10.95	155.2	0.0	811.1
89.25	Bot - Section 3	0.00	1.33	8.504	14.37	187.69	0.650	0.000	4.25	13.990	9.09	130.7	0.0	673.5
90.00		0.00	1.33	8.525	14.41	187.19	0.650	0.000	0.75	2.469	1.60	23.1	0.0	196.8
91.25	RB1	0.00	1.34	8.558	14.46	186.36	0.650	0.000	1.25	4.094	2.66	38.5	0.0	326.3
94.25	Top - Section 2	0.00	1.35	8.638	14.60	184.32	0.650	0.000	3.00	9.719	6.32	92.2	0.0	774.6
95.00		0.00	1.35	8.657	14.63	186.22	0.650	0.000	0.75	2.406	1.56	22.9	0.0	77.5
99.25	RT1 RB2	0.00	1.37	8.766	14.81	183.24	0.650	0.000	4.25	13.459	8.75	129.6	0.0	433.2
100.00		0.00	1.37	8.785	14.85	182.71	0.650	0.000	0.75	2.344	1.52	22.6	0.0	75.4
105.00		0.00	1.39	8.908	15.06	179.07	0.650	0.000	5.00	15.386	10.00	150.6	0.0	495.1
107.25	RT2	0.00	1.40	8.963	15.15	177.39	0.650	0.000	2.25	6.788	4.41	66.8	0.0	218.4
110.00		0.00	1.41	9.028	15.26	175.31	0.650	0.000	2.75	8.182	5.32	81.1	0.0	263.2
115.00		0.00	1.43	9.143	15.45	171.45	0.650	0.000	5.00	14.553	9.46	146.2	0.0	468.1
120.00		0.00	1.45	9.255	15.64	167.48	0.650	0.000	5.00	14.136	9.19	143.7	0.0	454.6
125.00		0.00	1.46	9.363	15.82	163.42	0.650	0.000	5.00	13.719	8.92	141.1	0.0	441.1
127.00	Appurtenance(s)	0.00	1.47	9.406	15.90	161.77	0.650	0.000	2.00	5.371	3.49	55.5	0.0	172.7
130.00		0.00	1.48	9.469	16.00	159.27	0.650	0.000	3.00	7.932	5.16	82.5	0.0	255.0
135.00		0.00	1.50	9.572	16.18	155.04	0.650	0.000	5.00	12.886	8.38	135.5	0.0	414.1
139.00	Bot - Section 4	0.00	1.51	9.652	16.31	151.59	0.650	0.000	4.00	10.009	6.51	106.1	0.0	321.6
140.00		0.00	1.51	9.672	16.35	150.72	0.650	0.000	1.00	2.492	1.62	26.5	0.0	139.2
142.75	Top - Section 3	0.00	1.52	9.726	16.44	148.32	0.650	0.000	2.75	6.766	4.40	72.3	0.0	378.0
145.00		0.00	1.53	9.769	16.51	148.26	0.650	0.000	2.25	5.442	3.54	58.4	0.0	131.4
148.00	Appurtenance(s)	0.00	1.54	9.826	16.61	145.60	0.650	0.000	3.00	7.125	4.63	76.9	0.0	172.0
150.00	Appurtenance(s)	0.00	1.54	9.864	16.67	143.81	0.650	0.000	2.00	4.667	3.03	50.6	0.0	112.6
155.00		0.00	1.56	9.957	16.83	139.28	0.650	0.000	5.00	11.375	7.39	124.4	0.0	274.5
157.00	Appurtenance(s)	0.00	1.56	9.994	16.89	137.46	0.650	0.000	2.00	4.433	2.88	48.7	0.0	107.0
160.00		0.00	1.57	10.048	16.98	134.70	0.650	0.000	3.00	6.525	4.24	72.0	0.0	157.4
165.00		0.00	1.58	10.136	17.13	130.05	0.650	0.000	5.00	10.542	6.85	117.4	0.0	254.3
167.00	Appurtenance(s)	0.00	1.59	10.171	17.19	128.17	0.650	0.000	2.00	4.100	2.67	45.8	0.0	98.9
169.00		0.00	1.59	10.206	17.25	126.28	0.650	0.000	2.00	4.033	2.62	45.2	0.0	97.3

## Wind Loading - Shaft

**Structure:** CT13071-A-SBA

**Site Name:** Woodbridge

**Height:** 169.00 (ft)

**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F

**Exposure:** C

**Gh:** 1.69

**Struct Class:** II

6/21/2016

Page: 28



**Totals:** 169.00

4,949.1

27,200.5



## Discrete Appurtenance Forces

**Structure:** CT13071-A-SB  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)


**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 29



**Load Case:** 50 mph Wind with 0" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 25

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa Factor	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	167.00	LNx-6515DS	3	10.171	17.190	0.84	28.75	150.90	0.000	0.000	494.26	0.00	0.00
2	167.00	Ericsson S11B12	3	10.171	17.190	0.50	4.96	153.00	0.000	0.000	85.35	0.00	0.00
3	167.00	Ericsson KRY 112 144/1	3	10.171	17.190	0.50	0.61	33.00	0.000	0.000	10.57	0.00	0.00
4	167.00	AIR B4A B2P	3	10.171	17.190	0.86	16.98	271.20	0.000	0.000	291.82	0.00	0.00
5	167.00	AIR B2A B4P	3	10.171	17.190	0.86	16.98	274.50	0.000	0.000	291.82	0.00	0.00
6	167.00	T-Arms/Commscope	3	10.180	17.204	0.75	15.19	1020.00	0.000	0.500	261.29	0.00	130.65
7	157.00	DB846H80E-SX	2	9.994	16.889	1.10	11.02	32.00	0.000	0.000	186.15	0.00	0.00
8	157.00	ALU RRH2X60-AWS RRH	3	9.994	16.889	0.50	5.94	180.00	0.000	0.000	100.32	0.00	0.00
9	157.00	BXA-70063/6CF	1	9.994	16.889	0.70	5.41	17.00	0.000	0.000	91.39	0.00	0.00
10	157.00	DB846F65ZAXY	4	9.994	16.889	0.93	26.23	84.00	0.000	0.000	442.93	0.00	0.00
11	157.00	RFS DB T1-6Z-8AB-OZ	1	9.994	16.889	0.67	2.51	19.00	0.000	0.000	42.32	0.00	0.00
12	157.00	GPS	1	9.994	16.889	1.00	1.00	10.00	0.000	0.000	16.89	0.00	0.00
13	157.00	HBX-6517DS-VTM	6	9.994	16.889	0.75	23.85	112.20	0.000	0.000	402.80	0.00	0.00
14	157.00	SLCP 2x6014F	2	9.994	16.889	0.89	12.83	40.00	0.000	0.000	216.75	0.00	0.00
15	157.00	T-Arms	3	9.994	16.889	0.75	18.00	1050.00	0.000	0.000	304.00	0.00	0.00
16	150.00	Collar Mount	1	9.864	16.670	1.00	3.00	100.00	0.000	0.000	50.01	0.00	0.00
17	148.00	T-Arms	3	9.826	16.607	0.75	18.00	1050.00	0.000	0.000	298.92	0.00	0.00
18	148.00	Raycap	2	9.826	16.607	0.67	1.97	65.60	0.000	0.000	32.71	0.00	0.00
19	148.00	Ericsson RRUS 32-RRU	3	9.826	16.607	0.50	2.90	231.00	0.000	0.000	48.08	0.00	0.00
20	148.00	CCI HPA-65R-BUU-H6	1	9.826	16.607	0.85	8.81	51.00	0.000	0.000	146.24	0.00	0.00
21	148.00	CCI HPA-65R-BUU-H8	2	9.826	16.607	0.79	21.01	136.00	0.000	0.000	348.97	0.00	0.00
22	148.00	Cci OPA-65R-LCUU-H6	1	9.826	16.607	0.79	8.18	73.00	0.000	0.000	135.91	0.00	0.00
23	148.00	Cci OPA-65R-LCUU-H8	2	9.826	16.607	0.79	20.51	176.00	0.000	0.000	340.57	0.00	0.00
24	148.00	Ericsson RRUS 12-B2-RRU	3	9.826	16.607	0.50	5.50	174.00	0.000	0.000	91.42	0.00	0.00
25	148.00	Powerwave LGP21401 TMA	6	9.826	16.607	0.50	3.87	84.60	0.000	0.000	64.27	0.00	0.00
26	148.00	Ericsson RRUS A2 Module	3	9.826	16.607	0.50	2.79	63.60	0.000	0.000	46.33	0.00	0.00
27	148.00	Ericsson RRUS-11-RRU	3	9.826	16.607	0.60	5.29	150.00	0.000	0.000	87.88	0.00	0.00
28	148.00	Powerwave 1001940-Bias Ts	3	9.826	16.607	0.50	0.12	6.00	0.000	0.000	1.99	0.00	0.00
29	148.00	Powerwave 7770	3	9.826	16.607	0.73	12.88	105.00	0.000	0.000	213.85	0.00	0.00
30	148.00	Powerwave LGP13519	6	9.826	16.607	0.50	1.02	31.80	0.000	0.000	16.94	0.00	0.00
31	127.00	VHLP800-11	1	9.406	15.896	1.00	8.43	48.00	1.455	0.000	134.00	194.98	0.00
32	127.00	VHLP2-11	3	9.406	15.896	0.90	12.64	81.00	1.455	0.000	200.86	292.26	0.00
33	127.00	Sector Frames	3	9.406	15.896	0.75	33.75	1500.00	0.000	0.000	536.50	0.00	0.00
34	127.00	LLPX310R	3	9.406	15.896	0.69	10.00	85.80	0.000	0.000	158.93	0.00	0.00
35	127.00	2.5GHz RRH BTS	3	9.406	15.896	0.73	3.99	99.00	0.000	0.000	63.36	0.00	0.00
<b>Totals:</b>								<b>7,758.20</b>			<b>6,256.41</b>		

## Total Applied Force Summary

**Structure:** CT13071-A-SB  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II


6/21/2016

Page: 30



**Load Case:** 50 mph Wind with 0" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 25

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		173.92	1562.16	0.00	0.00
10.00		170.99	1538.53	0.00	0.00
15.00		168.06	1514.90	0.00	0.00
20.00		165.13	1491.27	0.00	0.00
25.00		162.20	1467.64	0.00	0.00
30.00		159.27	1444.01	0.00	0.00
35.00		158.99	1420.38	0.00	0.00
40.00		162.08	1396.76	0.00	0.00
40.75		24.17	207.48	0.00	0.00
45.00		141.60	1991.49	0.00	0.00
47.00		66.66	926.20	0.00	0.00
50.00		100.78	723.50	0.00	0.00
55.00		169.89	1189.63	0.00	0.00
60.00		170.69	1169.38	0.00	0.00
65.00		171.09	1149.13	0.00	0.00
70.00		171.11	1128.88	0.00	0.00
75.00		170.82	1108.62	0.00	0.00
80.00		170.22	1088.37	0.00	0.00
85.00		169.36	1068.12	0.00	0.00
89.25		142.91	891.97	0.00	0.00
90.00		27.12	235.37	0.00	0.00
91.25		45.18	390.60	0.00	0.00
94.25		108.43	928.84	0.00	0.00
95.00		26.94	116.02	0.00	0.00
99.25		152.90	651.70	0.00	0.00
100.00		26.74	113.99	0.00	0.00
105.00		178.42	752.19	0.00	0.00
107.25		79.44	334.08	0.00	0.00
110.00		94.71	404.61	0.00	0.00
115.00		161.61	725.19	0.00	0.00
120.00		159.35	711.68	0.00	0.00
125.00		156.94	698.18	0.00	0.00
127.00	(13) appurtenances	1155.51	2089.29	487.24	0.00
130.00		92.10	397.37	0.00	0.00
135.00		151.66	651.48	0.00	0.00
139.00		119.17	511.46	0.00	0.00
140.00		29.74	186.68	0.00	0.00
142.75		81.33	508.51	0.00	0.00
145.00		65.83	238.20	0.00	0.00
148.00	(41) appurtenances	1960.96	2712.01	0.00	0.00
150.00	(1) appurtenances	107.25	278.94	0.00	0.00
155.00		141.25	440.27	0.00	0.00
157.00	(23) appurtenances	1858.98	1717.47	0.00	0.00
160.00		72.02	197.02	0.00	0.00
165.00		117.38	320.27	0.00	0.00
167.00	(18) appurtenances	1480.92	2027.87	0.00	130.65
169.00		45.22	97.25	0.00	0.00

## Total Applied Force Summary

**Structure:** CT13071-A-SB      **Code:** EIA/TIA-222-F      6/21/2016  
**Site Name:** Woodbridge      **Exposure:** C  
**Height:** 169.00 (ft)      **Gh:** 1.69  
**Base Elev:** 0.000 (ft)      **Struct Class:** II

Page: 31



<b>Totals:</b>	<b>11,687.06</b>	<b>42,914.98</b>	<b>487.24</b>	<b>130.65</b>
----------------	------------------	------------------	---------------	---------------

## Resulting Forces and Deflections

**Structure:** CT13071-A-SB  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)


**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 32



**Load Case:** 50 mph Wind with 0" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 25

Elev (ft)	Lateral FX (-) (kips)	Axial FY (-) (kips)	Lateral FZ (kips)	Moment MX (ft-kips)	Torsion MY (ft-kips)	Moment MZ (ft-kips)	Deflect X (in)	Deflect Z (in)	Deflect Resultant (in)	Rotation Sway (deg)	Rotation Twist (deg)
0.00	-11.712	-42.908	0.000	-0.002	-0.486	-1451.743	0.000	0.000	0.000	0.000	0.000
5.00	-11.585	-41.332	0.000	-0.002	-0.486	-1393.186	-0.036	0.000	0.036	-0.067	0.000
10.00	-11.459	-39.781	0.000	-0.002	-0.486	-1335.261	-0.142	0.000	0.142	-0.134	0.000
15.00	-11.332	-38.253	0.000	-0.002	-0.486	-1277.969	-0.319	0.000	0.319	-0.202	0.000
20.00	-11.205	-36.749	0.000	-0.002	-0.486	-1221.310	-0.568	0.000	0.568	-0.271	0.000
25.00	-11.078	-35.268	0.000	-0.003	-0.486	-1165.285	-0.889	0.000	0.889	-0.341	0.000
30.00	-10.951	-33.812	0.000	-0.003	-0.486	-1109.895	-1.284	0.000	1.284	-0.412	0.000
35.00	-10.822	-32.379	0.000	-0.003	-0.486	-1055.138	-1.754	0.000	1.754	-0.483	0.000
40.00	-10.669	-30.976	0.000	-0.003	-0.486	-1001.030	-2.298	0.000	2.298	-0.555	0.000
40.75	-10.663	-30.762	0.000	-0.003	-0.486	-993.028	-2.387	0.000	2.387	-0.566	0.000
45.00	-10.524	-28.764	0.000	-0.003	-0.486	-947.711	-2.919	0.000	2.919	-0.628	0.000
47.00	-10.465	-27.832	0.000	-0.003	-0.486	-926.664	-3.189	0.000	3.189	-0.658	0.000
50.00	-10.385	-27.098	0.000	-0.003	-0.486	-895.270	-3.617	0.000	3.617	-0.703	0.000
55.00	-10.237	-25.896	0.000	-0.004	-0.486	-843.345	-4.396	0.000	4.396	-0.784	0.000
60.00	-10.085	-24.715	0.000	-0.004	-0.486	-792.161	-5.261	0.000	5.261	-0.866	0.000
65.00	-9.929	-23.554	0.000	-0.004	-0.486	-741.739	-6.212	0.000	6.212	-0.948	0.000
70.00	-9.771	-22.415	0.000	-0.005	-0.486	-692.094	-7.249	0.000	7.249	-1.030	-0.001
75.00	-9.610	-21.296	0.000	-0.005	-0.486	-643.241	-8.372	0.000	8.372	-1.112	-0.001
80.00	-9.446	-20.198	0.000	-0.006	-0.487	-595.193	-9.581	0.000	9.581	-1.194	-0.001
85.00	-9.279	-19.121	0.000	-0.006	-0.487	-547.963	-10.874	0.000	10.874	-1.275	-0.001
89.25	-9.128	-18.226	0.000	-0.006	-0.487	-508.528	-12.041	0.000	12.041	-1.343	-0.001
90.00	-9.101	-17.989	0.000	-0.006	-0.487	-501.682	-12.253	0.000	12.253	-1.356	-0.001
91.25	-9.055	-17.595	0.000	-0.006	-0.487	-490.306	-12.610	0.000	12.610	-1.376	-0.001
94.25	-8.931	-16.666	0.000	-0.007	-0.487	-463.142	-13.487	0.000	13.487	-1.412	-0.001
95.00	-8.912	-16.545	0.000	-0.007	-0.487	-456.444	-13.709	0.000	13.709	-1.421	-0.001
99.25	-8.752	-15.892	0.000	-0.007	-0.487	-418.570	-15.004	0.000	15.004	-1.485	-0.001
100.00	-8.734	-15.772	0.000	-0.007	-0.487	-412.006	-15.238	0.000	15.238	-1.497	-0.001
105.00	-8.549	-15.017	0.000	-0.007	-0.487	-368.335	-16.844	0.000	16.844	-1.568	-0.001
107.25	-8.470	-14.680	0.000	-0.008	-0.487	-349.099	-17.591	0.000	17.591	-1.600	-0.001
110.00	-8.381	-14.268	0.000	-0.008	-0.487	-325.808	-18.524	0.001	18.524	-1.638	-0.001
115.00	-8.221	-13.534	0.000	-0.009	-0.487	-283.903	-20.294	0.001	20.294	-1.738	-0.001
120.00	-8.060	-12.815	0.000	-0.010	-0.487	-242.799	-22.165	0.001	22.165	-1.831	-0.002
125.00	-7.892	-12.114	0.000	-0.011	-0.487	-202.502	-24.130	0.001	24.130	-1.918	-0.002
127.00	-6.674	-10.061	0.000	0.006	0.000	-186.717	-24.940	0.001	24.940	-1.951	-0.002
130.00	-6.578	-9.660	0.000	0.005	0.000	-166.695	-26.182	0.001	26.182	-1.998	-0.002
135.00	-6.413	-9.008	0.000	0.004	0.000	-133.804	-28.312	0.001	28.312	-2.068	-0.002
139.00	-6.280	-8.497	0.000	0.003	0.000	-108.151	-30.067	0.001	30.067	-2.118	-0.002
140.00	-6.246	-8.310	0.000	0.003	0.000	-101.872	-30.512	0.001	30.512	-2.130	-0.002
142.75	-6.149	-7.802	0.000	0.003	0.000	-84.695	-31.748	0.001	31.748	-2.159	-0.002
145.00	-6.078	-7.564	0.000	0.002	0.000	-70.859	-32.771	0.001	32.771	-2.180	-0.002
148.00	-4.017	-4.927	0.000	0.002	0.000	-52.625	-34.151	0.002	34.151	-2.210	-0.002
150.00	-3.901	-4.651	0.000	0.001	0.000	-44.592	-35.080	0.002	35.080	-2.227	-0.002
155.00	-3.744	-4.215	0.000	0.001	0.000	-25.089	-37.431	0.002	37.431	-2.258	-0.002
157.00	-1.819	-2.572	0.000	0.001	0.000	-17.601	-38.379	0.002	38.379	-2.267	-0.002
160.00	-1.739	-2.378	0.000	0.000	0.000	-12.145	-39.806	0.002	39.806	-2.276	-0.002
165.00	-1.610	-2.063	0.000	0.000	0.000	-3.448	-42.195	0.002	42.195	-2.285	-0.002
167.00	-0.049	-0.095	0.000	0.000	0.000	-0.098	-43.152	0.002	43.152	-2.286	-0.002
169.00	-0.045	0.000	0.000	0.000	0.000	0.000	0.000	0.000	44.110	-2.286	-0.002

## Resulting Forces and Deflections

**Structure:** CT13071-A-SB

**Site Name:** Woodbridge

**Height:** 169.00 (ft)

**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F

**Exposure:** C

**Gh:** 1.69

**Struct Class:** II

6/21/2016

Page: 33



## Resulting Stresses

**Structure:** CT13071-A-SBA  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II


6/21/2016

Page: 34



**Load Case:** 50 mph Wind with 0" Ice

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations:** 25

### Applied Stresses

Elev (ft)	fa Axial (Y) (ksi)	fvx Shear (X) (ksi)	fvz Shear (Z) (ksi)	fvt Torsion (ksi)	fbx Bending (X) (ksi)	fbz Bending (Z) (ksi)	fb Combined (ksi)	Fb Allow Stress (ksi)	f/Fb Stress Ratio
0.00	0.55	0.30	0.00	0.00	0.00	16.35	16.92	52.0	0.325
5.00	0.54	0.31	0.00	0.00	0.00	16.27	16.83	52.0	0.324
10.00	0.53	0.31	0.00	0.00	0.00	16.19	16.73	52.0	0.322
15.00	0.52	0.31	0.00	0.00	0.00	16.09	16.62	52.0	0.320
20.00	0.51	0.31	0.00	0.00	0.00	15.98	16.50	52.0	0.317
25.00	0.50	0.32	0.00	0.00	0.00	15.85	16.36	52.0	0.315
30.00	0.49	0.32	0.00	0.00	0.00	15.72	16.21	52.0	0.312
35.00	0.48	0.32	0.00	0.00	0.00	15.56	16.05	52.0	0.309
40.00	0.47	0.32	0.00	0.00	0.00	15.39	15.87	52.0	0.305
40.75	0.47	0.33	0.00	0.00	0.00	15.37	15.84	52.0	0.305
45.00	0.44	0.33	0.00	0.00	0.00	15.21	15.66	52.0	0.301
47.00	0.50	0.38	0.00	0.00	0.00	17.02	17.53	52.0	0.337
50.00	0.49	0.38	0.00	0.00	0.00	16.87	17.37	52.0	0.334
55.00	0.48	0.38	0.00	0.00	0.00	16.60	17.09	52.0	0.329
60.00	0.47	0.38	0.00	0.01	0.00	16.30	16.78	52.0	0.323
65.00	0.45	0.39	0.00	0.01	0.00	15.98	16.45	52.0	0.316
70.00	0.44	0.39	0.00	0.01	0.00	15.62	16.08	52.0	0.309
75.00	0.43	0.39	0.00	0.01	0.00	15.23	15.68	52.0	0.302
80.00	0.42	0.39	0.00	0.01	0.00	14.80	15.23	52.0	0.293
85.00	0.41	0.40	0.00	0.01	0.00	14.33	14.75	52.0	0.284
89.25	0.40	0.40	0.00	0.01	0.00	13.89	14.30	52.0	0.275
90.00	0.39	0.40	0.00	0.01	0.00	13.81	14.22	52.0	0.274
91.25	0.39	0.40	0.00	0.01	0.00	13.67	10.34	52.0	0.199
94.25	0.55	0.59	0.00	0.01	0.00	10.14	10.14	52.0	0.195
95.00	0.55	0.59	0.00	0.01	0.00	13.22	13.22	51.2	0.258
99.25	0.54	0.60	0.00	0.01	0.00	12.59	12.59	51.7	0.243
100.00	0.53	0.60	0.00	0.01	0.00	12.48	12.48	51.8	0.241
105.00	0.52	0.60	0.00	0.01	0.00	11.67	11.67	52.0	0.225
107.25	0.52	0.60	0.00	0.01	0.00	11.29	11.81	52.0	0.227
110.00	0.51	0.61	0.00	0.01	0.00	16.12	16.66	52.0	0.321
115.00	0.50	0.61	0.00	0.01	0.00	14.88	15.42	52.0	0.297
120.00	0.49	0.62	0.00	0.01	0.00	13.51	14.04	52.0	0.270
125.00	0.47	0.62	0.00	0.01	0.00	11.98	12.50	52.0	0.241
127.00	0.40	0.53	0.00	0.00	0.00	11.33	11.76	52.0	0.226
130.00	0.39	0.54	0.00	0.00	0.00	10.51	10.94	52.0	0.210
135.00	0.38	0.54	0.00	0.00	0.00	9.00	9.43	52.0	0.181
139.00	0.36	0.54	0.00	0.00	0.00	7.68	8.10	52.0	0.156
140.00	0.36	0.54	0.00	0.00	0.00	7.34	7.75	52.0	0.149
142.75	0.45	0.72	0.00	0.00	0.00	8.18	8.72	52.0	0.168
145.00	0.44	0.72	0.00	0.00	0.00	7.06	7.61	51.2	0.148
148.00	0.30	0.49	0.00	0.00	0.00	5.47	5.83	51.7	0.113
150.00	0.28	0.48	0.00	0.00	0.00	4.77	5.12	52.0	0.099
155.00	0.27	0.48	0.00	0.00	0.00	2.89	3.26	52.0	0.063
157.00	0.16	0.23	0.00	0.00	0.00	2.09	2.29	52.0	0.044
160.00	0.16	0.23	0.00	0.00	0.00	1.51	1.71	52.0	0.033
165.00	0.14	0.22	0.00	0.00	0.00	0.46	0.72	52.0	0.014
167.00	0.01	0.01	0.00	0.00	0.00	0.01	0.02	52.0	0.000

## Resulting Stresses

**Structure:** CT13071-A-SBA

**Code:** EIA/TIA-222-F

6/21/2016

**Site Name:** Woodbridge

**Exposure:** C

**Height:** 169.00 (ft)

**Gh:** 1.69

**Base Elev:** 0.000 (ft)

**Struct Class:** II

Page: 35



169.00	0.00	0.01	0.00	0.00	0.00	0.00	0.01	52.0	0.000
--------	------	------	------	------	------	------	------	------	-------

## Final Analysis Summary

**Structure:** CT13071-A-SBA  
**Site Name:** Woodbridge  
**Height:** 169.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-F  
**Exposure:** C  
**Gh:** 1.69  
**Struct Class:** II

6/21/2016  
 Page: 36



### Reactions

Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)
85 mph Wind with 0" Ice	33.8	0.00	42.86	0.02	1.38	4188.59
73.61 mph Wind with 0.5" Ice	26.9	0.00	51.67	0.02	1.12	3350.93
50 mph Wind with 0" Ice	11.7	0.00	42.91	0.00	0.49	1451.74

### Max Stresses

Load Case	fa Axial (Y) (ksi)	fvx Shear (X) (ksi)	fvz Shear (Z) (ksi)	fvT Torsion (ksi)	fbx Bending (X) (ksi)	fbz Bending (Z) (ksi)	Combined Stress (ksi)	Allowable Stress (ksi)	Elev (ft)	Stress Ratio
85 mph Wind with 0" Ice	0.48	1.09	0.00	0.01	0.00	49.06	49.58	52.0	47.00	0.954
73.61 mph Wind with 0.5" Ice	0.61	0.87	0.00	0.01	0.00	39.30	39.94	52.0	47.00	0.768
50 mph Wind with 0" Ice	0.50	0.38	0.00	0.00	0.00	17.02	17.53	52.0	47.00	0.337

### Additional Steel Summary

Intermediate Connectors  
  Upper Termination  
  Lower Termination  
  Max Member

Elev From (ft)	Elev To (ft)	Member	VQ/I (lb/in)	V (kips)	Shear Allow (kips)	MQ/I (kips)	Num Reqd	Num Actual	MQ/I (kips)	Num Reqd	Num Actual	MQ/I (kips)	Ta (kips)	Pa (kips)	Ratio
91.3	99.3	(3) LNP-LP6X100-G-10TT	-349.9	-8.05	22.5	200.4	0	10	172.1	0	9	210.7	260.0	260.4	0.809
99.3	107.3	(3) LNP-LP6X100-G-10TT	-363.4	-8.36	22.5	179.5	8	9	200.5	0	9	200.5	260.0	260.4	0.770





# Monopole Mat Foundation Design

Date  
6/20/2016

Customer Name:	AT&T	EIA/TIA Standard:	EIA-222-F
Site Name:		Structure Height (Ft.):	169
Site Number:	CT13071-A-SBA	Engineer Name:	U. Atluri
Engr. Number:	22848	Engineer Login ID:	

**Foundation Info Obtained from:**

Drawings/Calculations

**Structure Type:**

Monopole

**Analysis or Design?**

Analysis

**Base Reactions (Unfactored)**

Axial Load (Kips):	42.9	Shear Force (Kips):	33.8
Uplift Force (Kips):	0.0	Moment (Kips-ft):	4188.6

Allowable overstress %: 5.0%

**Foundation Geometries:**

Diameter of Pier (ft.):	7.0	Depth of Base BG (ft.):	6.0
Pier Height A. G. (ft.):	0.50	Thickness of Pad (ft.):	2.00
Length of Pad (ft.):	24.5	Width of Pad (ft.):	24.5

Final Length of pad (ft)	24.5	Final width of pad (ft):	24.5
Control Value for Cell D18:	0	Control Value for Cell F18:	0

**Material Properties and Rebar Info:**


Concrete Strength (psi):	4000	Steel Elastic Modulus:	29000	ksi
Vertical bar yield (ksi)	60	Tie steel yield (ksi):	60	
Vertical Rebar Size #:	9	Tie / Stirrup Size #:	4	
Qty. of Vertical Rebars:	36	Tie Spacing (in):	6.0	
Pad Rebar Yield (Ksi):	60	Pad Steel Rebar Size (#):	8	
Concrete Cover (in.):	3	Unit Weight of Concrete:	150.0	pcf

Rebar at the bottom of the concrete pad:			
Qty. of Rebar in Pad (L):	46	Qty. of Rebar in Pad (W):	46
Rebar at the top of the concrete pad:			
Qty. of Rebar in Pad (L):	46	Qty. of Rebar in Pad (W):	46

Apply 1.35 factor for e/w Per G: 1.35

**Soil Design Parameters:**

Soil Unit Weight (pcf):	120.0	Soil Buoyant Weight:	50.0	Pcf
Water Table B.G.S. (ft):	99.0	Unit Weight of Water:	62.4	pcf
Allowable Net Soil Bearing (psf):	6666	Allowable Skin Friction:	200	Psf
Consider Friction for O.T.M. (Y/N):	Yes	Consider Friction for bearing (Y/N):	No	
Consider soil hori. force for O.T.M.:	Yes	Reduction factor on the maximum soil bearing pressure:	1.00	



**Foundation Analysis and Design:**

Total Dry Soil Volume (cu. Ft.):	2247.06	Total Dry Soil Weight (Kips):	269.65
Total Buoyant Soil Volume (cu. Ft.):	0.00	Total Buoyant Soil Weight (Kips):	0.00
Total Effective Soil Weight (Kips):	269.65	Weight from the Concrete Block at Top (K):	0.00
Total Dry Concrete Volume (cu. Ft.):	1373.68	Total Dry Concrete Weight (Kips):	206.05
Total Buoyant Concrete Volume (cu. Ft.):	0.00	Total Buoyant Concrete Weight (Kips):	0.00
Total Effective Concrete Weight (Kips):	206.05	Total Vertical Load on Base (Kips):	518.60

**Check Soil Capacities:**

Calculated Maxium Net Soil Pressure under the base (psf):	4066	<	Allowable Soil Bearing (psf):	6666	0.61	OK!
Allowable Foundation Overturning Resistance (SF=1.5, kips-ft.):	4355.3	<	Applied Momont (kips-ft):	4375	1.00	OK!
Factor of Safety Against Overturning (O. R. Moment/Design Moment):	1.49					OK!

Load/  
Capacity  
Ratio

**Check the capacities of Reinforcing Concrete:**

Strength reduction factor (Flexure and axial tension):	0.90	Strength reduction factor (Shear):	0.75	
Strength reduction factor (Axial compression):	0.65	Wind Load Factor on Concrete Design:	1.30	

Load/  
Capacity  
Ratio

(1) Concrete Pier:

Vertical Steel Rebar Area (sq. in./each):	1.00	Tie / Stirrup Area (sq. in./each):	0.20		
Calculated Moment Capacity (Mn,Kips-Ft):	6090.2	> Design Factored Moment (Mu, Kips-Ft):	5642.9	0.93	OK!
Calculated Shear Capacity (Kips):	794.5	> Design Factored Shear (Kips):	43.9	0.06	OK!
Calculated Tension Capacity (Tn, Kips):	1944.0	> Design Factored Tension (Tu Kips):	0.0	0.00	OK!
Calculated Compression Capacity (Pn, Kips):	9734.2	> Design Factored Axial Load (Pu Kips):	55.8	0.01	OK!
Moment & Axial Strength Combination(Pu/Pn+Mu/Mn):	0.93	OK! Check Tie Spacing (Design/Required):		0.5	OK!
Pier Reinforcement Ratio:	0.006	Reinforcement Ratio is satisfied per ACI			

(2).Concrete Pad:

One-Way Design Shear Capacity (L-Direction, Kips):	571.8	> One-Way Factored Shear (L-D. Kips):	405.4	0.71	OK!
One-Way Design Shear Capacity (W-Direction, Kips):	571.8	> One-Way Factored Shear (W-D., Kips)	405.4	0.71	OK!
One-Way Design Shear Capacity (Corner-Corner. Kips):	645.2	> One-Way Factored Shear (C-C, Kips):	572.9	0.89	OK!
Lower Steel Pad Reinforcement Ratio (L-Direct. ):	0.0060	OK! Lower Steel Pad Reinf. Ratio (W-Direc	0.0060		
Lower Steel Pad Moment Capacity (L-Direction. Kips-ft):	3174.0	> Moment at Bottom ( L-Direct. K-Ft):	1098.0	0.35	OK!
Lower Steel Pad Moment Capacity (W-Direction. Kips-ft):	3174.0	> Moment at Bottom ( W-Direct. K-Ft):	1098.0	0.35	OK!
Lower Steel Pad Moment Capacity (Corner-Corner,K-ft):	4424.9	> Moment at Bottom ( C-C Dir. K-Ft):	1552.8	0.35	OK!
Upper Steel Pad Reinforcement Ratio (L-Direct. ):	0.0060	OK! Upper Steel Reinf. Ratio (W-Direct. ):	0.0060		
Upper Steel Pad Moment Capacity (L-Direction. Kips-ft):	3174.0	> Moment at the top (L-Dir Kips-Ft):	580.1	0.18	OK!
Upper Steel Pad Moment Capacity (W-Direction. Kips-ft):	3174.0	> Moment at the top (W-Dir Kips-Ft):	580.1	0.18	OK!
Upper Steel Pad Moment Capacity (Corner-Corner. K-ft):	4424.9	> Moment at the top (C-C Direc. K-Ft):	893.0	0.20	OK!

**PROJECT INFORMATION**

- SCOPE OF WORK:
- REMOVE (1) EXISTING GSM ANTENNA PER SECTOR WITH (3) SECTORS, FOR A TOTAL OF (3) EXISTING ANTENNAS TO BE REMOVED. REMOVE DIPLEXERS AT ANTENNA LOCATION (TYP 3 SECTORS)
  - NEW AT&T ANTENNAS: (1) NEW ANTENNA PER SECTOR WITH (3) SECTORS, FOR A TOTAL OF (3) NEW ANTENNAS; (6) EXISTING LTE/UMTS ANTENNAS TO REMAIN (2 PER SECTOR)
  - AT&T RRUs: (1) NEW RRUs PER SECTOR WITH (3) SECTORS, FOR A TOTAL OF (3) NEW RRUs; (2) EXISTING RRU PER SECTOR TO REMAIN, FOR A TOTAL OF (6) EXISTING RRUs.
  - (1) EXISTING A2 MODULE PER SECTOR TO REMAIN, FOR A TOTAL OF (3) EXISTING A2 MODULES.
  - (1) NEW DC6 SQUID
  - (1) FIBER TRUNK / (2) DC TRUNKS

SITE ADDRESS: 1 DEERFIELD LANE  
ANSONIA, CT 06401

LATITUDE: 41.3505556 41° 21' 02.00016"N  
LONGITUDE: -72.600250 -73° 02' 57.3"W

USID: 97775


TOWER OWNER:

TYPE OF SITE: MONOPOLE/INDOOR EQUIPMENT

MONOPOLE HEIGHT: 170'-0"±  
RAD CENTER: 148'-0"±

CURRENT USE: UNMANNED WIRELESS TELECOMMUNICATIONS FACILITY

PROPOSED USE: UNMANNED WIRELESS TELECOMMUNICATIONS FACILITY



**at&t**  
**MOBILITY**

**FA CODE: 10126685**  
**SITE NUMBER: CT2359**  
**SITE NAME: ANSONIA DEERFIELD LN**

**PROJECT TEAM**

**CLIENT REPRESENTATIVE**

COMPANY: EMPIRE TELECOM  
ADDRESS: 16 ESQUIRE ROAD  
BILLERICA, MA 01821  
CONTACT: DAVID COOPER  
PHONE: 617-639-4908  
EMAIL: dcooper@empiretelecomm.com

**SITE ACQUISITION:**

COMPANY: EMPIRE TELECOM  
ADDRESS: 16 ESQUIRE ROAD  
BILLERICA, MA 01821  
CONTACT: DAVID COOPER  
PHONE: 617-639-4908  
EMAIL: dcooper@empiretelecomm.com

**ZONING:**

COMPANY: EMPIRE TELECOM  
ADDRESS: 16 ESQUIRE ROAD  
BILLERICA, MA 01821  
CONTACT: DAVID COOPER  
PHONE: 617-639-4908  
EMAIL: dcooper@empiretelecomm.com

**ENGINEERING:**

COMPANY: COM-EX CONSULTANTS, LLC  
ADDRESS: 115 ROUTE 46  
SUITE E39  
MOUNTAIN LAKES, NJ 07046  
CONTACT: NICHOLAS D. BARILE, P.E.  
PHONE: 862-209-4300  
EMAIL: nbarile@comexconsultants.com

**RF ENGINEER:**


COMPANY: AT&T MOBILITY - NEW ENGLAND  
ADDRESS: 550 COCHITUATE ROAD  
SUITE 550 13 & 14  
FRAMINGHAM, MA 01701  
CONTACT: CAMERON SYME  
PHONE: 508-596-7146  
EMAIL: cs6970@att.com

**CONSTRUCTION MANAGEMENT:**

COMPANY: EMPIRE TELECOM  
ADDRESS: 16 ESQUIRE ROAD  
BILLERICA, MA 01821  
CONTACT: GRZEGORZ "GREG" DORMAN  
PHONE: 484-683-1750  
EMAIL: gdorman@empiretelecomm.com

**VICINITY MAP**

1. TAKE RAMP LEFT FOR I-91 SOUTH, 9.7 MI. 2. AT EXIT 17, TAKE RAMP RIGHT FOR CT-15 SOUTH TOWARD W. CROSS PKWY / E. MAIN ST, 21.8 MI. 3. TAKE RAMP RIGHT FOR CT-34 WEST / DERBY AVE, 0.8 MI. 4. TURN RIGHT ONTO SADOW LN, 0.5 MI. 5. TURN RIGHT ONTO MARSHALL LN, 1.0 MI. 6. TURN RIGHT ONTO CT-243 / PULASKI HWY, 0.2 MI. 7. TURN RIGHT ONTO BENZ ST 0.6 MI. 8. TURN RIGHT ONTO FORD ST, AND THEN IMMEDIATELY TURN LEFT ONTO BENZ ST, 0.5 MI. 9. TURN RIGHT ONTO MILON RD, 343 FT. 10. KEEP STRAIGHT ONTO DEERFIELD LN, 48 FT. ARRIVE AT 1 DEERFIELD LN, ANSONIA, CT 06401.



**GENERAL NOTES**

- THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY, AND COPYRIGHTED WORK OF AT&T. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.
- THE FACILITY IS AN UNMANNED PRIVATE AND SECURED EQUIPMENT INSTALLATION. IT IS ONLY ACCESSED BY TRAINED TECHNICIANS FOR PERIODIC ROUTINE MAINTENANCE AND THEREFORE DOES NOT REQUIRE ANY WATER OR SANITARY SEWER SERVICE. THE FACILITY IS NOT GOVERNED BY REGULATIONS REQUIRING PUBLIC ACCESS PER ADA REQUIREMENTS.
- CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE AT&T REPRESENTATIVE IN WRITING OF DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.


**DRAWING INDEX**

		REV.
T-1	TITLE SHEET	0
GN-1	GROUNDING & GENERAL NOTES	0
A-1	COMPOUND LAYOUT	0
A-2	EQUIPMENT LAYOUTS	0
A-3	ANTENNA LAYOUTS & ELEVATIONS	0
A-4	DETAILS	0
A-5	ANTENNA MOUNTING DETAILS	0
G-1	GROUNDING, ONE-LINE DIAGRAM & DETAILS	0

**APPROVALS**

THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE SUBCONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN, ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR SITE MODIFICATIONS.

DISCIPLINE:	NAME:	DATE:
SITE ACQUISITION:		
CONSTRUCTION MANAGER:		
AT&T PROJECT MANAGER:		



CONNECTICUT LAW REQUIRES TWO WORKING DAYS NOTICE PRIOR TO ANY EARTH MOVING ACTIVITIES BY CALLING 800-922-4455 OR DIAL 811




**SITE NUMBER: CT2359**  
**SITE NAME: ANSONIA DEERFIELD LN**

1 DEERFIELD LANE  
ANSONIA, CT 06401  
NEW HAVEN COUNTY



NO.	DATE	REVISIONS	BY	CHK	APP'D
0	08/09/16	ISSUED AS FINAL	NJM	NDB	NDB

SCALE: AS SHOWN    DESIGNED BY: NJM    DRAWN BY: AM



AT&T		
DRAWING TITLE:		
JOB NUMBER	DRAWING NUMBER	REV
15204-EMP	T-1	0

**GROUNDING NOTES:**

1. THE SUBCONTRACTOR SHALL REVIEW AND INSPECT THE EXISTING FACILITY GROUNDING SYSTEM AND LIGHTNING PROTECTION SYSTEM (AS DESIGNED AND INSTALLED) FOR STRICT COMPLIANCE WITH THE NEC (AS ADOPTED BY THE AHJ), THE SITE-SPECIFIC (UL, LPI, OR NFPA) LIGHTING PROTECTION CODE, AND GENERAL COMPLIANCE WITH TELCORDIA AND TIA GROUNDING STANDARDS. THE SUBCONTRACTOR SHALL REPORT ANY VIOLATIONS OR ADVERSE FINDINGS TO THE CONTRACTOR FOR RESOLUTION.
2. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION, AND AC POWER GES'S) SHALL BE BONDED TOGETHER, AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
3. THE SUBCONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR NEW GROUND ELECTRODE SYSTEMS. THE SUBCONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS. TESTS SHALL BE PERFORMED IN ACCORDANCE WITH 25471-000-3PS-EG00-0001, DESIGN & TESTING OF FACILITY GROUNDING FOR CELL SITES.
4. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
5. EACH BTS CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, 6 AWG STRANDED COPPER OR LARGER FOR INDOOR BTS; 2 AWG STRANDED COPPER FOR OUTDOOR BTS.
6. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
7. APPROVED ANTIOXIDANT COATINGS (I.E., CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
8. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED WITH STAINLESS STEEL HARDWARE TO THE BRIDGE AND THE TOWER GROUND BAR.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
11. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH 6 AWG COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
12. GROUND CONDUCTORS USED IN THE FACILITY GROUND AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC PLASTIC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (E.G., NON-METALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
13. ALL TOWER GROUNDING SYSTEMS SHALL COMPLY WITH THE REQUIREMENTS OF ANSI/TIA 222. FOR TOWERS BEING BUILT TO REV-G OF THE STANDARD, THE WIRE SIZE OF THE BURIED GROUND RING AND CONNECTIONS BETWEEN THE TOWER AND THE BURIED GROUND RING SHALL BE CHANGED FROM 2 AWG TO 2/0 AWG. IN ADDITION, THE MINIMUM LENGTH OF THE GROUND RODS SHALL BE INCREASED FROM EIGHT FEET (8') TO TEN FEET (10').
14. ALL NEW STRUCTURES WITH A FOUNDATION AND/OR FOOTING HAVING 20 FT. OR MORE 1/2" OR GREATER ELECTRICALLY CONDUCTIVE REINFORCING STEEL MUST HAVE IT BONDED TO THE GROUND RING USING AN EXOTHERMIC WELD CONNECTION USING #2 AWG SOLID TINNED COPPER GROUND WIRE, PER NEC 250.50.

**GENERAL NOTES:**

1. FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:  
 CONTRACTOR - EMPIRE TELECOM  
 SUBCONTRACTOR - GENERAL CONTRACTOR (CONSTRUCTION)  
 OWNER - AT&T MOBILITY  
 OEM - ORIGINAL EQUIPMENT MANUFACTURER
2. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING SUBCONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CONTRACTOR (EMPIRE TELECOM).
3. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES. SUBCONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS, AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
4. DRAWINGS PROVIDED HERE ARE NOT TO BE SCALED AND ARE INTENDED TO SHOW OUTLINE ONLY.
5. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES, AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
6. THE SUBCONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
7. IF THE SPECIFIED EQUIPMENT CANNOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE SUBCONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION SPACE FOR APPROVAL BY THE CONTRACTOR.
8. SUBCONTRACTOR SHALL DETERMINE ACTUAL ROUTING OF CONDUIT, POWER AND T1 CABLES, GROUNDING CABLES AS SHOWN ON THE POWER, GROUNDING AND TELCO PLAN DRAWING. SUBCONTRACTOR SHALL UTILIZE EXISTING TRAYS AND/OR SHALL ADD NEW TRAYS AS NECESSARY. SUBCONTRACTOR SHALL CONFIRM THE ACTUAL ROUTING WITH THE CONTRACTOR. ROUTING OF TRENCHING SHALL BE APPROVED BY CONTRACTOR
9. THE SUBCONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT SUBCONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
10. SUBCONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OFF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
11. SUBCONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION.
12. ALL CONCRETE REPAIR WORK SHALL BE DONE IN ACCORDANCE WITH AMERICAN CONCRETE INSTITUTE (ACI) 301.
13. ANY NEW CONCRETE NEEDED FOR THE CONSTRUCTION SHALL HAVE 4000 PSI STRENGTH AT 28 DAYS UNLESS OTHERWISE SPECIFIED. ALL CONCRETING WORK SHALL BE DONE IN ACCORDANCE WITH ACI 318 CODE REQUIREMENTS.
14. ALL STRUCTURAL STEEL WORK SHALL BE DETAILED, FABRICATED AND ERECTED IN ACCORDANCE WITH AISC SPECIFICATIONS. ALL STRUCTURAL STEEL SHALL BE ASTM A36 (Fy=36 ksi). ALL STEEL EXPOSED TO WEATHER SHALL BE HOT DIPPED GALVANIZED. TOUCH UP ALL SCRATCHES AND OTHER MARKS IN THE FIELD AFTER STEEL IS ERECTED USING A COMPATIBLE ZINC RICH PAINT.
15. CONSTRUCTION SHALL COMPLY WITH SPECIFICATION 25741-000-3APS-A00Z-00002, "GENERAL CONSTRUCTION SERVICES FOR CONSTRUCTION OF AT&T MOBILITY SITES."
16. SUBCONTRACTOR SHALL VERIFY ALL EXISTING DIMENSIONS AND CONDITIONS PRIOR TO COMMENCING ANY WORK. ALL DIMENSIONS OF EXISTING CONSTRUCTION SHOWN ON THE DRAWINGS MUST BE VERIFIED. SUBCONTRACTOR SHALL NOTIFY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO ORDERING MATERIAL OR PROCEEDING WITH CONSTRUCTION.
17. THE EXISTING CELL SITE IS IN FULL COMMERCIAL OPERATION. ANY CONSTRUCTION WORK BY SUBCONTRACTOR SHALL NOT DISRUPT THE EXISTING NORMAL OPERATION. ANY WORK ON EXISTING EQUIPMENT MUST BE COORDINATED WITH CONTRACTOR. ALSO, WORK MAY NEED TO BE SCHEDULED FOR AN APPROPRIATE MAINTENANCE WINDOW USUALLY IN LOW TRAFFIC PERIODS AFTER MIDNIGHT.
18. SINCE THE CELL SITE MAY BE ACTIVE, ALL SAFETY PRECAUTIONS MUST BE TAKEN WHEN WORKING AROUND HIGH LEVELS OF ELECTROMAGNETIC RADIATION. EQUIPMENT SHOULD BE SHUTDOWN PRIOR TO PERFORMING ANY WORK THAT COULD EXPOSE THE WORKERS TO DANGER. PERSONAL RF EXPOSURE MONITORS ARE REQUIRED TO BE WORN TO ALERT OF ANY DANGEROUS EXPOSURE LEVELS.

19. SUBCONTRACTOR'S WORK SHALL COMPLY WITH ALL APPLICABLE NATIONAL, STATE, AND LOCAL CODES AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION (AHJ) FOR THE LOCATION. THE EDITION OF THE AHJ ADOPTED CODES AND STANDARDS IN EFFECT ON THE DATE OF CONTRACT AWARD SHALL GOVERN THE DESIGN.
  - INTERNATIONAL BUILDING CODE: IBC 2009 WITH LOCAL & COUNTY AMENDMENTS
  - NATIONAL ELECTRICAL CODE: NEC 2011 WITH LOCAL & COUNTY AMENDMENTS
  - FIRE/LIFE SAFETY CODE: NFPA-101 2009 WITH LOCAL & COUNTY AMENDMENTS
20. SUBCONTRACTOR'S WORK SHALL COMPLY WITH THE LATEST EDITION OF THE FOLLOWING STANDARDS:
  - AMERICAN CONCRETE INSTITUTE (ACI) 318, BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE
  - AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC), MANUAL OF STEEL CONSTRUCTION, THIRTEENTH EDITION
  - AMERICAN SOCIETY OF TESTING OF MATERIALS, ASTM
  - TELECOMMUNICATIONS INDUSTRY ASSOCIATION (ANSI/TIA-222-G-1), STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWER AND ANTENNA SUPPORTING STRUCTURES:
  - TIA 607, COMMERCIAL BUILDING GROUNDING AND BONDING REQUIREMENTS FOR TELECOMMUNICATIONS
  - OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION, OSHA
  - INSTITUTE FOR ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE) 81, GUIDE FOR MEASURING EARTH RESISTIVELY, GROUND IMPEDANCE, AND EARTH SURFACE POTENTIALS OF A GROUND SYSTEM IEEE 1100 (1999) RECOMMENDED PRACTICE FOR POWERING AND GROUNDING OF ELECTRONIC EQUIPMENT
  - TELCORDIA GR-1503, COAXIAL CABLE CONNECTIONS
21. FOR ANY CONFLICTS BETWEEN SECTIONS OF LISTED CODES AND STANDARDS REGARDING MATERIAL, METHODS OF CONSTRUCTION, OR OTHER REQUIREMENTS, THE MOST RESTRICTIVE REQUIREMENT SHALL GOVERN. WHERE THERE IS CONFLICT BETWEEN A GENERAL REQUIREMENT AND A SPECIFIC REQUIREMENT, THE SPECIFIC REQUIREMENT SHALL GOVERN.
22. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, ANGLES AND EXISTING CONDITIONS AT THE SITE PRIOR TO FABRICATION AND/OR INSTALLATION OF ANY WORK IN THE CONTRACT AREA AND SUBMIT TO THE ENGINEER ANY DISCREPANCIES FROM THE DRAWINGS.




**SITE NUMBER: CT2359**  
**SITE NAME: ANSONIA DEERFIELD LN**



1 DEERFIELD LANE  
ANSONIA, CT 06401  
NEW HAVEN COUNTY




0	08/09/16	ISSUED AS FINAL	NJM	NDB	NDB
NO.	DATE	REVISIONS	BY	CHK	APP'D
SCALE: AS SHOWN		DESIGNED BY: NJM	DRAWN BY: AM		



<b>AT&amp;T</b>		
DRAWING TITLE: <b>GROUNDING &amp; GENERAL NOTES</b>		
JOB NUMBER 15204-EMP	DRAWING NUMBER GN-1	REV 0



**COMPOUND LAYOUT**  
SCALE: 3/16" = 1'-0"



**NOTE:**  
CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, ANGLES, AND EXISTING CONDITIONS AT THE SITE PRIOR TO FABRICATION AND/OR INSTALLATION OF ANY WORK IN THE CONTRACT AREA AND SUBMIT TO THE ENGINEER ANY DISCREPANCIES FROM THE DRAWINGS.

**COM-EX**  
Consultants  
115 ROUTE 46  
SUITE E39  
MOUNTAIN LAKES, NJ 07046  
PHONE: 862.209.4300  
FAX: 862.209.4301

**EMPIRE**  
telecom  
16 ESQUIRE ROAD  
BILLERICA, MA 01821


**SITE NUMBER: CT2359**  
**SITE NAME: ANSONIA DEERFIELD LN**  
1 DEERFIELD LANE  
ANSONIA, CT 06401  
NEW HAVEN COUNTY

 **at&t**  
MOBILITY  
550 COCHITUATE ROAD  
FRAMINGHAM, MA 01701

0	08/09/16	ISSUED AS FINAL	NJM	NDB	NDB
NO.	DATE	REVISIONS	BY	CHK	APP'D
SCALE: AS SHOWN		DESIGNED BY: NJM	DRAWN BY: AM		



<b>AT&amp;T</b>		
DRAWING TITLE: <b>COMPOUND LAYOUT</b>		
JOB NUMBER 15204-EMP	DRAWING NUMBER A-1	REV 0




**EXISTING EQUIPMENT LAYOUT**


SCALE: 1" = 2'-0"



( IN FEET )  
1/2 Inch = 1 Foot




NORTH




**PROPOSED EQUIPMENT LAYOUT**

SCALE: 1" = 2'-0"




( IN FEET )  
1/2 Inch = 1 Foot







NORTH

0	08/09/16	ISSUED AS FINAL	NJM	NDB	NDB
NO.	DATE	REVISIONS	BY	CHK	APP'D
SCALE: AS SHOWN		DESIGNED BY: NJM	DRAWN BY: AM		



<b>AT&amp;T</b>		
DRAWING TITLE: <b>EQUIPMENT LAYOUTS</b>		
JOB NUMBER 15204-EMP	DRAWING NUMBER A-2	REV 0



**COM-EX**  
Consultants  
115 ROUTE 46  
SUITE E39  
MOUNTAIN LAKES, NJ 07046  
PHONE: 862.209.4300  
FAX: 862.209.4301

**EMPIRE**  
telecom  
16 ESQUIRE ROAD  
BILLERICA, MA 01821


**SITE NUMBER: CT2359**  
**SITE NAME: ANSONIA DEERFIELD LN**  
1 DEERFIELD LANE  
ANSONIA, CT 06401  
NEW HAVEN COUNTY

**at&t**  
MOBILITY  
550 COCHITUATE ROAD  
FRAMINGHAM, MA 01701

0	08/09/16	ISSUED AS FINAL	NJM	NDB	NDB
NO.	DATE	REVISIONS	BY	CHK	APP'D
SCALE: AS SHOWN		DESIGNED BY: NJM	DRAWN BY: AM		


STATE OF CONNECTICUT  
Professional Engineer  
No. 38643  
Professional Engineer

**AT&T**  
DRAWING TITLE:  
**ANTENNA LAYOUTS & ELEVATIONS**  
JOB NUMBER: 15204-EMP  
DRAWING NUMBER: A-3  
REV: 0




FRONT VIEW

SIDE VIEW




BOTTOM VIEW

MANUFACTURER	CCI
MODEL	HPA-65R-BUU-H6
WEIGHT	51.0 LBS



FRONT VIEW

SIDE VIEW




BOTTOM VIEW

MANUFACTURER	CCI
MODEL	HPA-65R-BUU-H8
WEIGHT	68.0 LBS

**LTE ANTENNA DETAILS**

SCALE: N.T.S.




MODEL	L x W x H	WEIGHT
*RRUS-11	19.69" x 16.97" x 7.17"	50.7 LBS
*RRUS-12	20.4" x 18.5" x 7.5"	58 LBS
*A2 MODULE	16.4" x 15.2" x 3.4"	22 LBS
RRUS-32	29.9" x 13.3" x 9.5"	77 LBS

\*DENOTES EXISTING.

**RRUS DETAIL**

SCALE: N.T.S.

0	08/09/16	ISSUED AS FINAL	NJM	NDB	NDB
NO.	DATE	REVISIONS	BY	CHK	APP'D
SCALE: AS SHOWN		DESIGNED BY: NJM	DRAWN BY: AM		




<b>AT&amp;T</b>		
DRAWING TITLE: <b>DETAILS</b>		
JOB NUMBER 15204-EMP	DRAWING NUMBER A-4	REV 0



EXISTING LTE RRU TO REMAIN  
(TYP. 2 PER SECTOR, 6 TOTAL)

RRUS MOUNTED ON EXISTING PIPE  
• (1) NEW RRU PER SECTOR  
(3 TOTAL)

PROPOSED AT&T LTE ANTENNA  
MOUNTED ON EXISTING PIPE  
(TYP. OF 1 PER SECTOR, 3  
TOTAL)




**PROPOSED ANTENNA MOUNTING DETAIL (FRONT VIEW)**

SCALE: N.T.S.

EXISTING DC-6 SQUID TO  
REMAIN (1 TOTAL)

EXISTING MOUNT PIPE, TYP.

PROPOSED AT&T LTE ANTENNA  
MOUNTED ON EXISTING PIPE  
(TYP. OF 1 PER SECTOR, 3  
TOTAL)



**PROPOSED ANTENNA MOUNTING DETAIL (SIDE VIEW)**

SCALE: N.T.S.

**EXISTING ANTENNA SCHEDULE**

SECTOR	POSITION	MAKE	MODEL	SIZE (INCHES)
ALPHA	A1	POWERWAVE	7770	55"x11"x5"
	A2	CCI	OPA-65R-LCUU-H6	72"x14.8"x7.4"
	A3	-	-	-
	A4	POWERWAVE	7770	55"x11"x5"
BETA	B1	POWERWAVE	7770	55"x11"x5"
	B2	CCI	OPA-65R-LCUU-H8	92.7"x14.4"x7"
	B3	-	-	-
	B4	POWERWAVE	7770	55"x11"x5"
GAMMA	G1	POWERWAVE	7770	55"x11"x5"
	G2	CCI	OPA-65R-LCUU-H8	92.7"x14.4"x7"
	G3	-	-	-
	G4	POWERWAVE	7770	55"x11"x5"

**FINAL ANTENNA SCHEDULE**

SECTOR	POSITION	MAKE	MODEL	SIZE (INCHES)
ALPHA	A1	POWERWAVE	7770	55"x11"x5"
	A2	CCI	OPA-65R-LCUU-H6	72"x14.8"x7.4"
	A3	-	-	-
	A4	CCI	HPA-65R-BUU-H6	72"x14.8"x9"
BETA	B1	POWERWAVE	7770	55"x11"x5"
	B2	CCI	OPA-65R-LCUU-H8	92.7"x14.4"x7"
	B3	-	-	-
	B4	CCI	HPA-65R-BUU-H8	92.4"x14.8"x7.4"
GAMMA	G1	POWERWAVE	7770	55"x11"x5"
	G2	CCI	OPA-65R-LCUU-H8	92.7"x14.4"x7"
	G3	-	-	-
	G4	CCI	HPA-65R-BUU-H8	92.4"x14.8"x7.4"

PROJECT OWNER IS RESPONSIBLE FOR PROVIDING A STRUCTURAL STABILITY ANALYSIS TO DETERMINE THE CAPACITY AND SUITABILITY OF THE EXISTING ANTENNA SUPPORT STRUCTURE TO SAFELY CARRY ALL ADDITIONAL LOADS IMPOSED BY THE PROPOSED EQUIPMENT AS SHOWN HEREIN. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR INCORPORATING ANY REQUIRED STRUCTURAL MODIFICATIONS INTO THEIR SCOPE OF WORK.

**PROPOSED RRU SCHEDULE**

SECTOR	MAKE	MODEL	SIZE (INCHES)	ADDITIONAL COMPONENT	SIZE (INCHES)
ALPHA	ERICSSON	RRUS-32	29.9"x13.3"x9.5"		
	ERICSSON	RRUS-12(EXISTING)	20.4"x18.5"x7.5"	ERICSSON A2 MODULE (EXISTING)	16.4"x15.2"x3.4"
	ERICSSON	RRUS-11(EXISTING)	19.7"x16.9"x7.2"		
	ERICSSON	RRUS-11(EXISTING) (GROUND LEVEL)	19.7"x16.9"x7.2"		
BETA	ERICSSON	RRUS-32	29.9"x13.3"x9.5"		
	ERICSSON	RRUS-12(EXISTING)	20.4"x18.5"x7.5"	ERICSSON A2 MODULE (EXISTING)	16.4"x15.2"x3.4"
	ERICSSON	RRUS-11(EXISTING)	19.7"x16.9"x7.2"		
	ERICSSON	RRUS-11(EXISTING) (GROUND LEVEL)	19.7"x16.9"x7.2"		
GAMMA	ERICSSON	RRUS-32	29.9"x13.3"x9.5"		
	ERICSSON	RRUS-12(EXISTING)	20.4"x18.5"x7.5"	ERICSSON A2 MODULE (EXISTING)	16.4"x15.2"x3.4"
	ERICSSON	RRUS-11(EXISTING)	19.7"x16.9"x7.2"		
	ERICSSON	RRUS-11(EXISTING) (GROUND LEVEL)	19.7"x16.9"x7.2"		

**COM-EX**  
Consultants  
115 ROUTE 46  
SUITE E39  
MOUNTAIN LAKES, NJ 07046  
PHONE: 862.209.4300  
FAX: 862.209.4301

**EMPIRE**  
telecom  
16 ESQUIRE ROAD  
BILLERICA, MA 01821

**SITE NUMBER: CT2359**  
**SITE NAME: ANSONIA DEERFIELD LN**

1 DEERFIELD LANE  
ANSONIA, CT 06401  
NEW HAVEN COUNTY


**at&t**  
MOBILITY  
550 COCHITUATE ROAD  
FRAMINGHAM, MA 01701

NO.	DATE	REVISIONS	BY	CHK	APP'D
0	08/09/16	ISSUED AS FINAL	NJM	NDB	NDB


SCALE: AS SHOWN    DESIGNED BY: NJM    DRAWN BY: AM

SEAL  
STATE OF CONNECTICUT  
PROFESSIONAL ENGINEER  
NO. 38643


**AT&T**  
DRAWING TITLE:  
**ANTENNA MOUNTING DETAILS**  
JOB NUMBER: 15204-EMP    DRAWING NUMBER: A-5    REV: 0




**GROUND WIRE TO GROUND BAR CONNECTION DETAIL**  
SCALE: N.T.S.




**GROUNDING RISER DIAGRAM**  
SCALE: N.T.S.



**TYPICAL PLUMBING DIAGRAM (PER SECTOR)**  
SCALE: N.T.S.



**TYPICAL GROUND BAR CONNECTION DETAIL**  
SCALE: N.T.S.



ITEM NO.	QTY.	DESCRIPTION
1	1	SOLID GROUND BAR (20"x 4"x 1/4")
2	2	WALL MOUNTING BRACKET
3	2	INSULATORS
4	4	5/8"-11x1" H.H.C.S.
5	4	5/8" LOCK WASHER

- NOTES:
- EACH GROUND CONDUCTOR TERMINATING ON ANY GROUND BAR SHALL HAVE AN IDENTIFICATION TAG ATTACHED AT EACH END THAT WILL IDENTIFY ITS ORIGIN AND DESTINATION
- SECTION "P" - SURGE PRODUCERS**
- CABLE ENTRY PORTS (HATCH PLATES) (#2)
  - GENERATOR FRAMEWORK (IF AVAILABLE) (#2)
  - TELCO GROUND BAR
  - COMMERCIAL POWER COMMON NEUTRAL/GROUND BOND (#2)
  - +24V POWER SUPPLY RETURN BAR (#2)
  - 48V POWER SUPPLY RETURN BAR (#2)
  - RECTIFIER FRAMES
- SECTION "A" - SURGE ABSORBERS**
- INTERIOR GROUND RING (#2)
  - EXTERNAL EARTH GROUND FIELD (BURIED GROUND RING) (#2)
  - METALLIC COLD WATER PIPE (IF AVAILABLE) (#2)
  - BUILDING STEEL (IF AVAILABLE) (#2)

**GROUND BAR DETAIL**  
SCALE: N.T.S.

# MODIFICATION AND DESIGN DRAWINGS FOR AN EXISTING 169' SABRE MONOPOLE

PROPOSED CARRIER: AT&T

SITE: CT13071-A-SBA / WOODBRIDGE

COORDINATES (LATITUDE: 41.350750°, LONGITUDE: -73.049250°)

## CONSTRUCTION CLASS

TES HAS DETERMINED THIS AS A  
CLASS II CONSTRUCTION PROJECT  
PER TIA-1019-A.

COMPLETE FABRICATION DRAWINGS FOR ALL MATERIALS REQUIRED FOR  
THIS PROJECT ARE AVAILABLE FROM TOWER ENGINEERING SOLUTIONS  
(TES). PLEASE CONTACT TES FOR MORE INFORMATION.

SHEET	SHEET TITLE	REV
T-1	TITLE SHEET	0
BOM	BILL OF MATERIALS	0
GN-1	GENERAL NOTES	0
A-1	TOWER PROFILE	0
A-2	REINFORCEMENT ASSEMBLY (3) P6X100-G-10TT (18 SIDE 3 PIECES ON FLAT # 1, 7 AND 13)	0

**NOTE:**

1. THE MODIFICATION DRAWINGS ARE BASED ON THE  
TES PROJECT NO. 22621, DATED 05/24/2016.



**Tower Engineering Solutions**  
8445 FREEPORT PARKWAY, SUITE 375  
IRVING, TX 75063  
PH: (972) 483-0607




5900 BROKEN SOUND PARKWAY, NW  
BOCA RATON, FL 33487  
(800)-487-SITE

TES JOB NO:  
22848

CUSTOMER SITE NO:  
CT13071-A-SBA

CUSTOMER SITE NAME:  
WOODBRIDGE  
1 DEERFIELD LANE  
ANSONIA, CT 06401



DRAWN BY: AD      CHECKED BY: USA/KMM

REV.	DESCRIPTION	BY	DATE
△	FIRST ISSUE	AD	06/23/16
△			
△			
△			

SHEET TITLE:  
  
TITLE SHEET

This drawing/document is the property  
of **Tower Engineering Solutions, LLC**.  
Information contained herein is  
considered confidential in nature and is  
to be used only for the specific site  
that it was intended for. Reproduction,  
transmission, publication or disclosure  
by any method is prohibited except by  
express written permission from **Tower  
Engineering Solutions, LLC**. Without  
exception, the information on this  
drawing/document remains the property  
of **Tower Engineering Solutions, LLC**.

SHEET NUMBER:      REV #:  
T-1      0



**GENERAL NOTES**

1. ALL WORK SHALL COMPLY WITH THE ANSI/TIA-222-F, TIA-1019-A, AND ANY OTHER GOVERNING BUILDING CODES AND OSHA SAFETY REGULATIONS.
2. ALL WORK INDICATED ON THE DRAWINGS SHALL BE PERFORMED BY QUALIFIED CONTRACTORS EXPERIENCED IN TELECOMMUNICATIONS TOWER, POLE AND FOUNDATION CONSTRUCTION.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN AND FABRICATION OF ALL MISCELLANEOUS PARTS (SUCH AS SHIMS), TEMPORARY SUPPORTS, AND GUYINGS, ETC., PER TIA-1019-A, TO COMPLETE THE ASSEMBLY AS SHOWN IN THE DRAWINGS.
4. CONTRACTOR SHALL PROCEED WITH THE INSTALLATION WORK CAREFULLY SO THE WORK WILL NOT DAMAGE ANY EXISTING CABLE, EQUIPMENT OR THE STRUCTURE.
5. THE USE OF GAS TORCH OR WELDER, ARE NOT ALLOWED ON ANY TOWER STRUCTURE WITHOUT THE CONSENT OF THE TOWER OWNER.
6. GENERALLY THE CONTRACTOR IS RESPONSIBLE TO CONDUCT AN ONSITE VISIT SURVEY OF THE JOB SITE AFTER AWARD, AND REPORT ANY ISSUES WITH THE SITE TO **TES** BEFORE PROCEEDING CONSTRUCTION.

**FABRICATION**

1. ALL STEEL SHALL MEET OR EXCEED THE MINIMUM STRENGTH AS SPECIFIED IN THE DRAWINGS. IF YIELD STRENGTH WAS NOT NOTED IN THE DRAWINGS, CONTRACTORS SHALL CONTACT TES FOR DIRECTION.
2. ALL FIELD CUT EDGES SHALL BE GROUND SMOOTH. ALL FIELD CUT AND DRILLED SURFACES SHALL BE REPAIRED WITH A MINIMUM OF TWO COATES OF ZRC GALVILITE COLD GALVANIZING COMPOUND PER ASTM A780 AND MANUFACTURER'S RECOMMENDATIONS.

**WELDING**

1. ALL WELDING SHALL BE PERFORMED BY AWS CERTIFIED WELDERS AND IN ACCORDANCE WITH THE LATEST EDITION OF THE AWS WELDING CODE D1.1. ALL ELECTRODES TO BE LOW HYDROGEN, MATCHING FILLER METAL, PER AWS D1.1, UNO. (E700XX UNLESS NOTED OTHERWISE).
2. PRIOR TO FIELD WELDING GALVANIZED MATERIAL, CONTRACTOR SHALL GRIND OFF GALVANIZING APPROX. 0.5" BEYOND THE PROPOSED FIELD WELD SURFACES.
3. ALL WELDS SHALL BE INSPECTED VISUALLY. A MINIMUM OF 25% OF WELDS SHALL BE INSPECTED WITH DYE PENETRANT OR MAGNETIC PARTICLE TO MEET THE ACCEPTANCE CRITERIA OF AWS D1.1. 100% OF WELDS SHALL BE INSPECTED IF DEFECTS ARE FOUND.
4. WELD INSPECTIONS SHALL BE PERFORMED BY AN AWS CERTIFIED WELD INSPECTOR.
5. AFTER INSPECTION, ALL FIELD WELDED SURFACES SHALL BE REPAIRED WITH A MINIMUM OF TWO COATS OF ZRC GALVILITE COLD GALVANIZING COMPOUND PER ASTM A780 AND MANUFACTURER'S RECOMMENDATIONS.

**BOLTED ASSEMBLIES AND TIGHTENING OF CONNECTIONS**

1. ALL HIGH STRENGTH BOLTS SHALL CONFORM TO THE PROVISIONS OF THE SPECIFICATIONS FOR STRUCTURAL JOINTS USING A325 OR A490 BOLTS AS APPROVED BY THE RCSC.
2. FLANGE BOLTS SHALL BE TIGHTENED BY THE AISC "TURN-OF-THE-NUT" METHOD. THE FOLLOWING CHART SHOULD BE USED FOR THE "TURN-OF-THE-NUT" TIGHTENING.
3. SPLICE BOLTS AND ALL OTHER BOLTS IN BEARING TYPE CONNECTIONS SHALL BE TIGHTENED TO A SNUG-TIGHT CONDITION.
4. THE SNUG-TIGHT CONDITION IS DEFINED AS THE TIGHTNESS ATTAINED BY EITHER A FEW IMPACTS OF AN IMPACT WRENCH OR THE FULL EFFORT OF AN IRONWORKER WITH AN ORDINARY SPUD WRENCH TO BRING THE CONNECTED PLIES INTO FIRM CONTACT.

**VERIFICATION AND INSPECTION**

1. IF APPLICABLE, VERIFICATION INSPECTION TO BE PERFORMED SHALL BE IN ACCORDANCE TO 2005 CONNECTICUT STATE BUILDING CODE SECTION 1705 - TABLE 1702.1.1 FOR STEEL CONSTRUCTION OTHER THAN STRUCTURAL STEEL AND FOR CONCRETE CONSTRUCTION.

TABLE 8.2 NUT ROTATION FROM SNUG-TIGHT CONDITION FOR TURN-OF-NUT PRETENSIONING<sup>a,b</sup>

BOLT LENGTH*	DISPOSITION OF OUTER FACE OF BOLTED PARTS		
	BOTH FACES NORMAL TO BOLT AXIS	ONE FACE NORMAL TO BOLT AXIS, OTHER SLOPED NOT MORE THAN 1:20 <sup>d</sup>	BOTH FACES SLOPED NOT MORE THAN 1:20 FROM NORMAL TO BOLT AXIS <sup>d</sup>
NOT MORE THAN 4d <sub>b</sub>	1/3 TURN	1/2 TURN	2/3 TURN
MORE THAN 4d <sub>b</sub> BUT NOT MORE THAN 8d <sub>b</sub>	1/2 TURN	2/3 TURN	5/6 TURN
MORE THAN 8d <sub>b</sub> BUT NOT MORE THAN 12d <sub>b</sub>	2/3 TURN	5/6 TURN	1 TURN

<sup>a</sup> NUT ROTATION IS RELATIVE TO BOLT REGARDLESS OF THE ELEMENT (NUT OR BOLT) BEING TURNED. FOR REQUIRED NUT ROTATIONS OF 1/2 TURN AND LESS, THE TOLERANCE IS PLUS OR MINUS 30 DEGREES; FOR REQUIRED NUT ROTATIONS OF 2/3 TURN AND MORE, THE TOLERANCE IS PLUS OR MINUS 45 DEGREES.

<sup>b</sup> APPLICATION ONLY TO JOINTS IN WHICH ALL MATERIAL WITHIN THE GRIP IS STEEL.

<sup>c</sup> WHEN THE BOLT LENGTH EXCEEDS 12d, THE REQUIRED NUT ROTATION SHALL BE DETERMINED BY ACTUAL TESTING IN A SUITABLE TENSION CALIBRATOR THAT SIMULATES THE CONDITIONS OF SOLIDLY FITTING STEEL.

<sup>d</sup> BEVELED WASHER NOT USED.

SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS, JUNE 30, 2004 RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS

**INSTALLATION TORQUE REQUIRED FOR HOLLO BOLTS AND AJAX BOLTS:**

1. HB12 HOLLO BOLT: 59 FT-LBS
2. HB16 HOLLO BOLT: 140 FT-LBS
3. HB20 HOLLO BOLT: 221 FT-LBS
4. M20 AJAX BOLT: 390 FT-LBS.



**Tower Engineering Solutions**

8445 FREEPORT PARKWAY, SUITE 375  
IRVING, TX 75063  
PH: (972) 483-0607



5900 BROKEN SOUND PARKWAY, NW  
BOCA RATON, FL 33487  
(800)-487-SITE

TES JOB NO:  
22848

CUSTOMER SITE NO:  
CT13071-A-SBA

CUSTOMER SITE NAME:  
WOODBIDGE  
1 DEERFIELD LANE  
ANSONIA, CT 06401

DRAWN BY: AD CHECKED BY: USA/KMM

REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	AD	06/23/16

SHEET TITLE:

GENERAL NOTES

This drawing/document is the property of **Tower Engineering Solutions, LLC**. Information contained herein is considered confidential in nature and is to be used only for the specific site that it was intended for. Reproduction, transmission, publication or disclosure by any method is prohibited except by express written permission from **Tower Engineering Solutions, LLC**. Without exception, the information on this drawing/document remains the property of **Tower Engineering Solutions, LLC**.

SHEET NUMBER: REV #:

GN-1 0

**NOTES:**

1. TEMPORARILY RELOCATE ANY EXISTING COAX ATTACHED TO THE MONOPOLE AND ANY OTHER MEMBERS WHERE OBSTRUCTION WITH THE PROPOSED MODIFICATION MAY OCCUR.
2. TEMPORARILY RELOCATE EXISTING EQUIPMENT AROUND THE FOUNDATION MAY BE REQUIRED DURING CONSTRUCTION.





PHOTO 1




PHOTO 2

EXISTING SAFETY CLIMB CABLE GUID TO BE RELOCATED TO ACCOMMODATE NEW INSTALLATION OF REINFORCEMENT FLAT. SEE SAFETY CABLE GUIDE BRACKET INSTALLATION DETAIL.



SAFETY CABLE GUIDE BRACKET INSTALLATION DETAIL



**Tower Engineering Solutions**  
8445 FREEPORT PARKWAY, SUITE 375  
IRVING, TX 75063  
PH: (972) 483-0607



5900 BROKEN SOUND PARKWAY, NW  
BOCA RATON, FL 33487  
(800)-487-SITE

TES JOB NO:  
22848

CUSTOMER SITE NO:  
CT13071-A-SBA

CUSTOMER SITE NAME:  
WOODBIDGE  
1 DEERFIELD LANE  
ANSONIA, CT 06401

DRAWN BY: AD CHECKED BY: USA/KMM



REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	AD	06/23/16

SHEET TITLE:  
**TOWER PROFILE**

This drawing/document is the property of Tower Engineering Solutions, LLC. Information contained herein is considered confidential in nature and is to be used only for the specific site that it was intended for. Reproduction, transmission, publication or disclosure by any method is prohibited except by express written permission from Tower Engineering Solutions, LLC. Without exception, the information on this drawing/document remains the property of Tower Engineering Solutions, LLC.

SHEET NUMBER:  
**A-1**

REV #:  
**0**



- NOTES:**
1. REFER TO SHEET A-1 FOR FLAT BAR ELEVATION.
  2. INSTALLATION TORQUE FOR HOLLO-BOLTS:  
M16 HOLLO-BOLTS: 140 FT-LBS.

ITEM NO.	QTY.	PART NO.	DESCRIPTION (BASE SECTION)
1	3	P6X100-G-10TT	PL 1" X 6" X 10'-0" A572-65
2	60	HB16-2	LINDAPTER 5/8" TYPE HB HOLLO-BOLT (HCF)



**Tower Engineering Solutions**  
 8445 FREEPORT PARKWAY, SUITE 375  
 IRVING, TX 75063  
 PH: (972) 483-0607



5900 BROKEN SOUND PARKWAY, NW  
 BOCA RATON, FL 33487  
 (800)-487-SITE

TES JOB NO:  
22848

CUSTOMER SITE NO:  
CT13071-A-SBA

CUSTOMER SITE NAME:  
WOODBRIDGE  
 1 DEERFIELD LANE  
 ANSONIA, CT 06401

DRAWN BY: AD      CHECKED BY: USA/KMM

REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	AD	06/23/16

SHEET TITLE:  
**REINFORCEMENT ASSEMBLY**  
 (3) P6X100-G-10TT  
 (18 SIDE 3 PIECES ON  
 FLAT # 1, 7 AND 13)

This drawing/document is the property of Tower Engineering Solutions, LLC. Information contained herein is considered confidential in nature and is to be used only for the specific site that it was intended for. Reproduction, transmission, publication or disclosure by any method is prohibited except by express written permission from Tower Engineering Solutions, LLC. Without exception, the information on this drawing/document remains the property of Tower Engineering Solutions, LLC.

SHEET NUMBER:      REV #:

A-2                      0