



February 8th, 2018

Melanie A. Bachman Executive
Director Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: Notice of Exempt Modification – Antenna Swap and RRU Add
Property Address: 497 Middle Turnpike, Storrs Mansfield, CT
Applicant: AT&T Mobility, LLC

Dear Ms. Bachman:

On behalf of AT&T, please accept this application as notification pursuant to R.C.S.A. §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. §16- 50j-72(b) (2).

AT&T currently maintains a wireless telecommunications facility consisting of nine (9) wireless telecommunication antennas at an antenna center line height of 122-feet on an existing 120-foot monopole, owned by Crown Castle at 12 Gill St. Suite 5800, Woburn, MA 01801. AT&T now intends to swap (3) 4' Powerwave 7770 panel antennas for (2) 6' CCI HPA-65R-BUU-H6 and (1) 8' CCI HPA-65R-BUU-H8 Panel Antennas, each swap occurring in position [3], all sectors for a total of three (3) antennas being swapped. AT&T is also relocation (2) 6' KMW AM-X-CD-16-65-00T-RET and (1) 8' Andrew SBNH-1D6565C Panel Antennas from position [3] to position [4], all sectors. AT&T also wishes to add (1) RRUS-32 in position [3] all sectors, for a total of (3) RRUs 32s being added. All of the changes will take place on the existing antenna mount.

Per the Decision and Order letter, the construction of the aforementioned monopole was approved on September 12th, 2003 by the Connecticut Siting Council.

In addition, attached is a summary of the planned modifications including power density calculations reflecting the change in AT&T's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

Please accept this letter pursuant to Regulation of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b) (2). In accordance with R.C.S.A., a copy of this letter is being sent to Linda Painter – Director of Planning and Development, Town of Mansfield, CT, 4 South Eagleville Road, Mansfield, CT 06268 and Paul Shapiro – Mayor, Town of Mansfield, CT, 4 South Eagleville Road, Mansfield, CT 06268. A copy of this letter is also being sent to the property owner, Ann Brodin, Trustee of the Bernard R. Brodin Revocable Trust, 106 Coleman Rd. Manchester, CT 06040 and to the tower company, Crown Castle, 3 Corporate Park Drive, Suite 101, Clifton Park, NY 12065.

The following is a list of subsequent decisions by the Connecticut Siting Council:

- **EM-CING-078-081204-** New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located at 111 Middle Turnpike, **Mansfield**, Connecticut.
- **EM-CING-078-081215-** New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located at 497 Middle Turnpike, **Mansfield**, Connecticut.
- **EM-AT&T-078-120607** – AT&T Mobility notice of intent to modify an existing telecommunications facility located at 111 Middle Turnpike, **Mansfield**, Connecticut.
- **EM-AT&T-078-120618** – AT&T Mobility notice of intent to modify an existing telecommunications facility located at 497 Middle Turnpike, **Mansfield**, Connecticut.



The planned modifications to AT&T's facility fall squarely within those activities explicitly provided for in R.C.S.A. §16-50j-72(b) (2).

1. The proposed modifications will not result in an increase in the height of the existing tower. AT&T's replacement antennas will be installed at the 167-foot level of the 181-foot monopole.
2. The proposed modifications will not involve any changes to ground-mounted equipment and, therefore, will not require an extension of the site boundary.
3. The proposed modifications will not increase the noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the modified facility will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) safety standard. A cumulative worst-case RF emissions calculation for AT&T's modified facility is provided in the RF Emissions Compliance Report, included in Tab 2.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The tower and its foundation can support AT&T's proposed modifications. (See Structural Analysis Report included in Tab 3).

For the foregoing reasons, AT&T respectfully submits that the proposed modifications to the above referenced telecommunications facility constitutes an exempt modification under R.C.S.A. §16-50j-72(b) (2).

Sincerely,

Romina Kirchmaier

CC w/enclosures:

Linda Painter – Director of Planning and Development

Paul Shapiro – Mayor, Town of Mansfield, CT

Ann Brodin, Trustee of the Bernard R. Brodin Revocable Trust – Property Owner

Crown Castle, Tower Company

DOCKET NO. 247 – AT&T Wireless PCS, LLC d/b/a	}	Connecticut
AT&T Wireless application for a Certificate of	}	
Environmental Compatibility and Public Need for the	}	Siting
construction, maintenance and operation of a	}	
telecommunications facility in Mansfield, Connecticut.	}	Council

September 12, 2003

Decision and Order

Pursuant to the foregoing Findings of Fact and Opinion, the Connecticut Siting Council (Council) finds that the effects associated with the construction, operation, and maintenance of a telecommunications facility including effects on the natural environment; ecological integrity and balance; public health and safety; scenic, historic, and recreational values; forests and parks; air and water purity; and fish and wildlife are not disproportionate either alone or cumulatively with other effects when compared to need, are not in conflict with the policies of the State concerning such effects, and are not sufficient reason to deny the application and therefore directs that a Certificate of Environmental Compatibility and Public Need, as provided by General Statutes § 16-50k, be issued to AT&T Wireless PCS, LLC (AT&T) for the construction, maintenance and operation of a wireless telecommunications facility at proposed Site A-1 located at 497 Middle Turnpike, Mansfield, Connecticut. We deny certification of the proposed Site B located off Cedar Swamp Road, Mansfield, Connecticut.

The facility shall be constructed, operated, and maintained substantially as specified in the Council's record in this matter, and subject to the following conditions:

1. There shall be a minimal shift in the tower's location in a southerly direction to the extent necessary to keep the tower's setback radius within the host property's boundaries.
2. The tower shall be constructed as a monopole, no taller than necessary to provide the proposed telecommunications services, sufficient to accommodate the antennas of AT&T and other entities, both public and private, but such tower shall not exceed a height of 120 feet above ground level.
3. Construction activities shall be conducted between November 1 and April 1 in order to minimize possible disturbance of any *Clemmys insculpta* (wood turtles) in the vicinity of the site.
4. The Certificate Holder shall prepare a Development and Management (D&M) Plan for this site in compliance with Sections 16-50j-75 through 16-50j-77 of the Regulations of Connecticut State Agencies. The D&M Plan shall be submitted to and approved by the Council prior to the commencement of facility construction and shall include:
 - a. a detailed site development plan that depicts the location of the access road, compound, tower, and utility line;
 - b. specifications for the tower, tower foundation, antennas, equipment building, and security fence;
 - c. construction plans for site clearing, water drainage, and erosion and sedimentation control consistent with the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, as amended.
5. The Certificate Holder shall, prior to the commencement of operation, provide the Council worst-case modeling of electromagnetic radio frequency power densities of all proposed entities' antennas at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin No. 65, August 1997. The Certificate Holder shall provide a recalculated report of electromagnetic radio frequency power density if and when circumstances in operation cause a change in power density above the levels calculated and provided pursuant to this Decision and Order.
6. Upon the establishment of any new state or federal radio frequency standards applicable to frequencies of this facility, the facility granted herein shall be brought into compliance with such standards.

7. The Certificate Holder shall permit public or private entities to share space on the proposed tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing. Should the local municipality have a need to locate antennas on this tower, the Certificate Holder shall provide appropriate space on the tower with no lease charges.

8. If the facility does not initially provide wireless services within one year of completion of construction or ceases to provide wireless services for a period of one year, this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made.

9. Any antenna that becomes obsolete and ceases to function shall be removed within 60 days after such antennas become obsolete and cease to function.

10. Unless otherwise approved by the Council, this Decision and Order shall be void if the facility authorized herein is not operational within one year of the effective date of this Decision and Order or within one year after all appeals to this Decision and Order have been resolved.

Pursuant to General Statutes § 16-50p, we hereby direct that a copy of the Findings of Fact, Opinion, and Decision and Order be served on each person listed below, and notice of issuance shall be published in The Hartford Courant.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with Section 16-50j-17 of the Regulations of Connecticut State Agencies.

The parties and intervenors to this proceeding are:

Applicant

AT&T Wireless PCS, LLC
d/b/a AT&T Wireless

Its Representative

Christopher B. Fisher, Esq.
Cuddy & Feder & Worby LLP
90 Maple Avenue
White Plains, NY 10601
(914) 761-1300
(914) 761-6405 - fax



**SmartLink, LLC on behalf of
AT&T Mobility, LLC
Site FA – 10071108
Site ID – CT5822 (2C-3C)
USID – 27067
Site Name – Mansfield Four
Corners
Site Compliance Report**

**497 Middle Turnpike
Storrs Manfield, CT 06268**

Latitude: N41-49-21.69
Longitude: W472-17-10.68
Structure Type: Monopole

Report generated date: November 14, 2017
Report by: Jake Jordan
Customer Contact: Romina Kirchmaier

**AT&T Mobility, LLC will be compliant when the
remediation recommended in Section 5.2 or
other appropriate remediation is implemented.**

Sitesafe logo is a registered trademark of Site Safe, Inc. All rights reserved.



Table of Contents

1	GENERAL SITE SUMMARY	2
1.1	REPORT SUMMARY	2
2	SCALE MAPS OF SITE.....	3
3	ANTENNA INVENTORY	5
4	EMISSION PREDICTIONS	6
5	SITE COMPLIANCE	9
5.1	SITE COMPLIANCE STATEMENT	9
5.2	ACTIONS FOR SITE COMPLIANCE	9
6	REVIEWER CERTIFICATION	10
	APPENDIX A – STATEMENT OF LIMITING CONDITIONS	11
	APPENDIX B – REGULATORY BACKGROUND INFORMATION	12
	FCC RULES AND REGULATIONS	12
	OSHA STATEMENT.....	13
	APPENDIX C – SAFETY PLAN AND PROCEDURES.....	14
	APPENDIX D – RF EMISSIONS.....	15
	APPENDIX E – ASSUMPTIONS AND DEFINITIONS	16
	GENERAL MODEL ASSUMPTIONS	16
	USE OF GENERIC ANTENNAS	16
	DEFINITIONS	17
	APPENDIX F – REFERENCES	19

1 General Site Summary

1.1 Report Summary

AT&T Mobility, LLC	Summary
Access to Antennas Locked?	No
RF Sign(s) @ access point(s)	None
RF Sign(s) @ antennas	None
Barrier(s) @ sectors	None
Max cumulative simulated RFE level on the Rooftop	<1% General Public Limit
FCC & AT&T Compliant?	Will Be Compliant

The following documents were provided by the client and were utilized to create this report:

RFDS: NEW-ENGLAND_CONNECTICUT_CTL05822_2018-LTE-Multi-Carrier_LTE_sp656b_PTN_10071108_27067_06-26-2017_Final-Approved_v2.00

CD's: 10071108_AE201_171016_CTL05822_REV1



RF Powers Used: RFDS

2 Scale Maps of Site

The following diagrams are included:

-) Site Scale Map
-) Elevation View
-) AT&T Mobility, LLC Contribution

Site Scale Map: Mansfield Four Corners



www.sitesafe.com
Site Name: Mansfield Four Corners
11/14/2017 11:14:08 AM

AT&T MOBILITY LLC

VERIZON WIRELESS

T-MOBILE

SPRINT

UNKNOWN CARRIER

Caution 1

Caution 2

Notice 2

Notice 1

Warning

Info 1

Info 2

Carrier Identification

Sign Legend

Barrier

Proposed Barriers/
Signs

3 Antenna Inventory

The following antenna inventory on this and the following page, were obtained by the customer and were utilized to create the site model diagrams:

Ant ID	Operator	Antenna Make & Model	Type	TX Freq (MHz)	Az (Deg)	Hor BW (Deg)	Ant Len (ft)	Ant Gain (dBd)	2G GSM Radio(s)	3G UMTS Radio(s)	4G Radio(s)	Total ERP (Watts)	X	Y	Z
1	AT&T MOBILITY LLC	Powerwave 7770	Panel	850	0	82	4.6	11.51	0	1	0	401.5	36.9'	59.3'	119.7'
1	AT&T MOBILITY LLC	Powerwave 7770	Panel	1900	0	86	4.6	13.41	0	1	0	401.5	36.9'	59.3'	119.7'
2	AT&T MOBILITY LLC (Proposed)	CCI Antennas HPA-65R-BUU-H6	Panel	737	0	66.2	6	11.68	0	0	1	2951.4	45.6'	59.2'	119'
2	AT&T MOBILITY LLC (Proposed)	CCI Antennas HPA-65R-BUU-H6	Panel	1900	0	61.1	6	14.53	0	0	1	4842.1	45.6'	59.2'	119'
3	AT&T MOBILITY LLC	KMW AM-X-CD-16-65-00T	Panel	737	0	65	6	13.36	0	0	1	1475.7	49.1'	58.8'	119'
4	AT&T MOBILITY LLC	Powerwave 7770	Panel	850	120	82	4.6	11.51	0	1	0	401.5	50.2'	56.7'	119.7'
4	AT&T MOBILITY LLC	Powerwave 7770	Panel	1900	120	86	4.6	13.41	0	1	0	401.5	50.2'	56.7'	119.7'
5	AT&T MOBILITY LLC (Proposed)	CCI Antennas HPA-65R-BUU-H6	Panel	737	120	66.2	6	11.68	0	0	1	2951.4	46.4'	50.1'	119'
5	AT&T MOBILITY LLC (Proposed)	CCI Antennas HPA-65R-BUU-H6	Panel	1900	120	61.1	6	14.53	0	0	1	4842.1	46.4'	50.1'	119'
6	AT&T MOBILITY LLC	KMW AM-X-CD-16-65-00T	Panel	737	120	65	6	13.36	0	0	1	1475.7	44.4'	46.2'	119'
7	AT&T MOBILITY LLC	Powerwave 7770	Panel	850	240	82	4.6	11.51	0	1	0	401.5	41.9'	46.3'	119.7'
7	AT&T MOBILITY LLC	Powerwave 7770	Panel	1900	240	86	4.6	13.41	0	1	0	401.5	41.9'	46.3'	119.7'
8	AT&T MOBILITY LLC (Proposed)	CCI Antennas HPA-65R-BUU-H6	Panel	737	240	66.2	6	11.68	0	0	1	2951.4	37.1'	54.1'	119'
8	AT&T MOBILITY LLC (Proposed)	CCI Antennas HPA-65R-BUU-H6	Panel	1900	240	61.1	6	14.53	0	0	1	4842.1	37.1'	54.1'	119'
9	AT&T MOBILITY LLC	KMW AM-X-CD-16-65-00T	Panel	737	240	65	6	13.36	0	0	1	1475.7	35.3'	57.2'	119'


NOTE: X, Y and Z indicate relative position of the bottom of the antenna to the origin location on the site, displayed in the model results diagram. Specifically, the Z reference indicates the bottom of the antenna height above the main site level unless otherwise indicated. The distance to the bottom of the antenna is calculated by subtracting half of the length of the antenna from the antenna centerline. Effective Radiated Power (ERP) is provided by the operator or based on Sitesafe experience. The values used in the modeling may be greater than are currently deployed. For other operators at this site the use of "Generic" as an antenna model or "Unknown" for a wireless operator means the information with regard to operator, their FCC license and/or antenna information was not available nor could it be secured while on site. Other operator's equipment, antenna models and powers used for modeling are based on obtained information or Sitesafe experience.

4 Emission Predictions


In the RF Exposure Simulations below all heights are reflected with respect to main site level. In most rooftop cases this is the height of the main rooftop and in other cases this can be ground level. Each different height area, rooftop, or platform level is labeled with its height relative to the main site level. Emissions are calculated appropriately based on the relative height and location of that area to all antennas.

The Antenna Inventory heights are referenced to the same level.

RF Exposure Simulation For: Mansfield Four Corners
Elevation View




% of FCC Public Exposure Limit
Spatial average 0' - 6'



(Feet)
0 10.4 20.7
www.sitesafe.com
Site Name: Mansfield Four Corners
11/10/2017 2:09:26 PM


SitesafeTC Version: 1.0.0.0 - 0.0.0.266
Sitesafe OET-65 Model
Near Field Boundary: 1.5 * Aperture
Reflection Factor: 1
Single Level (0)

RF Exposure Simulation For: Mansfield Four Corners AT&T Mobility, LCC Contribution



% of FCC Public Exposure Limit
Spatial average 0' - 6'

(Feet)
0 5.5 10.9
www.sitesafe.com
Site Name: Mansfield Four Corners
11/10/2017 1:57:38 PM



SitesafeTC Version: 1.0.0.0 - 0.0.0.266
Sitesafe OET-65 Model
Near Field Boundary: 1.5 * Aperture
Reflection Factor: 1
Single Level (0)

5 Site Compliance

5.1 Site Compliance Statement

Upon evaluation of the cumulative RF emission levels from all operators at this site, RF hazard signage and antenna locations, Sitesafe has determined that:

AT&T Mobility, LLC will be compliant when the remediation recommended in Section 5.2 or other appropriate remediation is implemented.

Based on measurement or predictions, other wireless operators on this site may be out of RF exposure compliance with FCC regulations on this site. We recommend that those operators review this site with respect to RF exposure compliance.

The compliance determination is based on General Public RFE levels derived from theoretical modeling, RF signage placement, proposed antenna inventory and the level of restricted access to the antennas at the site. Any deviation from the AT&T Mobility, LLC's proposed deployment plan could result in the site being rendered non-compliant.

Modeling is used for determining compliance and the percentage of MPE contribution.

5.2 Actions for Site Compliance

Based on FCC regulations, common industry practice, and our understanding of AT&T Mobility, LLC RF Safety Policy requirements, this section provides a statement of recommendations for site compliance. Recommendations have been proposed based on our understanding of existing access restrictions, signage, and an analysis of predicted RFE levels.

AT&T Mobility, LLC will be made compliant if the following changes are implemented:

Site Access Location

-) Ensure site access is locked.
-) Yellow caution 2 sign required.

Site Gate Location

-) Information 1 sign required.

6 Reviewer Certification

The reviewer whose signature appears below hereby certifies and affirms:

That I am an employee of Sitesafe, Inc., in Arlington, Virginia, at which place the staff and I provide RF compliance services to clients in the wireless communications industry; and

That I am thoroughly familiar with the Rules and Regulations of the Federal Communications Commission (FCC) as well as the regulations of the Occupational Safety and Health Administration (OSHA), both in general and specifically as they apply to the FCC Guidelines for Human Exposure to Radio-frequency Radiation; and

That I have thoroughly reviewed this Site Compliance Report and believe it to be true and accurate to the best of my knowledge as assembled by and attested to by Jake Jordan.

November 10, 2017

Appendix A – Statement of Limiting Conditions

Sitesafe has provided computer generated model(s) in this Site Compliance Report to show approximate dimensions of the site, and the model is included to assist the reader of the compliance report to visualize the site area, and to provide supporting documentation for Sitesafe's recommendations.

Sitesafe may note in the Site Compliance Report any adverse physical conditions, such as needed repairs, that Sitesafe became aware of during the normal research involved in creating this report. Sitesafe will not be responsible for any such conditions that do exist or for any engineering or testing that might be required to discover whether such conditions exist. Because Sitesafe is not an expert in the field of mechanical engineering or building maintenance, the Site Compliance Report must not be considered a structural or physical engineering report.

Sitesafe obtained information used in this Site Compliance Report from sources that Sitesafe considers reliable and believes them to be true and correct. Sitesafe does not assume any responsibility for the accuracy of such items that were furnished by other parties. When conflicts in information occur between data collected by Sitesafe provided by a second party and data collected by Sitesafe, the data will be used.

Appendix B – Regulatory Background Information

FCC Rules and Regulations

In 1996, the Federal Communication Commission (FCC) adopted regulations for the evaluating of the effects of RF emissions in 47 CFR § 1.1307 and 1.1310. The guideline from the FCC Office of Engineering and Technology is Bulletin 65 ("OET Bulletin 65"), *Evaluating Compliance with FCC Guidelines for Human Exposure to Radio Frequency Electromagnetic Fields*, Edition 97-01, published August 1997. Since 1996 the FCC periodically reviews these rules and regulations as per their congressional mandate.

FCC regulations define two separate tiers of exposure limits: Occupational or "Controlled environment" and General Public or "Uncontrolled environment". The General Public limits are generally five times more conservative or restrictive than the Occupational limit. These limits apply to accessible areas where workers or the general public may be exposed to Radio Frequency (RF) electromagnetic fields.


Occupational or Controlled limits apply in situations in which persons are exposed as a consequence of their employment and where those persons exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.

An area is considered a Controlled environment when access is limited to these aware personnel. Typical criteria are restricted access (i.e. locked or alarmed doors, barriers, etc.) to the areas where antennas are located coupled with proper RF warning signage. A site with Controlled environments is evaluated with Occupational limits.

All other areas are considered Uncontrolled environments. If a site has no access controls or no RF warning signage it is evaluated with General Public limits.

The theoretical modeling of the RF electromagnetic fields has been performed in accordance with OET Bulletin 65. The Maximum Permissible Exposure (MPE) limits utilized in this analysis are outlined in the following diagram:

FCC Limits for Maximum Permissible Exposure (MPE)
Plane-wave Equivalent Power Density



Limits for Occupational/Controlled Exposure (MPE)

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (H) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842/f	4.89/f	(900/f ²)*	6
30-300	61.4	0.163	1.0	6
300-1500	--	--	f/300	6
1500-100,000	--	--	5	6

Limits for General Population/Uncontrolled Exposure (MPE)

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (H) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f ²)*	30
30-300	27.5	0.073	0.2	30
300-1500	--	--	f/1500	30
1500-100,000	--	--	1.0	30

f = frequency in MHz

*Plane-wave equivalent power density

OSHA Statement

The General Duty clause of the OSHA Act (Section 5) outlines the occupational safety and health responsibilities of the employer and employee. The General Duty clause in Section 5 states:

(a) Each employer –

- (1) shall furnish to each of his employees employment and a place of employment which are free from recognized hazards that are causing or are likely to cause death or serious physical harm to his employees;
- (2) shall comply with occupational safety and health standards promulgated under this Act.

(b) Each employee shall comply with occupational safety and health standards and all rules, regulations, and orders issued pursuant to this Act which are applicable to his own actions and conduct.

OSHA has defined Radiofrequency and Microwave Radiation safety standards for workers who may enter hazardous RF areas. Regulation Standards 29 CFR § 1910.147 identify a generic Lock Out Tag Out procedure aimed to control the unexpected energization or start up of machines when maintenance or service is being performed.

Appendix C – Safety Plan and Procedures

The following items are general safety recommendations that should be administered on a site by site basis as needed by the carrier.

General Maintenance Work: Any maintenance personnel required to work immediately in front of antennas and / or in areas indicated as above 100% of the Occupational MPE limits should coordinate with the wireless operators to disable transmitters during their work activities.

Training and Qualification Verification: All personnel accessing areas indicated as exceeding the General Population MPE limits should have a basic understanding of EME awareness and RF Safety procedures when working around transmitting antennas. Awareness training increases a workers understanding to potential RF exposure scenarios. Awareness can be achieved in a number of ways (e.g. videos, formal classroom lecture or internet based courses).

Physical Access Control: Access restrictions to transmitting antennas locations is the primary element in a site safety plan. Examples of access restrictions are as follows:

-) Locked door or gate
-) Alarmed door
-) Locked ladder access
-) Restrictive Barrier at antenna (e.g. Chain link with posted RF Sign)

RF Signage: Everyone should obey all posted signs at all times. RF signs play an important role in properly warning a worker prior to entering into a potential RF Exposure area.

Assume all antennas are active: Due to the nature of telecommunications transmissions, an antenna transmits intermittently. Always assume an antenna is transmitting. Never stop in front of an antenna. If you have to pass by an antenna, move through as quickly and safely as possible thereby reducing any exposure to a minimum.

Maintain a 3 foot clearance from all antennas: There is a direct correlation between the strength of an EME field and the distance from the transmitting antenna. The further away from an antenna, the lower the corresponding EME field is.

Site RF Emissions Diagram: Section 4 of this report contains an RF Diagram that outlines various theoretical Maximum Permissible Exposure (MPE) areas at the site. The modeling is a worst case scenario assuming a duty cycle of 100% for each transmitting antenna at full power. This analysis is based on one of two access control criteria: General Public criteria means the access to the site is uncontrolled and anyone can gain access. Occupational criteria means the access is restricted and only properly trained individuals can gain access to the antenna locations.

Appendix D – RF Emissions

The RF Emissions Simulation(s) in this report display theoretical spatially averaged percentage of the Maximum Permissible Exposure for all systems at the site unless otherwise noted. These diagrams use modeling as prescribed in OET Bulletin 65 and assumptions detailed in Appendix E.

The key at the bottom of each RF Emissions Simulation indicates percentages displayed referenced to FCC General Public Maximum Permissible Exposure (MPE) limits. Color coding on the diagram is as follows:

- J Areas indicated as Gray are predicted to be below 5% of the MPE limits. **Gray represents areas more than 20 times below the most conservative exposure limit.**
- J Green represents areas are predicted to be between 5% and 100% of the MPE limits. **Green areas are accessible to anyone.**
- J Blue represents areas predicted to exceed the General Public MPE limits but are less than Occupational limits. **Blue areas should be accessible only to RF trained workers.**
- J Yellow represents areas predicted to exceed Occupational MPE limits. **Yellow areas should be accessible only to RF trained workers able to assess current exposure levels.**
- J Red represents areas predicted to have exposure more than 10 times the Occupational MPE limits. **Red indicates that the RF levels must be reduced prior to access.** An RF Safety Plan is required which outlines how to reduce the RF energy in these areas prior to access.

Appendix E – Assumptions and Definitions

General Model Assumptions

In this site compliance report, it is assumed that all antennas are operating at **full power at all times**. Software modeling was performed for all transmitting antennas located on the site. Sitesafe has further assumed a 100% duty cycle and maximum radiated power.

The modeling is based on recommendations from the FCC's OET-65 bulletin with the following variances per AT&T guidance. Reflection has not been considered in the modeling, i.e. the reflection factor is 1.0. The near / far field boundary has been set to 1.5 times the aperture height of the antenna and modeling beyond that point is the lesser of the near field cylindrical model and the far field model taking into account the gain of the antenna.

The site has been modeled with these assumptions to show the maximum RF energy density. Areas modeled with exposure greater than 100% of the General Public MPE level may not actually occur, but are shown as a prediction that could be realized. Sitesafe believes these areas to be safe for entry by occupationally trained personnel utilizing appropriate personal protective equipment (in most cases, a personal monitor).

Use of Generic Antennas

For the purposes of this report, the use of "Generic" as an antenna model, or "Unknown" for an operator means the information about a carrier, their FCC license and/or antenna information was not provided and could not be obtained while on site. In the event of unknown information, Sitesafe will use our industry specific knowledge of equipment, antenna models, and transmit power to model the site. If more specific information can be obtained for the unknown measurement criteria, Sitesafe recommends remodeling of the site utilizing the more complete and accurate data. Information about similar facilities is used when the service is identified and associated with a particular antenna. If no information is available regarding the transmitting service associated with an unidentified antenna, using the antenna manufacturer's published data regarding the antenna's physical characteristics makes more conservative assumptions.

Where the frequency is unknown, Sitesafe uses the closest frequency in the antenna's range that corresponds to the highest Maximum Permissible Exposure (MPE), resulting in a conservative analysis.

Definitions

5% Rule – The rules adopted by the FCC specify that, in general, at multiple transmitter sites actions necessary to bring the area into compliance with the guidelines are the shared responsibility of all licensees whose transmitters produce field strengths or power density levels at the area in question in excess of 5% of the exposure limits. In other words, any wireless operator that contributes 5% or greater of the MPE limit in an area that is identified to be greater than 100% of the MPE limit is responsible taking corrective actions to bring the site into compliance.

Compliance – The determination of whether a site is safe or not with regards to Human Exposure to Radio Frequency Radiation from transmitting antennas.

Decibel (dB) – A unit for measuring power or strength of a signal.

Duty Cycle – The percent of pulse duration to the pulse period of a periodic pulse train. Also, may be a measure of the temporal transmission characteristic of an intermittently transmitting RF source such as a paging antenna by dividing average transmission duration by the average period for transmission. A duty cycle of 100% corresponds to continuous operation.

Effective (or Equivalent) Isotropic Radiated Power (EIRP) – The product of the power supplied to the antenna and the antenna gain in a given direction relative to an isotropic antenna.

Effective Radiated Power (ERP) – In a given direction, the relative gain of a transmitting antenna with respect to the maximum directivity of a half wave dipole multiplied by the net power accepted by the antenna from the connecting transmitter.

Gain (of an antenna) – The ratio of the maximum intensity in a given direction to the maximum radiation in the same direction from an isotropic radiator. Gain is a measure of the relative efficiency of a directional antennas as compared to an omni directional antenna.

General Population/Uncontrolled Environment – Defined by the FCC, as an area where exposure to RF energy may occur to persons who are **unaware** of the potential for exposure and who have no control of their exposure. General Population is also referenced as General Public.

Generic Antenna – For the purposes of this report, the use of "Generic" as an antenna model means the antenna information was not provided and could not be obtained while on site. In the event of unknown information, Sitesafe will use our industry specific knowledge of antenna models to select a worst case scenario antenna to model the site.

Isotropic Antenna – An antenna that is completely non-directional. In other words, an antenna that radiates energy equally in all directions.

Maximum Measurement – This measurement represents the single largest measurement recorded when performing a spatial average measurement.

Maximum Permissible Exposure (MPE) – The maximum levels of RF exposure a person may be exposed to without harmful effect and with acceptable safety factor.

Occupational/Controlled Environment – Defined by the FCC, as an area where Radio Frequency Radiation (RFR) exposure may occur to persons who are **aware** of the

potential for exposure as a condition of employment or specific activity and can exercise control over their exposure.

OET Bulletin 65 – Technical guideline developed by the FCC's Office of Engineering and Technology to determine the impact of Radio Frequency radiation on Humans. The guideline was published in August 1997.

OSHA (Occupational Safety and Health Administration) – Under the Occupational Safety and Health Act of 1970, employers are responsible for providing a safe and healthy workplace for their employees. OSHA's role is to promote the safety and health of America's working men and women by setting and enforcing standards; providing training, outreach and education; establishing partnerships; and encouraging continual process improvement in workplace safety and health. For more information, visit www.osha.gov.

Radio Frequency (RF) – The frequencies of electromagnetic waves which are used for radio communications. Approximately 3 kHz to 300 GHz.

Radio Frequency Exposure (RFE) – The amount of RF power density that a person is or might be exposed to.

Spatial Average Measurement – A technique used to average a minimum of ten (10) measurements taken in a ten (10) second interval from zero (0) to six (6) feet. This measurement is intended to model the average power density an average sized human will be exposed to at a location.

Transmitter Power Output (TPO) – The radio frequency output power of a transmitter's final radio frequency stage as measured at the output terminal while connected to a load.

Appendix F – References

The following references can be followed for further information about RF Health and Safety.

Sitesafe, Inc.

<http://www.sitesafe.com>

FCC Radio Frequency Safety

<http://www.fcc.gov/encyclopedia/radio-frequency-safety>

National Council on Radiation Protection and Measurements (NCRP)

<http://www.ncrponline.org>

Institute of Electrical and Electronics Engineers, Inc., (IEEE)

<http://www.ieee.org>

American National Standards Institute (ANSI)

<http://www.ansi.org>

Environmental Protection Agency (EPA)

<http://www.epa.gov/radtown/wireless-tech.html>

National Institutes of Health (NIH)

<http://www.niehs.nih.gov/health/topics/agents/emf/>

Occupational Safety and Health Agency (OSHA)

<http://www.osha.gov/SLTC/radiofrequencyradiation/>

International Commission on Non-Ionizing Radiation Protection (ICNIRP)

<http://www.icnirp.org>

World Health Organization (WHO)

<http://www.who.int/peh-emf/en/>

National Cancer Institute

<http://www.cancer.gov/cancertopics/factsheet/Risk/cellphones>

American Cancer Society (ACS)

http://www.cancer.org/docroot/PED/content/PED_1_3X_Cellular_Phone_Towers.asp?sitearea=PED

European Commission Scientific Committee on Emerging and Newly Identified Health Risks

http://ec.europa.eu/health/ph_risk/committees/04_scenihp/docs/scenihp_o_022.pdf

Fairfax County, Virginia Public School Survey

<http://www.fcps.edu/fts/safety-security/RFEESurvey/>

UK Health Protection Agency Advisory Group on Non-ionising Radiation

http://www.hpa.org.uk/webw/HPAweb&HPAwebStandard/HPAweb_C/1317133826368

Norwegian Institute of Public Health

<http://www.fhi.no/dokumenter/545eea7147.pdf>

StartAntennaData It is advisable to provide an ID (ant 1) for all antennas

		(MHz)	Trans	Trans	Coax	Coax	Other	Input	Calc			(ft)	(ft)	(ft)		(ft)	dBd	BWdth	Uptime	ON
ID	Name	Freq	Power	Count	Len	Type	Losses	Power	Power	Mfg	Model	X	Y	Z	Type	Aper	Gain	Pt Dir	Profile	flag
1	AT&T MOB	850	28.35794		1	0		28.35794		Powerwav	7770		36.88	59.34	119.7085	Panel	4.583	11.51 82;0	100%	ON•
1	AT&T MOB	1900	18.30943		1	0		18.30943		Powerwav	7770		36.88	59.34	119.7085	Panel	4.583	13.41 86;0	100%	ON•
2	AT&T MOB	737	200.4608		1	0		200.4608		CCI Antenn	HPA-65R-B		45.63	59.22	119	Panel	6	11.68 66.2;0	100%	ON•
2	AT&T MOB	1900	170.6201		1	0		170.6201		CCI Antenn	HPA-65R-B		45.63	59.22	119	Panel	6	14.53 61.1;0	100%	ON•
3	AT&T MOB	737	68.07696		1	0		68.07696		KMW	AM-X-CD-1		49.13	58.84	119	Panel	6	13.36 65;0	100%	ON•
4	AT&T MOB	850	28.35794		1	0		28.35794		Powerwav	7770		50.15	56.65	119.7085	Panel	4.583	11.51 82;120	100%	ON•
4	AT&T MOB	1900	18.30943		1	0		18.30943		Powerwav	7770		50.15	56.65	119.7085	Panel	4.583	13.41 86;120	100%	ON•
5	AT&T MOB	737	200.4608		1	0		200.4608		CCI Antenn	HPA-65R-B		46.38	50.09	119	Panel	6	11.68 66.2;120	100%	ON•
5	AT&T MOB	1900	170.6201		1	0		170.6201		CCI Antenn	HPA-65R-B		46.38	50.09	119	Panel	6	14.53 61.1;120	100%	ON•
6	AT&T MOB	737	68.07696		1	0		68.07696		KMW	AM-X-CD-1		44.38	46.22	119	Panel	6	13.36 65;120	100%	ON•
7	AT&T MOB	850	28.35794		1	0		28.35794		Powerwav	7770		41.88	46.34	119.7085	Panel	4.583	11.51 82;240	100%	ON•
7	AT&T MOB	1900	18.30943		1	0		18.30943		Powerwav	7770		41.88	46.34	119.7085	Panel	4.583	13.41 86;240	100%	ON•
8	AT&T MOB	737	200.4608		1	0		200.4608		CCI Antenn	HPA-65R-B		37.11	54.11	119	Panel	6	11.68 66.2;240	100%	ON•
8	AT&T MOB	1900	170.6201		1	0		170.6201		CCI Antenn	HPA-65R-B		37.11	54.11	119	Panel	6	14.53 61.1;240	100%	ON•
9	AT&T MOB	737	68.07696		1	0		68.07696		KMW	AM-X-CD-1		35.25	57.24	119	Panel	6	13.36 65;240	100%	ON•

StartSymbolData


Property Location: 497 MIDDLE TPKE										MAP ID: 8/ 14/ 19/ /										Bldg Name:										State Use: 201																			
Vision ID: 5973										Account # 8 14 19										Bldg #: 1 of 2										Sec #: 1 of 1 Card 1 of 2										Print Date: 05/10/2016 09:08									
CURRENT OWNER										TOPO.		UTILITIES		STRT./ROAD		LOCATION		CURRENT ASSESSMENT										6078 MANSFIELD, CT <																					

CONSTRUCTION DETAIL				CONSTRUCTION DETAIL (CONTINUED)			
Element	Cd.	Ch.	Description	Element	Cd.	Ch.	Description
Style	19		Store				
Model	94		Comm/Ind				
Grade	04		D				
Stories	2						
Occupancy	2			MIXED USE			
Exterior Wall 1	17		Stucco on Mas.	Code	Description		Percentage
Exterior Wall 2				201	Commercial Improv		100
Roof Structure	03		Gable				
Roof Cover	03		Asphalt Shingl				
Interior Wall 1	05		Drywall				
Interior Wall 2				COST/MARKET VALUATION			
Interior Floor 1	14		Carpet	Adj. Base Rate:			74.55
Interior Floor 2							
Heating Fuel	03		Gas				
Heating Type	05		Hot Water	AYB			1928
AC Type	04		Unit/AC				
Bldg Use	201		Commercial Improv	Dep Code			F
				Remodel Rating			
				Year Remodeled			
				Dep %			47
				Functional ObsInc			10
				External ObsInc			
				Cost Trend Factor			1
Heat/AC	02		HEAT/AC SPLIT	Condition			
Frame Type	03		MASONRY	% Complete			
Baths/Plumbing	02		AVERAGE	Overall % Cond			43
Ceiling/Wall	06		CEIL & WALLS	Apprais Val			118,200
Rooms/Prtns	02		AVERAGE	Dep % Ovr			0
Wall Height	10			Dep Ovr Comment			
				Misc Imp Ovr			0
				Misc Imp Ovr Comment			
				Cost to Cure Ovr			0
				Cost to Cure Ovr Comment			

OB-OUTBUILDING & YARD ITEMS(L) / XF-BUILDING EXTRA FEATURES(B)												
Code	Description	Sub	Sub Descript	L/B	Units	Unit Price	Yr	Gde	Dp Rt	Cnd	%Cnd	Apr Value
PAV1 FGR1	Paving Garage			L	9,000	1.80	1980			F	50	8,100
				L	1,024	25.00	1997	C	A	70	17,900	

BUILDING SUB-AREA SUMMARY SECTION						
<i>Code</i>	<i>Description</i>	<i>Living Area</i>	<i>Gross Area</i>	<i>Eff. Area</i>	<i>Unit Cost</i>	<i>Undeprec. Value</i>
BAS	First Floor	1,836	1,836		74.55	136,865
BSM	Basement	0	1,292		14.89	19,233
FUS	Finished Upper Story	1,292	1,292		74.55	96,312
STP	Stoop	0	48		7.77	373
UEP	Utility Enclosed Porch	0	48		37.27	1,789
UST	Utility Storage	0	912		22.40	20,425

<i>Ttl. Gross Liv/Lease Area:</i>		3,128	5,428		



Property Location: 497 MIDDLE TPKE
Vision ID: 5973

Account # 8 14 19

MAP ID: 8/ 14/ 19/ /

Bldg #: 2 of 2

Bldg Name:

Sec #: 1 of 1

Card 2 of 2

State Use: 201

Print Date: 05/10/2016 09:08

CURRENT OWNER		TOPO.		UTILITIES		STRT./ROAD		LOCATION		CURRENT ASSESSMENT				6078 MANSFIELD, CT VISION			
BRODIN ANN TRUSTEE OF THE BERNARD R BRODIN REVOCABLE TR 106 COLEMAN RD MANCHESTER, CT 06040 Additional Owners:		1	Level	1	Well	1	Paved	2	Suburban	Description	Code	Appraised Value	Assessed Value				
		4	Rolling	2	Septic			4	Bus. District	Com Land	2-1	444,700	311,300				
										Com Bldg	2-2	338,200	236,700				
										Com OB	2-5	253,500	177,500				
										Ind Land	3-1	153,000	107,100				
SUPPLEMENTAL DATA																	
Other ID: Census 8813 Devel. Lot#																	
GIS ID: 8.14.19										ASSOC PID#							
										Total				1,189,400		832,600	

RECORD OF OWNERSHIP		BK-VOL/PAGE		SALE DATE		q/u	v/i	SALE PRICE		V.C.	PREVIOUS ASSESSMENTS (HISTORY)											
BRODIN ANN TRUSTEE OF THE BRODIN ANN TRUSTEE OF THE BRODIN BERNARD R EST OF		763/ 988		05/14/2014		U	I	58,000		01 00	Yr.	Code	Assessed Value		Yr.	Code	Assessed Value		Yr.	Code	Assessed Value	
		757/ 131		09/06/2013		U	I				2015	2-1	311,300		2014	2-1	311,300		2014	2-1	311,300	
		699/ 309		12/21/2010		U	V				2015	2-2	236,700		2014	2-2	236,700		2014	2-2	236,700	
		185/ 259		12/12/1980		U	I				2015	2-5	177,500		2014	2-5	177,500		2014	2-5	177,500	
													2015	3-1	107,100		2014	3-1	107,100		2014	3-1
											Total:		832,600		Total:		832,600		Total:		832,600	

EXEMPTIONS				OTHER ASSESSMENTS				This signature acknowledges a visit by a Data Collector or Assessor				
Year	Type	Description	Amount	Code	Description	Number	Amount					Comm. Int.
Total:												

ASSESSING NEIGHBORHOOD					APPRAISED VALUE SUMMARY								
NBHD/ SUB		NBHD Name		Street Index Name					Tracing		Batch		
0001/A													

NOTES					APPRAISED VALUE SUMMARY							
1995-9 HOLE GOLF COURSE												
11/26/2003-PAR3 GOLF CL&P ESMT V532 P135												
BP#03-04-328TELECOM TOWER AT&T30YR LEASE												
04/14/2004-CO RESTAUR-FANATIC EXPERIENCE												
01/10/2008-CO(BP#07-08-377)CELL ANTENNAE					Total Appraised Parcel Value				1,189,400			
&SHED 08/12/2010-CO(BP#10-11-053)REMODEL									Valuation Method:			
					Adjustment:				0			
					Net Total Appraised Parcel Value				1,189,400			

BUILDING PERMIT RECORD									VISIT/ CHANGE HISTORY								
Permit ID	Issue Date	Type	Description	Amount	Insp. Date	% Comp.	Date Comp.	Comments	Date	Type	IS	ID	Cd.	Purpose/Result			
									09/06/2014			RH	01	Measured			
									06/21/2011			IL	16	Appraiser Date			
									01/20/2000			BM	15	Collector Date			

LAND LINE VALUATION SECTION																			
B #	Use Code	Use Description	Zone	D	Front	Depth	Units	Unit Price	I. Factor	S.A.	Acre Disc	C. Factor	ST. Idx	Adj.	Notes- Adj	Special Pricing	S Adj Fact	Adj. Unit Price	Land Value
2	201	Commercial Improv					0 SF	0.00	1.0000		1.0000	1.00		0.00			.00	0.00	0

Total Card Land Units:			0.00 AC		Parcel Total Land Area:			30.88 AC			Total Land Value:			0	
------------------------	--	--	---------	--	-------------------------	--	--	----------	--	--	-------------------	--	--	---	--

CONSTRUCTION DETAIL				CONSTRUCTION DETAIL (CONTINUED)			
Element	Cd.	Ch.	Description	Element	Cd.	Ch.	Description
Style	19		Store				
Model	94		Comm/Ind				
Grade	06		C-				
Stories	1						
Occupancy	1						
Exterior Wall 1	25		Vinyl				
Exterior Wall 2							
Roof Structure	03		Gable				
Roof Cover	03		Asphalt Shingl				
Interior Wall 1	05		Drywall				
Interior Wall 2							
Interior Floor 1	14		Carpet				
Interior Floor 2							
Heating Fuel	02		Oil				
Heating Type	04		Forced Air				
AC Type	03		Central				
Bldg Use	201		Commercial Improv				
Heat/AC	01		HEAT/AC PKGS				
Frame Type	02		WOOD FRAME				
Baths/Plumbing	02		AVERAGE				
Ceiling/Wall	06		CEIL & WALLS				
Rooms/Prtns	02		AVERAGE				
Wall Height	10						

OB-OUTBUILDING & YARD ITEMS(L) / XF-BUILDING EXTRA FEATURES(B)												
Code	Description	Sub	Sub Descript	L/B	Units	Unit Price	Yr	Gde	Dp Rt	Cnd	%Cnd	Apr Value
SHD1	Shed			L	80	12.00	1996	C		A	70	700
GLF2	Golf Course Fai			L	9	40,000.00	1996	D		A	70	226,800

BUILDING SUB-AREA SUMMARY SECTION							
Code	Description	Living Area	Gross Area	Eff. Area	Unit Cost	Undeprec. Value	
BAS	First Floor	3,200	3,200		81.78	261,702	
FOP	Framed Open Porch	0	1,176		20.45	24,044	
Ttl. Gross Liv/Lease Area:		3,200	4,376				

	FOP	58	
	12		
		46	
BAS	BAS		52
	40		4040
34		46	12



Date: October 19, 2017

Marianne Dunst
Crown Castle
3530 Toringdon Way, Suite 300
Charlotte, NC 28277



Crown Castle
2000 Corporate Drive
Canonsburg, PA 15317
(724) 416-2000

Subject: Structural Analysis Report

Carrier Designation: AT&T Mobility Co-Locate
Carrier Site Number: CTL05822
Carrier Site Name: Mansfield - Four Corners

Crown Castle Designation: Crown Castle BU Number: 842867
Crown Castle Site Name: MANSFIELD FOUR CORNERS
Crown Castle JDE Job Number: 466595
Crown Castle Work Order Number: 1474958
Crown Castle Application Number: 411405 Rev. 1

Engineering Firm Designation: Crown Castle Project Number: 1474958

Site Data: 497 MIDDLE TURNPIKE, STORRS MANSFIELD, Tolland County, CT
Latitude 41° 49' 32.81", Longitude -72° 16' 54.46"
120 Foot - Monopole Tower

Dear Marianne Dunst,

Crown Castle is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 1474958, in accordance with application 411405, revision 1.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC5: Existing + Proposed Equipment

Note: See Table I and Table II for the proposed and existing loading, respectively.

Sufficient Capacity

This analysis has been performed in accordance with the 2016 Connecticut State Building Code based upon an ultimate 3-second gust wind speed of 130 mph converted to a nominal 3-second gust wind speed of 101 mph per Section 1609.3 and Appendix N as required for use in the TIA-222-G Standard per Exception #5 of Section 1609.1.1. Exposure Category B and Risk Category II were used in this analysis.

All equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at Crown Castle appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects, please give us a call.

Structural analysis prepared by: Cindy Dostatni / RTC

Respectfully submitted by:

Maham Barimani, P.E.
Senior Project Engineer

A handwritten signature in blue ink, appearing to read 'Barimani', written over the circular professional engineer seal.




TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 - Tower Component Stresses vs. Capacity - LC5

4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 120 ft Monopole tower designed by Pennsummit Tubular, LLC in November of 2003. The tower was originally designed for a wind speed of 85 mph per TIA/EIA-222-F.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA-222-G Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a 3-second gust wind speed of 101 mph with no ice, 50 mph with 1-inch ice thickness and 60 mph under service loads, exposure category B.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
120.0	122.0	2	cci antennas	HPA-65R-BUU-H6 w/ Mount Pipe	2 1	7/8 3/8	-
		1	cci antennas	HPA-65R-BUU-H8 w/ Mount Pipe			
		3	ericsson	RRUS 32 B2			
		3	kathrein	78211056			
		6	powerwave technologies	7020.00			
		6	powerwave technologies	LGP 17201			

Table 2 - Existing Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
120.0	123.0	3	ericsson	RRUS 11	2 1 1	7/8 1/2 conduit	2
		3	powerwave technologies	7770.00 w/ Mount Pipe			
		6	powerwave technologies	LGP21401			
		6	powerwave technologies	LGP21903			
	122.0	1	andrew	SBNH-1D6565C w/ Mount Pipe	12	1-1/4	1
		3	ericsson	RRUS 11			
		2	kmw communications	AM-X-CD-16-65-00T-RET w/ Mount Pipe			
		3	powerwave technologies	7770.00 w/ Mount Pipe			
		1	raycap	DC6-48-60-18-8F			
	120.0	1	tower mounts	Platform Mount [LP 303-1]			
109.0	109.0	3	alcatel lucent	RRH 2x40-700 W/SOLAR	19	1-5/8	1
		3	alcatel lucent	RRH2X60-1900			
		3	alcatel lucent	RRH2X60-AWS			
		6	commscope	HBXX-6517DS-A2M w/ Mount Pipe			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
		1	commscope	LNx-4514DS-A1M w/ Mount Pipe			
		2	commscope	LNx-6514DS-A1M w/ Mount Pipe			
		3	commscope	LNx-8513DS-VTM w/ Mount Pipe			
		2	rfs celwave	DB-T1-6Z-8AB-0Z			
		1	tower mounts	Platform Mount [LP 303-1]			

Notes:

- 1) Existing equipment
- 2) Equipment to be removed; not considered in this analysis

Table 3 - Design Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
119.5	119.5	6	powerwave technologies	7920	-	-
110.0	110.0	6	generic	1x4 Panel		
100.0	100.0	6	generic	1x4 Panel		
90.0	90.0	6	generic	1x4 Panel		
80.0	80.0	3	generic	1x4 Panel		
70.0	70.0	3	generic	1x4 Panel		

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

Document	Remarks	Reference	Source
4-GEOTECHNICAL REPORTS	VN Engineers, Inc.	4713232	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	PennSummit Tubular, LLC	4858941	CCISITES
4-TOWER MANUFACTURER DRAWINGS	PennSummit Tubular, LLC	5214860	CCISITES

3.1) Analysis Method

tnxTower (version 7.0.5.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	120 - 70.75	Pole	TP32.28x18x0.1875	1	-9.55	1145.06	66.0	Pass
L2	70.75 - 34.75	Pole	TP42.35x30.7452x0.3125	2	-16.24	2764.08	42.4	Pass
L3	34.75 - 0	Pole	TP51.8x40.2019x0.375	3	-27.60	4124.76	38.1	Pass
							Summary	
						Pole (L1)	66.0	Pass
						Rating =	66.0	Pass

Table 6 - Tower Component Stresses vs. Capacity - LC5

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	33.4	Pass
1	Base Plate	0	29.4	Pass
1	Base Foundation Structure	0	34.7	Pass
1	Base Foundation Soil Interaction	0	49.4	Pass

Structure Rating (max from all components) =	66%
---	------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations

The tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.



PROJECT:	LTE 2C / 3C
SITE NUMBER:	CTL05822
FA NUMBER:	10071108
PTN NUMBER:	2051A0DB5N / 2051A0DB6B
PACE NUMBER:	MRCTB025472 / MRCTB025566
CROWN BU#:	842867
SITE NAME:	MANSFIELDS FOUR CORNERS
SITE ADDRESS:	497 MIDDLE TURNPIKE STORRS MANSFIELD, CT



1100 E. WOODFIELD ROAD, SUITE 500
SCHAUMBURG, ILLINOIS 60173
TEL: 847-908-8400
COA# PEC.0001444
www.FullertonEngineering.com

REV	DATE	DESCRIPTION	B'Y
0	09/23/17	90% REVIEW	EE
1	10/16/17	FOR PERMIT	EE

I HEREBY CERTIFY THAT THESE DRAWINGS WERE
PREPARED BY ME OR UNDER MY DIRECT
SUPERVISION AND CONTROL, AND TO THE BEST
OF MY KNOWLEDGE AND BELIEF COMPLY WITH
THE REQUIREMENTS OF ALL APPLICABLE CODES

- FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION.
- ADA ACCESS REQUIREMENTS ARE NOT REQUIRED.
- THIS FACILITY DOES NOT REQUIRE POTABLE WATER AND WILL NOT PRODUCE ANY SEWAGE

PROJECT INFORMATION

<u>SITE NAME:</u>	MANSFIELD FOUR CORNERS
<u>SITE NUMBER:</u>	CTL05822
<u>SITE ADDRESS:</u>	497 MIDDLE TURNPIKE STORRS MANSFIELD, CT 10071108
<u>FA NUMBER:</u>	2051A0DB5N / 2051A0DB6B
<u>PACE NUMBER:</u>	MRCTB025472 / MRCTB025566
<u>USID NUMBER:</u>	27067
<u>CROWN BU#:</u>	842867
<u>APPLICANT:</u>	AT&T WIRELESS 550 COCHITUATE ROAD SUITE 550 13 AND 14 FRAMINGHAM, MA 01701
<u>TOWER OWNER:</u>	CROWN CASTLE INTERNATIONAL 12 GILL STREET, SUITE 5800 WOBURN, MA 01801
<u>JURISDICTION:</u>	TOLLAND COUNTY
<u>COUNTY:</u>	TOLLAND
<u>SITE COORDINATES FROM</u>	(RFDS)
<u>LATITUDE:</u>	41.8254°
<u>LONGITUDE:</u>	-72.2816°
<u>GROUND ELEV.:</u>	623'
<u>PROPOSED USE:</u>	TELECOMMUNICATIONS FACILITY
<u>AT&T RF MANAGER:</u>	DEEPAK RATHORE
<u>PHONE:</u>	(860) 965-3068
<u>EMAIL:</u>	dr701e@att.com

SCOPE OF WORK

LTE 850 WILL BE 2C/3C AT THE SITE WITH BRONZE CONFIGURATION.
PROPOSED 2C/3C PROJECT SCOPE HEREIN BASED ON RFDS ID # 1839937, VERSION 2.00
LAST UPDATED 09/14/17.

- (3) NEW ANTENNAS TO REPLACE (3) EXISTING ANTENNAS
- (3) NEW RRUS-32
- (3) NEW RRUS-B14
- UPGRADE DUL TO 5216 AND ADD XMU

- CONTRACTOR SHALL FURNISH ALL MATERIAL WITH THE EXCEPTION OF AT&T SUPPLIED MATERIAL
- ALL MATERIAL SHALL BE INSTALLED BY THE CONTRACTOR, UNLESS STATED OTHERWISE.

SITE LOCATION MAP



NO SCALE

APPLICABLE BUILDING CODES AND STANDARDS

ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES.

BUILDING CODE: 2012 INTERNATIONAL BUILDING CODE
2016 CONNECTICUT STATE BUILDING CODE SUPPLEMENT

ELECTRICAL CODE: 2014 NATIONAL ELECTRIC CODE

DRAWING INDEX

T1	TITLE SHEET
SP1	NOTES AND SPECIFICATIONS
SP2	NOTES AND SPECIFICATIONS
A1	COMPOUND PLAN
A2	EQUIPMENT PLAN
A3	ELEVATIONS
A4	ANTENNA PLANS
A5	EQUIPMENT DETAILS
A6	ANTENNA & CABLE CONFIGURATION
A7	CABLE NOTES AND COLOR CODING
A8	GROUNDING DETAILS

PROJECT CONSULTANTS

<u>PROJECT MANAGER:</u>	SMARTLINK
ADDRESS:	85 RANGEWAY ROAD, SUITE 102 NORTH BILLERICA, MA 01862
CONTACT:	EDWARD WEISSMAN (917) 528-1857
EMAIL:	Edward.Weissman@smartlinkllc.com
<u>SITE ACQUISITION:</u>	SMARTLINK
ADDRESS:	85 RANGEWAY ROAD, SUITE 102 NORTH BILLERICA, MA 01862
CONTACT:	SHARON KEEFE (978) 930-3918
EMAIL:	Sharon.Keefe@smartlinkllc.com
<u>ENGINEER/ARCHITECT:</u>	FULLERTON ENGINEERING
ADDRESS:	1100 E. WOODFIELD ROAD, SUITE 500 SCHAUMBURG, IL 60173
CONTACT:	MILEN DIMITROV (847) 908-8439
EMAIL:	MDimitrov@FullertonEngineering.com
<u>CONSTRUCTION:</u>	SMARTLINK
ADDRESS:	85 RANGEWAY ROAD, SUITE 102 NORTH BILLERICA, MA 01862
CONTACT:	MARK DONNELLY (617) 515-2080
EMAIL:	mark.donnelly@smartlinkllc.com

DIRECTIONS

SCAN QR CODE FOR LINK
TO SITE LOCATION MAP



NOTE: DRAWING SCALES ARE FOR 11"x17" SHEETS UNLESS OTHERWISE NOTED

	SITE NAME
--	-----------

MANSFIELDS
FOUR CORNERS

	SITE NUMBER:
--	--------------

CTL05822

	SITE ADDRESS
--	--------------

497 MIDDLE TURNPIKE
STORRS MANSFIELD. CT

	SHEET NAME
--	------------

TITLE SHEET

SHEET NUMBER

T1

GENERAL CONSTRUCTION

1. FOR THE PURPOSE OF CONSTRUCTION DRAWINGS, THE FOLLOWING DEFINITIONS SHALL APPLY:
CONTRACTOR/CM – SMARTLINK
OWNER – AT&T WIRELESS
2. ALL SITE WORK SHALL BE COMPLETED AS INDICATED ON THE DRAWINGS AND AT&T PROJECT SPECIFICATIONS.
3. GENERAL CONTRACTOR SHALL VISIT THE SITE AND SHALL FAMILIARIZE HIMSELF WITH ALL CONDITIONS AFFECTING THE PROPOSED WORK AND SHALL MAKE PROVISIONS. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS, DIMENSIONS, AND CONFIRMING THAT THE WORK MAY BE ACCOMPLISHED AS SHOWN PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK.
4. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES. GENERAL CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS, AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF WORK.
5. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES, AND APPLICABLE REGULATIONS.
6. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES, AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
7. PLANS ARE NOT TO BE SCALED. THESE PLANS ARE INTENDED TO BE A DIAGRAMMATIC OUTLINE ONLY UNLESS OTHERWISE NOTED. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS OTHERWISE NOTED. SPACING BETWEEN EQUIPMENT IS THE MINIMUM REQUIRED CLEARANCE. THEREFORE, IT IS CRITICAL TO FIELD VERIFY DIMENSIONS, SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE ENGINEER PRIOR TO PROCEEDING WITH THE WORK. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF WORK AND PREPARED BY THE ENGINEER PRIOR TO PROCEEDING WITH WORK.
8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
9. IF THE SPECIFIED EQUIPMENT CANNOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION SPACE FOR APPROVAL BY THE ENGINEER PRIOR TO PROCEEDING.
10. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF WORK AREA, ADJACENT AREAS AND BUILDING OCCUPANTS THAT ARE LIKELY TO BE AFFECTED BY THE WORK UNDER THIS CONTRACT. WORK SHALL CONFIRM TO ALL OSHA REQUIREMENTS AND THE LOCAL JURISDICTION.
11. GENERAL CONTRACTOR SHALL COORDINATE WORK AND SCHEDULE WORK ACTIVITIES WITH OTHER DISCIPLINES.
12. ERECTION SHALL BE DONE IN A WORKMANLIKE MANNER BY COMPETENT EXPERIENCED WORKMAN IN ACCORDANCE WITH APPLICABLE CODES AND THE BEST ACCEPTED PRACTICE. ALL MEMBERS SHALL BE LAID PLUMB AND TRUE AS INDICATED ON THE DRAWINGS.
13. SEAL PENETRATIONS THROUGH FIRE RATED AREAS WITH UL LISTED MATERIALS APPROVED BY LOCAL JURISDICTION. CONTRACTOR SHALL KEEP AREA CLEAN, HAZARD FREE, AND DISPOSE OF ALL DEBRIS.
14. WORK PREVIOUSLY COMPLETED IS REPRESENTED BY LIGHT SHADED LINES AND NOTES. THE SCOPE OF WORK FOR THIS PROJECT IS REPRESENTED BY DARK SHADED LINES AND NOTES. CONTRACTOR SHALL NOTIFY THE GENERAL CONTRACTOR OF ANY EXISTING CONDITIONS THAT DEViate FROM THE DRAWINGS PRIOR TO BEGINNING CONSTRUCTION.
15. CONTRACTOR SHALL PROVIDE WRITTEN NOTICE TO THE CONSTRUCTION MANAGER 48 HOURS PRIOR TO COMMENCEMENT OF WORK.
16. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.
17. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES PRIOR TO THE START OF CONSTRUCTION.
18. GENERAL CONTRACTOR SHALL COORDINATE AND MAINTAIN ACCESS FOR ALL TRADES AND CONTRACTORS TO THE SITE AND/OR BUILDING.
19. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR SECURITY OF THE SITE FOR THE DURATION OF CONSTRUCTION UNTIL JOB COMPLETION.

20. THE GENERAL CONTRACTOR SHALL MAINTAIN IN GOOD CONDITION ONE COMPLETE SET OF PLANS WITH ALL REVISIONS, ADDENDA, AND CHANGE ORDERS ON THE PREMISES AT ALL TIMES.
21. THE GENERAL CONTRACTOR SHALL PROVIDE PORTABLE FIRE EXTINGUISHERS WITH A RATING OF NOT LESS THAN 2-A OT 2-A:10-B:C AND SHALL BE WITHIN 25 FEET OF TRAVEL DISTANCE TO ALL PORTIONS OF WHERE THE WORK IS BEING COMPLETED DURING CONSTRUCTION.
22. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC, AND OTHER UTILITIES SHALL BE PROTECTED AT ALL TIMES, AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY THE ENGINEER. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS SHALL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION, B) CONFINED SPACE, C) ELECTRICAL SAFETY, AND D) TRENCHING & EXCAVATION.
23. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC, AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED, CAPPED, PLUGGED OR OTHERWISE DISCONNECTED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, AS DIRECTED BY THE RESPONSIBLE ENGINEER, AND SUBJECT TO THE APPROVAL OF THE OWNER AND/OR LOCAL UTILITIES.
24. THE AREAS OF THE OWNER'S PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION.
25. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO THE EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE FEDERAL AND LOCAL JURISDICTION FOR EROSION AND SEDIMENT CONTROL.
26. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUNDING. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.
27. THE SUBGRADE SHALL BE BROUGHT TO A SMOOTH UNIFORM GRADE AND COMPACTED TO 95 PERCENT STANDARD PROCTOR DENSITY UNDER PAVEMENT AND STRUCTURES AND 80 PERCENT STANDARD PROCTOR DENSITY IN OPEN SPACE. ALL TRENCHES IN PUBLIC RIGHT OF WAY SHALL BE BACKFILLED WITH FLOWABLE FILL OR OTHER MATERIAL PRE-APPROVED BY THE LOCAL JURISDICTION.
28. ALL NECESSARY RUBBISH, STUMPS, DEBRIS, STICKS, STONES, AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN A LAWFUL MANNER.
29. ALL BROCHURES, OPERATING AND MAINTENANCE MANUALS, CATALOGS, SHOP DRAWINGS, AND OTHER DOCUMENTS SHALL BE TURNED OVER TO THE GENERAL CONTRACTOR AT COMPLETION OF CONSTRUCTION AND PRIOR TO PAYMENT.
30. CONTRACTOR SHALL SUBMIT A COMPLETE SET OF AS-BUILT REDLINES TO THE GENERAL CONTRACTOR UPON COMPLETION OF PROJECT AND PRIOR TO FINAL PAYMENT.
31. CONTRACTOR SHALL LEAVE PREMISES IN A CLEAN CONDITION.
32. THE PROPOSED FACILITY WILL BE UNMANNED AND DOES NOT REQUIRE POTABLE WATER OR SEWER SERVICE, AND IS NOT FOR HUMAN HABITAT (NO HANDICAP ACCESS REQUIRED).
33. OCCUPANCY IS LIMITED TO PERIODIC MAINTENANCE AND INSPECTION, APPROXIMATELY 2 TIMES PER MONTH, BY AT&T TECHNICIANS.
34. NO OUTDOOR STORAGE OR SOLID WASTE CONTAINERS ARE PROPOSED.
35. ALL MATERIAL SHALL BE FURNISHED AND WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST REVISION AT&T MOBILITY GROUNDING STANDARD "TECHNICAL SPECIFICATION FOR CONSTRUCTION OF GSM/GPRS WIRELESS SITES" AND "TECHNICAL SPECIFICATION FOR FACILITY GROUNDING". IN CASE OF A CONFLICT BETWEEN THE CONSTRUCTION SPECIFICATION AND THE DRAWINGS, THE DRAWINGS SHALL GOVERN.
36. CONTRACTORS SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS REQUIRED FOR CONSTRUCTION. IF CONTRACTOR CANNOT OBTAIN A PERMIT, THEY MUST NOTIFY THE GENERAL CONTRACTOR IMMEDIATELY.
37. CONTRACTOR SHALL REMOVE ALL TRASH AND DEBRIS FROM THE SITE ON A DAILY BASIS.
38. INFORMATION SHOWN ON THESE DRAWINGS WAS OBTAINED FROM SITE VISITS AND/OR DRAWINGS PROVIDED BY THE SITE OWNER. CONTRACTORS SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO ORDERING MATERIAL OR PROCEEDING WITH CONSTRUCTION.
39. NO WHITE STROBE LIGHTS ARE PERMITTED. LIGHTING IF REQUIRED, WILL MEET FAA STANDARDS AND REQUIREMENTS.

ANTENNA MOUNTING

40. DESIGN AND CONSTRUCTION OF ANTENNA SUPPORTS SHALL CONFORM TO CURRENT ANSI/TIA-222 OR APPLICABLE LOCAL CODES.

41. ALL STEEL MATERIALS SHALL BE GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123 "ZINC (HOT-DIP GALVANIZED) COATINGS ON IRON AND STEEL PRODUCTS", UNLESS NOTED OTHERWISE.
42. ALL BOLTS, ANCHORS AND MISCELLANEOUS HARDWARE SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM A153 "ZINC-COATING (HOT-DIP) ON IRON AND STEEL HARDWARE", UNLESS NOTED OTHERWISE.
43. DAMAGED GALVANIZED SURFACES SHALL BE REPAIRED BY COLD GALVANIZING IN ACCORDANCE WITH ASTM A780.
44. ALL ANTENNA MOUNTS SHALL BE INSTALLED WITH LOCK NUTS, DOUBLE NUTS AND SHALL BE TORQUED TO MANUFACTURER'S RECOMMENDATIONS.
45. CONTRACTOR SHALL INSTALL ANTENNA PER MANUFACTURER'S RECOMMENDATION FOR INSTALLATION AND GROUNDING.
46. ALL UNUSED PORTS ON ANY ANTENNAS SHALL BE TERMINATED WITH A 50-OHM LOAD TO ENSURE ANTENNAS PERFORM AS DESIGNED.
47. PRIOR TO SETTING ANTENNA AZIMUTHS AND DOWNTILTS, ANTENNA CONTRACTOR SHALL CHECK THE ANTENNA MOUNT FOR TIGHTNESS AND ENSURE THAT THEY ARE PLUMB. ANTENNA AZIMUTHS SHALL BE SET FROM TRUE NORTH AND BE ORIENTED WITHIN +/- 5% AS DEFINED BY THE RFDS. ANTENNA DOWNTILTS SHALL BE WITHIN +/- 0.5% AS DEFINED BY THE RFDS. REFER TO ND-00246.
48. JUMPERS FROM THE TMA'S MUST TERMINATE TO OPPOSITE POLARIZATION'S IN EACH SECTOR.
49. CONTRACTOR SHALL RECORD THE SERIAL #, SECTOR, AND POSITION OF EACH ACTUATOR INSTALLED AT THE ANTENNAS AND PROVIDE THE INFORMATION TO AT&T.
50. TMA'S SHALL BE MOUNTED ON PIPE DIRECTLY BEHIND ANTENNAS AS CLOSE TO ANTENNA AS FEASIBLE IN A VERTICAL POSITION.
- TORQUE REQUIREMENTS**
51. ALL RF CONNECTIONS SHALL BE TIGHTENED BY A TORQUE WRENCH.
52. ALL RF CONNECTIONS, GROUNDING HARDWARE AND ANTENNA HARDWARE SHALL HAVE A TORQUE MARK INSTALLED IN A CONTINUOUS STRAIGHT LINE FROM BOTH SIDES OF THE CONNECTION.
- A. RF CONNECTION BOTH SIDES OF THE CONNECTOR.
B. GROUNDING AND ANTENNA HARDWARE ON THE NUT SIDE STARTING FROM THE THREADS TO THE SOLID SURFACE. EXAMPLE OF SOLID SURFACE: GROUND BAR, ANTENNA BRACKET METAL.

FIBER & POWER CABLE MOUNTING

53. THE FIBER OPTIC TRUNK CABLES SHALL BE INSTALLED INTO CONDUITS, CHANNEL CABLE TRAYS, OR CABLE TRAY. WHEN INSTALLING FIBER OPTIC TRUNK CABLES INTO A CABLE TRAY SYSTEM, THEY SHALL BE INSTALLED INTO AN INTER DUCT AND A PARTITION BARRIER SHALL BE INSTALLED BETWEEN THE 600 VOLT CABLES AND THE INTER DUCT IN ORDER TO SEGREGATE CABLE TYPES. OPTIC FIBER TRUNK CABLES SHALL HAVE APPROVED CABLE RESTRAINTS EVERY (60) SIXTY FEET AND SECURELY FASTENED TO THE CABLE TRAY SYSTEM. NFPA 70 (NEC) ARTICLE 770 RULES SHALL APPLY.
54. THE TYPE TC-ER CABLES SHALL BE INSTALLED INTO CONDUITS, CHANNEL CABLE TRAYS, OR CABLE TRAY AND SHALL BE SECURED AT INTERVALS NOT EXCEEDING (6) SIX FEET. AN EXCEPTION; WHERE TYPE TC-ER CABLES ARE NOT SUBJECT TO PHYSICAL DAMAGE, CABLES SHALL BE PERMITTED TO MAKE A TRANSITION BETWEEN CONDUITS, CHANNEL CABLE TRAYS, OR CABLE TRAY WHICH ARE SERVING UTILIZATION EQUIPMENT OR DEVICES, A DISTANCE (6) SIX FEET SHALL NOT BE EXCEEDED WITHOUT CONTINUOUS SUPPORTING. NFPA 70 (NEC) ARTICLES 336 AND 392 RULES SHALL APPLY.
55. WHEN INSTALLING OPTIC FIBER TRUNK CABLES OR TYPE TC-ER CABLES INTO CONDUITS, NFPA 70 (NEC) ARTICLE 300 RULES SHALL APPLY.

COAXIAL CABLE NOTES

62. TYPES AND SIZES OF THE ANTENNA CABLE ARE BASED ON ESTIMATED LENGTHS. PRIOR TO ORDERING CABLE, CONTRACTOR SHALL VERIFY ACTUAL LENGTH BASED ON CONSTRUCTION LAYOUT AND NOTIFY THE PROJECT MANAGER IF ACTUAL LENGTHS EXCEED ESTIMATED LENGTHS.
63. CONTRACTOR SHALL VERIFY THE DOWN-TILT OF EACH ANTENNA WITH A DIGITAL LEVEL.
64. CONTRACTOR SHALL CONFIRM COAX COLOR CODING PRIOR TO CONSTRUCTION.
65. ALL JUMPERS TO THE ANTENNAS FROM THE MAIN TRANSMISSION LINE SHALL BE 1/2" DIA. LDF AND SHALL NOT EXCEED 6'-0".

66. ALL COAXIAL CABLE SHALL BE SECURED TO THE DESIGNED SUPPORT STRUCTURE, IN AN APPROVED MANNER, AT DISTANCES NOT TO EXCEED 4'-0" OC.
67. CONTRACTOR SHALL FOLLOW ALL MANUFACTURER'S RECOMMENDATIONS REGARDING BOTH THE INSTALLATION AND GROUNDING OF ALL COAXIAL CABLES, CONNECTORS, ANTENNAS, AND ALL OTHER EQUIPMENT.
68. CONTRACTOR SHALL GROUND ALL EQUIPMENT. INCLUDING ANTENNAS, RET MOTORS, TMA'S, COAX CABLES, AND RET CONTROL CABLES AS A COMPLETE SYSTEM. GROUNDING SHALL BE EXECUTED BY QUALIFIED WIREMEN IN COMPLIANCE WITH MANUFACTURER'S SPECIFICATION AND RECOMMENDATION.
69. CONTRACTOR SHALL PROVIDE STRAIN-RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES, COAX CABLES, AND RET CONTROL CABLES. CABLE STRAIN-RELIEFS AND CABLE SUPPORTS SHALL BE APPROVED FOR THE PURPOSE. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
70. CONTRACTOR TO VERIFY THAT EXISTING COAX HANGERS ARE STACKABLE SNAP IN HANGERS. IF EXISTING HANGERS ARE NOT STACKABLE SNAP IN HANGERS THE CONTRACTOR SHALL REPLACE EXISTING HANGERS WITH NEW SNAP IN HANGERS IF APPLICABLE.

GENERAL CABLE AND EQUIPMENT NOTES

71. CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY ANTENNA, TMAS, DIPLEXERS, AND COAX CONFIGURATION, MAKE AND MODELS PRIOR TO INSTALLATION.
72. ALL CONNECTIONS FOR HANGERS, SUPPORTS, BRACING, ETC. SHALL BE INSTALLED PER TOWER MANUFACTURER'S RECOMMENDATIONS.
73. CONTRACTOR SHALL REFERENCE THE TOWER STRUCTURAL ANALYSIS/DESIGN DRAWINGS FOR DIRECTIONS ON CABLE DISTRIBUTION/ROUTING.
74. ALL OUTDOOR RF CONNECTORS/CONNECTIONS SHALL BE WEATHERPROOFED, EXCEPT THE RET CONNECTORS, USING BUTYL TAPE AFTER INSTALLATION AND FINAL CONNECTIONS ARE MADE. BUTYL TAPE SHALL HAVE A MINIMUM OF ONE-HALF TAPE WIDTH OVERLAP ON EACH TURN AND EACH LAYER SHALL BE WRAPPED THREE TIMES. WEATHERPROOFING SHALL BE SMOOTH WITHOUT BUCKLING. BUTYL BLEEDING IS NOT ALLOWED.
75. IF REQUIRED TO PAINT ANTENNAS AND/OR COAX:
A. TEMPERATURE SHALL BE ABOVE 50° F.
B. PAINT COLOR MUST BE APPROVED BY BUILDING OWNER/LANDLORD.
C. FOR REGULATED TOWERS, FAA/FCC APPROVED PAINT IS REQUIRED.
D. DO NOT PAINT OVER COLOR CODING OR ON EQUIPMENT MODEL NUMBERS
76. ALL CABLES SHALL BE GROUNDED WITH COAXIAL CABLE GROUND KITS. FOLLOW THE MANUFACTURER'S RECOMMENDATIONS.
A. GROUNDING AT THE ANTENNA LEVEL.
B. GROUNDING AT MID LEVEL, TOWERS WHICH ARE OVER 200'-0", ADDITIONAL CABLE GROUNDING REQUIRED.
C. GROUNDING AT BASE OF TOWER PRIOR TO TURNING HORIZONTAL.
D. GROUNDING OUTSIDE THE EQUIPMENT SHELTER AT ENTRY PORT.
E. GROUNDING INSIDE THE EQUIPMENT SHELTER AT THE ENTRY PORT.
77. ALL PROPOSED GROUND BAR DOWNLEADS ARE TO BE TERMINATED TO THE EXISTING ADJACENT GROUND BAR DOWNLEADS A MINIMUM DISTANCE OF 4'-0" BELOW GROUND BAR. TERMINATIONS MAY BE EXOTHERMIC OR COMPRESSION.



at&t

550 COCHITUATE ROAD
SUITE 550 13 AND 14
FRAMINGHAM, MA 01701



smartlink


1362 MELLON ROAD
SUITE 140
HANOVER, MD 21076



1100 E. WOODFIELD ROAD, SUITE 500
SCHAUMBURG, ILLINOIS 60173
TEL: 847-908-8400
COA# PEC.0001444
www.FullertonEngineering.com

REV	DATE	DESCRIPTION	BY
0	09/23/17	90% REVIEW	EB
1	10/16/17	FOR PERMIT	EB

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME

MANSFIELDS
FOUR CORNERS

SITE NUMBER:

CTL05822

SITE ADDRESS

497 MIDDLE TURNPIKE
STORRS MANSFIELD, CT

SHEET NAME

NOTES AND
SPECIFICATIONS

SHEET NUMBER

SP1

ABBREVIATIONS

AFF

AGL

AMSL

APPROX

ATS

AWG

BLDG

BTS

CL

CLR

COL

CONC

CND

DWG

FT

EGB

ELEC

EMT

ELEV

EQUIP

(E)

EXT

FND

F

FIF

GA

GALV

GPS

GND

GSM

LTE

MAX

MCPA

MFR

MGB

MIN

MTS

N.T.S.

O.C.

OE/OT

PPC

PL

RBS

RET

RRU

RGS

IN

INT

LB(S), #

SF

STL

TMA

TYP

UE/UT

UNO

UMTS

VIF

W/

XFMR

ABOVE FINISHED FLOOR

ABOVE GRADE LEVEL

ABOVE MEAN SEA LEVEL

APPROXIMATE

AUTOMATIC TRANSFER SWITCH

AMERICAN WIRE GAUGE

BUILDING

BASE TRANSMISSION STATION

CENTERLINE

CLEAR

COLUMN

CONCRETE

CONDUIT

DRAWING

FOOT(FEET)

EQUIPMENT GROUND BAR

ELECTRICAL

ELECTRICAL METALLIC TUBING

ELEVATION

EQUIPMENT

EXISTING

EXTERIOR

FOUNDATION

FIBER

FACILITY INTERFACE FRAME

GAUGE

GALVANIZED

GLOBAL POSITIONING SYSTEM

GROUND

GLOBAL SYSTEM FOR MOBILE COMMUNICATION

LONG TERM EVOLUTION

MAXIMUM

MULTI-CARRIER POWER AMPLIFIER

MANUFACTURER

MASTER GROUND BAR

MINIMUM

MANUAL TRANSFER SWITCH

NOT TO SCALE

ON CENTER

OVERHEAD ELECTRIC/TELCO

POWER PROTECTION CABINET

PROPERTY LINE

RADIO BASED STATION

REMOTE ELECTRIC TILT

REMOTE RADIO UNIT

RIGID GALVANIZED STEEL

INCH(ES)

INTERIOR

POUND(S)

SQUARE FOOT

STEEL

TOWER MOUNTED AMPLIFIER

TYPICAL

UNDERGROUND ELECTRIC/TELCO

UNLESS NOTED OTHERWISE

UNIVERSAL MOBILE TELE-COMMUNICATION SYSTEM

VERIFY IN FIELD

WITH

TRANSFORMER

SYMBOLS

▲

REVISION

⊕

WORK POINT

⦿

UTILITY POLE

▨

COMPRESSED STONE

▧

BRICK

▩

CONCRETE

▤

EARTH

◻

GRAVEL

▨

MASONRY

▧

STEEL

CENTERLINE

PROPERTY LINE

LEASE LINE

EASEMENT LINE

✕

CHAIN LINK FENCE

□

WOOD FENCE

UE

BELOW GRADE ELECTRIC

UT

BELOW GRADE TELEPHONE

OE/OT

OVERHEAD ELECTRIC/TELEPHONE

⬅

SECTION REFERENCE

COMPOUND PLAN

SCALE: 1/16" = 1'-0"

1

The diagram is a compound plan of a site. It shows an existing equipment shelter, an existing propane tank, an existing chain link fence, an existing gravel area, an existing ice bridge, an existing access gate, an existing monopole, and an existing utility H-frame. It also shows new and existing AT&T equipment cabinets on an existing concrete pad. The plan includes labels for various materials like compressed stone, brick, concrete, earth, gravel, masonry, and steel. It also shows symbols for centerline, property line, lease line, easement line, chain link fence, wood fence, and underground/overhead electric/telephone lines. A north arrow is located in the bottom right corner of the plan area.

EXISTING PROpane TANK

EXISTING EQUIPMENT SHELTER

EXISTING ICE BRIDGE (TYP.)

EXISTING GRAVEL AREA

EXISTING CHAIN LINK FENCE (TYP.)

NEW AND EXISTING AT&T EQUIPMENT CABINETS ON EXISTING 10'-0"x13'-0" CONCRETE PAD SEE A2 FOR DETAIL

(2) NEW RRUS B14 4478 UNITS ON NEW UNISTRUT FRAME (1 FOR SECTOR ALPHA) (1 FOR BETA & GAMMA) SEE A4 FOR DETAILS

REPLACE (3) EXISTING AT&T ANTENNAS WITH (3) NEW ANTENNAS (3) NEW RRUS-32 UNITS ON EXISTING MONOPOLE SEE A4 FOR DETAILS

(6) EXISTING AT&T ANTENNAS (3) EXISTING RRU UNITS (1) EXISTING RAYCAP UNIT ON EXISTING MONOPOLE TO REMAIN

EXISTING ACCESS GATE

EXISTING MONOPOLE

EXISTING UTILITY H-FRAME

at&t

550 COCHITUATE ROAD
SUITE 550 13 AND 14
FRAMINGHAM, MA 01701

smartlink

1362 MELLON ROAD
SUITE 140
HANOVER, MD 21076

FULLERTON

ENGINEERING • DESIGN

1100 E. WOODFIELD ROAD, SUITE 500
SCHAUMBURG, ILLINOIS 60173
TEL: 847-908-8400
COA# PEC.0001444
www.FullertonEngineering.com

REV	DATE	DESCRIPTION	BY
0	09/23/17	90% REVIEW	EB
1	10/16/17	FOR PERMIT	EB

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.

STATE OF CONNECTICUT

HENRY M. BELLAGAMBA

25358

PROFESSIONAL ENGINEER

SITE NAME

MANSFIELDS
FOUR CORNERS

SITE NUMBER:

CTL05822

SITE ADDRESS

497 MIDDLE TURNPIKE
STORRS MANSFIELD, CT

SHEET NAME

COMPOUND
PLAN

SHEET NUMBER

A1

SITE PHOTO 1

SCALE: N.T.S.


2

SITE PHOTO 2

SCALE: N.T.S.

3

THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.



550 COCHITUATE ROAD
SUITE 550 13 AND 14
FRAMINGHAM, MA 01701




1362 MELLON ROAD
SUITE 140
HANOVER, MD 21076



1100 E. WOODFIELD ROAD, SUITE 500
SCHAUMBURG, ILLINOIS 60173
TEL: 847-908-8400
COA# PEC.0001444
www.FullertonEngineering.com

REV	DATE	DESCRIPTION	BY
0	09/23/17	90% REVIEW	EB
1	10/16/17	FOR PERMIT	EB

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME

MANSFIELDS
FOUR CORNERS

SITE NUMBER:

CTL05822

SITE ADDRESS


497 MIDDLE TURNPIKE
STORRS MANSFIELD, CT

SHEET NAME


EQUIPMENT
PLAN

SHEET NUMBER

A2



- NOTES:
1. CALCULATIONS FOR THE STRUCTURE WERE PREPARED BY OTHERS AND THOSE CALCULATIONS CERTIFY THE CAPACITY OF THE STRUCTURE TO SUPPORT THE NEW EQUIPMENT
 2. CALCULATIONS FOR THE ANTENNA MOUNTS WERE PREPARED BY FULLERTON AND THOSE CALCULATIONS CERTIFY THE CAPACITY OF THE STRUCTURE TO SUPPORT THE NEW EQUIPMENT
 3. CABLES NOT SHOWN FOR CLARITY



- NOTES:
1. ALL EQUIPMENT (ANTENNAS, LINES, ETC.) TO BE INSTALLED IN ACCORDANCE WITH PASSING STRUCTURAL ANALYSIS PROVIDED BY CROWN CASTLE.
 2. TAPE DROP FORMS AND PHOTOGRAPHS TO BE SUBMITTED PER CCI AND AT&T CLOSEOUT REQUIREMENTS.



550 COCHITUATE ROAD
SUITE 550 13 AND 14
FRAMINGHAM, MA 01701


1362 MELLON ROAD
SUITE 140
HANOVER, MD 21076


1100 E. WOODFIELD ROAD, SUITE 500
SCHAUMBURG, ILLINOIS 60173
TEL: 847-908-8400
COA# PEC.0001444
www.FullertonEngineering.com

REV	DATE	DESCRIPTION	BY
0	09/23/17	90% REVIEW	EB
1	10/16/17	FOR PERMIT	EB

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME
**MANSFIELDS
FOUR CORNERS**

SITE NUMBER:
CTL05822

SITE ADDRESS
**497 MIDDLE TURNPIKE
STORRS MANSFIELD, CT**

SHEET NAME
ELEVATIONS

SHEET NUMBER
A3


EXISTING ELEVATION

SCALE: 1/16" = 1'-0" 1

NEW ELEVATION

SCALE: 1/16" = 1'-0" 2


THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.



EXISTING ANTENNA PLAN

SCALE: 3/16" = 1'-0"

1



FINAL ANTENNA PLAN

SCALE: 3/16" = 1'-0"

2



550 COCHITUATE ROAD
SUITE 550 13 AND 14
FRAMINGHAM, MA 01701



1362 MELLON ROAD
SUITE 140
HANOVER, MD 21076



1100 E. WOODFIELD ROAD, SUITE 500
SCHAUMBURG, ILLINOIS 60173
TEL: 847-908-8400
COA# PEC.0001444
www.FullertonEngineering.com

REV	DATE	DESCRIPTION	BY
0	09/23/17	90% REVIEW	EB
1	10/16/17	FOR PERMIT	EB

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME

MANSFIELDS
FOUR CORNERS

SITE NUMBER:

CTL05822

SITE ADDRESS

497 MIDDLE TURNPIKE
STORRS MANSFIELD, CT

SHEET NAME

ANTENNA
PLANS

SHEET NUMBER


A4

<div><p>PLAN VIEW SIDE VIEW FRONT VIEW</p><p>CCI – HPA-65R-BUU-H8 HEXPORT MULTI-BAND ANTENNA FREQUENCY RANGE 698–806 MHz 824–894 MHz 1850–1990 MHz 1710–1755/2110–2170 MHz 2305–2360 MHz ANTENNA WITH BRACKET 68 Lbs 78 Lbs</p></div>		<div><p>NEW ANTENNA EXISTING ANTENNA MOUNTING PIPE TO BE REUSED, REPLACED OR RELOCATED AS REQUIRED NEW RRUS UNIT #2 AWG GREEN STRANDED INSULATED GROUND WIRE TO SECTOR GROUND BAR NEW FIBER AND DC POWER JUMPERS FROM RAYCAP UNIT TO RRU UNIT EXISTING RAYCAP UNIT EXISTING ANTENNA MOUNT NEW CLICK-ON-HANGERS, ANDREW PART # L4CLICK SECURED WITH 3/8"Ø THREADED ROD (TYP.) NEW RF JUMPER(S) FROM RRU TO ANTENNA</p></div>		NOT USED		NOT USED		<div><p>550 COCHITUATE ROAD SUITE 550 13 AND 14 FRAMINGHAM, MA 01701</p><p>1362 MELLON ROAD SUITE 140 HANOVER, MD 21076</p><p>1100 E. WOODFIELD ROAD, SUITE 500 SCHAUMBURG, ILLINOIS 60173 TEL: 847-908-8400 COA# PEC.0001444 www.FullertonEngineering.com</p><table><tr><th>REV</th><th>DATE</th><th>DESCRIPTION</th><th>BY</th></tr><tr><td>0</td><td>09/23/17</td><td>90% REVIEW</td><td>EB</td></tr><tr><td>1</td><td>10/16/17</td><td>FOR PERMIT</td><td>EB</td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr></table><p>I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.</p></div>		REV	DATE	DESCRIPTION	BY	0	09/23/17	90% REVIEW	EB	1	10/16/17	FOR PERMIT	EB																	ANTENNA SPEC		SCALE: N.T.S.	1	ANTENNA SCHEMATIC		SCALE: N.T.S.	2	NOT USED		SCALE: N.T.S.	3	NOT USED		SCALE: N.T.S.	4
REV	DATE	DESCRIPTION	BY																																																		
0	09/23/17	90% REVIEW	EB																																																		
1	10/16/17	FOR PERMIT	EB																																																		
<div><p>PLAN VIEW SIDE VIEW FRONT VIEW</p><p>ERICSSON – RRUS 32 B30 UNIT WEIGHT 60 Lbs</p></div>		<div><p>ERICSSON – RRUS 4478 B14</p><p>FREQUENCY RANGE TX 758–768 MHz RX 788–798 MHz TOTAL WEIGHT 59.9 Lbs</p></div>		NOT USED		NOT USED		<div><p>SITE NAME</p><p>MANSFIELDS FOUR CORNERS</p><p>SITE NUMBER:</p><p>CTL05822</p><p>SITE ADDRESS</p><p>497 MIDDLE TURNPIKE STORRS MANSFIELD, CT</p><p>SHEET NAME</p><p>EQUIPMENT DETAILS</p><p>SHEET NUMBER</p><p>A5</p></div>		RRU SPEC		SCALE: N.T.S.	5	A2 BOX SPEC		SCALE: N.T.S.	6	NOT USED		SCALE: N.T.S.	7	NOT USED		SCALE: N.T.S.	8																												


THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.

FINAL ANTENNA CONFIGURATION AND CABLE SCHEDULE SUPPLIED BY AT&T WIRELESS, FROM RF CONFIG. DATED (09/14/17)											
SECTOR	ANTENNA NUMBER	ANTENNA STATUS & TYPE	ANTENNA MODEL NUMBER	ANTENNA VENDOR	TMA/RRU UNIT (BY ANTENNAS)	TMA/RRU UNIT (BY EQUIPMENT)	AZIMUTH	ANTENNA CL. FROM GROUND	CABLE FEEDER		RAYCAP UNIT
									TYPE	LENGTH	
ALPHA	A-1	(E) UMTS ANTENNA	7770	POWERWAVE	(2) EXISTING TMA UNITS	—	0°	122'-0"	7/8"ø LDF5-50A	175'-0"	(1) (X) DC6-48-60-18-8F UNIT
									7/8"ø LDF5-50A	175'-0"	
	A-2	—	—	—	—	—	—	—	—	—	
	A-3	(N) LTE2C/3C ANTENNA	HPA-65R-BUU-H8	CCI	(1) NEW RRUS-32 UNIT	(1) NEW RRUS-B14 4478 UNIT	0°	122'-0"	SEE ANTENNA A-4 FOR CABLE TYPE AND LENGTH		
	A-4	(E) LTE1C ANTENNA	AM-X-CD-14-65 -00T-RET	KMW	(1) RELOCATED RRUS-11 UNIT	—	0°	122'-0"	(1) EXISTING FIBER CABLE	175'-0"	
(2) EXISTING DC POWER CABLES									175'-0"		
BETA	B-1	(E) UMTS ANTENNA	7770	POWERWAVE	(2) EXISTING TMA UNITS	—	120°	122'-0"	7/8"ø LDF5-50A	175'-0"	
									7/8"ø LDF5-50A	175'-0"	
	B-2	—	—	—	—	—	—	—	—	—	
	B-3	(N) LTE2C/3C ANTENNA	HPA-65R-BUU-H8	CCI	(1) NEW RRUS-32 UNIT	(1) NEW RRUS-B14 4478 UNIT	120°	122'-0"	SEE ANTENNA A-4 FOR CABLE TYPE AND LENGTH		
	B-4	(E) LTE1C ANTENNA	AM-X-CD-14-65 -00T-RET	KMW	(1) RELOCATED RRUS-11 UNIT	—	120°	122'-0"	(1) EXISTING FIBER CABLE	175'-0"	
(2) EXISTING DC POWER CABLES									175'-0"		
GAMMA	C-1	(E) UMTS ANTENNA	7770	POWERWAVE	(2) EXISTING TMA UNITS	—	240°	122'-0"	7/8"ø LDF5-50A	175'-0"	
									7/8"ø LDF5-50A	175'-0"	
	C-2	—	—	—	—	—	—	—	—	—	
	C-3	(N) LTE2C/3C ANTENNA	HPA-65R-BUU-H8	CCI	(1) NEW RRUS-32 UNIT	(1) NEW RRUS-B14 4478 UNIT	240°	122'-0"	SEE ANTENNA A-4 FOR CABLE TYPE AND LENGTH		
	C-4	(E) LTE1C ANTENNA	SBNH-1D6565C	COMMSCOPE	(1) RELOCATED RRUS-11 UNIT	—	240°	122'-0"	(1) EXISTING FIBER CABLE	175'-0"	
(2) EXISTING DC POWER CABLES									175'-0"		


LEGEND
(N) - NEW
(E) - EXISTING



550 COCHITUATE ROAD
SUITE 550 13 AND 14
FRAMINGHAM, MA 01701




1362 MELLON ROAD
SUITE 140
HANOVER, MD 21076



1100 E. WOODFIELD ROAD, SUITE 500
SCHAUMBURG, ILLINOIS 60173
TEL: 847-908-8400
COA# PEC.0001444
www.FullertonEngineering.com

REV	DATE	DESCRIPTION	BY
0	09/23/17	90% REVIEW	EB
1	10/16/17	FOR PERMIT	EB

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME

MANSFIELDS
FOUR CORNERS

SITE NUMBER:

CTL05822

SITE ADDRESS

497 MIDDLE TURNPIKE
STORRS MANSFIELD, CT

SHEET NAME

ANTENNA &
CABLE
CONFIGURATION

SHEET NUMBER

A6

1. CONTRACTOR IS TO REFER TO AT&T'S MOST CURRENT RADIO FREQUENCY DATA SHEET (RFDS) PRIOR TO CONSTRUCTION.
2. THE SIZE, HEIGHT, AND DIRECTION OF THE ANTENNAS SHALL BE ADJUSTED TO ACHIEVE THE AZIMUTHS SPECIFIED AND LIMIT SHADOWING AND TO MEET THE SYSTEM REQUIREMENTS.
3. CONTRACTOR SHALL VERIFY THE HEIGHT OF THE ANTENNA WITH THE AT&T WIRELESS PROJECT MANAGER.
4. VERIFY TYPE AND SIZE OF TOWER LEG PRIOR TO ORDERING ANY ANTENNA MOUNT.
5. UNLESS NOTED OTHERWISE THE CONTRACTOR MUST PROVIDE ALL MATERIAL NECESSARY.
6. ANTENNA AZIMUTHS ARE DEGREES OFF OF TRUE NORTH, BEARING CLOCKWISE, IN WHICH ANTENNA FACE IS DIRECTED. ALL ANTENNAS (AND SUPPORTING STRUCTURES AS PRACTICAL) SHALL BE ACCURATELY ORIENTED IN THE SPECIFIED DIRECTION.
7. CONTRACTOR SHALL VERIFY ALL RF INFORMATION PRIOR TO CONSTRUCTION.
8. SWEEP TEST SHALL BE PERFORMED BY GENERAL CONTRACTOR AND SUBMITTED TO AT&T WIRELESS CONSTRUCTION SPECIALIST. TEST SHALL BE PERFORMED PER AT&T WIRELESS STANDARDS.
9. CABLE LENGTHS WERE DETERMINED BASED ON THE DESIGN DRAWING. CONTRACTOR TO VERIFY ACTUAL LENGTH DURING PRE-CONSTRUCTION WALK.
10. CONTRACTOR TO USE ROSENBERGER FIBER LINE HANGER COMPONENTS (OR ENGINEER APPROVED EQUAL).

ANTENNA AND CABLING NOTES

SCALE: N.T.S. 1

RF, DC, & COAX CABLE MARKING LOCATIONS TABLE	
NO	LOCATIONS
1	EACH TOP-JUMPER SHALL BE COLOR CODED WITH (1) SET OF 3" WIDE BANDS.
2	EACH MAIN COAX SHALL BE COLOR CODED WITH (1) SET OF 3" WIDE BANDS NEAR THE TOP-JUMPER CONNECTION AND WITH (1) SET OF 3/4" WIDE COLOR BANDS JUST PRIOR TO ENTERING THE BTS OR TRANSMITTER BUILDING.
3	CABLE ENTRY PORT ON THE INTERIOR OF THE SHELTER.
4	ALL BOTTOM JUMPERS SHALL BE COLOR CODED WITH (1) SET OF 3/4" WIDE BANDS ON EACH END OF THE BOTTOM JUMPER.
5	ALL BOTTOM JUMPERS SHALL BE COLOR CODED WITH (1) SET OF 3/4" WIDE BANDS ON EACH END OF THE BOTTOM JUMPER.


CABLE MARKING DIAGRAM

SCALE: N.T.S. 2

1. THE ANTENNA SYSTEM COAX SHALL BE LABELED WITH VINYL TAPE.
2. THE STANDARD IS BASED ON EIGHT COLORED TAPES-RED, BLUE, GREEN, YELLOW, ORANGE, BROWN, WHITE, AND VIOLET. THESE TAPES MUST BE 3/4" WIDE & UV RESISTANT SUCH AS SCOTCH 35 VINYL ELECTRICAL COLOR CODING TAPE AND SHOULD BE READILY AVAILABLE TO THE ELECTRICIAN OR CONTRACTOR ON SITE.
3. USING COLOR BANDS ON THE CABLES, MARK ALL RF CABLE BY SECTOR AND CABLE NUMBER AS SHOWN ON "CABLE COLOR CHART".
4. WHEN AN EXISTING COAXIAL LINE THAT IS INTENDED TO BE A SHARED LINE BETWEEN TECHNOLOGIES IS ENCOUNTERED, THE CONTRACTOR SHALL REMOVE THE EXISTING COLOR CODING SCHEME AND REPLACE IT WITH THE COLOR CODING STANDARD. IN THE ABSENCE OF AN EXISTING COLOR CODING AND TAGGING SCHEME, OR WHEN INSTALLING PROPOSED COAXIAL CABLES, THIS GUIDELINE SHALL BE IMPLEMENTED AT THAT SITE REGARDLESS OF TECHNOLOGY.
5. ALL COLOR CODE TAPE SHALL BE 3M-35 AND SHALL BE INSTALLED USING A MINIMUM OF (3) THREE WRAPS OF TAPE AND SHALL BE NEATLY TRIMMED AND SMOOTHED OUT SO AS TO AVOID UNRAVELING.
6. ALL COLOR BANDS INSTALLED AT THE TOP OF THE TOWER SHALL BE A MINIMUM OF 3" WIDE, AND SHALL HAVE A MINIMUM OF 3/4" OF SPACE BETWEEN EACH COLOR.
7. ALL COLOR CODES SHALL BE INSTALLED SO AS TO ALIGN NEATLY WITH ONE ANOTHER FROM SIDE-TO-SIDE.
8. IF EXISTING CABLES AT THE SITE ALREADY HAVE A COLOR CODING SCHEME AND THEY ARE NOT INTENDED TO BE REUSED OR SHARED WITH THE NEW TECHNOLOGY, THE EXISTING COLOR CODING SCHEME SHALL REMAIN UNTOUCHED.

CABLE MARKING NOTES

SCALE: N.T.S. 3




CABLE COLOR CODING DIAGRAM

SCALE: N.T.S. 4



REV	DATE	DESCRIPTION	BY
0	09/23/17	90% REVIEW	EB
1	10/16/17	FOR PERMIT	EB

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.




SITE NAME
**MANSFIELDS
FOUR CORNERS**

SITE NUMBER:
CTL05822

SITE ADDRESS
**497 MIDDLE TURNPIKE
STORRS MANSFIELD, CT**

SHEET NAME
**CABLE NOTES
AND COLOR
CODING**


SHEET NUMBER
A7



GROUNDING SCHEMATIC

SCALE: N.T.S.


1



GROUND BAR DETAIL

SCALE: N.T.S.


2



LUG DETAIL

SCALE: N.T.S.


3



EXOTHERMIC WELD DETAILS

SCALE: N.T.S.

4



RAYCAP DC POWER AND ALARM DET.

SCALE: N.T.S.

5

NOT USED

SCALE: N.T.S.

6

**at&t**
550 COCHITUATE ROAD
SUITE 550 13 AND 14
FRAMINGHAM, MA 01701


**smartlink**
1362 MELLON ROAD
SUITE 140
HANOVER, MD 21076

FULLERTON
ENGINEERING • DESIGN

1100 E. WOODFIELD ROAD, SUITE 500
SCHAUMBURG, ILLINOIS 60173
TEL: 847-908-8400
COA# PEC.0001444
www.FullertonEngineering.com

REV	DATE	DESCRIPTION	BY
0	09/23/17	90% REVIEW	EB
1	10/16/17	FOR PERMIT	EB

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME

**MANSFIELDS
FOUR CORNERS**

SITE NUMBER:

CTL05822

SITE ADDRESS

**497 MIDDLE TURNPIKE
STORRS MANSFIELD, CT**

SHEET NAME

**GROUNDING
DETAILS**

SHEET NUMBER

A8

From: TrackingUpdates@fedex.com
Sent: Tuesday, February 13, 2018 9:35 AM
To: Romina Kirchmaier
Subject: FedEx Shipment 771441086053 Delivered

Follow up
Flagged

Your package has been delivered

Tracking # 771441086053

Ship date:
Mon, 2/12/2018

Romina Kirchmaier

Romina Kirchmaier
NORTH BILLERICA, MA 01862
US

Delivery date:
Tue, 2/13/2018 9:30 am

Paul Shapiro

TOWN OF MANSFIELD
4 S EAGLEVILLE RD
STORRS MANSFIELD, CT
06268257404
US



FedEx

Shipment Facts

Our records indicate that the following package has been delivered.

Tracking number: 771441086053

Status: Delivered: 02/13/2018 09:30
AM Signed for By: TSMITH

Reference: CTL05822

Signed for by: TSMITH

Delivery location: Storrs Mansfield, CT


Service type: FedEx Ground

Packaging type: Package

Number of pieces: 1

Weight: 1.00 lb.

Standard transit: 2/13/2018

 Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 8:34 AM CST on 02/13/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above.

Standard transit is the date the package should be delivered by, based on the selected service, destination, and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.

© 2018 Federal Express Corporation. The content of this message is protected by copyright and trademark laws under U.S. and international law. Review our [privacy policy](#). All rights reserved.

Thank you for your business.

From: TrackingUpdates@fedex.com
Sent: Tuesday, February 13, 2018 10:35 AM
To: Romina Kirchmaier
Subject: FedEx Shipment 771441118784 Delivered

Follow up
Flagged

Your package has been delivered

Tracking # 771441118784

Ship date:
Mon, 2/12/2018

Romina Kirchmaier
Romina Kirchmaier
NORTH BILLERICA, MA 01862
US

Delivery date:
Tue, 2/13/2018 10:34
am


Paul Pedicone
CROWN CASTLE
3 CORPORATE DR
STE 101
CLIFTON PARK, NY
12065863526
US



Shipment Facts

Our records indicate that the following package has been delivered.

Tracking number: 771441118784
Status: Delivered: 02/13/2018 10:34
AM Signed for By: BROADS
Reference: CTL05822
Signed for by: BROADS
Delivery location: Clifton Park, NY
Service type: FedEx Ground
Packaging type: Package
Number of pieces: 1
Weight: 1.00 lb.
Standard transit: 2/13/2018

 Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 9:35 AM CST on 02/13/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above.

Standard transit is the date the package should be delivered by, based on the selected service, destination, and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.

© 2018 Federal Express Corporation. The content of this message is protected by copyright and trademark laws under U.S. and international law. Review our [privacy policy](#). All rights reserved.

Thank you for your business.

From: TrackingUpdates@fedex.com
Sent: Tuesday, February 13, 2018 10:22 AM
To: Romina Kirchmaier
Subject: FedEx Shipment 771441104251 Delivered

Follow up
Flagged

Your package has been delivered

Tracking # 771441104251

Ship date:
Mon, 2/12/2018

Romina Kirchmaier
Romina Kirchmaier
NORTH BILLERICA, MA 01862
US

Delivery date:
**Tue, 2/13/2018 10:20
am**


Ann Brodin
ANN BRODIN
106 COLEMAN RD
MANCHESTER, CT
06042337906
US



Shipment Facts

Our records indicate that the following package has been delivered.

Tracking number:	<u>771441104251</u>
Status:	Delivered: 02/13/2018 10:20 AM Signed for By: Signature Not Req
Reference:	CTL05822
Signed for by:	Signature Not Req
Service type:	FedEx Ground
Packaging type:	Package
Number of pieces:	1
Weight:	1.00 lb.
Standard transit:	2/13/2018

 Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 9:21 AM CST on 02/13/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above.

Standard transit is the date the package should be delivered by, based on the selected service, destination, and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.

© 2018 Federal Express Corporation. The content of this message is protected by copyright and trademark laws under U.S. and international law. Review our [privacy policy](#). All rights reserved.

Thank you for your business.

From: TrackingUpdates@fedex.com
Sent: Tuesday, February 13, 2018 9:32 AM
To: Romina Kirchmaier
Subject: FedEx Shipment 771441076111 Delivered

Follow up
Flagged

Your package has been delivered

Tracking # 771441076111

Ship date:
Mon, 2/12/2018
Romina Kirchmaier
Romina Kirchmaier
NORTH BILLERICA, MA 01862
US


Delivery date:
Tue, 2/13/2018 9:28 am
Linda Painter
TOWN OF MANSFIELD -
PLANNING
4 S EAGLEVILLE RD
STORRS MANSFIELD, CT
06268257404
US



Shipment Facts

Our records indicate that the following package has been delivered.

Tracking number: 771441076111
Status: Delivered: 02/13/2018 09:28 AM
Signed for By: LPAINTER
Reference: CTL05822
Signed for by: LPAINTER
Delivery location: Storrs Mansfield, CT
Service type: FedEx Ground
Packaging type: Package
Number of pieces: 1
Weight: 1.00 lb.
Standard transit: 2/13/2018

 Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 8:31 AM CST on 02/13/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above.

Standard transit is the date the package should be delivered by, based on the selected service, destination, and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.

© 2018 Federal Express Corporation. The content of this message is protected by copyright and trademark laws under U.S. and international law. Review our [privacy policy](#). All rights reserved.

Thank you for your business.