



May 28<sup>th</sup>, 2019

Melanie A. Bachman Executive  
Director Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**Re:** Notice of Exempt Modification – Antenna and RRU Add  
**Property Address:** 613 Connecticut Avenue, Norwalk, CT 06850  
**Applicant:** AT&T Mobility, LLC

Dear Ms. Bachman:

On behalf of AT&T, please accept this application as notification pursuant to R.C.S.A. §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. §16- 50j-72(b) (2).

AT&T currently maintains a wireless telecommunications facility consisting of nine (9) wireless telecommunication antennas at an antenna center line height of 153-feet on an existing 150-foot monopole, owned by Crown Castle at 3 Corporate Park Drive, Suite 101, Clifton Park, NY 12065. AT&T now intends to swap the existing position [2] antenna with one (1) proposed 6' Quintel QS66512-2 and add one (1) 4' Andrew SBNHH-1D65A to position [3] each sector, for a total of six (6) proposed antennas. In addition, AT&T is looking to install one (1) RRUS-E2 and one (1) RRUs 4478 B5 in position [4], one (1) RRUs B144 4478 in position [3], and one (1) RRUs 32 B66 in position [2], each sector, for a total of twelve (12) new RRUs to be installed. Lastly, AT&T is proposing to add one (1) additional Raycap DC Surge Suppressor and two (2) DC Power Cables to their existing antenna array. The proposed Raycap DC Surge Suppressor, along with the (3) proposed RRUs-32 B66 and the (3) proposed B14 4478 RRUs will be collar mounted immediately below the existing platform mount on new a proposed Collar Mount (Commscope P/N MC-RR1050-3). The remaining changes will take place on the existing antenna platform mount.

Attached is a summary of the planned modifications including power density calculations reflecting the change in AT&T's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

Please accept this letter pursuant to Regulation of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b) (2). In accordance with R.C.S.A., a copy of this letter is being sent to Steven Kleppin, Zoning and Planning – Director, City of Norwalk, CT, 125 East Ave. Room #223, Norwalk, CT 06856 and Harry W. Rilling, Mayor – City of Norwalk, CT, 125 East Ave. Norwalk, CT 06856. A copy of this letter is being sent to the property owner, Home Depot USA Inc. ATTN: Prop Tax Dept #6204, PO BOX 105842, Atlanta, GA 30348. A copy of this letter is also being sent to the tower company, Crown Castle at 3 Corporate Park Drive, Suite 101, Clifton Park, NY 12065.

The following is a list of subsequent decisions by the Connecticut Siting Council:

- **EM-CING-051-103-135-035-050922** - New Cingular Wireless PCS, LLC. notice of intent to modify existing telecommunications facilities located at 281 Woodhouse Road, Fairfield; 3965 Congress Street, Fairfield; 600 Connecticut Ave., **Norwalk**; 1590 Newfield Ave, Stamford; and 126 Ledge Road, Darien, Connecticut.
- **EM-CING-103-111230** - New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located at 613 Connecticut Avenue, **Norwalk**, Connecticut.
- **EM-AT&T-103-160621** – AT&T notice of intent to modify an existing telecommunications facility located at 600 Connecticut Avenue, **Norwalk**, Connecticut. [Decision](#).
- **EM-AT&T-103a-180509** – AT&T notice of intent to modify an existing telecommunications facility located at 613 Connecticut Avenue, **Norwalk**, Connecticut.



The planned modifications to AT&T's facility fall squarely within those activities explicitly provided for in R.C.S.A. §16-50j-72(b) (2).

1. The proposed modifications will not result in an increase in the height of the existing tower. AT&T's replacement antennas will be installed at the 153-foot level of the 150-foot self-support tower.
2. The proposed modifications will not involve any changes to ground-mounted equipment and, therefore, will not require an extension of the site boundary.
3. The proposed modifications will not increase the noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the modified facility will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) safety standard. A cumulative worst-case RF emissions calculation for AT&T's modified facility is provided in the RF Emissions Compliance Report, included in [Tab 2](#).
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The tower and its foundation can support AT&T's proposed modifications. (See Structural Analysis Report included in [Tab 3](#)).

For the foregoing reasons, AT&T respectfully submits that the proposed modifications to the above referenced telecommunications facility constitutes an exempt modification under R.C.S.A. §16-50j-72(b) (2).

Sincerely,

Romina Kirchmaier

CC w/enclosures:  
Steven Kleppin – Director of Planning and Zoning, City of Norwalk, CT  
Harry W. Rilling – Mayor, City of Norwalk, CT  
Home Depot USA Inc. – Land Owner  
Crown Castle – Tower Company



**Smartlink on behalf of  
AT&T Mobility, LLC  
Site FA – 10034974  
USID – 60395  
Site ID – CT2108 (MRCTB017068-  
MRCTB025304-MRCTB025283-  
MRCTB025338-MRCTB026716)  
Site Name – Norwalk West-CT  
Ave**

**613 Connecticut Avenue  
Norwalk, CT 06850**

Latitude: N41-5-49.47

Longitude: W73-26-56.60

Structure Type: Monopole

Report generated date: April 12, 2019

Report by: Nick Kutzke

Customer Contact: Romina Kirchmaier

**AT&T Mobility, LLC will be compliant when the  
remediation recommended in Section 5.2 or  
other appropriate remediation is implemented.**

Sitesafe logo is a registered trademark of Site Safe, LLC. All rights reserved.

# Table of Contents

|          |   |           |
|----------|---|-----------|
| <b>1</b> | <b>GENERAL SITE SUMMARY.....</b>                            | <b>2</b>  |
| 1.1      | REPORT SUMMARY .....  | 2         |
| 1.2      | FALL ARREST ANCHOR POINT SUMMARY .....                      | 2         |
| 1.3      | SIGNAGE SUMMARY .....                                       | 3         |
| <b>2</b> | <b>SCALE MAPS OF SITE.....</b>                              | <b>4</b>  |
| <b>3</b> | <b>ANTENNA INVENTORY .....</b>                              | <b>6</b>  |
| <b>4</b> | <b>EMISSION PREDICTIONS .....</b>                           | <b>8</b>  |
| <b>5</b> | <b>SITE COMPLIANCE .....</b>                                | <b>11</b> |
| 5.1      | SITE COMPLIANCE STATEMENT .....                             | 11        |
| 5.2      | ACTIONS FOR SITE COMPLIANCE .....                           | 11        |
| <b>6</b> | <b>REVIEWER CERTIFICATION .....</b>                         | <b>12</b> |
|          | <b>APPENDIX A – STATEMENT OF LIMITING CONDITIONS .....</b>  | <b>13</b> |
|          | <b>APPENDIX B – REGULATORY BACKGROUND INFORMATION .....</b> | <b>14</b> |
|          | FCC RULES AND REGULATIONS .....                             | 14        |
|          | OSHA STATEMENT.....   | 15        |
|          | <b>APPENDIX C – SAFETY PLAN AND PROCEDURES.....</b>         | <b>16</b> |
|          | <b>APPENDIX D – RF EMISSIONS.....</b>                       | <b>17</b> |
|          | <b>APPENDIX E – ASSUMPTIONS AND DEFINITIONS .....</b>       | <b>18</b> |
|          | GENERAL MODEL ASSUMPTIONS .....                             | 18        |
|          | USE OF GENERIC ANTENNAS .....                               | 18        |
|          | DEFINITIONS .....   | 19        |
|          | <b>APPENDIX F – REFERENCES .....</b>                        | <b>21</b> |

# 1 General Site Summary

## 1.1 Report Summary

| AT&T Mobility, LLC                               | Summary                  |
|--|--------------------------|
| Max Cumulative Simulated RFE Level on the Ground | <1% General Public Limit |
| Compliant per FCC Rules and Regulations?         | Will Be Compliant        |
| Compliant per AT&T Mobility, LLC's Policy?       | No                       |

The following documents were provided by the client and were utilized to create this report:

**RFDS:** 10034974\_PM201\_180531\_CTL02108 - Carrier Jobs

**CD's:** 10034974\_AE201\_190311\_CTL02108\_Rev5 4-5-6-7-RRH Add Revised










**RF Powers Used:** 10034974\_PM201\_180531\_CTL02108 - Carrier Jobs

## 1.2 Fall Arrest Anchor Point Summary










| Fall Arrest Anchor & Parapet Info | Parapet Available (Y/N) | Parapet Height (inches) | Fall Arrest Anchor Available (Y/N) |
|-----------------------------------|-------------------------|-------------------------|------------------------------------|
| Roof Safety Info                  | N                       | NA                      | N                                  |

### 1.3 Signage Summary

#### a. Existing AT&T Signage

| AT&T Signage Locations |  |  |  |  |  |  |  |  |  |
|------------------------|---|---|---|---|---|--|---|---|---|
|                        | Information 1   | Information 2   | Notice  | Notice 2  | Caution   | Caution 2  | Warning   | Warning 2   | Barriers  |
| Access Point(s)        |   |   |   |   |   |  |   |   |   |
| Alpha                  |   |   |   |   |   |  |   |   |   |
| Beta                   |   |   |   |   |   |  |   |   |   |
| Gamma                  |   |   |   |   |   |  |   |   |   |
| Delta                  |   |   |   |   |   |  |   |   |   |
| Epsilon                |   |   |   |   |   |  |   |   |   |

#### b. Proposed AT&T Signage



| AT&T Signage Locations |  |  |  |  |  |  |  |  |  |
|------------------------|---|---|---|---|---|--|---|---|---|
|                        | Information 1   | Information 2   | Notice  | Notice 2  | Caution   | Caution 2  | Warning   | Warning 2   | Barriers  |
| Access Point(s)        |   |   |   |   |   | 1  |   |   |   |
| Alpha                  |   |   |   |   |   |  |   |   |   |
| Beta                   |   |   |   |   |   |  |   |   |   |
| Gamma                  |   |   |   |   |   |  |   |   |   |
| Delta                  |   |   |   |   |   |  |   |   |   |
| Epsilon                |   |   |   |   |   |  |   |   |   |

## 2 Scale Maps of Site

The following diagrams are included:

- Site Scale Map
- RF Exposure Diagram
- RF Exposure Diagram – Side View

Site Scale Map For: Norwalk West-CT Ave



**Carrier Identification**

- AT&T MOBILITY LLC (Blue circle)
- VERIZON WIRELESS (Red circle)
- T-MOBILE (Pink circle)
- SPRINT (Yellow circle)
- UNKNOWN CARRIER (White circle)

**Sign Legend**

- Caution 1 (Yellow tower icon)
- Caution 2 (Yellow tower icon)
- Notice 2 (Light blue tower icon)
- Notice 1 (Dark blue tower icon)
- Warning (Orange tower icon)
- Warning 2 (Orange tower icon)
- Info 1 (Green 'i' icon)
- Info 2 (Green 'i' icon)
- RSP (RF Safety Plan) (Black square with white text)

**Barrier** (Red solid line)

**Proposed Barriers/ Signs** (Red dashed line)



### 3 Antenna Inventory

The following antenna inventory was obtained by the customer and was utilized to create the site model diagrams:

| Ant ID | Operator                     | Antenna Make & Model | Type  | TX Freq (MHz) | Technology | Az (Deg) | Hor BW (Deg) | Ant Len (ft) | Power | Power Type | Power Unit | Misc Loss | TX Count | Total ERP (Watts) | Ant Gain (dBd) | Z (AGL) | MDT | EDT |
|--------|------------------------------|----------------------|-------|---------------|------------|----------|--------------|--------------|-------|------------|------------|-----------|----------|-------------------|----------------|---------|-----|-----|
| 1      | AT&T MOBILITY LLC            | Powerwave 7770       | Panel | 850           | UMTS       | 143      | 82           | 4.6          | 40    | TPO        | Watt       | 0         | 1        | 566.3             | 11.51          | 150.7'  | 0°  | 8°  |
| 2      | AT&T MOBILITY LLC (Proposed) | Quintel QS66512-2    | Panel | 2100          | LTE        | 30       | 57           | 6            | 160   | TPO        | Watt       | 0         | 1        | 4787.6            | 14.76          | 150'    | 0°  | 4°  |
| 2      | AT&T MOBILITY LLC            | Quintel QS66512-2    | Panel | 737           | LTE        | 30       | 69           | 6            | 60    | TPO        | Watt       | 0         | 1        | 839.8             | 11.46          | 150'    | 0°  | 2°  |
| 2      | AT&T MOBILITY LLC            | Quintel QS66512-2    | Panel | 1900          | LTE        | 30       | 68           | 6            | 160   | TPO        | Watt       | 0         | 1        | 4169.8            | 14.16          | 150'    | 0°  | 4°  |
| 3      | AT&T MOBILITY LLC (Proposed) | Andrew SBNHH-1D65A   | Panel | 763           | LTE        | 30       | 66           | 4.6          | 160   | TPO        | Watt       | 0         | 1        | 2153.4            | 11.29          | 150.7'  | 0°  | 2°  |
| 4      | AT&T MOBILITY LLC (Proposed) | Andrew SBNHH-1D65A   | Panel | 722           | LTE        | 30       | 66           | 4.6          | 80    | TPO        | Watt       | 0         | 1        | 1076.7            | 11.29          | 150.7'  | 0°  | 3°  |
| 4      | AT&T MOBILITY LLC (Proposed) | Andrew SBNHH-1D65A   | Panel | 850           | LTE        | 30       | 61           | 4.6          | 160   | TPO        | Watt       | 0         | 1        | 2244.5            | 11.47          | 150.7'  | 0°  | 2°  |
| 4      | AT&T MOBILITY LLC            | Andrew SBNHH-1D65A   | Panel | 2300          | LTE        | 30       | 61           | 4.6          | 100   | TPO        | Watt       | 0         | 1        | 2691.5            | 14.3           | 150.7'  | 0°  | 3°  |
| 5      | AT&T MOBILITY LLC            | Powerwave 7770       | Panel | 850           | UMTS       | 263      | 82           | 4.6          | 40    | TPO        | Watt       | 0         | 1        | 566.3             | 11.51          | 150.7'  | 0°  | 6°  |
| 6      | AT&T MOBILITY LLC (Proposed) | Quintel QS66512-2    | Panel | 2100          | LTE        | 150      | 57           | 6            | 160   | TPO        | Watt       | 0         | 1        | 4787.6            | 14.76          | 150'    | 0°  | 6°  |
| 6      | AT&T MOBILITY LLC            | Quintel QS66512-2    | Panel | 737           | LTE        | 150      | 69           | 6            | 60    | TPO        | Watt       | 0         | 1        | 839.8             | 11.46          | 150'    | 0°  | 9°  |
| 6      | AT&T MOBILITY LLC            | Quintel QS66512-2    | Panel | 1900          | LTE        | 150      | 68           | 6            | 160   | TPO        | Watt       | 0         | 1        | 4169.8            | 14.16          | 150'    | 0°  | 6°  |
| 7      | AT&T MOBILITY LLC (Proposed) | Andrew SBNHH-1D65A   | Panel | 763           | LTE        | 150      | 66           | 4.6          | 160   | TPO        | Watt       | 0         | 1        | 2153.4            | 11.29          | 150.7'  | 0°  | 9°  |
| 8      | AT&T MOBILITY LLC (Proposed) | Andrew SBNHH-1D65A   | Panel | 722           | LTE        | 150      | 66           | 4.6          | 80    | TPO        | Watt       | 0         | 1        | 1076.7            | 11.29          | 150.7'  | 0°  | 3°  |
| 8      | AT&T MOBILITY LLC (Proposed) | Andrew SBNHH-1D65A   | Panel | 850           | LTE        | 150      | 61           | 4.6          | 160   | TPO        | Watt       | 0         | 1        | 2244.5            | 11.47          | 150.7'  | 0°  | 9°  |
| 8      | AT&T MOBILITY LLC            | Andrew SBNHH-1D65A   | Panel | 2300          | LTE        | 150      | 61           | 4.6          | 100   | TPO        | Watt       | 0         | 1        | 2691.5            | 14.3           | 150.7'  | 0°  | 3°  |
| 9      | AT&T MOBILITY LLC            | Powerwave 7770       | Panel | 850           | UMTS       | 23       | 82           | 4.6          | 40    | TPO        | Watt       | 0         | 1        | 566.3             | 11.51          | 150.7'  | 0°  | 7°  |
| 10     | AT&T MOBILITY LLC (Proposed) | Quintel QS66512-2    | Panel | 2100          | LTE        | 270      | 57           | 6            | 160   | TPO        | Watt       | 0         | 1        | 4787.6            | 14.76          | 150'    | 0°  | 2°  |
| 10     | AT&T MOBILITY LLC            | Quintel QS66512-2    | Panel | 737           | LTE        | 270      | 69           | 6            | 60    | TPO        | Watt       | 0         | 1        | 839.8             | 11.46          | 150'    | 0°  | 6°  |
| 10     | AT&T MOBILITY LLC            | Quintel QS66512-2    | Panel | 1900          | LTE        | 270      | 68           | 6            | 160   | TPO        | Watt       | 0         | 1        | 4169.8            | 14.16          | 150'    | 0°  | 2°  |
| 11     | AT&T MOBILITY LLC (Proposed) | Andrew SBNHH-1D65A   | Panel | 763           | LTE        | 270      | 66           | 4.6          | 160   | TPO        | Watt       | 0         | 1        | 2153.4            | 11.29          | 150.7'  | 0°  | 6°  |
| 12     | AT&T MOBILITY LLC (Proposed) | Andrew SBNHH-1D65A   | Panel | 722           | LTE        | 270      | 66           | 4.6          | 850   | TPO        | Watt       | 0         | 1        | 11439.8           | 11.29          | 150.7'  | 0°  | 3°  |
| 12     | AT&T MOBILITY LLC (Proposed) | Andrew SBNHH-1D65A   | Panel | 850           | LTE        | 270      | 61           | 4.6          | 160   | TPO        | Watt       | 0         | 1        | 2244.5            | 11.47          | 150.7'  | 0°  | 6°  |



| Ant ID | Operator          | Antenna Make & Model | Type  | TX Freq (MHz) | Technology | Az (Deg) | Hor BW (Deg) | Ant Len (ft) | Power | Power Type | Power Unit | Misc Loss | TX Count | Total ERP (Watts) | Ant Gain (dBd) | Z (AGL) | MDT | EDT |
|--------|-------------------|----------------------|-------|---------------|------------|----------|--------------|--------------|-------|------------|------------|-----------|----------|-------------------|----------------|---------|-----|-----|
| 12     | AT&T MOBILITY LLC | Andrew SBNHH-1D65A   | Panel | 2300          | LTE        | 270      | 61           | 4.6          | 100   | TPO        | Watt       | 0         | 1        | 2691.5            | 14.3           | 150.7'  | 0°  | 3°  |

NOTE: X, Y and Z indicate relative position of the bottom of the antenna to the origin location on the site, displayed in the model results diagram. Specifically, the Z reference indicates the bottom of the antenna height above the main site level unless otherwise indicated. The distance to the bottom of the antenna is calculated by subtracting half of the length of the antenna from the antenna centerline. Effective Radiated Power (ERP) is provided by the operator or based on Sitesafe experience. The values used in the modeling may be greater than are currently deployed. For other operators at this site the use of "Generic" as an antenna model or "Unknown" for a wireless operator means the information with regard to operator, their FCC license and/or antenna information was not available nor could it be secured while on site. Other operator's equipment, antenna models and powers used for modeling are based on obtained information or Sitesafe experience.


**Note:** The 2100, 722 and 850 MHz LTE technologies are being added to an existing antenna.

## 4 Emission Predictions



In the RF Exposure Simulations below all heights are reflected with respect to main site level. In most rooftop cases this is the height of the main rooftop and in other cases this can be ground level. Each different height area, rooftop, or platform level is labeled with its height relative to the main site level. Emissions are calculated appropriately based on the relative height and location of that area to all antennas. The total analyzed elevations in the below RF Exposure Simulations are listed below.

- GROUND = 0'


The Antenna Inventory heights are referenced to the same level.




% of FCC Public Exposure Limit  
Spatial average 0' - 6'



# RF Exposure Simulation For: Norwalk West-CT Ave Side View



% of FCC Public Exposure Limit



(Feet)  
 0      17.5      35  
 www.sitesafe.com  
 Site Name: Norwalk West-CT Ave  
 4/12/2019 7:28:52 AM

Sitesafe OET-65 Model  
 Near Field Boundary:  
 1.5 \* Aperture  
 Reflection Factor: 1  
 Single Level (0)

## 5 Site Compliance

### 5.1 Site Compliance Statement

Upon evaluation of the cumulative RF emission levels from all operators at this site, RF hazard signage and antenna locations, Sitesafe has determined that:

AT&T Mobility, LLC will be compliant when the remediation recommended in Section 5.2 or other appropriate remediation is implemented.

The compliance determination is based on General Public RFE levels derived from theoretical modeling, RF signage placement, proposed antenna inventory and the level of restricted access to the antennas at the site. Any deviation from the AT&T Mobility, LLC's proposed deployment plan could result in the site being rendered non-compliant.

Modeling is used for determining compliance and the percentage of MPE contribution.

### 5.2 Actions for Site Compliance

Based on FCC regulations, common industry practice, and our understanding of AT&T Mobility, LLC RF Safety Policy requirements, this section provides a statement of recommendations for site compliance. Recommendations have been proposed based on our understanding of existing access restrictions, signage, and an analysis of predicted RFE levels.

AT&T Mobility, LLC will be made compliant if the following changes are implemented:

#### Site Access Location

(1) Yellow Caution 2B sign(s) required.

#### Notes:

- Signage may already be in place. Sitesafe does not have record of any existing signage because there were no previous visits or data supplied regarding them. All remediation is based on a worst-case scenario.

## 6 Reviewer Certification

The reviewer whose signature appears below hereby certifies and affirms:

That I am an employee of Sitesafe, LLC., in Vienna, Virginia, at which place the staff and I provide RF compliance services to clients in the wireless communications industry; and

That I am thoroughly familiar with the Rules and Regulations of the Federal Communications Commission (FCC) as well as the regulations of the Occupational Safety and Health Administration (OSHA), both in general and specifically as they apply to the FCC Guidelines for Human Exposure to Radio-frequency Radiation; and

That I have thoroughly reviewed this Site Compliance Report and believe it to be true and accurate to the best of my knowledge as assembled by and attested to by Nick Kutzke.

April 12, 2019

## Appendix A – Statement of Limiting Conditions

Sitesafe has provided computer generated model(s) in this Site Compliance Report to show approximate dimensions of the site, and the model is included to assist the reader of the compliance report to visualize the site area, and to provide supporting documentation for Sitesafe's recommendations.

Sitesafe may note in the Site Compliance Report any adverse physical conditions, such as needed repairs, that Sitesafe became aware of during the normal research involved in creating this report. Sitesafe will not be responsible for any such conditions that do exist or for any engineering or testing that might be required to discover whether such conditions exist. Because Sitesafe is not an expert in the field of mechanical engineering or building maintenance, the Site Compliance Report must not be considered a structural or physical engineering report.

Sitesafe obtained information used in this Site Compliance Report from sources that Sitesafe considers reliable and believes them to be true and correct. Sitesafe does not assume any responsibility for the accuracy of such items that were furnished by other parties. When conflicts in information occur between data collected by Sitesafe provided by a second party and data collected by Sitesafe, the data will be used.



## Appendix B – Regulatory Background Information

### FCC Rules and Regulations

In 1996, the Federal Communications Commission (FCC) adopted regulations for the evaluating of the effects of RF emissions in 47 CFR § 1.1307 and 1.1310. The guideline from the FCC Office of Engineering and Technology is Bulletin 65 (“OET Bulletin 65”), *Evaluating Compliance with FCC Guidelines for Human Exposure to Radio Frequency Electromagnetic Fields*, Edition 97-01, published August 1997. Since 1996 the FCC periodically reviews these rules and regulations as per their congressional mandate.

FCC regulations define two separate tiers of exposure limits: Occupational or “Controlled environment” and General Public or “Uncontrolled environment”. The General Public limits are generally five times more conservative or restrictive than the Occupational limit. These limits apply to *accessible* areas where workers or the general public may be exposed to Radio Frequency (RF) electromagnetic fields.


Occupational or Controlled limits apply in situations in which persons are exposed as a consequence of their employment and where those persons exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.

An area is considered a Controlled environment when access is limited to these aware personnel. Typical criteria are restricted access (i.e. locked or alarmed doors, barriers, etc.) to the areas where antennas are located coupled with proper RF warning signage. A site with Controlled environments is evaluated with Occupational limits.

All other areas are considered Uncontrolled environments. If a site has no access controls or no RF warning signage it is evaluated with General Public limits.

The theoretical modeling of the RF electromagnetic fields has been performed in accordance with OET Bulletin 65. The Maximum Permissible Exposure (MPE) limits utilized in this analysis are outlined in the following diagram:

**FCC Limits for Maximum Permissible Exposure (MPE)**  
Plane-wave Equivalent Power Density



### Limits for Occupational/Controlled Exposure (MPE)

| Frequency Range (MHz) | Electric Field Strength (E) (V/m) | Magnetic Field Strength (H) (A/m) | Power Density (S) (mW/cm <sup>2</sup> ) | Averaging Time  E  <sup>2</sup> ,  H  <sup>2</sup> or S (minutes) |
|-----------------------|-----------------------------------|-----------------------------------|---|---|
| 0.3-3.0               | 614                               | 1.63                              | (100)*                                  | 6   |
| 3.0-30                | 1842/f                            | 4.89/f                            | (900/f <sup>2</sup> )*                  | 6   |
| 30-300                | 61.4                              | 0.163                             | 1.0                                     | 6   |
| 300-1500              | --                                | --                                | f/300                                   | 6   |
| 1500-100,000          | --                                | --                                | 5                                       | 6   |

### Limits for General Population/Uncontrolled Exposure (MPE)

| Frequency Range (MHz) | Electric Field Strength (E) (V/m) | Magnetic Field Strength (H) (A/m) | Power Density (S) (mW/cm <sup>2</sup> ) | Averaging Time  E  <sup>2</sup> ,  H  <sup>2</sup> or S (minutes) |
|-----------------------|-----------------------------------|-----------------------------------|---|---|
| 0.3-1.34              | 614                               | 1.63                              | (100)*                                  | 30  |
| 1.34-30               | 824/f                             | 2.19/f                            | (180/f <sup>2</sup> )*                  | 30  |
| 30-300                | 27.5                              | 0.073                             | 0.2                                     | 30  |
| 300-1500              | --                                | --                                | f/1500                                  | 30  |
| 1500-100,000          | --                                | --                                | 1.0                                     | 30  |

f = frequency in MHz

\*Plane-wave equivalent power density

### OSHA Statement

The General Duty clause of the OSHA Act (Section 5) outlines the occupational safety and health responsibilities of the employer and employee. The General Duty clause in Section 5 states:

(a) Each employer –

- (1) shall furnish to each of his employees employment and a place of employment which are free from recognized hazards that are causing or are likely to cause death or serious physical harm to his employees;
- (2) shall comply with occupational safety and health standards promulgated under this Act.

(b) Each employee shall comply with occupational safety and health standards and all rules, regulations, and orders issued pursuant to this Act which are applicable to his own actions and conduct.

OSHA has defined Radiofrequency and Microwave Radiation safety standards for workers who may enter hazardous RF areas. Regulation Standards 29 CFR § 1910.147 identify a generic Lock Out Tag Out procedure aimed to control the unexpected energization or start up of machines when maintenance or service is being performed.

## Appendix C – Safety Plan and Procedures

The following items are general safety recommendations that should be administered on a site by site basis as needed by the carrier.

**General Maintenance Work:** Any maintenance personnel required to work immediately in front of antennas and / or in areas indicated as above 100% of the Occupational MPE limits should coordinate with the wireless operators to disable transmitters during their work activities.

**Training and Qualification Verification:** All personnel accessing areas indicated as exceeding the General Population MPE limits should have a basic understanding of EME awareness and RF Safety procedures when working around transmitting antennas. Awareness training increases a workers understanding to potential RF exposure scenarios. Awareness can be achieved in a number of ways (e.g. videos, formal classroom lecture or internet based courses).

**Physical Access Control:** Access restrictions to transmitting antennas locations is the primary element in a site safety plan. Examples of access restrictions are as follows:

- Locked door or gate
- Alarmed door
- Locked ladder access
- Restrictive Barrier at antenna (e.g. Chain link with posted RF Sign)

**RF Signage:** Everyone should obey all posted signs at all times. RF signs play an important role in properly warning a worker prior to entering into a potential RF Exposure area.

**Assume all antennas are active:** Due to the nature of telecommunications transmissions, an antenna transmits intermittently. Always assume an antenna is transmitting. Never stop in front of an antenna. If you have to pass by an antenna, move through as quickly and safely as possible thereby reducing any exposure to a minimum.

**Maintain a 3 foot clearance from all antennas:** There is a direct correlation between the strength of an EME field and the distance from the transmitting antenna. The further away from an antenna, the lower the corresponding EME field is.

**Site RF Emissions Diagram:** Section 4 of this report contains an RF Diagram that outlines various theoretical Maximum Permissible Exposure (MPE) areas at the site. The modeling is a worst case scenario assuming a duty cycle of 100% for each transmitting antenna at full power. This analysis is based on one of two access control criteria: General Public criteria means the access to the site is uncontrolled and anyone can gain access. Occupational criteria means the access is restricted and only properly trained individuals can gain access to the antenna locations.

## Appendix D – RF Emissions

The RF Emissions Simulation(s) in this report display theoretical spatially averaged percentage of the Maximum Permissible Exposure for all systems at the site unless otherwise noted. These diagrams use modeling as prescribed in OET Bulletin 65 and assumptions detailed in Appendix E.

The key at the bottom of each RF Emissions Simulation indicates percentages displayed referenced to FCC General Public Maximum Permissible Exposure (MPE) limits. Color coding on the diagram is as follows:

- Areas indicated as Gray are predicted to be below 5% of the MPE limits. Gray represents areas more than 20 times below the most conservative exposure limit.
- Green represents areas are predicted to be between 5% and 100% of the MPE limits. **Green areas are accessible to anyone.**
- Blue represents areas predicted to exceed the General Public MPE limits but are less than Occupational limits. **Blue areas should be accessible only to RF trained workers.**
- Yellow represents areas predicted to exceed Occupational MPE limits. Yellow areas should be accessible only to RF trained workers able to assess current exposure levels.
- Red represents areas predicted to have exposure more than 10 times the Occupational MPE limits. **Red indicates that the RF levels must be reduced prior to access.** An RF Safety Plan is required which outlines how to reduce the RF energy in these areas prior to access.

## Appendix E – Assumptions and Definitions

### General Model Assumptions

In this site compliance report, it is assumed that all antennas are operating at **full power at all times**. Software modeling was performed for all transmitting antennas located on the site. Sitesafe has further assumed a 100% duty cycle and maximum radiated power.

The modeling is based on recommendations from the FCC's OET-65 bulletin with the following variances per AT&T guidance. Reflection has not been considered in the modeling, i.e. the reflection factor is 1.0. The near / far field boundary has been set to 1.5 times the aperture height of the antenna and modeling beyond that point is the lesser of the near field cylindrical model and the far field model taking into account the gain of the antenna.

The site has been modeled with these assumptions to show the maximum RF energy density. Areas modeled with exposure greater than 100% of the General Public MPE level may not actually occur, but are shown as a prediction that could be realized. Sitesafe believes these areas to be safe for entry by occupationally trained personnel utilizing appropriate personal protective equipment (in most cases, a personal monitor).

### Use of Generic Antennas

For the purposes of this report, the use of "Generic" as an antenna model, or "Unknown" for an operator means the information about a carrier, their FCC license and/or antenna information was not provided and could not be obtained while on site. In the event of unknown information, Sitesafe will use our industry specific knowledge of equipment, antenna models, and transmit power to model the site. If more specific information can be obtained for the unknown measurement criteria, Sitesafe recommends remodeling of the site utilizing the more complete and accurate data. Information about similar facilities is used when the service is identified and associated with a particular antenna. If no information is available regarding the transmitting service associated with an unidentified antenna, using the antenna manufacturer's published data regarding the antenna's physical characteristics makes more conservative assumptions.

Where the frequency is unknown, Sitesafe uses the closest frequency in the antenna's range that corresponds to the highest Maximum Permissible Exposure (MPE), resulting in a conservative analysis.

## Definitions

**5% Rule** – The rules adopted by the FCC specify that, in general, at multiple transmitter sites actions necessary to bring the area into compliance with the guidelines are the shared responsibility of all licensees whose transmitters produce field strengths or power density levels at the area in question in excess of 5% of the exposure limits. In other words, any wireless operator that contributes 5% or greater of the MPE limit in an area that is identified to be greater than 100% of the MPE limit is responsible taking corrective actions to bring the site into compliance.

**Compliance** – The determination of whether a site is safe or not with regards to Human Exposure to Radio Frequency Radiation from transmitting antennas.

**Decibel (dB)** – A unit for measuring power or strength of a signal.

**Duty Cycle** – The percent of pulse duration to the pulse period of a periodic pulse train. Also, may be a measure of the temporal transmission characteristic of an intermittently transmitting RF source such as a paging antenna by dividing average transmission duration by the average period for transmission. A duty cycle of 100% corresponds to continuous operation.

**Effective (or Equivalent) Isotropic Radiated Power (EIRP)** – The product of the power supplied to the antenna and the antenna gain in a given direction relative to an isotropic antenna.

**Effective Radiated Power (ERP)** – In a given direction, the relative gain of a transmitting antenna with respect to the maximum directivity of a half wave dipole multiplied by the net power accepted by the antenna from the connecting transmitter.

**Gain (of an antenna)** – The ratio of the maximum intensity in a given direction to the maximum radiation in the same direction from an isotropic radiator. Gain is a measure of the relative efficiency of a directional antennas as compared to an omni directional antenna.

**General Population/Uncontrolled Environment** – Defined by the FCC, as an area where exposure to RF energy may occur to persons who are **unaware** of the potential for exposure and who have no control of their exposure. General Population is also referenced as General Public.

**Generic Antenna** – For the purposes of this report, the use of "Generic" as an antenna model means the antenna information was not provided and could not be obtained while on site. In the event of unknown information, Sitesafe will use our industry specific knowledge of antenna models to select a worst case scenario antenna to model the site.

**Isotropic Antenna** – An antenna that is completely non-directional. In other words, an antenna that radiates energy equally in all directions.

**Maximum Measurement** – This measurement represents the single largest measurement recorded when performing a spatial average measurement.

**Maximum Permissible Exposure (MPE)** – The maximum levels of RF exposure a person may be exposed to without harmful effect and with acceptable safety factor.

**Occupational/Controlled Environment** – Defined by the FCC, as an area where Radio Frequency Radiation (RFR) exposure may occur to persons who are aware of the

potential for exposure as a condition of employment or specific activity and can exercise control over their exposure.

**OET Bulletin 65** – Technical guideline developed by the FCC's Office of Engineering and Technology to determine the impact of Radio Frequency radiation on Humans. The guideline was published in August 1997.

**OSHA (Occupational Safety and Health Administration)** – Under the Occupational Safety and Health Act of 1970, employers are responsible for providing a safe and healthy workplace for their employees. OSHA's role is to promote the safety and health of America's working men and women by setting and enforcing standards; providing training, outreach and education; establishing partnerships; and encouraging continual process improvement in workplace safety and health. For more information, visit [www.osha.gov](http://www.osha.gov).

**Radio Frequency (RF)** – The frequencies of electromagnetic waves which are used for radio communications. Approximately 3 kHz to 300 GHz.

**Radio Frequency Exposure (RFE)** – The amount of RF power density that a person is or might be exposed to.

**Spatial Average Measurement** – A technique used to average a minimum of ten (10) measurements taken in a ten (10) second interval from zero (0) to six (6) feet. This measurement is intended to model the average power density an average sized human will be exposed to at a location.

**Transmitter Power Output (TPO)** – The radio frequency output power of a transmitter's final radio frequency stage as measured at the output terminal while connected to a load.

## Appendix F – References

The following references can be followed for further information about RF Health and Safety.

Sitesafe, LLC.

<http://www.sitesafe.com>

FCC Radio Frequency Safety

<http://www.fcc.gov/encyclopedia/radio-frequency-safety>

National Council on Radiation Protection and Measurements (NCRP)

<http://www.ncrponline.org>

Institute of Electrical and Electronics Engineers, Inc., (IEEE)

<http://www.ieee.org>

American National Standards Institute (ANSI)

<http://www.ansi.org>

Environmental Protection Agency (EPA)

<http://www.epa.gov/radtown/wireless-tech.html>

National Institutes of Health (NIH)

<http://www.niehs.nih.gov/health/topics/agents/emf/>

Occupational Safety and Health Agency (OSHA)

<http://www.osha.gov/SLTC/radiofrequencyradiation/>

International Commission on Non-Ionizing Radiation Protection (ICNIRP)

<http://www.icnirp.org>

World Health Organization (WHO)

<http://www.who.int/peh-emf/en/>

National Cancer Institute

<http://www.cancer.gov/cancertopics/factsheet/Risk/cellphones>

American Cancer Society (ACS)

[http://www.cancer.org/docroot/PED/content/PED\\_1\\_3X\\_Cellular\\_Phone\\_Towers.asp?sitearea=PED](http://www.cancer.org/docroot/PED/content/PED_1_3X_Cellular_Phone_Towers.asp?sitearea=PED)

European Commission Scientific Committee on Emerging and Newly Identified Health Risks

[http://ec.europa.eu/health/ph\\_risk/committees/04\\_scenihp/docs/scenihp\\_o\\_022.pdf](http://ec.europa.eu/health/ph_risk/committees/04_scenihp/docs/scenihp_o_022.pdf)

Fairfax County, Virginia Public School Survey

<http://www.fcps.edu/fts/safety-security/RFEESurvey/>

UK Health Protection Agency Advisory Group on Non-ionising Radiation

[http://www.hpa.org.uk/webw/HPAweb&HPAwebStandard/HPAweb\\_C/1317133826368](http://www.hpa.org.uk/webw/HPAweb&HPAwebStandard/HPAweb_C/1317133826368)

Norwegian Institute of Public Health

<http://www.fhi.no/dokumenter/545eea7147.pdf>



# 600 CONNECTICUT AVE

**Location** 600 CONNECTICUT AVE

**Mblu** 5/ 69/ 61/ 0/

**Acct#** 22907

**Owner** HOME DEPOT USA INC

**Assessment** \$26,703,250

**Appraisal** \$38,147,500

**PID** 22907

**Building Count** 2

## Current Value

| Appraisal      |              |              |              |
|----------------|--------------|--------------|--------------|
| Valuation Year | Improvements | Land         | Total        |
| 2018           | \$19,132,950 | \$19,014,550 | \$38,147,500 |

| Assessment     |              |              |              |
|----------------|--------------|--------------|--------------|
| Valuation Year | Improvements | Land         | Total        |
| 2018           | \$13,393,060 | \$13,310,190 | \$26,703,250 |

## Owner of Record

**Owner** HOME DEPOT USA INC

**Sale Price** \$17,750,000

**Co-Owner**

**Certificate**

**Address** ATTN PROP TAX DEPT #6204  
PO BOX 105842  
ATLANTA, GA 30348-5842

**Book & Page** 3254/22

**Sale Date** 09/06/1996

**Instrument** 25

## Ownership History

| Ownership History           |              |             |             |            |            |
|-----------------------------|--------------|-------------|-------------|------------|------------|
| Owner                       | Sale Price   | Certificate | Book & Page | Instrument | Sale Date  |
| HOME DEPOT USA INC          | \$17,750,000 |             | 3254/22     | 25         | 09/06/1996 |
| BTS NORWALK LIMITED PRTNR   | \$17,750,000 |             | 3254/22     |            | 09/06/1996 |
| HOBBS ENGINEERING COMPANY   | \$0          |             | 2237/206    |            | 08/08/1988 |
| HOBBS INTERNATIONAL INC     | \$0          |             | 1357/237    | 07         | 06/24/1981 |
| HOBBS EQUIPMENT COMPANY INC | \$0          |             | 0/0         |            |            |

## Building Information

### Building 1 : Section 1

**Year Built:** 1996

**Living Area:** 115,146

**Replacement Cost:** \$16,046,089

**Building Percent** 86

**Good:**

**Replacement Cost**

**Less Depreciation:** \$13,799,640

| Building Attributes |                     |
|---------------------|---------------------|
| Field               | Description         |
| STYLE               | Retail              |
| MODEL               | Commercial          |
| Grade               | A                   |
| Stories:            | 1.00                |
| Occupancy           | 1.00                |
| Exterior Wall 1     | Precast Panel       |
| Exterior Wall 2     |                     |
| Roof Structure      | Flat                |
| Roof Cover          | Rolled Compos       |
| Interior Wall 1     | Minimum             |
| Interior Wall 2     |                     |
| Interior Floor 1    | Concrete            |
| Interior Floor 2    |                     |
| Heating Fuel        | Gas                 |
| Heating Type        | Forced Air          |
| AC Percent          | 100                 |
| Heat Percent        | 100                 |
| Bldg Use            | Commercial Improved |
| Total Rooms         | 0                   |
| Bedrooms            | 0                   |
| Full Baths          | 0                   |
| Half Baths          | 2                   |
| Extra Fixtures      | 2                   |
| FBM Area            |                     |
| Heat/AC             | Heat/AC Pkg         |
| Frame               | Steel               |
| Plumbing            | Average             |
| Foundation          | Slab                |
| Partitions          | Light               |
| Wall Height         | 26.00               |
| % Sprinkler         | 100.00              |

**Building 2 : Section 1**

**Year Built:** 1996

**Living Area:** 172,328


**Replacement Cost:** \$7,229,160

**Building Photo**



(<http://images.vgsi.com/photos/NorwalkCTPhotos//00\00\67\32>).

**Building Layout**



(ParcelSketch.ashx?pid=22907&bid=22907)

| Building Sub-Areas (sq ft) |             |            | Legend      |
|----------------------------|-------------|------------|-------------|
| Code                       | Description | Gross Area | Living Area |
| BAS                        | First Floor | 115,146    | 115,146     |
| CAN                        | Canopy      | 5,250      | 0           |
|                            |             | 120,396    | 115,146     |

**Building Percent** 86  
**Good:**  
**Replacement Cost**  
**Less Depreciation:** \$6,217,080

**Building Attributes : Bldg 2 of 2**


| Field            | Description         |
|------------------|---------------------|
| STYLE            | Parking Garage      |
| MODEL            | Commercial          |
| Grade            | C                   |
| Stories:         | 1.00                |
| Occupancy        | 1.00                |
| Exterior Wall 1  | Vinyl Siding        |
| Exterior Wall 2  |                     |
| Roof Structure   | Flat                |
| Roof Cover       | Tar and Gravel      |
| Interior Wall 1  | Minimum             |
| Interior Wall 2  |                     |
| Interior Floor 1 | Concrete            |
| Interior Floor 2 |                     |
| Heating Fuel     | None                |
| Heating Type     | None                |
| AC Percent       | 0                   |
| Heat Percent     | 100                 |
| Bldg Use         | Commercial Improved |
| Total Rooms      | 0                   |
| Bedrooms         | 0                   |
| Full Baths       | 0                   |
| Half Baths       | 0                   |
| Extra Fixtures   | 0                   |
| FBM Area         |                     |
| Heat/AC          | None                |
| Frame            | Masonry             |
| Plumbing         | Average             |
| Foundation       | Poured Conc         |
| Partitions       | Average             |
| Wall Height      | 8.00                |
| % Sprinkler      | 0.00                |

**Building Photo**



(<http://images.vgsi.com/photos/NorwalkCTPhotos//00\00\90\30>).

**Building Layout**



(ParcelSketch.ashx?pid=22907&bid=50840)

| Building Sub-Areas (sq ft) |                      |            | Legend      |
|----------------------------|----------------------|------------|-------------|
| Code                       | Description          | Gross Area | Living Area |
| BAS                        | First Floor          | 86,164     | 86,164      |
| FUS                        | Finished Upper Story | 86,164     | 86,164      |
|                            |                      | 172,328    | 172,328     |

**Extra Features**

| Extra Features |             |      |       | Legend |
|----------------|-------------|------|-------|--------|
| Code           | Description | Size | Value | Bldg # |

|      |            |                |           |   |
|------|------------|----------------|-----------|---|
| ELV1 | Commercial | 2.00 STOP      | \$25,000  | 1 |
| SPR  | Sprinklers | 115146.00 S.F. | \$287,870 | 1 |

## Land

### Land Use

**Use Code** 201V  
**Description** Commercial Improved  
**Zone** B2  
**Neighborhood** C320

### Land Line Valuation

**Size (Acres)** 9.75  
**Frontage**  
**Depth**  
**Assessed Value** \$13,310,190  
**Appraised Value** \$19,014,550

## Outbuildings

| Outbuildings |              |          |                 |              |          | Legend |
|--------------|--------------|----------|-----------------|--------------|----------|--------|
| Code         | Description  | Sub Code | Sub Description | Size         | Value    | Bldg # |
| LT1          | Light 1      |          |                 | 7.00 UNITS   | \$5,030  | 1      |
| PAV1         | Paving Asph. |          |                 | 5000.00 S.F. | \$6,500  | 1      |
| FUEL         | Fuel Cell    | Ext      | Energy Cell     | 200.00 KW    | \$64,800 | 1      |

## Valuation History

| Appraisal      |              |              |              |
|----------------|--------------|--------------|--------------|
| Valuation Year | Improvements | Land         | Total        |
| 2018           | \$19,132,950 | \$19,014,550 | \$38,147,500 |
| 2017           | \$13,900,880 | \$15,832,340 | \$29,733,220 |
| 2016           | \$13,900,880 | \$15,832,340 | \$29,733,220 |

| Assessment     |              |              |              |
|----------------|--------------|--------------|--------------|
| Valuation Year | Improvements | Land         | Total        |
| 2018           | \$13,393,060 | \$13,310,190 | \$26,703,250 |
| 2017           | \$9,730,620  | \$11,082,640 | \$20,813,260 |
| 2016           | \$9,730,620  | \$11,082,640 | \$20,813,260 |

(c) 2019 Vision Government Solutions, Inc. All rights reserved.



Date: **May 16, 2019**

Cheryl Schultz  
Crown Castle  
3530 Toringdon Way, Suite 300  
Charlotte, NC 28277

Crown Castle  
2000 Corporate Drive  
Canonsburg, PA 15317  
(724) 416-2000

**Subject:** **Structural Opinion Letter**

**Carrier Designation:** **AT&T Mobility Co-Locate**  
**Carrier Site Number:** NORWALK WEST - CT Ave  
**Carrier Site Name:** CTL02108

**Crown Castle Designation:** **Crown Castle BU Number:** 841287  
**Crown Castle Site Name:** NORWALK WEST- CT AVE  
**Crown Castle JDE Number:** 482696  
**Crown Castle Work Order Number:** 1741809  
**Crown Castle Order Number:** 424185 Rev. 3

**Engineering Firm Designation:** **Crown Castle Project Number:** 1741809

**Site Data:** **600 Connecticut Ave, NORWALK, FAIRFIELD County, CT**  
**Latitude: 41° 5' 49.45" Longitude: -73° 26' 56.61"**  
**150 ft - Monopole**

Dear Cheryl Schultz,

Crown Castle is pleased to submit this "**Structural Opinion Letter**" to determine the structural integrity of the above mentioned tower.

The purpose of the opinion letter is to determine the suitability of the tower. This opinion is consistent with the guidelines as stated in the TIA-222-G standard and the 2018 Connecticut State Building Code based upon an ultimate 3-second gust wind speed of 120 mph.

Based on a comparison of the previous analysis loads (Crown Castle Work Order Number: 1522401/Previous Structural Analysis dated March 1, 2018) with the loads listed in Table 1, we have determined the tower structure and foundation **ARE** sufficient.

Respectfully submitted by:

Terry P. Styran, P.E.  
Senior Project Engineer



5/16/2019

**Table 1 - Proposed Antenna and Cable Information**

| Mounting Level (ft) | Center Line Elevation (ft) | Number of Antennas | Antenna Manufacturer   | Antenna Model             | Number of Feed Lines | Feed Line Size (in)             |
|---------------------|----------------------------|--------------------|------------------------|---------------------------|----------------------|---------------------------------|
| 152.0               | 152.0                      | 6                  | andrew                 | SBNHH-1D65A w/ Mount Pipe | 4<br>6<br>12<br>2    | 3/8<br>3/4<br>1-5/8<br>Conduits |
|                     |                            | 3                  | ericsson               | RRUS 11 B12               |                      |                                 |
|                     |                            | 3                  | ericsson               | RRUS 32                   |                      |                                 |
|                     |                            | 3                  | ericsson               | RRUS 32 B2                |                      |                                 |
|                     |                            | 3                  | ericsson               | RRUS 32 B66               |                      |                                 |
|                     |                            | 3                  | ericsson               | RRUS 4478 B14             |                      |                                 |
|                     |                            | 6                  | powerwave technologies | 7020.00                   |                      |                                 |
|                     |                            | 3                  | powerwave technologies | 7770.00 w/ Mount Pipe     |                      |                                 |
|                     |                            | 6                  | powerwave technologies | LGP21401                  |                      |                                 |
|                     |                            | 3                  | quintel technology     | QS66512-2 w/ Mount Pipe   |                      |                                 |
|                     |                            | 3                  | raycap                 | DC6-48-60-18-8F           |                      |                                 |
|                     |                            | 1                  | tower mounts           | Platform Mount [LP 603-1] |                      |                                 |
|                     |                            | 1                  | tower mounts           | Side Arm Mount [SO 102-3] |                      |                                 |
|                     |                            | 1                  | tower mounts           | Side Arm Mount [SO 202-3] |                      |                                 |



PROJECT: 4C/5C/6C/7C/RRH ADD  
 SITE NUMBER: CTL02108  
 FA NUMBER: 10034974  
 PTN NUMBER: 2051A0D0Q3, 2051A0CZR8, 2051A0CZJM, 2051A0EDXG, 2051A0494T  
 PACE NUMBER: MRCTB025283, MRCTB025338, MRCTB025304, MRCTB026716, MRCTB017068  
 CROWN BU#: 841287  
 SITE NAME: NORWALK WEST-CT AVE.  
 SITE ADDRESS: 613 CONNECTICUT AVENUE  
 NORWALK, CT 06850



**PROJECT INFORMATION**

**SITE NAME:** NORWALK WEST-CT AVE.  
**SITE NUMBER:** CTL02108  
**SITE ADDRESS:** 613 CONNECTICUT AVENUE NORWALK, CT 06850  
**FA NUMBER:** 10034974  
**PTN NUMBER:** 2051A0D0Q3, 2051A0CZR8, 2051A0CZJM, 2051A0EDXG, 2051A0494T  
**PACE NUMBER:** MRCTB025283, MRCTB025338, MRCTB025304, MRCTB026716, MRCTB017068  
**USID NUMBER:** 60395  
**CROWN BU#:** 841287  
**APPLICANT:** AT&T WIRELESS  
 550 COCHITUATE ROAD SUITE 550 13 AND 14 FRAMINGHAM, MA 01701  
**TOWER OWNER:** CROWN CASTLE INTERNATIONAL  
 12 GILL STREET, SUITE 5800 WOBURN, MA 01801  
**JURISDICTION:** CITY OF NORWALK  
**COUNTY:** FAIRFIELD  
**SITE COORDINATES FROM (RFDS)**  
**LATITUDE:** 41.097075°  
**LONGITUDE:** -73.449055°  
**GROUND ELEV.:** 152'  
**PROPOSED USE:** TELECOMMUNICATIONS FACILITY  
**AT&T RF MANAGER:** DEEPAK RATHORE  
**PHONE:** (860) 965-3068  
**EMAIL:** dr701e@att.com

**SCOPE OF WORK**

LTE 850/700/AWS/700 WILL BE 4C/5C/6C/7C/RRH ADD AT THE SITE WITH BRONZE CONFIGURATION. PROPOSED 4C/5C/6C/7C/RRH ADD PROJECT SCOPE HEREIN BASED ON RFDS ID # 1811293, VERSION 3.00 LAST UPDATED 03/28/18 & RFDS ID # 1000709, VERSION 4 LAST UPDATED 07/12/2017.

- (6) NEW ANTENNAS TO REPLACE (3) EXISTING ANTENNAS
- (3) NEW RRUS-32 B66
- (3) NEW RRUS-4478 B14
- (3) NEW RRUS-E2 B29
- (3) NEW RRUS-4478 B5
- (1) NEW RAYCAP UNIT, (2) DC POWER CABLES
- INSTALL 2ND XMU & IDL
- UPGRADE (2) EXISTING DUS W/ (2) NEW 5216

CONTRACTOR SHALL FURNISH ALL MATERIAL WITH THE EXCEPTION OF AT&T SUPPLIED MATERIAL.  
 ALL MATERIAL SHALL BE INSTALLED BY THE CONTRACTOR, UNLESS STATED OTHERWISE.

**APPLICABLE BUILDING CODES AND STANDARDS**

ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES.

**BUILDING CODE:** 2012 INTERNATIONAL BUILDING CODE  
 2018 CONNECTICUT STATE BUILDING CODE SUPPLEMENT

**ELECTRICAL CODE:** 2014 NATIONAL ELECTRIC CODE


- FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION.
- ADA ACCESS REQUIREMENTS ARE NOT REQUIRED.
- THIS FACILITY DOES NOT REQUIRE POTABLE WATER AND WILL NOT PRODUCE ANY SEWAGE

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



**SITE LOCATION MAP**



**DRAWING INDEX**

|     |                               |
|-----|-------------------------------|
| T1  | TITLE SHEET                   |
| SP1 | NOTES AND SPECIFICATIONS      |
| SP2 | NOTES AND SPECIFICATIONS      |
| A1  | COMPOUND PLAN                 |
| A2  | EQUIPMENT PLAN                |
| A3  | ELEVATIONS                    |
| A4  | ANTENNA PLANS                 |
| A5  | EQUIPMENT DETAILS             |
| A5A | MOUNTING DETAILS              |
| A6  | ANTENNA & CABLE CONFIGURATION |
| A7  | CABLE NOTES AND COLOR CODING  |
| A8  | GROUNDING DETAILS             |
| A9  | PLUMBING DIAGRAMS             |
| A9A | PLUMBING DIAGRAMS             |

**PROJECT CONSULTANTS**

**PROJECT MANAGER:** SMARTLINK  
 85 RANGEWAY ROAD, SUITE 102 NORTH BILLERICA, MA 01862  
**CONTACT:** EDWARD WEISSMAN (917) 528-1857  
**EMAIL:** Edward.Weissman@smartlinkllc.com

**SITE ACQUISITION:** SMARTLINK  
 85 RANGEWAY ROAD, SUITE 102 NORTH BILLERICA, MA 01862  
**CONTACT:** SHARON KEEFE (978) 930-3918  
**EMAIL:** Sharon.Keefe@smartlinkllc.com

**ENGINEER/ARCHITECT:** FULLERTON ENGINEERING  
 1100 E. WOODFIELD ROAD, SUITE 500 SCHAUMBURG, IL 60173  
**CONTACT:** MILEN DIMITROV (847) 908-8439  
**EMAIL:** MDimitrov@FullertonEngineering.com

**CONSTRUCTION:** SMARTLINK  
 85 RANGEWAY ROAD, SUITE 102 NORTH BILLERICA, MA 01862  
**CONTACT:** MARK DONNELLY (617) 515-2080  
**EMAIL:** mark.donnelly@smartlinkllc.com

**DIRECTIONS**

SCAN QR CODE FOR LINK TO SITE LOCATION MAP



NOTE: DRAWING SCALES ARE FOR 11"x17" SHEETS UNLESS OTHERWISE NOTED

SITE NAME  
**NORWALK WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
**613 CONNECTICUT AVENUE NORWALK, CT 06850**

SHEET NAME  
**TITLE SHEET**

SHEET NUMBER  
**T1**

**GENERAL CONSTRUCTION**

1. FOR THE PURPOSE OF CONSTRUCTION DRAWINGS, THE FOLLOWING DEFINITIONS SHALL APPLY:  
CONTRACTOR/CM – SMARTLINK  
OWNER – AT&T WIRELESS
2. ALL SITE WORK SHALL BE COMPLETED AS INDICATED ON THE DRAWINGS AND AT&T PROJECT SPECIFICATIONS.
3. GENERAL CONTRACTOR SHALL VISIT THE SITE AND SHALL FAMILIARIZE HIMSELF WITH ALL CONDITIONS AFFECTING THE PROPOSED WORK AND SHALL MAKE PROVISIONS. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS, DIMENSIONS, AND CONFIRMING THAT THE WORK MAY BE ACCOMPLISHED AS SHOWN PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK.
4. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES. GENERAL CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS, AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF WORK.
5. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES, AND APPLICABLE REGULATIONS.
6. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES, AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
7. PLANS ARE NOT TO BE SCALED. THESE PLANS ARE INTENDED TO BE A DIAGRAMMATIC OUTLINE ONLY UNLESS OTHERWISE NOTED. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS OTHERWISE NOTED. SPACING BETWEEN EQUIPMENT IS THE MINIMUM REQUIRED CLEARANCE. THEREFORE, IT IS CRITICAL TO FIELD VERIFY DIMENSIONS, SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE ENGINEER PRIOR TO PROCEEDING WITH THE WORK. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF WORK AND PREPARED BY THE ENGINEER PRIOR TO PROCEEDING WITH WORK.
8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
9. IF THE SPECIFIED EQUIPMENT CANNOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION SPACE FOR APPROVAL BY THE ENGINEER PRIOR TO PROCEEDING.
10. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF WORK AREA, ADJACENT AREAS AND BUILDING OCCUPANTS THAT ARE LIKELY TO BE AFFECTED BY THE WORK UNDER THIS CONTRACT. WORK SHALL CONFIRM TO ALL OSHA REQUIREMENTS AND THE LOCAL JURISDICTION.
11. GENERAL CONTRACTOR SHALL COORDINATE WORK AND SCHEDULE WORK ACTIVITIES WITH OTHER DISCIPLINES.
12. ERECTION SHALL BE DONE IN A WORKMANLIKE MANNER BY COMPETENT EXPERIENCED WORKMAN IN ACCORDANCE WITH APPLICABLE CODES AND THE BEST ACCEPTED PRACTICE. ALL MEMBERS SHALL BE LAID PLUMB AND TRUE AS INDICATED ON THE DRAWINGS.
13. SEAL PENETRATIONS THROUGH FIRE RATED AREAS WITH UL LISTED MATERIALS APPROVED BY LOCAL JURISDICTION. CONTRACTOR SHALL KEEP AREA CLEAN, HAZARD FREE, AND DISPOSE OF ALL DEBRIS.
14. WORK PREVIOUSLY COMPLETED IS REPRESENTED BY LIGHT SHADED LINES AND NOTES. THE SCOPE OF WORK FOR THIS PROJECT IS REPRESENTED BY DARK SHADED LINES AND NOTES. CONTRACTOR SHALL NOTIFY THE GENERAL CONTRACTOR OF ANY EXISTING CONDITIONS THAT DEVIATE FROM THE DRAWINGS PRIOR TO BEGINNING CONSTRUCTION.
15. CONTRACTOR SHALL PROVIDE WRITTEN NOTICE TO THE CONSTRUCTION MANAGER 48 HOURS PRIOR TO COMMENCEMENT OF WORK.
16. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.
17. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES PRIOR TO THE START OF CONSTRUCTION.
18. GENERAL CONTRACTOR SHALL COORDINATE AND MAINTAIN ACCESS FOR ALL TRADES AND CONTRACTORS TO THE SITE AND/OR BUILDING.
19. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR SECURITY OF THE SITE FOR THE DURATION OF CONSTRUCTION UNTIL JOB COMPLETION.

20. THE GENERAL CONTRACTOR SHALL MAINTAIN IN GOOD CONDITION ONE COMPLETE SET OF PLANS WITH ALL REVISIONS, ADDENDA, AND CHANGE ORDERS ON THE PREMISES AT ALL TIMES.
21. THE GENERAL CONTRACTOR SHALL PROVIDE PORTABLE FIRE EXTINGUISHERS WITH A RATING OF NOT LESS THAN 2-A OR 2-A:10-B:C AND SHALL BE WITHIN 25 FEET OF TRAVEL DISTANCE TO ALL PORTIONS OF WHERE THE WORK IS BEING COMPLETED DURING CONSTRUCTION.
22. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC, AND OTHER UTILITIES SHALL BE PROTECTED AT ALL TIMES, AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY THE ENGINEER. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS SHALL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION, B) CONFINED SPACE, C) ELECTRICAL SAFETY, AND D) TRENCHING & EXCAVATION.
23. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC, AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED, CAPPED, PLUGGED OR OTHERWISE DISCONNECTED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, AS DIRECTED BY THE RESPONSIBLE ENGINEER, AND SUBJECT TO THE APPROVAL OF THE OWNER AND/OR LOCAL UTILITIES.
24. THE AREAS OF THE OWNER'S PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION.
25. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO THE EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE FEDERAL AND LOCAL JURISDICTION FOR EROSION AND SEDIMENT CONTROL.
26. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUNDING. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.
27. THE SUBGRADE SHALL BE BROUGHT TO A SMOOTH UNIFORM GRADE AND COMPACTED TO 95 PERCENT STANDARD PROCTOR DENSITY UNDER PAVEMENT AND STRUCTURES AND 80 PERCENT STANDARD PROCTOR DENSITY IN OPEN SPACE. ALL TRENCHES IN PUBLIC RIGHT OF WAY SHALL BE BACKFILLED WITH FLOWABLE FILL OR OTHER MATERIAL PRE-APPROVED BY THE LOCAL JURISDICTION.
28. ALL NECESSARY RUBBISH, STUMPS, DEBRIS, STICKS, STONES, AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN A LAWFUL MANNER.
29. ALL BROCHURES, OPERATING AND MAINTENANCE MANUALS, CATALOGS, SHOP DRAWINGS, AND OTHER DOCUMENTS SHALL BE TURNED OVER TO THE GENERAL CONTRACTOR AT COMPLETION OF CONSTRUCTION AND PRIOR TO PAYMENT.
30. CONTRACTOR SHALL SUBMIT A COMPLETE SET OF AS-BUILT REDLINES TO THE GENERAL CONTRACTOR UPON COMPLETION OF PROJECT AND PRIOR TO FINAL PAYMENT.
31. CONTRACTOR SHALL LEAVE PREMISES IN A CLEAN CONDITION.
32. THE PROPOSED FACILITY WILL BE UNMANNED AND DOES NOT REQUIRE POTABLE WATER OR SEWER SERVICE, AND IS NOT FOR HUMAN HABITAT (NO HANDICAP ACCESS REQUIRED).
33. OCCUPANCY IS LIMITED TO PERIODIC MAINTENANCE AND INSPECTION, APPROXIMATELY 2 TIMES PER MONTH, BY AT&T TECHNICIANS.
34. NO OUTDOOR STORAGE OR SOLID WASTE CONTAINERS ARE PROPOSED.
35. ALL MATERIAL SHALL BE FURNISHED AND WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST REVISION AT&T MOBILITY GROUNDING STANDARD "TECHNICAL SPECIFICATION FOR CONSTRUCTION OF GSM/GPRS WIRELESS SITES" AND "TECHNICAL SPECIFICATION FOR FACILITY GROUNDING". IN CASE OF A CONFLICT BETWEEN THE CONSTRUCTION SPECIFICATION AND THE DRAWINGS, THE DRAWINGS SHALL GOVERN.
36. CONTRACTORS SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS REQUIRED FOR CONSTRUCTION. IF CONTRACTOR CANNOT OBTAIN A PERMIT, THEY MUST NOTIFY THE GENERAL CONTRACTOR IMMEDIATELY.
37. CONTRACTOR SHALL REMOVE ALL TRASH AND DEBRIS FROM THE SITE ON A DAILY BASIS.
38. INFORMATION SHOWN ON THESE DRAWINGS WAS OBTAINED FROM SITE VISITS AND/OR DRAWINGS PROVIDED BY THE SITE OWNER. CONTRACTORS SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO ORDERING MATERIAL OR PROCEEDING WITH CONSTRUCTION.
39. NO WHITE STROBE LIGHTS ARE PERMITTED. LIGHTING IF REQUIRED, WILL MEET FAA STANDARDS AND REQUIREMENTS.

40. DESIGN AND CONSTRUCTION OF ANTENNA SUPPORTS SHALL

**ANTENNA MOUNTING**

41. ALL STEEL MATERIALS SHALL BE GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123 "ZINC (HOT-DIP GALVANIZED) COATINGS ON IRON AND STEEL PRODUCTS", UNLESS NOTED OTHERWISE.
42. ALL BOLTS, ANCHORS AND MISCELLANEOUS HARDWARE SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM A153 "ZINC-COATING (HOT-DIP) ON IRON AND STEEL HARDWARE", UNLESS NOTED OTHERWISE.
43. DAMAGED GALVANIZED SURFACES SHALL BE REPAIRED BY COLD GALVANIZING IN ACCORDANCE WITH ASTM A780.
44. ALL ANTENNA MOUNTS SHALL BE INSTALLED WITH LOCK NUTS, DOUBLE NUTS AND SHALL BE TORQUED TO MANUFACTURER'S RECOMMENDATIONS.
45. CONTRACTOR SHALL INSTALL ANTENNA PER MANUFACTURER'S RECOMMENDATION FOR INSTALLATION AND GROUNDING.
46. ALL UNUSED PORTS ON ANY ANTENNAS SHALL BE TERMINATED WITH A 50-OHM LOAD TO ENSURE ANTENNAS PERFORM AS DESIGNED.
47. PRIOR TO SETTING ANTENNA AZIMUTHS AND DOWNTILTS, ANTENNA CONTRACTOR SHALL CHECK THE ANTENNA MOUNT FOR TIGHTNESS AND ENSURE THAT THEY ARE PLUMB. ANTENNA AZIMUTHS SHALL BE SET FROM TRUE NORTH AND BE ORIENTED WITHIN +/- 5% AS DEFINED BY THE RFDS. ANTENNA DOWNTILTS SHALL BE WITHIN +/- 0.5% AS DEFINED BY THE RFDS. REFER TO ND-00246.
48. JUMPERS FROM THE TMA'S MUST TERMINATE TO OPPOSITE POLARIZATION'S IN EACH SECTOR.
49. CONTRACTOR SHALL RECORD THE SERIAL #, SECTOR, AND POSITION OF EACH ACTUATOR INSTALLED AT THE ANTENNAS AND PROVIDE THE INFORMATION TO AT&T.
50. TMA'S SHALL BE MOUNTED ON PIPE DIRECTLY BEHIND ANTENNAS AS CLOSE TO ANTENNA AS FEASIBLE IN A VERTICAL POSITION.

**TORQUE REQUIREMENTS**

51. ALL RF CONNECTIONS SHALL BE TIGHTENED BY A TORQUE WRENCH.
52. ALL RF CONNECTIONS, GROUNDING HARDWARE AND ANTENNA HARDWARE SHALL HAVE A TORQUE MARK INSTALLED IN A CONTINUOUS STRAIGHT LINE FROM BOTH SIDES OF THE CONNECTION.  
A. RF CONNECTION BOTH SIDES OF THE CONNECTOR.  
B. GROUNDING AND ANTENNA HARDWARE ON THE NUT SIDE STARTING FROM THE THREADS TO THE SOLID SURFACE. EXAMPLE OF SOLID SURFACE: GROUND BAR, ANTENNA BRACKET METAL.

**FIBER & POWER CABLE MOUNTING**

53. THE FIBER OPTIC TRUNK CABLES SHALL BE INSTALLED INTO CONDUITS, CHANNEL CABLE TRAYS, OR CABLE TRAY. WHEN INSTALLING FIBER OPTIC TRUNK CABLES INTO A CABLE TRAY SYSTEM, THEY SHALL BE INSTALLED INTO AN INTER DUCT AND A PARTITION BARRIER SHALL BE INSTALLED BETWEEN THE 600 VOLT CABLES AND THE INTER DUCT IN ORDER TO SEGREGATE CABLE TYPES. OPTIC FIBER TRUNK CABLES SHALL HAVE APPROVED CABLE RESTRAINTS EVERY (60) SIXTY FEET AND SECURELY FASTENED TO THE CABLE TRAY SYSTEM. NFPA 70 (NEC) ARTICLE 770 RULES SHALL APPLY.
54. THE TYPE TC-ER CABLES SHALL BE INSTALLED INTO CONDUITS, CHANNEL CABLE TRAYS, OR CABLE TRAY AND SHALL BE SECURED AT INTERVALS NOT EXCEEDING (6) SIX FEET. AN EXCEPTION; WHERE TYPE TC-ER CABLES ARE NOT SUBJECT TO PHYSICAL DAMAGE, CABLES SHALL BE PERMITTED TO MAKE A TRANSITION BETWEEN CONDUITS, CHANNEL CABLE TRAYS, OR CABLE TRAY WHICH ARE SERVING UTILIZATION EQUIPMENT OR DEVICES, A DISTANCE (6) SIX FEET SHALL NOT BE EXCEEDED WITHOUT CONTINUOUS SUPPORTING. NFPA 70 (NEC) ARTICLES 336 AND 392 RULES SHALL APPLY.
55. WHEN INSTALLING OPTIC FIBER TRUNK CABLES OR TYPE TC-ER CABLES INTO CONDUITS, NFPA 70 (NEC) ARTICLE 300 RULES SHALL APPLY.

**COAXIAL CABLE NOTES**

62. TYPES AND SIZES OF THE ANTENNA CABLE ARE BASED ON ESTIMATED LENGTHS. PRIOR TO ORDERING CABLE, CONTRACTOR SHALL VERIFY ACTUAL LENGTH BASED ON CONSTRUCTION LAYOUT AND NOTIFY THE PROJECT MANAGER IF ACTUAL LENGTHS EXCEED ESTIMATED LENGTHS.
63. CONTRACTOR SHALL VERIFY THE DOWN-TILT OF EACH ANTENNA WITH A DIGITAL LEVEL.
64. CONTRACTOR SHALL CONFIRM COAX COLOR CODING PRIOR TO CONSTRUCTION.
65. ALL JUMPERS TO THE ANTENNAS FROM THE MAIN

TRANSMISSION LINE SHALL BE 1/2" DIA. LDF AND SHALL NOT EXCEED 6'-0".

66. ALL COAXIAL CABLE SHALL BE SECURED TO THE DESIGNED SUPPORT STRUCTURE, IN AN APPROVED MANNER, AT DISTANCES NOT TO EXCEED 4'-0" OC.
67. CONTRACTOR SHALL FOLLOW ALL MANUFACTURER'S RECOMMENDATIONS REGARDING BOTH THE INSTALLATION AND GROUNDING OF ALL COAXIAL CABLES, CONNECTORS, ANTENNAS, AND ALL OTHER EQUIPMENT.
68. CONTRACTOR SHALL GROUND ALL EQUIPMENT. INCLUDING ANTENNAS, RET MOTORS, TMA'S, COAX CABLES, AND RET CONTROL CABLES AS A COMPLETE SYSTEM. GROUNDING SHALL BE EXECUTED BY QUALIFIED WIREMEN IN COMPLIANCE WITH MANUFACTURER'S SPECIFICATION AND RECOMMENDATION.
69. CONTRACTOR SHALL PROVIDE STRAIN-RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES, COAX CABLES, AND RET CONTROL CABLES. CABLE STRAIN-RELIEFS AND CABLE SUPPORTS SHALL BE APPROVED FOR THE PURPOSE. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
70. CONTRACTOR TO VERIFY THAT EXISTING COAX HANGERS ARE STACKABLE SNAP IN HANGERS. IF EXISTING HANGERS ARE NOT STACKABLE SNAP IN HANGERS THE CONTRACTOR SHALL REPLACE EXISTING HANGERS WITH NEW SNAP IN HANGERS IF APPLICABLE.

**GENERAL CABLE AND EQUIPMENT NOTES**

71. CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY ANTENNA, TMAS, DIPLEXERS, AND COAX CONFIGURATION, MAKE AND MODELS PRIOR TO INSTALLATION.
72. ALL CONNECTIONS FOR HANGERS, SUPPORTS, BRACING, ETC. SHALL BE INSTALLED PER TOWER MANUFACTURER'S RECOMMENDATIONS.
73. CONTRACTOR SHALL REFERENCE THE TOWER STRUCTURAL ANALYSIS/DESIGN DRAWINGS FOR DIRECTIONS ON CABLE DISTRIBUTION/ROUTING.
74. ALL OUTDOOR RF CONNECTORS/CONNECTIONS SHALL BE WEATHERPROOFED, EXCEPT THE RET CONNECTORS, USING BUTYL TAPE AFTER INSTALLATION AND FINAL CONNECTIONS ARE MADE. BUTYL TAPE SHALL HAVE A MINIMUM OF ONE-HALF TAPE WIDTH OVERLAP ON EACH TURN AND EACH LAYER SHALL BE WRAPPED THREE TIMES. WEATHERPROOFING SHALL BE SMOOTH WITHOUT BUCKLING. BUTYL BLEEDING IS NOT ALLOWED.
75. IF REQUIRED TO PAINT ANTENNAS AND/OR COAX:  
A. TEMPERATURE SHALL BE ABOVE 50° F.  
B. PAINT COLOR MUST BE APPROVED BY BUILDING OWNER/LANDLORD.  
C. FOR REGULATED TOWERS, FAA/FCC APPROVED PAINT IS REQUIRED.  
D. DO NOT PAINT OVER COLOR CODING OR ON EQUIPMENT MODEL NUMBERS
76. ALL CABLES SHALL BE GROUNDED WITH COAXIAL CABLE GROUND KITS. FOLLOW THE MANUFACTURER'S RECOMMENDATIONS.  
A. GROUNDING AT THE ANTENNA LEVEL.  
B. GROUNDING AT MID LEVEL, TOWERS WHICH ARE OVER 200'-0", ADDITIONAL CABLE GROUNDING REQUIRED.  
C. GROUNDING AT BASE OF TOWER PRIOR TO TURNING HORIZONTAL.  
D. GROUNDING OUTSIDE THE EQUIPMENT SHELTER AT ENTRY PORT.  
E. GROUNDING INSIDE THE EQUIPMENT SHELTER AT THE ENTRY PORT.
77. ALL PROPOSED GROUND BAR DOWNLOADS ARE TO BE TERMINATED TO THE EXISTING ADJACENT GROUND BAR DOWNLOADS A MINIMUM DISTANCE OF 4'-0" BELOW GROUND BAR. TERMINATIONS MAY BE EXOTHERMIC OR COMPRESSION.



550 COCHITUATE ROAD  
SUITE 550 13 AND 14  
FRAMINGHAM, MA 01701



1362 MELLON ROAD  
SUITE 140  
HANOVER, MD 21076

**FULLERTON**  
ENGINEERING-DESIGN

1100 E. WOODFIELD ROAD, SUITE 500  
SCHAUMBURG, ILLINOIS 60173  
TEL: 847-908-8400  
COA# PEC.0001444  
www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME  
**NORWALK  
WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
**613 CONNECTICUT AVENUE  
NORWALK, CT 06850**


SHEET NAME  
**NOTES AND  
SPECIFICATIONS**

SHEET NUMBER  
**SP1**

THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.




**NOTICE**




**Beyond This Point** you are entering a controlled area where RF emissions *may exceed* the FCC General Population Exposure Limits.

Follow all posted signs and site guidelines for working in a RF environment.




Ref: 47CFR 1.1307(b)

**CAUTION**




**Beyond This Point** you are entering a controlled area where RF emissions *may exceed* the FCC Occupational Exposure Limits.


Obey all posted signs and site guidelines for working in a RF environment.




Ref: 47CFR 1.1307(b)



ALERTING SIGN  
(FOR CELL SITE BATTERIES)



ALERTING SIGN  
(FOR DIESEL FUEL)



ALERTING SIGN  
(FOR PROPANE)



550 COCHITUATE ROAD  
SUITE 550 13 AND 14  
FRAMINGHAM, MA 01701



smartlink  
1362 MELLON ROAD  
SUITE 140  
HANOVER, MD 21076

**FULLERTON**  
ENGINEERING-DESIGN

1100 E. WOODFIELD ROAD, SUITE 500  
SCHAUMBURG, ILLINOIS 60173  
TEL: 847-908-8400  
COA# PEC.0001444  
www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME  
**NORWALK  
WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
**613 CONNECTICUT AVENUE  
NORWALK, CT 06850**

SHEET NAME  
**NOTES AND  
SPECIFICATIONS**

SHEET NUMBER  
**SP2**

ALERTING SIGNS

**WARNING!**


DANGER DO NOT TOUCH TOWER!

SERIOUS "RF" BURN HAZARD!

MAINTAIN AN ADEQUATE CLEARANCE BETWEEN TOWER SUPPORTS AND GUY WIRES

FAILURE TO OBEY ALL POSTED SIGNS AND SITE GUIDELINES FOR WORKING IN A RADIO FREQUENCY ENVIRONMENT COULD RESULT IN SERIOUS INJURY. CONTACT CURRENT MAY EXCEED LIMITS PRESCRIBED BY ANSI/IEEE C95.1-1992 FOR CONTROLLED ENVIRONMENTS.



PROPERTY OF AT&T 

**AUTHORIZED  
PERSONNEL ONLY**

IN CASE OF EMERGENCY, OR PRIOR TO PERFORMING MAINTENANCE ON THIS SITE, CALL 800-638-2822 AND REFERENCE CELL SITE NUMBER \_\_\_\_\_

ALERTING SIGN

INFO SIGN #4

**INFORMATION**

AT&T operates telecommunications antennas at this location. Remain at least 3 feet away from any antenna and obey all posted signs.

Contact the owner(s) of the antenna(s) before working closer than 3 feet from the antenna.

Contact AT&T at \_\_\_\_\_ prior to performing any maintenance or repairs near AT&T antennas. This is Site # \_\_\_\_\_

Contact the management office if this door/hatch/gate is found unlocked.

**INFORMACION**


En esta propiedad se ubican antenas de telecomunicaciones operadas por AT&T. Favor mantener una distancia de no menos de 3 pies y obedecer todos los avisos.

Comuníquese con el propietario o los propietarios de las antenas antes de trabajar o caminar a una distancia de menos de 3 pies de la antena.

Comuníquese con AT&T \_\_\_\_\_ antes de realizar cualquier mantenimiento o reparaciones cerca de las antenas de AT&T.

Esta es la estación base número \_\_\_\_\_

Favor comunicarse con la oficina de la administración del edificio si esta puerta o compuerta se encuentra sin candado.



**INFORMATION**

- ACTIVE ANTENNAS ARE MOUNTED
- ON THE OUTSIDE OF THIS BUILDING
  - BEHIND THIS PANEL
  - ON THIS STRUCTURE

**STAY BACK A MINIMUM  
OF 3 FEET  
FROM THESE ANTENNAS**

Contact AT&T at \_\_\_\_\_ and follow their instructions prior to performing any maintenance or repairs closer than 3 feet from the antennas.

This is AT&T site # \_\_\_\_\_ 

STAY BACK 3 FEET FROM ANTENNA



GENERAL SIGNAGE GUIDELINES

| STRUCTURE TYPE                               | INFO SIGN #1   | INFO SIGN #2   | INFO SIGN #3            | INFO SIGN #4   | STRIPING                                       | NOTICE SIGN  | CAUTION SIGN  |
|--|--|--|-------------------------|--|--|--|---|
| <b>TOWERS</b>                                |  |  |                         |  |  |  |   |
| MONOPOLE/MONOPIPE/MONOPALM                   | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS | CLIMBING SIDE OF THE TOWER   | ON BACKSIDE OF ANTENNAS | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS |  |  | AT THE HEIGHT OF THE FIRST CLIMBING STEP, MIN 9 FT ABOVE GROUND |
| SEC TOWERS/TOWERS WITH HIGH VOLTAGE          | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS | CLIMBING SIDE OF THE TOWER   | ON BACKSIDE OF ANTENNAS | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS |  |  |   |
| LIGHT POLES/FLAG POLES                       | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS | ON THE POLE, NO LESS THAN 3FT BELOW THE ANTENNA AND LESS THAN 9FT ABOVE GROUND | ON BACKSIDE OF ANTENNAS | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS |  |  |   |
| UTILITY WOOD POLES (JPA)                     | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS | ON THE POLE, NO LESS THAN 3FT BELOW THE ANTENNA AND LESS THAN 9FT ABOVE GROUND | ON BACKSIDE OF ANTENNAS | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS |  | IF GP MAX VALUE OF MPE AT ANTENNA LEVEL IS: 0-99% NOTICE SIGN; OVER 99% CAUTION SIGN AT NO LESS THAN 3FT BELOW ANTENNA AND 9FT ABOVE GROUND  |   |
| MICROCELLS MOUNTED ON NON-JPA POLES          | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS | ON THE POLE, NO LESS THAN 3FT BELOW THE ANTENNA AND LESS THAN 9FT ABOVE GROUND | ON BACKSIDE OF ANTENNAS | ENTRANCE GATES, SHELTER DOORS OR ON THE OUTDOOR CABINETS |  | NOTICE OR CAUTION SIGN AT NO LESS THAN 9FT ABOVE GROUND. ONLY IF THE EXPOSURE EXCEEDS 90% OF THE GENERAL PUBLIC EXPOSURE AT EXPOSURE AT 6FT ABOVE GROUND OR AT OUTSIDE OF SURFACE OF ADJACENT BUILDING |   |
| <b>TOWERS</b>                                |  |  |                         |  |  |  |   |
| AT ALL ACCESS POINTS TO THE ROOF             | X  |  |                         | X  |  |  |   |
| ON ANTENNAS                                  | X  |  | X                       | X  |  |  |   |
| CONCEALED ANTENNAS                           | X  | X  |                         | X  |  |  |   |
| ANTENNAS MOUNTED FACING OUTSIDE THE BUILDING | X  | X  |                         | X  |  |  |   |
| ANTENNAS ON SUPPORT STRUCTURE                | X  | X  |                         | X  |  |  |   |
| ROOFVIEW GRAPH                               |  |  |                         |  |  |  |   |
| RADIATION AREA IS WITHIN 3FT FROM ANTENNA    | X  | ADJACENT TO EACH ANTENNA   |                         | X  |  | EITHER NOTICE OR CAUTION SIGN (BASED ON ROOFVIEW RESULTS) AT ANTENNA /BARRIER  |   |
| RADIATION AREA IS BEYOND 3FT FROM ANTENNA    | X  | ADJACENT TO EACH ANTENNA   |                         | X  | DIAGONAL, YELLOW STRIPING AS TO ROOFVIEW GRAPH |  |   |
| <b>CHURCH STEEPLES</b>                       | ACCESS TO STEEPLE  | ADJACENT TO ANTENNAS IF ANTENNAS ARE CONCEALED                                 | ON BACKSIDE OF ANTENNAS | ACCESS TO STEEPLE  |  |  | CAUTION SIGN AT THE ANTENNAS                                    |
| <b>WATER STATIONS</b>                        | ACCESS TO LADDER   | ADJACENT TO ANTENNAS IF ANTENNAS ARE CONCEALED                                 | ON BACKSIDE OF ANTENNAS | ACCESS TO LADDER   |  |  | CAUTION SIGN BESIDE INFO SIGN #1, MIN. 9FT ABOVE GROUND         |

NOTES FOR ROOFTOP SITES:

- EITHER NOTICE OR CAUTION SIGNS NEED TO BE POSTED AT EACH SECTOR AS CLOSE AS POSSIBLE TO: THE OUTER EDGE OF THE STRIPED OFF AREA OR THE OUTER ANTENNAS OF THE SECTOR
- IF ROOFVIEWS SHOWS: ONLY BLUE = NOTICE SIGN, BLUE AND YELLOW = CAUTION SIGN, ONLY YELLOW = CAUTION SIGN TO BE INSTALLED
- SHOULD THE REQUIRED STRIPING AREAS INTERFERE WITH ANY STRUCTURE OR EQUIPMENT (A/C, VENTS, ROOF HATCH, DOORS, OTHER ANTENNAS, DISHES, ETC.). PLEASE NOTIFY AT&T TO MODIFY THE STRIPING AREA, PRIOR TO STARTING THE WORK.

INFO SIGN #1

INFO SIGN #2

INFO SIGN #3

SIGNAGE GUIDELINES CHART


**ABBREVIATIONS**

|          |  |
|----------|--|
| AFF      | ABOVE FINISHED FLOOR                       |
| AGL      | ABOVE GRADE LEVEL                          |
| AMSL     | ABOVE MEAN SEA LEVEL                       |
| APPROX   | APPROXIMATE                                |
| ATS      | AUTOMATIC TRANSFER SWITCH                  |
| AWG      | AMERICAN WIRE GAUGE                        |
| BLDG     | BUILDING                                   |
| BTS      | BASE TRANSMISSION STATION                  |
| C        | CENTERLINE                                 |
| CLR      | CLEAR                                      |
| COL      | COLUMN                                     |
| CONC     | CONCRETE                                   |
| CND      | CONDUIT                                    |
| DWG      | DRAWING                                    |
| FT       | FOOT(FEET)                                 |
| EGB      | EQUIPMENT GROUND BAR                       |
| ELEC     | ELECTRICAL                                 |
| EMT      | ELECTRICAL METALLIC TUBING                 |
| ELEV     | ELEVATION                                  |
| EQUIP    | EQUIPMENT                                  |
| (E)      | EXISTING                                   |
| EXT      | EXTERIOR                                   |
| FND      | FOUNDATION                                 |
| F        | FIBER                                      |
| FIF      | FACILITY INTERFACE FRAME                   |
| GA       | GAUGE                                      |
| GALV     | GALVANIZED                                 |
| GPS      | GLOBAL POSITIONING SYSTEM                  |
| GND      | GROUND                                     |
| GSM      | GLOBAL SYSTEM FOR MOBILE COMMUNICATION     |
| LTE      | LONG TERM EVOLUTION                        |
| MAX      | MAXIMUM                                    |
| MCPA     | MULTI-CARRIER POWER AMPLIFIER              |
| MFR      | MANUFACTURER                               |
| MGB      | MASTER GROUND BAR                          |
| MIN      | MINIMUM                                    |
| MTS      | MANUAL TRANSFER SWITCH                     |
| N.T.S.   | NOT TO SCALE                               |
| O.C.     | ON CENTER                                  |
| OE/OT    | OVERHEAD ELECTRIC/TELCO                    |
| PPC      | POWER PROTECTION CABINET                   |
| PL       | PROPERTY LINE                              |
| RBS      | RADIO BASED STATION                        |
| RET      | REMOTE ELECTRIC TILT                       |
| RRU      | REMOTE RADIO UNIT                          |
| RGS      | RIGID GALVANIZED STEEL                     |
| IN       | INCH(ES)                                   |
| INT      | INTERIOR                                   |
| LB(S), # | POUND(S)                                   |
| SF       | SQUARE FOOT                                |
| STL      | STEEL                                      |
| TMA      | TOWER MOUNTED AMPLIFIER                    |
| TYP      | TYPICAL                                    |
| UE/UT    | UNDERGROUND ELECTRIC/TELCO                 |
| UNO      | UNLESS NOTED OTHERWISE                     |
| UMTS     | UNIVERSAL MOBILE TELE-COMMUNICATION SYSTEM |
| VIF      | VERIFY IN FIELD                            |
| W/       | WITH                                       |
| XFMR     | TRANSFORMER                                |

**SYMBOLS**

|  |                             |
|--|-----------------------------|
|  | REVISION                    |
|  | WORK POINT                  |
|  | UTILITY POLE                |
|  | COMPRESSED STONE            |
|  | BRICK                       |
|  | CONCRETE                    |
|  | EARTH                       |
|  | GRAVEL                      |
|  | MASONRY                     |
|  | STEEL                       |
|  | CENTERLINE                  |
|  | PROPERTY LINE               |
|  | LEASE LINE                  |
|  | EASEMENT LINE               |
|  | CHAIN LINK FENCE            |
|  | WOOD FENCE                  |
|  | BELOW GRADE ELECTRIC        |
|  | BELOW GRADE TELEPHONE       |
|  | OVERHEAD ELECTRIC/TELEPHONE |
|  | SECTION REFERENCE           |

**COMPOUND PLAN**



**SITE PHOTO 1** SCALE: N.T.S. 2



**SITE PHOTO 2** SCALE: N.T.S. 3

550 COCHITUATE ROAD  
SUITE 550 13 AND 14  
FRAMINGHAM, MA 01701

1362 MELLON ROAD  
SUITE 140  
HANOVER, MD 21076

**FULLERTON**  
ENGINEERING-DESIGN

1100 E. WOODFIELD ROAD, SUITE 500  
SCHAUMBURG, ILLINOIS 60173  
TEL: 847-908-8400  
COA# PEC.0001444  
www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME  
**NORWALK WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
**613 CONNECTICUT AVENUE  
NORWALK, CT 06850**

SHEET NAME  
**COMPOUND PLAN**

SHEET NUMBER  
**A1**

THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS PROJECT, ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.



550 COCHITUATE ROAD  
SUITE 550.13 AND 14  
FRAMINGHAM, MA 01701



1362 MELLON ROAD  
SUITE 140  
HANOVER, MD 21076



1100 E. WOODFIELD ROAD, SUITE 500  
SCHAUMBURG, ILLINOIS 60173  
TEL: 847-908-8400  
COA# PEC.0001444  
www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.




SITE NAME  
**NORWALK  
WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
**613 CONNECTICUT AVENUE  
NORWALK, CT 06850**

SHEET NAME  
**EQUIPMENT  
PLAN**

SHEET NUMBER  
**A2**



(3) NEW RRUS-E2  
MOUNTED ON EXISTING WALL  
SEE A4 FOR DETAILS

(3) NEW RRUS-B14 4478-B5 (850)  
MOUNTED ON EXISTING WALL  
SEE A4 FOR DETAILS

UPGRADE (2) EXISTING DUS TO (2) NEW 5216  
ADD 2ND XMU CARD & NEW IDLe

EXISTING CABLE RACK

EXISTING ACCESS DOOR



THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.

- NOTES:**
- CALCULATIONS FOR THE STRUCTURE WERE PREPARED BY OTHERS AND THOSE CALCULATIONS CERTIFY THE CAPACITY OF THE STRUCTURE TO SUPPORT THE NEW EQUIPMENT
  - CALCULATIONS FOR THE ANTENNA MOUNTS WERE PREPARED BY FULLERTON AND THOSE CALCULATIONS CERTIFY THE CAPACITY OF THE STRUCTURE TO SUPPORT THE NEW EQUIPMENT
  - CABLES NOT SHOWN FOR CLARITY

- NOTES:**
- ALL EQUIPMENT (ANTENNAS, LINES, ETC.) TO BE INSTALLED IN ACCORDANCE WITH PASSING STRUCTURAL ANALYSIS PROVIDED BY CROWN CASTLE.
  - TAPE DROP FORMS AND PHOTOGRAPHS TO BE SUBMITTED PER CCI AND AT&T CLOSEOUT REQUIREMENTS.
- NOTES:**
- 3 FEET MINIMUM SEPARATION BETWEEN LTE ANTENNAS
  - 6 FEET MINIMUM SEPARATION BETWEEN 700DE & 700BC



550 COCHITUATE ROAD  
SUITE 550 13 AND 14  
FRAMINGHAM, MA 01701



1362 MELLON ROAD  
SUITE 140  
HANOVER, MD 21076

**FULLERTON**  
ENGINEERING-DESIGN

1100 E. WOODFIELD ROAD, SUITE 500  
SCHAUMBURG, ILLINOIS 60173  
TEL: 847-908-8400  
COA# PEC.0001444  
www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.




SITE NAME  
**NORWALK  
WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
**613 CONNECTICUT AVENUE  
NORWALK, CT 06850**


SHEET NAME  
**ELEVATIONS**

SHEET NUMBER  
**A3**



EXISTING ELEVATION

SCALE: 1/32" = 1'-0" 1




NEW ELEVATION

SCALE: 1/32" = 1'-0" 2

THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.






PLAN VIEW SIDE VIEW FRONT VIEW

**COMMSCOPE – SBNHH-1D65A**


ANDREW® TRI-BAND ANTENNA  
 FREQUENCY RANGE 698–806 MHz  
 806–896 MHz  
 1710–1880 MHz  
 1850–1990 MHz  
 1920–2180 MHz  
 2300–2360 MHz  
 ANTENNA 33.5 Lbs  
 BRACKET 12.3 Lbs  
 TOTAL WEIGHT 45.8 Lbs



PLAN VIEW SIDE VIEW FRONT VIEW

**QUINTEL – QS66512-2**

MULTISERVE MULTIBAND 12 PORT ANTENNA  
 WITH QILT AND INTERNAL RET  
 FREQUENCY RANGE 2x698–806 MHz  
 2x824–894 MHz  
 4x1850–1990 MHz  
 4x1695–1780 +2110–2400 MHz  
 ANTENNA 111 Lbs  
 BRACKET 15 Lbs  
 TOTAL WEIGHT 126 Lbs



**ERICSSON – RRUS 4478 B14**

FREQUENCY RANGE TX 758–768 MHz  
 RX 788–798 MHz  
 TOTAL WEIGHT 59.9 Lbs



550 COCHITUATE ROAD  
 SUITE 550 13 AND 14  
 FRAMINGHAM, MA 01701



1362 MELLON ROAD  
 SUITE 140  
 HANOVER, MD 21076



1100 E. WOODFIELD ROAD, SUITE 500  
 SCHAUMBURG, ILLINOIS 60173  
 TEL: 847-908-8400  
 COA# PEC.0001444  
 www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |


I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.

ANTENNA SPEC SCALE: N.T.S. 1

ANTENNA SPEC SCALE: N.T.S. 2

ANTENNA SCHEMATIC SCALE: N.T.S. 3


RRU SPEC SCALE: N.T.S. 4



PLAN VIEW SIDE VIEW FRONT VIEW

**ERICSSON – RRUS 32 B66**


UNIT WEIGHT 60 Lbs



PLAN VIEW SIDE VIEW FRONT VIEW

**Ericsson – RRUS 4478 B5**


FREQUENCY RANGE TX = 869–894 MHz  
 RX = 824–849 MHz  
 TOTAL WEIGHT 56.1 Lbs



PLAN VIEW SIDE VIEW FRONT VIEW

**ERICSSON – RRUS E2**

WITH SOLAR SHIELD  
 UNIT WEIGHT 52.9 Lbs



PLAN VIEW FRONT VIEW SIDE VIEW

**RAYCAP – DC6-48-60-18-8F**

TOWER DC OVER VOLTAGE PROTECTION POWER CONNECTION SOLUTION  
 UNIT WEIGHT 32.8 Lbs

RRU SPEC SCALE: N.T.S. 5

RRU SPEC SCALE: N.T.S. 6

RRU SPEC SCALE: N.T.S. 7

RAYCAP SPEC SCALE: N.T.S. 8



SITE NAME  
**NORWALK WEST-CT AVE.**


SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
 613 CONNECTICUT AVENUE  
 NORWALK, CT 06850

SHEET NAME  
**EQUIPMENT DETAILS**

SHEET NUMBER  
**A5**


THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.



ANTENNA MOUNTING DETAIL @ NEW ANTENNA LOCATIONS (6 TYP.) SCALE: N.T.S. 1

| ITEM | PART NO.  | DESCRIPTION                    | QTY. | WEIGHT    |
|------|-----------|--------------------------------|------|-----------|
| 1    | MTC328601 | 10-50 RRU Mount Weldment       | 3    | 27.77 LBS |
| 2    | GUB-4240  | 1/2" X 2-1/2" X 4" GALV U-BOLT | 6    | 0.56 LBS  |
| 3    | MT-382-24 | 5/8" X 24" GALV THREADED ROD   | 6    | 2.07 LBS  |
| 4    | MT38240   | 3/8" X 40" GALV THREADED ROD   | 6    | 3.46 LBS  |
| 5    | GWFL-05   | 5/8" GALV FLAT WASHER          | 12   | 0.03 LBS  |
| 6    | GWL-05    | 5/8" GALV LOCK WASHER          | 12   | 0.00 LBS  |
| 7    | GN-05     | 5/8" GALV HEX NUT              | 12   | 0.04 LBS  |
| 8    | MT-XXX    | 2.375" OD PIPE (SEE TABLE)     | 2    | 21.80 LBS |

| REV. | DATE | DESCRIPTION      | BY  | DATE     |
|------|------|------------------|-----|----------|
| A    |      | INITIAL RELEASE  | MEM | 11/21/11 |
| B    |      | UPDATE MTC328601 | MSM | 09/06/12 |




NOTES:  
 1. ALL METRIC DIMENSIONS ARE IN BRACKETS.  
 2. USE OUTER ANGLES AND 40" ROD FOR POLES 30"-50".

|   |  |
|---|--|
| <p>These drawings and specifications are the property of Andrew Engineering Consultants, Inc. and are to be used only for the project and site specified herein. Any other use without the written consent of Andrew Engineering Consultants, Inc. is prohibited.</p> <p>ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED.<br/>       UNLESS OTHERWISE SPECIFIED, DIMENSIONS ARE TO CENTERLINE UNLESS OTHERWISE SPECIFIED.<br/>       DIMENSIONS TO CENTERLINE UNLESS OTHERWISE SPECIFIED.<br/>       DIMENSIONS TO CENTERLINE UNLESS OTHERWISE SPECIFIED.<br/>       DIMENSIONS TO CENTERLINE UNLESS OTHERWISE SPECIFIED.<br/>       DIMENSIONS TO CENTERLINE UNLESS OTHERWISE SPECIFIED.</p> | <p>REV. B</p> <p>DATE 11/21/11</p> <p>BY MSB</p> <p>SCALE 1:1</p> <p>PROJECT MC-RR1050-3</p> <p>DRAWING MOUNTING DETAIL</p> <p>WESTCHESTER, IL 60154</p> <p>U.S.A.</p> |
|---|--|

NOTE:  
 MOUNTING PIPES MUST BE PURCHASED SEPARATELY

COLLAR MOUNT SPEC SCALE: N.T.S. 2



RRU MOUNTING DETAIL SCALE: N.T.S. 3

550 COCHITUATE ROAD  
 SUITE 550 13 AND 14  
 FRAMINGHAM, MA 01701

1362 MELLON ROAD  
 SUITE 140  
 HANOVER, MD 21076

1100 E. WOODFIELD ROAD, SUITE 500  
 SCHAUMBURG, ILLINOIS 60173  
 TEL: 847-908-8400  
 COA# PEC.0001444  
 www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME  
**NORWALK WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
 613 CONNECTICUT AVENUE  
 NORWALK, CT 06850

SHEET NAME  
**MOUNTING DETAILS**

SHEET NUMBER  
**A5A**

THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.



550 COCHITUATE ROAD  
SUITE 550 13 AND 14  
FRAMINGHAM, MA 01701



1362 MELLON ROAD  
SUITE 140  
HANOVER, MD 21076



1100 E. WOODFIELD ROAD, SUITE 500  
SCHAUMBURG, ILLINOIS 60173  
TEL: 847-908-8400  
COA# PEC.0001444  
www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME  
**NORWALK  
WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
**613 CONNECTICUT AVENUE  
NORWALK, CT 06850**

SHEET NAME  
**ANTENNA &  
CABLE  
CONFIGURATION**

SHEET NUMBER  
**A6**

| FINAL ANTENNA CONFIGURATION AND CABLE SCHEDULE<br>SUPPLIED BY AT&T WIRELESS, FROM RF CONFIGS. DATED (7/15/17 & 3/28/18) |                |                          |                      |                |  |   |         |                        |  |         |  |         |
|---|----------------|--------------------------|----------------------|----------------|--|---|---------|------------------------|--|---------|--|---------|
| SECTOR  | ANTENNA NUMBER | ANTENNA STATUS & TYPE    | ANTENNA MODEL NUMBER | ANTENNA VENDOR | TMA/RRU UNIT (BY ANTENNAS)   | TMA/RRU UNIT (BY EQUIPMENT)                       | AZIMUTH | ANTENNA CL FROM GROUND | CABLE FEEDER   |         | RAYCAP UNIT  |         |
|   |                |                          |                      |                |  |   |         |                        | TYPE   | LENGTH  |  |         |
| ALPHA   | A-1            | (E) UMTS ANTENNA         | 7770                 | POWERWAVE      | (2) EXISTING TMA UNITS   | (2) EXISTING RRUW UNITS                           | 143°    | 153'-0"                | 1-5/8"φ LDF7-50A   | 230'-0" | (2) (E) DC6-48-60-18-8F UNIT<br>(1) (N) DC6-48-60-18-8F UNIT |         |
|   | A-2            | (N) LTE 1C/2C/6C ANTENNA | QS66512-2            | QUINTEL        | (1) EXISTING RRUS-11 UNIT<br>(1) EXISTING RRUS-32 B2 UNIT<br>(1) EXISTING RRUS-32 UNIT | -   | 30°     | 153'-0"                | (1) EXISTING FIBER CABLE<br>(2) EXISTING DC POWER CABLES   | 230'-0" |  |         |
|   | A-3            | (N) LTE 7C ANTENNA       | SBNHH-1D65A          | COMMSCOPE      | (1) NEW RRUS-B14 4478 UNIT   | -   | 30°     | 153'-0"                | SEE ANTENNA A-4 FOR FIBER CABLE<br>(2) NEW DC POWER CABLES |         |  | 230'-0" |
|   | A-4            | (E) LTE 3C/4C/5C ANTENNA | SBNHH-1D65A          | COMMSCOPE      | (1) EXISTING RRUS-32 UNIT  | (1) NEW RRUS-E2 UNIT<br>(1) NEW RRUS-4478 B5 UNIT | 30°     | 153'-0"                | (1) EXISTING FIBER CABLE<br>(2) EXISTING DC POWER CABLES   | 230'-0" |  |         |
| BETA  | B-1            | (E) UMTS ANTENNA         | 7770                 | POWERWAVE      | (2) EXISTING TMA UNITS   | (2) EXISTING RRUW UNITS                           | 263°    | 153'-0"                | 1-5/8"φ LDF7-50A<br>1-5/8"φ LDF7-50A                       | 230'-0" | (2) (E) DC6-48-60-18-8F UNIT<br>(1) (N) DC6-48-60-18-8F UNIT |         |
|   | B-2            | (N) LTE 1C/2C/6C ANTENNA | QS66512-2            | QUINTEL        | (1) EXISTING RRUS-11 UNIT<br>(1) EXISTING RRUS-32 B2 UNIT<br>(1) EXISTING RRUS-32 UNIT | -   | 150°    | 153'-0"                | SEE ANTENNA A-2 FOR CABLE TYPE AND LENGTH                  |         |  |         |
|   | B-3            | (N) LTE 7C ANTENNA       | SBNHH-1D65A          | COMMSCOPE      | (1) NEW RRUS-B14 4478 UNIT   | -   | 150°    | 153'-0"                | SEE ANTENNA A-3 FOR CABLE TYPE AND LENGTH                  |         |  |         |
|   | B-4            | (E) LTE 3C/4C/5C ANTENNA | SBNHH-1D65A          | COMMSCOPE      | (1) EXISTING RRUS-32 UNIT  | (1) NEW RRUS-E2 UNIT<br>(1) NEW RRUS-4478 B5 UNIT | 150°    | 153'-0"                | SEE ANTENNA A-4 FOR CABLE TYPE AND LENGTH                  |         |  |         |
| GAMMA   | C-1            | (E) UMTS ANTENNA         | 7770                 | POWERWAVE      | (2) EXISTING TMA UNITS   | (2) EXISTING RRUW UNITS                           | 23°     | 153'-0"                | 1-5/8"φ LDF7-50A<br>1-5/8"φ LDF7-50A                       | 230'-0" | (2) (E) DC6-48-60-18-8F UNIT<br>(1) (N) DC6-48-60-18-8F UNIT |         |
|   | C-2            | (N) LTE 1C/2C/6C ANTENNA | QS66512-2            | QUINTEL        | (1) EXISTING RRUS-11 UNIT<br>(1) EXISTING RRUS-32 B2 UNIT<br>(1) EXISTING RRUS-32 UNIT | -   | 270°    | 153'-0"                | SEE ANTENNA A-2 FOR CABLE TYPE AND LENGTH                  |         |  |         |
|   | C-3            | (N) LTE 7C ANTENNA       | SBNHH-1D65A          | COMMSCOPE      | (1) NEW RRUS-B14 4478 UNIT   | -   | 270°    | 153'-0"                | SEE ANTENNA A-3 FOR CABLE TYPE AND LENGTH                  |         |  |         |
|   | C-4            | (E) LTE 3C/4C/5C ANTENNA | SBNHH-1D65A          | COMMSCOPE      | (1) EXISTING RRUS-32 UNIT  | (1) NEW RRUS-E2 UNIT<br>(1) NEW RRUS-4478 B5 UNIT | 270°    | 153'-0"                | SEE ANTENNA A-4 FOR CABLE TYPE AND LENGTH                  |         |  |         |



- CONTRACTOR IS TO REFER TO AT&T'S MOST CURRENT RADIO FREQUENCY DATA SHEET (RFDS) PRIOR TO CONSTRUCTION.
- THE SIZE, HEIGHT, AND DIRECTION OF THE ANTENNAS SHALL BE ADJUSTED TO ACHIEVE THE AZIMUTHS SPECIFIED AND LIMIT SHADOWING AND TO MEET THE SYSTEM REQUIREMENTS.
- CONTRACTOR SHALL VERIFY THE HEIGHT OF THE ANTENNA WITH THE AT&T WIRELESS PROJECT MANAGER.
- VERIFY TYPE AND SIZE OF TOWER LEG PRIOR TO ORDERING ANY ANTENNA MOUNT.
- UNLESS NOTED OTHERWISE THE CONTRACTOR MUST PROVIDE ALL MATERIAL NECESSARY.
- ANTENNA AZIMUTHS ARE DEGREES OFF OF TRUE NORTH, BEARING CLOCKWISE, IN WHICH ANTENNA FACE IS DIRECTED. ALL ANTENNAS (AND SUPPORTING STRUCTURES AS PRACTICAL) SHALL BE ACCURATELY ORIENTED IN THE SPECIFIED DIRECTION.
- CONTRACTOR SHALL VERIFY ALL RF INFORMATION PRIOR TO CONSTRUCTION.
- SWEEP TEST SHALL BE PERFORMED BY GENERAL CONTRACTOR AND SUBMITTED TO AT&T WIRELESS CONSTRUCTION SPECIALIST. TEST SHALL BE PERFORMED PER AT&T WIRELESS STANDARDS.
- CABLE LENGTHS WERE DETERMINED BASED ON THE DESIGN DRAWING. CONTRACTOR TO VERIFY ACTUAL LENGTH DURING PRE-CONSTRUCTION WALK.
- CONTRACTOR TO USE ROSENBERGER FIBER LINE HANGER COMPONENTS (OR ENGINEER APPROVED EQUAL).

ANTENNA AND CABLING NOTES

SCALE: N.T.S. 1

| RF, DC, & COAX CABLE MARKING LOCATIONS TABLE |  |
|--|--|
| NO   | LOCATIONS  |
| 1  | EACH TOP-JUMPER SHALL BE COLOR CODED WITH (1) SET OF 3" WIDE BANDS.  |
| 2  | EACH MAIN COAX SHALL BE COLOR CODED WITH (1) SET OF 3" WIDE BANDS NEAR THE TOP-JUMPER CONNECTION AND WITH (1) SET OF 3/4" WIDE COLOR BANDS JUST PRIOR TO ENTERING THE BTS OR TRANSMITTER BUILDING. |
| 3  | CABLE ENTRY PORT ON THE INTERIOR OF THE SHELTER.   |
| 4  | ALL BOTTOM JUMPERS SHALL BE COLOR CODED WITH (1) SET OF 3/4" WIDE BANDS ON EACH END OF THE BOTTOM JUMPER.  |
| 5  | ALL BOTTOM JUMPERS SHALL BE COLOR CODED WITH (1) SET OF 3/4" WIDE BANDS ON EACH END OF THE BOTTOM JUMPER.  |


CABLE MARKING DIAGRAM

SCALE: N.T.S. 2

- THE ANTENNA SYSTEM COAX SHALL BE LABELED WITH VINYL TAPE.
- THE STANDARD IS BASED ON EIGHT COLORED TAPES-RED, BLUE, GREEN, YELLOW, ORANGE, BROWN, WHITE, AND VIOLET. THESE TAPES MUST BE 3/4" WIDE & UV RESISTANT SUCH AS SCOTCH 35 VINYL ELECTRICAL COLOR CODING TAPE AND SHOULD BE READILY AVAILABLE TO THE ELECTRICIAN OR CONTRACTOR ON SITE.
- USING COLOR BANDS ON THE CABLES, MARK ALL RF CABLE BY SECTOR AND CABLE NUMBER AS SHOWN ON "CABLE COLOR CHART".
- WHEN AN EXISTING COAXIAL LINE THAT IS INTENDED TO BE A SHARED LINE BETWEEN TECHNOLOGIES IS ENCOUNTERED, THE CONTRACTOR SHALL REMOVE THE EXISTING COLOR CODING SCHEME AND REPLACE IT WITH THE COLOR CODING STANDARD. IN THE ABSENCE OF AN EXISTING COLOR CODING AND TAGGING SCHEME, OR WHEN INSTALLING PROPOSED COAXIAL CABLES, THIS GUIDELINE SHALL BE IMPLEMENTED AT THAT SITE REGARDLESS OF TECHNOLOGY.
- ALL COLOR CODE TAPE SHALL BE 3M-35 AND SHALL BE INSTALLED USING A MINIMUM OF (3) THREE WRAPS OF TAPE AND SHALL BE NEATLY TRIMMED AND SMOOTHED OUT SO AS TO AVOID UNRAVELING.
- ALL COLOR BANDS INSTALLED AT THE TOP OF THE TOWER SHALL BE A MINIMUM OF 3" WIDE, AND SHALL HAVE A MINIMUM OF 3/4" OF SPACE BETWEEN EACH COLOR.
- ALL COLOR CODES SHALL BE INSTALLED SO AS TO ALIGN NEATLY WITH ONE ANOTHER FROM SIDE-TO-SIDE.
- IF EXISTING CABLES AT THE SITE ALREADY HAVE A COLOR CODING SCHEME AND THEY ARE NOT INTENDED TO BE REUSED OR SHARED WITH THE NEW TECHNOLOGY, THE EXISTING COLOR CODING SCHEME SHALL REMAIN UNTOUCHED.

CABLE MARKING NOTES

SCALE: N.T.S. 3



CABLE COLOR CODING DIAGRAM

SCALE: N.T.S. 4



550 COCHITUATE ROAD  
SUITE 550 13 AND 14  
FRAMINGHAM, MA 01701



1362 MELLON ROAD  
SUITE 140  
HANOVER, MD 21076



1100 E. WOODFIELD ROAD, SUITE 500  
SCHAUMBURG, ILLINOIS 60173  
TEL: 847-908-8400  
COA# PEC.0001444  
www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME

**NORWALK  
WEST-CT AVE.**

SITE NUMBER:

**CTL02108**

SITE ADDRESS


613 CONNECTICUT AVENUE  
NORWALK, CT 06850

SHEET NAME


**CABLE NOTES  
AND COLOR  
CODING**

SHEET NUMBER


**A7**




GROUNDING SCHEMATIC SCALE: N.T.S. 1



GROUND BAR DETAIL SCALE: N.T.S. 2




EXOTHERMIC WELD DETAILS SCALE: N.T.S. 4



- NOTE: MINIMUM OF 3 THREADS TO BE VISIBLE (TYP.)  
 2 HOLE, LONG BARREL TINNED SOLID COPPER LUG (TYP.)
- TIN COATED SOLID COPPER BUSS BAR PER AT&T SPECIFICATIONS
- CHERRY INSULATOR INSTALLED IF REQUIRED PER AT&T SPECIFICATIONS
- NOTES:
- ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING SPLIT WASHERS.
  - COAT WIRE END WITH ANTI-OXIDATION COMPOUND PRIOR TO INSERTION INTO LUG BARREL AND CRIMPING.
  - APPLY ANTI-OXIDATION COMPOUND BETWEEN ALL LUGS AND BUSS BARS PRIOR TO MATING AND BOLTING.

LUG DETAIL SCALE: N.T.S. 3



RAYCAP DC POWER AND ALARM DET. SCALE: N.T.S. 5

NOT USED SCALE: N.T.S. 6

**at&t**  
 550 COCHITUATE ROAD  
 SUITE 550 13 AND 14  
 FRAMINGHAM, MA 01701

**smartlink**  
 1362 MELLON ROAD  
 SUITE 140  
 HANOVER, MD 21076

**FULLERTON**  
 ENGINEERING-DESIGN  
 1100 E. WOODFIELD ROAD, SUITE 500  
 SCHAUMBURG, ILLINOIS 60173  
 TEL: 847-908-8400  
 COA# PEC.0001444  
 www.FullertonEngineering.com

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME  
**NORWALK WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
 613 CONNECTICUT AVENUE  
 NORWALK, CT 06850

SHEET NAME  
**GROUNDING DETAILS**

SHEET NUMBER  
**A8**

THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.




550 COCHITUATE ROAD  
SUITE 550 13 AND 14  
FRAMINGHAM, MA 01701



1362 MELLON ROAD  
SUITE 140  
HANOVER, MD 21076



1100 E. WOODFIELD ROAD, SUITE 500  
SCHAUMBURG, ILLINOIS 60173  
TEL: 847-908-8400  
COA# PEC.0001444  
www.FullertonEngineering.com



\*BASED ON RFDS V3.0, DATED (03/28/18)  
LTE 4C, 5C, 6C & 7C

| REV | DATE     | DESCRIPTION      | BY |
|-----|----------|------------------|----|
| 0   | 11/13/17 | 90% REVIEW       | EB |
| 1   | 12/18/17 | FOR PERMIT       | KC |
| 2   | 05/02/18 | FOR CONSTRUCTION | EB |
| 3   | 05/03/18 | RRH ADD AND BWE  | KC |
| 4   | 11/30/18 | MOUNT REVISION   | EB |
| 5   | 03/11/19 | RF REDLINES      | EB |

I HEREBY CERTIFY THAT THESE DRAWINGS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND CONTROL, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF COMPLY WITH THE REQUIREMENTS OF ALL APPLICABLE CODES.



SITE NAME  
**NORWALK  
WEST-CT AVE.**

SITE NUMBER:  
**CTL02108**

SITE ADDRESS  
**613 CONNECTICUT AVENUE  
NORWALK, CT 06850**

SHEET NAME  
**PLUMBING DIAGRAMS**

SHEET NUMBER  
**A9**

THESE DRAWINGS ARE THE PROPERTY OF FULLERTON ENGINEERING CONSULTANTS, INC. IT IS FOR THE EXCLUSIVE USE OF THIS PROJECT. ANY RE-USE OF THIS DRAWING WITHOUT THE EXPRESSED WRITTEN CONSENT OF FULLERTON ENGINEERING CONSULTANTS, INC. IS PROHIBITED.

